

SURGERY OF CHILDHOOD

BY

JOHN FRASER

MC MD CHM FRCSE

REGIUS PROFESSOR OF CLINICAL SURGERY IN THE UNIVERSITY
OF EDINBURGH CONSULTING SURGEON TO THE ROYAL
HOSPITAL FOR SICK CHILDREN EDINBURGH

IN TWO VOLUMES

Vol I

ILLUSTRATED

LONDON

EDWARD ARNOLD & CO

1926

[All rights reserved]

Made and Printed in Great Britain by
Butler & Tanner Ltd, Frome and London

THIS BOOK IS DEDICATED
TO
SIR HAROLD STILES KBE, FRCSE

PREFACE

To any who may be interested enough to open the pages of these volumes I offer sincere apologies for the length of the production. Longfellow in his "Wind over the Chimney" tells us that books are "sepulchres of thought," and if I have dug a grave of disconcerting depth it is because of the multiplicity of the thoughts.

The basis of this work is formed by the lectures and clinics delivered at the Edinburgh Royal Hospital for Sick Children. The matter of these deliveries has been adapted to render them suitable for publication, illustrations have been supplied, and, where necessary, references to literature have been added.

If the work possesses any virtues, it owes them in no small measure to those who have contributed in varied ways to its production—by the excellence of the precept and example, by suggestions and kindly criticism, by consulting literature, by supplying illustrations, by reading proofs, by affording permission for reproduction—a veritable host of helpers without whose aid this work could never have been completed. My difficulty is to thank the many friends who have helped me, and if in my acknowledgments I have forgotten any, it is not that I am ungrateful.

My first and my deepest debt I owe to Sir Harold Stiles—a pioneer in pediatric surgery, as he has been in so many branches of the surgical art. I can say with truth that he taught me the bulk of what I know, and of what I have herein set forth regarding the surgery of childhood. Words do not suffice to express the weight of my indebtedness nor the depths of my gratitude. A number of the photographs with which the book is illustrated have come from his collection, and it is virtually the wealth of his experience which has given these pages any richness they possess.

Three of my colleagues have contributed chapters upon subjects in which they are particularly interested. Dr. Douglas Guthrie is the writer of the chapter dealing with diseases of the ear, and in part the chapter on diseases of the nose and throat, Miss Gertrude Herzfeld contributed the section dealing with congenital club foot, and Mr. Norman Dott supplied the chapter which describes the surgery of transfusion and infusion, he has also given me invaluable assistance in the compilation of the section dealing with hydrocephalus.

Many of my former residents at the Children's Hospital have given me the most loyal and ungrudging assistance. I am particularly

indebted to Dr. Dodds, Dr. Crowe, Dr. Hera Röss, Dr. Maxwell, Dr. Fowley, Dr. Rabkin, Dr. Douglas, Dr. Brodie and Dr. Price.

My colleagues on the Staff of the Children's Hospital, medical and surgical, have been most generous in their help and co-operation. Dr. J. W. L. Spence, radiographer to the Hospital, has taken infinite trouble in providing X-ray photographs in illustration of cases; in this connection also I desire to acknowledge the assistance I have received from Dr. Edmund Price, who lent me a number of X-ray illustrations from his collection. Miss Malcolm has been good enough to contribute the section dealing with the making of celluloid splints. The Hospital had the benefit for several years of the generous voluntary work of this lady and her assistants, and the reader will, I am sure, agree that the value of this book has been enhanced by Miss Malcolm's contribution.

Mr. Smith, technical assistant in the University Department of Clinical Surgery, has given me great assistance in the photographic part of this work.

I am exceedingly grateful to Messrs. A. & C. Black, the publishers of *Tuberculosis of the Bones and Joints in Children*, for their courtesy in permitting me to use certain illustrations and to adapt portions of the text of that book. A similar courtesy has been extended to me by the Editors of the *Edinburgh Medical Journal* and the *British Journal of Surgery*, privileges which I am glad to acknowledge.

The majority of the line and wash illustrations have been carried out for me by one who is my second self—my wife—and she knows how grateful I am; the rest have been drawn by Mr. James Murray.

The wearisome business of proof reading has been most generously undertaken by Dr. Torrance Thomson and Mr. T. M. Millar. Dr. Thomson was good enough to correct the original galley proofs; he wielded the blue pencil with a true editorial hand, to the great benefit of the work. My secretary, Miss Rice, has been most helpful in numerous ways; the great burden of the typing and clerical work has fallen upon her, and she has left no stone unturned to make her share of the task successful. If the book has any real value it is due in no small measure to the generous assistance of many collaborators, and to all of them I tender my thanks.

32 MORAY PLACE,
EDINBURGH.

January, 1926.

CHAP.		PAGE
XIX	TUBERCULOSIS OF JOINTS CONSIDERED LOCALLY. THE HIP, KNEE, ANKLE, SHOULDER, ELBOW AND WRIST JOINTS	395
XX	SYPHILITIC DISEASE OF JOINTS	451
XXI	JOINT HÆMORRHAGE IN HÆMOPHILIA	454
XXII	ARTHRITIS DEFORMANS	456
XXIII	THE SURGICAL ASPECTS OF THE BLOOD AND ITS DISEASES	459

PART II

XXIV	DEFORMITIES AND ANOMALIES OF THE SKULL	465
XXV	SURGERY OF THE SKULL AND ITS CONTENTS	467
XXVI	SURGERY OF THE FACE AND MOUTH	524
XXVII	AFFECTIONS OF THE EAR	568
XXVIII	AFFECTIONS OF THE NOSE AND THROAT	585
	INDEX	<i>At end of Vol. II</i>

SURGERY OF CHILDHOOD

PART I

CHAPTER I

GENERAL CONSIDERATIONS

The Qualifications of the Pediatric Surgeon

The surgeon who hopes to deal successfully with children must possess an insight into the psychology of the individual child, in addition to his special knowledge of pediatrics and his capacity to observe and discriminate.

Children are remarkably sensitive to sympathy or the reverse, and success at the initial examination depends largely on the early establishment of friendly relations.

The majority of children who are brought to the surgeon for examination are in an antagonistic frame of mind. Active or passive compulsion may have been necessary to secure their attendance, or the art of deception has been brought into play, and the child has been beguiled into the consulting-room with all sorts of promises and assurances. Such being the case, one must be prepared in many instances to appear in the guise of an enemy, and it is in convincing the child of friendship towards him that the art is required. It may be said from this standpoint that one meets with two types of children. There is the precocious child, who likes to be taken notice of and spoken to, and there is the diffident, shy individual, who is instantly alarmed by what he considers unjustified advances. These two types must be approached in entirely different ways. With the first you may strike up an immediate acquaintance, talk to him, question him, and you will charm his interest from the beginning, but do not tease him. The second individual will have nothing to do with such a progressive attitude. He may emphatically resent any advances until he has quietly summed up your character and formed a judgment upon it. In dealing with a child of this type it is wiser at first to ignore him completely, to continue with whatever work you are engaged, or to carry on your conversation with his parents or his friends. Presently his diffidence and shyness will subside, possibly he may feel a little neglected, and now is the opportunity to begin your advances and to secure his friendship. These points are of considerable importance in the successful examination of children. They are simple details, yet their neglect may greatly increase the difficulty of investigation. The remarks, naturally, apply to children who have passed the period of babyhood. In dealing with babies the problem

is less difficult ; the various idiosyncrasies of character have not yet become established, and may therefore be ignored. Much of the examination of the baby may be completed while the child is asleep. The movement of joints and abdominal examination can be advantageously carried out at this time. The suddenly-awakening baby, however, is apt to be alarmed if its eyes first alight upon a stranger ; it is therefore better that it should remain in its mother's arms. Never stare persistently at a child ; even young babies resent it, and older children become restless and uncomfortable.

The Expression of Disease in Children, and Features which Modify it

The early years of life may be divided into two periods—infancy and childhood. Infancy is the time elapsing between birth and the complete eruption of the first dentition, an event which should take place about the end of the second year. Childhood extends from this age to the development of puberty, about the thirteenth or fifteenth years. Of the surgical diseases which occur during these periods a few are peculiar to this time of life, and are 'children's diseases' proper ; others, while essentially the same as the affections of later years, are variously modified by the conditions which characterize early age. Let us consider what these modifying features are. In the infant, absence of speech deprives the examiner of the assistance afforded by the description of subjective symptoms, and in older children the ease may be little better, since with them words are not prompted by sufficient knowledge to be of great service.

The activity of the growth and development of children has a powerful influence upon disease. It is this which renders children liable to be affected by slight causes, and makes disease sudden in its onset, short in its course, and intense in its symptoms. This influence is especially important in relation to the nervous system ; for the activity of this system in healthy children often causes a trifling illness to assume an aspect of the greatest gravity, while the nervous depression which accompanies chronic wasting diseases may so obscure symptoms that a dangerous intercurrent affection may appear trifling, or may remain altogether latent.

But the modifying features of children's diseases are not necessarily detrimental in their influence. Disease in the child is usually uncomplicated, and its course and symptoms are unlikely to be modified by tissue lesions, which result from previous disease, from vicious habits, or from mental over-work and nerve strain. Further, the confusing element of misstated subjective symptoms is absent, while correct diagnosis is facilitated by the ease with which physical examination of the whole body can be conducted.

The clinician will do well to remember that the inarticulate expression of disease in infants possesses one outstanding advantage—it is

honest An infant's philosophy may be summed up in the statement, "All that is painful is evil, while all that is pleasant is good"

The Examination of Children

We have often been impressed and amused by the attitude which the student displays when he is first called upon to examine a small child A sense of loneliness and helplessness seems to afflict him as he realizes that his examination has to be conducted in an atmosphere which may be antagonistic, or at the best passive, while the diagnosis has to be made without the assistance which subjective symptoms would afford

An outline of a simple routine method of examination may therefore prove of value to the student

Questioning the Attendants When the patient is under seven or eight years of age the only way of obtaining the previous history is to question the mother or nurse The account must be carefully elicited, and considered with due reference to the narrator's intelligence 'It is unwise to discredit entirely any statement without excellent reasons, for many women, otherwise unreliable, are accurate observers when their powers are guided by affection The value of their observation is increased by the fact that they are thoroughly acquainted with the child's habits and disposition, and therefore they often detect an abnormality which the surgeon may overlook

Information from the attendants will be obtained on the following points —

(1) *The Family History* The family history, as far back as the parents, should be invariably investigated Enquiry is chiefly directed to the detection of chronic maladies and transmissible diseases, such as tuberculosis and syphilis An enquiry into the occurrence of still birth is important

(2) *The Post natal History of the Child* This will necessarily include a number of different items —

- (a) The manner of feeding during infancy, whether at the breast or from the bottle, and, if the latter, the composition of the food employed, and the method of its preparation, sterilization, etc
- (b) The date of commencement and the regularity of dentition
- (c) The general state of health in regard to strength or weakness, and liability to illness
- (d) The time of occurrence and the nature of any prominent attack of illness, especially of the exanthemata
- (e) The hygienic surroundings

(3) *Date of onset of Present Illness* This is often an easy matter, as the introduction of the illness may have been marked by some outstanding feature, such as vomiting, sometimes it is more difficult, and, when there is uncertainty, it is better to question back day by

day until a time is reached at which the child was perfectly well, and to date the onset from this period. Disturbed sleep and irritability of temper are often the earliest indications of commencing illness.

(4) *The Mode of Attack, with the Symptoms and subsequent Course of the Disease.* The questions employed in this interrogation should be of a general nature; leading questions should not be put. They should touch upon all the systems of the body, and, when a definite track of information is started, it must be followed to the end.

(5) *Treatment.* This stage of the investigation is closed by an enquiry as to the treatment which the child has already received.

Inspection of the Child. With the trained eye and ear valuable information may be obtained by simply looking at a sick child, and listening to its cry and speech. The information gained by inspection is sometimes spoken of as *the features of the disease*, and they are alluded to under different headings.

Facial Expression. The face of a healthy sleeping child wears an expression of perfect repose; the eyelids are completely closed, the lips slightly parted, and, while a faint sound of regular breathing is heard, there is no perceptible movement of the nostrils.

When awake and passive, the healthy infant's face has a look of wondering observation of whatever is going on about it. With increasing age the expression of intelligence increases, and there is the familiar bright, happy face of perfect childhood, indicative of careless contentment, and yet mobile in response to emotions. The picture is altered by the onset of disease, and pain quickly sets its mark upon the countenance.

There are several general surgical diseases (tuberculosis, syphilis, and rickets) which are associated with characteristic facial appearances, and these are alluded to under their respective headings. Many local surgical diseases have characteristic facial changes which the trained eye will detect, and which may weigh in the decision of an otherwise doubtful diagnosis. Cerebral abscess, hydrocephalus, intussusception, acute general peritonitis—each of them and many others possess characteristic facial signs. The first care, therefore, in examination will be to scrutinize the child's face, and mentally to compare its expression with the picture of health.

Decubitus. Much valuable information may be gained from observing the patient's posture or decubitus. When a child becomes muscularly and mentally inactive, it may be taken as an indication that the illness or injury from which he suffers is severe. The disinclination to continue muscular activity should always be interpreted as an early sign of ill-health, and this is often expressed by the child in a desire to be left undisturbed. A diminution of mental activity is the common accompaniment of diminished muscular activity, and the child loses interest in its surroundings and playmates, because the exertion demanded by the attentive attitude is unpleasant.

There are certain abnormal positions and gestures which have

special significance, and we may consider the more common and simple of these. Sleeping with the head thrown back and the mouth open is a frequent accompaniment of enlarged tonsils, the existence of colic is shown by repeated extension and retraction of the legs, clenching of the hands, flexion and extension of the forearms, and a writhing movement of the trunk. The lateral position is assumed in diseases of the lungs and pleuræ, the dorsal position with flexed knees is the position of election in acute inflammation of the peritoneum, it is also assumed in perinephric inflammation, but in this condition the thigh on the affected side only is flexed. It must not be forgotten that in children a full bladder sometimes compels a child to assume the dorsal position. The sick child lies on its abdomen in certain cases of Pott's disease, in acute inflammatory conditions of the back, and in certain non-inflammatory conditions of the abdomen, such as simple colic. The characteristic postures of spinal caries, of hip diseases, and numerous other conditions are referred to later.

The child's gestures are seldom of value from the diagnostic point of view, but such obvious movements as the carrying of the hand to the head, ear, or mouth, indicate irritation and pain in these various situations.

The Skin In the natural order of events any morbid condition of the skin which may exist will now attract attention, there are many manifestations of this region which are of great surgical significance, as, for example, syphilis, tuberculosis, or the petechial evidences of a purpuric condition.

The Cry Crying is the chief, if not the only, means which the young infant possesses of indicating displeasure, discomfort, or suffering. Even long after the power of speech has been developed, the cry continues to be the main channel of complaint. It must be remembered that hunger may be the cause of the most incessant, unappeasable crying, but such a cause may be easily excluded by putting the child to the breast, or by offering it a properly prepared bottle. With this exception, pain is the origin of persistent crying.

In many cases the cry has a distinctive feature. The hydrocephalic cry, denoting pain in the head, is a sudden, sharp, loud, and paroxysmal shriek, in retropharyngeal abscess the cry has a characteristic hollow, muffled sound, in empyema, croup, laryngeal syphilis, and many other conditions it has distinctive features, which are capable of recognition in the light of careful observation and experience.

Not only is the cry often typical in tone, but much may be learnt by noticing the exact period, in relation to certain functions, at which the cry begins. Crying associated with micturition may suggest phimosis, balanitis, or a meatal ulcer, and an anal fissure may be recognized by observing that the child cries most bitterly during and after defæcation.

There are several other sources of information which should be investigated before proceeding to the physical examination, though

strictly speaking they do not come under the head of inspection of the child. There are the changes in the odour of the breath, and the character of the fæces, the urine, and of material ejected by vomiting.

The Breath. The breath of a healthy child is odourless, except perhaps immediately after taking nourishment, when it may for a short time have the smell of milk or other food. Any persistent odour is abnormal. Morbid conditions which prevent the elimination of nitrogenous elements through the mucous membrane of the intestines, or retard the passage of decomposing detritus along the bowel will cause an offensive breath, and therefore conditions characterized by high temperature, catarrhal inflammation of the gastro-intestinal tract, chronic debilitating diseases, and structural lesions of the kidneys are associated with this sign. The reason is an obvious one, for the system, in order to get rid of the poisonous matter of accumulated waste, and to maintain the balance between the constant construction and destruction of tissue, must throw off elsewhere what the intestinal tract and the kidneys fail to excrete; so the lungs assume a vicarious activity, and the expired air becomes tainted.

Local causes of foul breath or 'halitosis,' as it is called, must not be overlooked—decayed teeth, caries of the nasal and maxillary bones, ulceration of the mucous membrane of the upper respiratory tract, and cancrum oris.

There is a general condition—a metabolic disturbance—which gives the breath a characteristic odour, the sweet apple-like taint of acidosis. It is difficult to over-estimate the importance of this observation in surgical work, and the subject is elaborated later.

As regards the character of the fæcal evacuations, of the urine, and of vomited matter, the possible variations are so wide that they are dealt with under the individual headings of various diseases.

Physical Examination

The methods of physical examination are identical with those employed in adults, but, bearing in mind the importance of acquiring information with the least possible amount of disturbance of the child, the order is altered somewhat. Features of the examination to which the child is likely to object, such as investigation of the throat, mouth or bowel, should be deferred to the end.

The pulse and respiration counts should not be taken at the commencement of the examination,—the child is in all probability excited by the novelty of his position, and it is well to wait until the preliminary excitement has passed before making these important observations. If the temperature is taken in the axilla it is convenient to begin with this manœuvre.

While in many local surgical conditions a general examination may be unnecessary, it is a sound principle to carry out as a routine a

rapid general examination in every case, some feature may be discovered which has an important bearing upon the local condition.

The order which the examination follows is a matter of individual choice, but it is a reasonable plan to begin with a local examination of the part affected, and afterwards to investigate the physical condition of the lungs, heart, abdominal organs, to determine the degree of muscular development, to ascertain the character of the pulse and respiration, and finally to examine the mouth, throat, and, if need be, the bowel.

This volume is concerned with the surgery of infancy and childhood, and therefore one is anxious to avoid details which appear to be of purely medical interest, but there are several general observations in regard to the physical examination to which it is important to refer.

The Respiration In children of both sexes the respiration is chiefly abdominal in type, and it is not until the age of puberty that the movements of the female child change, becoming superior costal. Consequently, in estimating the number of respirations per minute it is best to place the fingers lightly on the epigastrium. The count should be taken by the watch, and the most convenient time is while the child is asleep. Soon after birth the respirations number forty four per minute, between the ages of two months and two years thirty five, and between two and twelve years twenty three. During sleep the frequency is reduced. Children under two breathe unevenly and irregularly; in sleep there is greater regularity, after the second year the movement becomes steady and regular.

The Pulse To obtain reliable data, the pulse must be felt while the patient is quiet. The best opportunity is during sleep, but, if this should be impossible, advantage may be taken of the time when the child is nursing at the breast, feeding from a bottle, or playing with a toy. If the patient is an infant it is sometimes impossible to feel the beat of the radial artery, and it is necessary to ascertain the frequency of the pulse by auscultation. The child's pulse differs from the adult's in certain characters—it is more frequent, more irregular, more irritable, and necessarily of smaller volume. The frequency of the pulse varies with age, and the following table gives the average rate —

Age	Pulse per minute
From birth to second month	160 to 130
second to sixth month	130 , 120
, sixth to twelfth month	120 „ 110
first year to third year	110 „ 100
, third year to fifth year	100 „ 90
, fifth year to tenth year	90 „ 80
, tenth year to twelfth year	80 „ 70

These figures represent the pulse in a waking but passive state, during sleep the frequency is less.

The Temperature. The temperature must be estimated before removing the clothing, and a clinical thermometer must always be used. The instrument is placed in the rectum or groin of the infant or young child, in the axilla or mouth of an older one.

During the first week of life the temperature fluctuates considerably; after that period the 'puerile norm'—98.5° to 99° F.—is established, but, until the fourth or fifth month the temperature is influenced by healthy causes of variation, the fluctuation varying between 0.5° and 1.5° F. By the fifth month regular morning and evening oscillation begins, and the definite laws of temperature are followed.

The temperature of the young child has two peculiarities which are of special importance to the surgeon—a sudden rise bears less significance than the corresponding event in an adult, because instability of the heat centre in the child renders it liable to influences which would have little or no effect in later life; on the other hand, babies and young children are peculiarly intolerant of a high temperature (104–105° F.) persisting over any length of time, and remedies for its reduction are early required.

Surgical operations, and especially operations on the neck, illustrate the instability of the infant's heat centre. Within a few hours after removal of tuberculous glands from the neck the temperature may reach 106° F., apparently from a reflex disorganization of the heat centre. Non-recognition of this complication may lead to a fatal termination.

General Development. The healthy child under two years of age is plump of body and round of limb, with the head and abdomen large in proportion to the rest of the frame. As age advances the figure gradually assumes the characteristics of adolescence. To be robust the newly-born child must have a certain average size and weight. Subsequently, under normal circumstances, there is a regular rate of increase in both these respects. At birth the child's length is about 19 inches. Growth is quickest in the first weeks of life; in the first year there is an increase of from 5 to 6½ inches; in the second and third from 2½ to 3½ inches; in the fourth about 2 inches; and from the fifth to the sixteenth year the annual growth amounts to from 1½ to 2 inches. The average weight at birth is from 6 to 8 lb., and the daily increase in weight should range from a quarter to three-quarters of an ounce.

Measurement and weight form important links in the evidence of a child's physical condition, because the fact that either falls short of the normal standard infers the existence of some fault in the processes of nutrition.

The age at which a child sits erect, at which it walks, and at which the anterior fontanelle becomes ossified are points closely associated with the subject of development and nutrition.

For some months after birth, if the child is 'sat up' the head and

shoulders fall forwards, the spine from the cervical region to the sacrum forming a continuous curve convex backwards. Towards the end of the eighth month the back becomes more erect, and by the ninth month the spine assumes an almost perpendicular line. Any delay in these changes indicates general debility. At the end of the fourteenth month the child should be able to walk alone, and the spine then assumes the S like curve of the healthy adult. Delay or errors in walking may be due to systemic weakness, or to local disease, and the influences of the latter upon gait are discussed below.

In an infant, the condition of the fontanelle should be observed. The anterior fontanelle should be ossified, or completely closed, at some period between the fifteenth and twentieth months. The closure




FIG 1 —The relative Proportion of the Body at different Ages (After Stratz)

is delayed in rickets, which is pre eminently a disease of malnutrition, hydrocephalus has a similar effect, but for a different reason. In a state of health the opening while still membranous is level with the cranial bones, or very slightly depressed. Conditions of systemic exhaustion cause marked sinking, and the depression is an indication for stimulation, abnormal bulging of the fontanelle is evidence of increased intra cranial tension.

Abdominal Examination The routine of abdominal examination is similar to that followed in the adult, inspection is followed by palpation and percussion. As with the adult, it is important that the hands of the examiner are comfortably warm.

Inspection reveals disproportion in size or form of the abdomen, the state of the integuments, of the superficial veins, and of the

Bony processes, such as the medial humeral epicondyle, are particularly susceptible to direct violence, while the foot frequently suffers from weights being dropped upon it

Indirect violence The force transmitted to the bone is one of bending (Fig 5), leverage, rotation or compression, and the bone yields at sites known to be structurally weak. Such a fracture is the usual fracture of the clavicle, where in trans-



FIG 5 A transverse fracture due to bending strain on close examination always shows small oblique cracks running from the fracture line towards the surface of compression



FIG 6 Occasionally the main line of fracture follows one of these finer lines producing the half oblique half transverse fracture of Fig 4



FIG 7 Less commonly the fracture runs along the fissures on either side of the point of compression and separates a chip of bone. This chip always has its base on the side of compression and so when present can be used to determine the direction of the bending strain (See Figs 254, 554)

highly sinuous component, shorter, and more transverse, uniting the ends of the vertical fissure. The first represents the hinge on which the second S shaped portion opens out if the rotation has continued. As a consequence the wavy portion always shows a greater width of fracture line (Figs 3, 255). If the surface of the bone on which each component lies can be identified, and this requires at least two radiographs, the direction of rotation can be determined. Thus in Fig 3 the vertical component lies behind, and the direction of rotation of the lower fragment is to the right, or of the upper fragment to the left.

Fractures from indirect violence are rarely compound, and then

mitting an abnormal force from the arm to the trunk the bone snaps at its weakest point. In this case the force is a combination of leverage and compression. More interesting are the spiral or helical fractures which occur in the long bones, particularly the humerus and tibia, where rotational force can be developed by the forearm or the foot.

Helical (or Spiral) Fractures can always be recognised by certain peculiar characteristics. In the radiographs two components can always be seen, first a long almost vertical component, which, if there has been no displacement, may remain in close approximation, and second, a

as a rule indirectly so. There is usually a gross displacement of the bones, and damage to soft parts, from continuation of the force or the falling of the body.

Muscular violence Fractures from muscular contraction characteristically affect two sites, the olecranon and the patella. They are due to the peculiar position of these bones together with the strength of the muscles inserted into them, which may exert a sudden immense force in the effort to throw a ball or to regain balance. Very rarely a long bone snaps from placing excessive voluntary strain on it, e.g., the humerus in a woman wringing out clothes, or a rib in a severe bout of coughing.

Bone fatigue "March fracture" of the metatarsals has long been recognised as due to repeated minor trauma which may accumulate and produce a fracture, or result in proliferative periostitis to strengthen the weak area without a fracture becoming visible. The condition has now been recognised as affecting other sites, notably the neck of the femur and the upper third of the tibia (fig 542). It is characteristically seen in the adolescent subjected to undue exertion over a long period, and affects sites liable to peculiar strain in maintaining the body weight. The condition appears to be related to the similar phenomenon of fatigue in metals, the inorganic substance of the bone slowly altering in a crystalline configuration until a complete cleavage plane appears (See p 514).

Varieties of Fracture

Fractures may be classified in a number of ways, all interlocking with each other. They may be divided up according to the mechanisms previously described, or

1 According to whether the fracture communicates with the outside air

Simple, or "closed"

Compound or "open" { Direct
Indirect

2 According to the degree of fracture

Complete { Impacted
Unimpacted
Incomplete { Greenstick
Infraction

3 According to the line of fracture

Oblique
Spiral (helical)
Transverse
Comminuted

SIMPLE FRACTURE is the term applied to any complete or incomplete uncomplicated fracture

COMPLETE FRACTURE The line of fracture runs across the bone dividing it into two or more entirely separate portions (Figs 1-4)

INCOMPLETE FRACTURE The line of fracture does not run entirely through the bone so that part is intact and serves as a support for the fractured ends (Fig 9)




FIG 8 The method of production of a greenstick fracture. Compare with the previous figures showing the results of a bending strain acting on adult bone. In a greenstick fracture the bone breaks on the side of the midline undergoing traction. The bone on the side of the compression remains intact



FIG 9 A greenstick fracture

GREENSTICK FRACTURE

This is a classical variety of incomplete fracture in the young. Owing to the mechanical forces developed inside a bent hollow rod, a compression strain is developed on the inside of the bend, and a tension strain in the outer half of the bone. Bone which shows the same physical qualities as cast iron is most resistant to compression and least resistant

to tension. Fracture of the outer half of the bone therefore occurs leaving the inner half of the bone intact. As the continuity of the bone is not lost, function may remain good, and the fracture may not



FIG 10 An incomplete fracture of the lower end of the radius. Compare with Fig 347




FIG 11 An impaction fracture of the upper end of the humerus. Compare with Fig 253

be noticed till a lump of callus appears on the bone. This is frequently seen in greenstick fractures of the clavicle in children.

In a few cases the bone may be bent without any fracture being

visible in the radiograph. The fractures are then small scattered lesions through the bone. The condition is treated similarly to fracture but immobilisation need not be so prolonged. In greenstick fracture the deformity is often marked, and during reduction the bone is not infrequently broken. This is not always due to a further fracture of the bone, but due to impaction of the bone on the inner side simulating incomplete fracture.

IMPACTION FRACTURES ("Bamboo fractures") This is another variety of incomplete fracture occurring in young bones. As a result of compression violence there is a small expansion of the bone at the junction of the cancellous end of the bone and the compact bone of the shaft. This results in a slight irregularity resembling the ridge on a bamboo stem being seen in the X ray. This appearance may be seen in both the lateral and antero-posterior views of the bone, but is frequently seen in one view only, the other view showing a more marked deformity. The lesion is most commonly seen in the lower end of the radius in children, occurring a little above the site of Colles's fracture in the adult (Figs 10, 347).

IMPACTED FRACTURES Following the break in the bone the continuation of the force jams the broken ends into one another, and the resultant interlocking of bony spicules gives the bone a moderate degree of rigidity, which may allow a considerable degree of function. It is characteristically seen in fractures of the upper end of the humerus, where the cancellous head is driven over the compact bone of the humeral shaft. Impaction is important in aiding fixation and indicates, as a rule, that little displacement has occurred.

COMMUNUTED FRACTURES Where the bone is broken into more than two fragments the term comminuted is applied. Where there



FIG 12 A comminuted fracture. The comminutions are multiple due to direct violence. Fig 7 illustrates the type of comminution due to indirect (bending) violence.

SIMPLE FRACTURE is the term applied to any complete or incomplete uncomplicated fracture

COMPLETE FRACTURE The line of fracture runs across the bone dividing it into two or more entirely separate portions (Figs 1-4)

INCOMPLETE FRACTURE The line of fracture does not run entirely through the bone so that part is intact and serves as a support for the fractured ends (Fig 9)




FIG 8 The method of production of a greenstick fracture Compare with the previous figures showing the results of a bending strain acting on adult bone In a greenstick fracture the bone breaks on the side of the midline undergoing traction The bone on the side of the compression remains intact




FIG 9 A green stick fracture

to tension Fracture of the outer half of the bone therefore occurs leaving the inner half of the bone intact As the continuity of the bone is not lost, function may remain good, and the fracture may not

GREENSTICK FRACTURE

This is a classical variety of incomplete fracture in the young Owing to the mechanical forces developed inside a bent hollow rod, a compression strain is developed on the inside of the bend, and a tension strain in the outer half of the bone Bone which shows the same physical qualities as cast iron is most resistant to compression and least resistant



FIG 10 An infraction fracture of the lower end of the radius Compare with FIG 347




FIG 11 An impaction fracture of the upper end of the humerus Compare with FIG 251

be noticed till a lump of callus appears on the bone This is frequently seen in greenstick fractures of the clavicle in children

In a few cases the bone may be bent without any fracture being

likely in the direct lesion than in the indirect, though the withdrawal of the spicule through the skin may draw dirt in with it. Indirect compound fractures of this type are almost exclusively met with in the leg, associated with spiral fracture of the tibia. As the spicule of bone may have withdrawn before the case is seen the importance of a careful examination of the skin for puncture wounds needs emphasis. It is also to be borne in mind that all wounds over fractures do not necessarily communicate with them, and in the repair of such wounds every effort should be made to preserve an undamaged wall of tissue between the fracture and the wound.

REFERENCES

General

- The following general text books are available for consultation, and have been freely used. The American text books treat the subject in a complete manner, the remaining books incomplete.
- SEER, KRLOP 'Fractures' C V Mosby London, Henry Kimpton, 4th Ed, 1942 (Contains further reference lists)
- SEUNDEN C L 'The Treatment of Fractures' W B Saunders & Co, Philadelphia and London, 11th Ed, 1939
- MATTI H 'Die Knochenbrüche und ihre Behandlung' Julius Springer, Berlin 1931 (Contains many foreign references, mostly German)
- KEE and CORWELL 'The Management of Fractures, Dislocations and Sprains' C V Mosby London Henry Kimpton, 4th Ed, 1942
- WATSON JONES 'Fractures and other Bone and Joint Injuries' Edinburgh E & S Livingstone 4th Ed 1949
- BONFELT, L 'Technik der Knochenbruchbehandlung' Vienna, Wilhelm Maudrich 5th Ed, 1937 (Enlarged edition in two volumes. Most of the important points are found in the English translation of the 4th edition, edited by L W Hey Groves Bristol John Wright & Sons, 1936)

Pathological Fractures

- JOLL C A "Metastatic Tumours of Bone," *Brit J Surg*, 1923-24, 11, 38
- WATSON JONES 'Fractures' E & S Livingstone 1949
- GESCHICHTER and COPTLAND 'Tumours of Bone' 3rd Ed, New York 1949
- WATSON JONES 'Pathological Fractures of the Neck of the Femur,' *Brit J Surg* 1936 23, 799

Direct Injury

- KEITH and HALL 'Gunshot Injuries of the Long Bones' *Brit J Surg*, 1919 7 149 (Describes the mode of injury by missiles)

EPIPHYSEAL SEPARATIONS These occur on the metaphyseal side of the epiphyseal line. They are usually fracture separations, a small portion of metaphysis being broken off with the epiphysis. This fragment is important in reduction, as by catching on the metaphysis it may prevent over correction. There is no bony crepitus palpable in a pure epiphyseal separation as the abrasion of the surfaces is softened by the cartilage (Fig 13)

Crepitus may however be obtained from the small piece of metaphysis which is fractured, and so the sign is unreliable. Provided the epiphysis is cleanly fractured on the metaphyseal side, and the epiphyseal plate remains intact no interference with growth need be anticipated if the separation is reasonably well reduced. If the epiphyseal plate is fractured there is a likelihood of interference with growth. This is due to the occurrence of premature synostosis between epiphysis and diaphysis at the site of damage to the epiphyseal plate. Growth continues in the undamaged portion of the epiphyseal plate with resultant distortion (Figs 563, 565)



FIG 13 Separation of the lower epiphysis of the radius showing the small wedge of metaphysis which is fractured and remains attached to it in this case displaced dorsally

LIGAMENT TRACTION FRACTURES (Sprain fractures) Ligaments as a rule yield at their bony insertion rather than tear. When this occurs a small flake of bone is removed with the ligament, and this can be seen in the X ray. This lesion is frequently seen in the region of the ankle. Its importance depends on the degree of subluxation of the joint such a separation has allowed, and this must be estimated clinically and radiologically. The treatment of the lesser isolated lesion is that of a severe sprain (Figs 592, 618)

COMPOUND FRACTURES (Open fractures) When the fracture communicates with the outside air it is said to be compound or open. The importance lies in the enormously increased risks of infection of the bone. The fracture may be compound from rupture of the skin covering the bone, or of a mucous surface such as the mouth, bladder or nose. Where the force producing the injury has resulted in breaking the skin over the bone the fracture is *directly* compound, but where the displacement after the injury has resulted in a sharp spicule of bone being driven through the skin it is said to be *indirectly* compound. The importance of this observation is that the conveyance of infection from outside inwards is much more

fractures involving joints fragments of articular cartilage and ligaments are added. The blood remains fluid in the centre of this mass for some hours, clotting usually about the end of the first day. Fresh handling of the limb produces fresh hemorrhage and an increase in size of the hematoma mass. The common conception of the periosteum forming a limiting membrane to such a mass of jumbled tissues is quite erroneous. Only in children is the periosteum of any




FIG. 16. Section of the proliferated periosteal tissue of a four day old fracture

- A, Cellular proliferation of the periosteum
 - B, Cartilaginous differentiation of the cells. No blood vessels present
 - C, Early formation of bone around vascular spaces
- The section shows a full range of differentiated cells between fibroblasts and bone

thickness and strength. In the adult it is a friable membrane, which usually remains attached to the bone, and tears along the margins of the fissures. The wall of the fracture hematoma is thus formed almost entirely of soft tissues.

Organisation of the hematoma Aseptic inflammatory changes commence at once in the tissues around the fracture and organisation of the clot commences at the junction of the clot and

CHAPTER II

THE REPAIR OF FRACTURES

SOME knowledge of the process of repair in bone is essential to the satisfactory treatment of fractures. The primary stimulus to the formation of bone is still a quarrelling ground for the erudite, and no attempt can be made here to give more than an account of the observed facts and their relation to treatment. It is to be noted though the processes in a healing fracture have been separated for discussion, they may all be taking place in different parts of the same healing tissues at the same time (Fig 23)




FIG 14 Hematoma around the fracture

- A Compact bone of the shaft
- B Hemorrhage escaping into muscles through torn periosteum
- C Periosteum
- D Hematoma under stripped up periosteum
- E, Medullary cavity




FIG 15 Stage of granulation tissue

- A Active dilated blood vessels
- B Remaining unorganized hematoma
- C Organized granulation tissue

Hæmatoma Immediately following a fracture there is an outpouring of blood into the tissue spaces around the bone ends from the marrow tissues, the torn periosteum, and the damaged muscles. The amount of blood will vary depending on the amount of periosteal tearing, the comminution and displacement of the bone ends, the laceration of the surrounding tissues, and the size of the blood vessels torn and the resistance offered by the tissues. If displacement occurs, a cavity containing lacerated muscle, fragments of bone, bone marrow, and fascia will be found around and between the ends of the bones. Occasionally even tendons and nerves will be included. In

and assume the characteristics of osteoblasts. Further osteoblasts develop around these centres, and the older cells then deposit lime salts among the collagen fibrils forming callus. This change first becomes visible in the angle between the elevated periosteum and the shaft of the bone, where there is a good blood supply from the first, and this process spreads itself through the granulation tissue down to the fracture site. At this stage we have the first appearance of changes visible in the X ray, usually somewhere about the tenth day. As early callus is not very radio opaque, the time of its appearance on a film will be much affected by the quality of the radiograph and the density of overlying tissues.

The second process commences opposite the bone ends, and here certain fibroblasts grow to resemble cartilage cells. The number of




FIG. 19. Osteoclasts arranged around a bony trabecula.

these cells which appears seems to depend on the amount of movement at the fracture site, and is minimal with absolute fixation of the bones. As it is some abnormality in the production of these cells which leads to false joint formation this is an important point.

Organisation of callus. Callus has appeared in the angle between the periosteum and the shaft on the sixth day, and becomes obvious to the X ray on the tenth day, but it requires twenty five days before it is firm. Two processes are occurring in this callus. New bone is being differentiated from the young osteoblasts and the cartilage cells, and at the same time the ends of the fractured bones, which are at first coated with a layer of dead cells, are being remodelled. This appears to occur from resorption of the lime in the exoplasm of the osteoblasts which become larger and their cell walls less definite. Several of these cells lying in contact with one another will thus appear to be in a bony lacuna, and, owing to the poor

living tissues. From the second to the thirteenth day the hæmorrhagic mass becomes encapsulated with a fibrous tissue layer produced by the activity of fibroblasts appearing from the capillary networks invading the hæmatoma. This progresses layer on layer till the whole mass is vascularised and replaced by granulation tissue. The outer layers of fibrous tissue commence to differentiate into fibrocartilage and hyaline cartilage first. The fragments of dead bone are absorbed in various ways and soft tissues interposed are also absorbed as a rule, without the progress of union being affected. Thus fibrous tissue framework often extends into the muscles around the fracture which have been bruised, and so they may be involved in the further process of repair. With the organisation of




FIG 17 Commencing organisation of granulation tissue and formation of callus

- A Callus commencing to form in the angle between the bone and the periosteum
- B Granulation tissue organised in the medullary cavity
- C Subperiosteal granulation tissue




FIG 18 The organisation of the callus to bone

- A Bone appearing in the angle between the periosteum and the shaft where it is first visible as a fluffy shadow in the X ray
- B Organised callus

the callus this tends to retrogress but a persistent fibrosis may remain with consequent adhesion of the muscle to the periosteum, and loss of contractility. This is seen frequently in the quadriceps.

Organisation of the granulation tissue For reasons variously attributed to the presence of excessive calcium in the region, to the mechanical stresses of the region and to inherent properties in the cells of the periosteum, the granulation tissue commences to differentiate itself in the direction of bone. Two processes become obvious. First certain fibroblasts lay down collagen fibrils in their exoplasm,

site. If the bone is meeting at a slight angle a compression strain will occur on the inner aspect of the angle and a tension strain on the outer aspect. Compact bone will be laid down most rapidly and solidly in the area under compression. This important fact is the clue to the success of weight bearing in producing union in fractures of the lower limb.

Over a long period of time the bone will slowly be restored to normal size, and the prominence of the callus decreased. If the bone is malunited the further growth of the bone will tend to restore it to the normal. In young people this power of adaptation is very great, but it diminishes rapidly with the cessation of growth. The development of bone at the fracture site occurs in accordance with the demands of function, and so is greatly aided by the activity of the muscles and joints in relation to the fracture. For some time after a fracture the bone at the fracture site remains increased in density and thickness and slightly tender.

The Formation of Bone

Without going into the experimental evidence we can say that the following factors influence the formation of bone. It is uncertain which is the primary stimulus, but it is possible that there is an interaction of several factors.

1 The quantity and activity of the fibroblasts. The cause of their differentiation into osteoblasts is unknown.




FIG. 22 The organised new bone

A B Slight thickening of the shaft indicates the site of the old fracture; the bone on the inside of the curve being slightly thicker than that on the outside.




FIG. 23 Section of a healing fracture —

A Outer fibrous sheath continuous with periosteum
B Calcification spreading among organised fibrous tissue
C Organising hematoma
D Subperiosteal calcification and new bone formation

2 The presence of some inorganic calcium and phosphorus, possibly the factor stimulating the fibroblasts.

3 The presence of a good blood supply to the part.

definition of their cell walls will appear as multi nucleated masses, to which the name of "osteoclast" has been given. These groups of cells are merely osteoblasts in an anabolic phase preparatory to undergoing a katabolic phase in conformity with the demands of their new situation. Should a small piece of bone become avascular, this process cannot occur from internal cellular change, and must occur very slowly from outside cellular activity.

Organisation of bone Callus first becomes converted into bone at the point where it is first laid down. Fine trabecular bone is laid down which slowly extends throughout the organising callus, which, once it has firmly joined the bone ends, commences to shrink in size. As time progresses this bone organises itself into compact and cancellous bone, the so called intermediate callus between the bone ends becoming organised into compact bone, continuous with the compact bone of the shaft. This reorganisation of the bone takes place with definite regard to the stress and strain passing through the fracture.




FIG 20 The fracture firmly united by new bone

A Internal callus B Intermediate callus C External callus D Resolving external callus E See Fig 21



FIG 21 Union in a transverse fracture of the femur showing the increased strength of callus deposited on the side of the fracture under compression strain

tive treatment of the fracture will therefore delay the development of rigidity, though this may be offset by the closer interlocking of the fracture

Radiological changes The importance of these changes as a guide to the union of fractures has perhaps been over estimated. As a guide to the type and degree of non union radiographs are of inestimable value, but in the early stages, and often until the bone is fit clinically for weight bearing, the density of the shadow cast by the fine lamellar bone in the callus is slight and is obscured by the shadow of the soft tissues. Clinically firm union may be present before there is radiological confirmation, and it is important to remember that if the fracture site is rigid, painless on attempted bending at the line of fracture, and not tender to the touch, no advantage is obtained from further delay. At all stages in the healing process all radio opaque material at the fracture site is bone, and this is commonly seen first at the tenth day at the point where the bone, the attached periosteum, and the elevated periosteum meet. The necessity for removing all splinting and plaster when making a radiological attempt to estimate union should not need emphasis, but is often neglected.

Avascular bone necrosis

The improvement of radiological apparatus and technique has brought to light an interesting series of changes which occur in a fragment of bone deprived of its blood supply. Bone may be rendered avascular in various ways. A fragment, as in Fig. 24, may be thrown off from the cortex into the hematoma surrounding a fracture, and so be deprived of its blood supply. It does not necessarily follow that the fragment will die. The fragments may survive in the tissue fluids and in larger fragments the superficial cells survive. The bone can however no longer take part in its usual metabolism and its density must remain constant for a considerable time. With the increased blood supply and fibroblastic activity in the vicinity of the fracture, and the enforced rest of the limb, decalcification occurs in the vicinity of the fracture in which the isolated fragment cannot partake. It therefore appears, by virtue of retaining its normal density, much denser than the surrounding parts. Such a fragment will be slowly absorbed and replaced by living bone in the manner of a bone graft.

Larger portions of bone may be deprived of their blood supply if this is dependent on a few vessels susceptible to pressure or division. Thus in fractures of the navicular the main blood supply enters across a transverse line to which the axis of the bone lies obliquely. The proximal half of the bone is articular and the blood supply limited,

4 The quality of the blood It must contain adequate calcium, phosphorus and vitamins

It is to be noted, however, that the blood calcium, phosphorus, and phosphatase are not significantly altered during healing

5 The amount of movement at the fracture site This modifies the differentiation of fibroblasts in an unknown manner resulting in increased production of cartilage, and combined with other factors in false joint formation

Certain of these factors are under our control We can assure that the patient has an adequate diet, and that the movement at the fracture site is restricted The presence of fibroblasts and adequate calcium and phosphorus at the fracture site is a normal occurrence in a healthy individual Only the blood supply is liable to variation Normally this is assured by the active granulation tissue, but if an inflammatory process occurs in the vicinity of the fracture the blood supply may be excessively increased This will result in a decalcification of the region and delay in the union, which will take longer to consolidate

If the fracture site becomes infected still further vascular disturbance occurs, with increased destruction of tissues, and healing is further delayed

The sequence of tissue changes described is constant for all fractures but varies in rate in different parts of the fracture The exact time of the various changes varies with —

- 1 Individual bones
- 2 Age of the patient
- 3 Type of fracture (oblique or transverse)
- 4 Site of fracture (shaft or end of bone)
- 5 Amount of displacement of the fractured ends
- 6 Volume of interposed fragments and injured tissue
- 7 General constitutional conditions vitaminosis undernourishment chronic nephritis and other illnesses

The strength of union in the early days will depend on the area of callus surrounding the bone ends, imparting rigidity to the fracture Reduction in the size of the hematoma by opera-



FIG 24 Well united fracture in the young showing an avascular sclerotic fragment incorporated in the callus

the fluids bathing it it adsorbs calcium and phosphorus which crystallise in its interstices and greatly increase its density relative to all bones normal or decalcified. A similar reaction is seen in




FIG 26 Diagrammatic representation of a section at the junction between living bone and a bone graft. The bone graft lies below. A section of a healing fracture is similar if the bone graft is replaced by active bone.

- A, Living bone as shown by the presence of nuclei in the bony lacunae.
- B, Subperiosteal proliferation of osteoblasts forming new bone (Fig 15).
- C, Dead bone on the surface, as indicated by the empty lacunae under going absorption.
- D, New cancellous bone uniting the graft to its bed.
- E, New bone formed by some surviving cells in the periosteum of the graft.
- F, Dead bone of the graft showing the empty lacunae.
- G, New bone in the medullary cavity.

loose bony fragments in joints. The density achieved is unmistakable. It indicates that the fragment is acting as a foreign body and that any attempt at obtaining union is a waste of time. Where the bone forms part of a joint, as in the case of the navicular,

fractures therefore lying proximal to this line (Fig 386) may cut the proximal pole off from its blood supply and it undergoes avascular necrosis. Following im-



FIG 25 A gutter graft for an ununited fracture of the humerus which has not taken and undergone sclerosis having failed to provoke union in spite of moderate callus reaction. The graft is too long and holding the bones apart. It would have been better to dispense with the wires for retaining it.

lar necrosis. Following immobilisation of the wrist the proximal pole first appears to be increased in density. This is apparent from about the third week on, becoming gradually more marked as the decalcification in the vicinity progresses. With the passage of time and if kept at rest the fragment is invaded with capillaries, absorbed, and rebuilt by a creeping replacement. Its density thus slowly returns to that of the surrounding bones. On the commencement of exercise it partakes in the general increase in density of the bones of the limb, but its surface will not be found so clean or well defined as the rest of the bones. The length of time taken for this process varies from six to eighteen months. The replaced bone lacks the finer modelling of the original bone and its cartilage covered surfaces are defective. Though the bone has ostensibly recovered it has taken the first backward step in a series of retrograde changes which lead ultimately to a degenerative arthritis.

Should the avascular fragment not be immobilised the revascularisation of the bone is prevented by recurrent damage to the capillary loops, and the bony fragment comes to lie like a foreign body in a fibrous tissue sheath. From

channel of granulation tissue. Should the callus provoked be successful in bridging the gap the graft may be successful in spite of its failure to "take."

REFERENCES

Development and Structure

- MORRIS, P. I. D. "Bone" Cambridge University Press, 1936
 COWDERY "Special Cytology" Hoeber, New York Vol. 2

Repair

- LENICHR and POLICARD "Physiology of Bone" London, 1928
 PHEMISTER "Repair of Bone in the presence of Aseptic Necrosis, from Fractures Transplantations and Vascular Destructions" *J Bone and Joint Surg*, 1939, 12, 769
 BLAISDELL and COWAN "Repair of Simple Fractures," *Arch Surg*, 1926, 12, 619
 GALLIE and ROBERTSON "The Repair of Bone," *Brit J Surg*, 1919, 7, 211
 WATSON JONES and ROBERTS "Calcification, Decalcification and Ossification" *Brit J Surg*, 1934, 21, 461
 HEATZ J. "Studies in the Healing of Fractures" Oxford University Press, 1936 (With special reference to the significance of the vitamin content of the diet.)
 HALL, A. "Histological Study of the Early Phases of Bone Repair," *J Bone and Joint Surg*, 1939, 12, 827
 UST, M. A. and JOHNSON, R. W. "The Healing of Fractures in Man under Clinical Conditions," *J Bone and Joint Surg*, 1943, 35, 375

Avascular Necrosis

- WATSON JONES "Fractures" 4th Edition, E & S Livingstone, 1949
 WATSON JONES and ROBERTS "Significance of the Density of Bone Shadows," *Brit J Surg*, 1934, 21, 467
 SANTOS "Changes in the Head of the Femur after Intracapsular Fracture," *Arch Surg* 1930, 21, 470
 FAIRBANK, H. A. T. "Increased and Decreased Density of Bone," *Brit J Surg*, 1939, 27, 1

Bone Grafts

- HENDERSON, M. "Bone Grafts in Ununited Fractures," *J Bone and Joint Surg*, 1938, 20, 635
 See also references in Chapter IX

it may be tolerated for a time, but eventually leads to a degenerative arthritis. It is therefore best excised.

The blood supply of small bones is variable, and it is not always possible to forecast the occurrence of avascular necrosis from the line of fracture. Crushing and impaction of cancellous surfaces, with subsequent thrombosis, may play a part, while the temporary disturbance of the whole blood supply to a limb may precipitate a case by causing a thrombosis. Movements or unsuitable splintage may damage or pull on ligaments carrying the remaining channels of supply. All these may therefore influence the occurrence of necrosis and make its occurrence unpredictable. Certain bones from the delicacy of their blood supply are particularly susceptible to the condition, and must be watched for such changes by serial radiographs at monthly intervals. These bones are —

- | | | | |
|---|--|---------------------------------|---------|
| 1 | Lunate | } after fracture or dislocation | (p 403) |
| 2 | Navicular | | (p 394) |
| 3 | The head of the femur, after fracture or dislocation (p 465) | | |
| 4 | The talus following dislocations or fracture dislocations (p 575, Fig 623) | | |

The importance of avascular necrosis is threefold —

- (a) It delays and may prevent union entirely.
- (b) When union has occurred a considerably longer period must elapse before use of a limb is permitted if the new bone is not to be crushed or eroded at once.
- (c) The replaced bone, if partaking in a joint, and this is usually the case, is degenerate and eventually after a longer or shorter period leads to a degenerative arthritis.

Bone grafts

Similar radiological changes may be seen in bone grafts, and vary only in degree from the successful to the unsuccessful graft. In the successful graft the bone cells survive on the surface and rapidly unite with new bone from the soft tissues nearby to bed the graft firmly. The rest of the graft which appears denser than the surrounding bone is slowly replaced by creeping replacement and gradually assumes a density similar to the surrounding bones. With compact bone the replacement of the graft is slow, and attention has therefore been directed to the use of cancellous bone in the hope that it will revascularise more rapidly. In certain cases in which the compact graft is not needed to maintain length or stability its use has been very successful.

In unsuccessful bone grafts the graft rapidly assumes the characteristics of a foreign body becoming markedly increased in density and lying separated from the new bone formed in the vicinity by a

retention of a fracture It must be combated at once by elevation and fixation of the part, and later may be dispersed by massage and effleurage. Accompanying swelling and bruising fracture blisters are often seen. They are serous effusions, often blood-stained, between the dermis and epidermis. The more superficial the bone, and the larger the hematoma, the more likely these blisters are to occur. They take twelve to twenty-four hours to appear, but if the skin is supported by an unpadded plaster do not appear, though if this plaster is split they will appear along the line of cleavage.

LOSS OF FUNCTION is a classical, but variable, sign. Impacted or green stick fractures may show little loss of function. A patient may walk on an abduction fracture of the neck of the femur, and it is an unfortunate commonplace that fractures of the spine are not recognised till the patient has walked for a few days thus compressing the fractured vertebra, and producing deformity.

DEFORMITY This is another variable feature. It may be gross or only detectable by careful measurement. In compound fractures the wound may be considered as part of the deformity, and in it the fractured bone ends may be seen. Previous deformities from disease or accident must be considered.

ABNORMAL MOBILITY In order to detect this one may have to inflict considerable pain, and on this ground alone it is often better neglected. In order to detect it one must have a knowledge of the normal degree of movement of joints, and one must where possible compare it with the intact limb, to allow for individual variations. Mobility may be excessive at a joint, or in one direction at a joint, or it may be detected at a point where there is no joint. This latter sign is certain evidence of fracture. The nearer the lesion is to a joint the more the abnormal mobility will be camouflaged by the normal joint movements, and the more difficult it is to determine.

A less emphasised point is the loss of mobility at certain joints such as the hip and shoulder after fracture in the vicinity. This is noted in impacted fractures where function is not entirely lost, and is due to several factors, the spasm of surrounding muscles from the pain, the irregularity of joint surfaces acting mechanically to prevent movement, and distension of the joint capsule from blood and synovial fluid.

LOSS OF TRANSMITTED MOVEMENT from one part of a bone to another is certain evidence of fracture. It is commonly elicited in fractures of the humerus, when the head may not rotate under the deltoid on rotating the elbow. Similarly the head of the radius may not turn under the thumb when the shaft of the radius is fractured.

CHAPTER III

SIGNS AND SYMPTOMS OF FRACTURES

WITH the exception of spontaneous and fatigue fractures, a history of injury is always obtained, though in cases such as fracture of the neck of the femur, produced by a stumble, the injury may be very slight. In cases of fatigue fracture such as "march" fracture of a metatarsal there may be no history of injury, merely one of pain over a period of time.

PAIN is a prominent feature of all fractures unless the patient has some neurological lesion such as tabes, producing anaesthesia, or is hopelessly drunk. A sufficiency of alcohol may be quite efficient as an anæsthetic for fracture reduction.

The elicitation of pain may be important in examination. Compressing the thorax antero posteriorly may produce pain over the site of a fractured rib, and similarly the pressure backwards on both anterior superior iliac spines may give localised pain in fractures of the pelvis (Figs 218 and 449).

The localisation of the pain is always important, and in many cases is the main distinguishing feature between one fracture and the next. The general tenderness which is the usual accompaniment of the pain is of little value unless it can be localised. In the more superficial bones this localisation is of great value in diagnosing the site of the fracture, but it must be remembered that a subperiosteal hæmatoma is very tender, and may in certain cases cause legitimate confusion requiring an X-ray to distinguish it. In finding the point of maximum tenderness it is best to get the patient to localise it with one finger first, and then to follow that up with a careful one finger examination of the part.

SWELLING The degree of swelling varies with a number of factors. The site of fracture, the dependency of the part, the activity of the circulation, the amount of displacement, and the treatment, all influence it. It is particularly marked in elbow fractures where the tissues seem to leave space for a large effusion of blood, and in the femur where there is often gross displacement. It is less marked in fractures of the wrist and lower leg. In these latter situations, however, it assumes a greater importance, as, owing to the subcutaneous situation of the bones which occupy a great part of any transverse section of the limb at these levels, there is little room for expansion if the limb is placed in a complete plaster, and serious pressure may be produced. The avoidance of swelling is important as it interferes with the diagnosis, reduction, and more particularly

Retention of a fracture It must be combated at once by elevation and fixation of the part, and later may be dispersed by massage and effluage. Accompanying swelling and bruising fracture blisters are often seen. They are serous effusions, often blood-stained, between the dermis and epidermis. The more superficial the bone, and the larger the hematoma, the more likely these blisters are to occur. They take twelve to twenty-four hours to appear, but if the skin is supported by an unpadded plaster do not appear, though if this plaster is split they will appear along the line of cleavage.

Loss of function is a classical, but variable, sign. Impacted or green stick fractures may show little loss of function. A patient may walk on an abduction fracture of the neck of the femur, and it is an unfortunate commonplace that fractures of the spine are not recognised till the patient has walked for a few days thus compressing the fractured vertebra, and producing deformity.

Deformity This is another variable feature. It may be gross or only detectable by careful measurement. In compound fractures the wound may be considered as part of the deformity, and in it the fractured bone ends may be seen. Previous deformities from disease or accident must be considered.

Abnormal mobility In order to detect this one may have to inflict considerable pain, and on this ground alone it is often better neglected. In order to detect it one must have a knowledge of the normal degree of movement of joints, and one must where possible compare it with the intact limb, to allow for individual variations. Mobility may be excessive at a joint, or in one direction at a joint, or it may be detected at a point where there is no joint. This latter sign is certain evidence of fracture. The nearer the lesion is to a joint the more the abnormal mobility will be camouflaged by the normal joint movements, and the more difficult it is to determine.

A less emphasised point is the loss of mobility at certain joints such as the hip and shoulder after fracture in the vicinity. This is noted in impacted fractures where function is not entirely lost, and is due to several factors, the spasm of surrounding muscles from the pain, the irregularity of joint surfaces acting mechanically to prevent movement, and distension of the joint capsule from blood and synovial fluid.

Loss of transmitted movement from one part of a bone to another is certain evidence of fracture. It is commonly elicited in fractures of the humerus, when the head may not rotate under the deltoid on rotating the elbow. Similarly the head of the radius may not turn under the thumb when the shaft of the radius is fractured.

CREPITUS This is not such a useful sign as it sounds. The issue may be confused by other forms of crepitus, such as capsular crepitus, tenosynovitis, or that due to arthritis. Where the fracture involves cartilaginous surfaces it will not be felt, and the separation of an epiphysis will produce a soft crepitus from the friction of bone on cartilage. Unless there is some need for the information the elicitation of crepitus is to be avoided on account of the pain it produces.

The Examination of the Patient

This will include not only an evaluation of the points mentioned, but a careful examination of the whole of the body to exclude other lesions carried out in the following order:

- 1 **HISTORY** Of the present accident
Of past accidents or deformities
- 2 **INSPECTION** Comparison with the normal limb
- 3 **PALPATION** Comparison of bony points, etc.
- 4 **MENSURATION** Comparison of length or girth of the limb, and the use of special lines such as Nelaton's
- 5 **GENERAL EXAMINATION**
 - (a) For injuries to other parts of the limb
 - (b) For injuries elsewhere in the body
 - (c) To exclude associated disease
- 6 **SPECIAL EXAMINATION** X ray
 - (a) Plain
 - (b) Radiography under strain (Ruptures of ligaments)
 - (c) Tomography (Fractures of the spine)

It is quite possible to treat a fracture of the skull in an unconscious patient and overlook a fracture of the spine with no deformity. One has seen a fracture of the shaft of the femur on one side duly recognised while an impacted pertrochanteric fracture of the other side was missed. It is always advisable to examine the other joints and bones concerned in the transmission of the fracturing force to the trunk. Thus a Colles's fracture may be treated in a sling and the fact overlooked that at the same time an impacted fracture of the upper end of the humerus was present, with resultant permanent stiffness of the shoulder. The after treatment of a Colles's fracture should in any case avoid this, but all patients do not yet get adequate after treatment.

Radiography

The necessity to X ray the patient will have been decided by the previous examination, on one of the following grounds:

1 To establish accurate diagnosis of position and type in an undoubted fracture

2 To establish the diagnosis in a doubtful fracture

3 To produce evidence of absence of bony damage in medico-legal cases

4 At the request of the patient or another doctor

X rays produce the only detailed and accurate evidence of the lesion and are invaluable for reduction. No patient should be deprived of an X ray, because the condition can be diagnosed without it, if further treatment is contemplated. Without the assistance of a radiograph the doctor cannot be said to be exercising reasonable care in the handling of the case because he is not putting himself in possession of all the available facts, a prerequisite of "reasonable care." Certain fractures, such as that of the clavicle, require no X ray, or the private patient may be spared the expense, but the matter should be put to him, and if the accident is anything but domestic an X-ray should be taken for medico-legal purposes.

In the treatment of a fracture the following X-rays will be necessary

1 Films before reduction

2 Films after reduction, and after any further attempts if the first is not satisfactory

3 Films during retention

If by continuous traction As often as is necessary
Change of weight, position, or suspension demand it at least once weekly

If by fixation At the end of a week or earlier if there is likely to be displacement

Every time the plaster or retaining apparatus is changed

4 At the end of treatment

Certain variations of this will be found possible in minor fractures, but in a fracture such as the femur all the above-mentioned films will be necessary for efficient treatment

X-rays must fulfil certain conditions to be of full value in the assistance they offer. Unless the conditions set out below are adhered to the X ray may be more confusing than helping. The films must be accurately aligned antero-posterior and lateral views, and in certain fractures must be supplemented by oblique views. Unless the films are accurately taken in these directions it will be difficult to estimate the displacement in many cases. A film in one direction only may completely overlook displacement in another direction, and a second film at right angles to it is an absolute necessity, often for diagnosis, and always for correct orientation.

An oblique fracture without displacement may only show on one film as there will be no changes in bony density to record in an X-ray passing through it at right angles to the fracture line. In certain fractures it may be necessary to give the patient a local or general anæsthetic to place the limb in a suitable position for both X-rays, but though this is irksome it is a far more satisfactory way of solving difficulties than by taking stereoscopic X-rays.

The film must be of a suitable density and clarity to show the bony trabeculae or else a fine fracture will be overlooked. In order to check accurately the position of fractures of long bones the film must be of sufficient size to include the nearest joint, and it is often desirable to have a film including the joints at both ends of the bone. No X-rays should be taken before reduction without first removing strapping or metal splints as they may obscure important points. After reduction it may not always be possible to get the retentive apparatus out of the way but this should be attempted wherever possible. The translucency of plaster to X-rays is one of its great advantages.

Missed Fractures and Errors of Interpretation

Fractures are most commonly missed because on clinical examination it is thought unnecessary to X-ray the part. Such an error is

commonly seen in fractures of the spine where 70 per cent of cases are not diagnosed at the first examination. In this particular case the taking of an accurate history of the fall is all important as it will raise suspicion, which will demand a confirmatory X-ray.

The difficulties which may occur with X-rays have been mentioned above, oblique fractures only showing in one film or fractures of one bone being



FIG. 27 Well developed triangular fracture showing the features which distinguish it from a recent fracture

overlain by the shadow of another bone, and such like. Fine fractures in the small bones may only be detected by a hand lens. This may be noted in the carpal navicular. On the first examination the bone is regarded as normal but three weeks later on account of pain a further X-ray is taken. This may show some rarefaction in the bone along a definite fracture line. In such cases a careful examination of the first film will show a fine crack which has been over-

looked (Fig. 394). It must never be forgotten that the finding of one fracture does not preclude the presence of a second, and the whole of the film must be carefully searched.

The following may be mistaken for recent fractures:

1 The persistence of a fracture line from an old fracture of the skull.

2 The foramina of nutrient vessels, often prominent in the metacarpals.

3 Sesamoid bones. See Figs. 368, 619.

4 Accessory bones. See Figs. 27, 190, 537.

5 Old collapse fractures of the vertebrae.

6 Old ununited fractures, such as that of the ulnar styloid or navicular.

7 Small fragments of bone in the neighbourhood of osteoarthritic joints.

8 Last traces of the epiphyseal lines, and ununited secondary centres persisting (Figs. 561, 653).



FIG. 28. Old ununited fracture of the ulnar styloid showing well the thin layer of compact bone over the fractured surface and the smoothness of the surfaces distinguishing it from any recent fracture. A malunited Colles's fracture.

Careful history and examination of the films will exclude such lesions. Old fractures and sesamoid bones and accessory bones will show a rounded off margin, and a layer of condensed bone across the supposedly fractured surface. In recent fractures the fracture line is irregular, often soft or blurred in cancellous bone, or sharp and clear in compact bone.

NOTE. The inspection during the last two years of all the X rays taken in the Casualty Department and the nearby Fracture Clinic at the West London Hospital has enabled me to analyse the common errors in diagnosis among casualty officers. They may be grouped as follows:

	Per cent
1 Ignorance. Fractures seen significance not recognised	10
2 Over anxiety. Fracture diagnosed when none present	5
3 Failure to assess clinical signs and X ray case	20
4 Failure to see fracture in films	15
5 Fracture diagnosed on account of presence of old ununited fracture or other pathology	30
6 Failure to take adequate X rays	15
7 Administrative errors, patients departing without X rays, etc.	5

Supplementary Radiographs

The use of certain additional films may be of assistance in coming to a definite opinion in doubtful cases. These are summarised below.

1 The oblique view. The value of this in supplementing the usual antero-posterior and lateral views has been emphasised for the navicular. It is useful in other situations, either to show up a doubtful fissure by getting the central ray of the tube to coincide with the fracture, or by providing a new view point to clear up a doubtful fracture (*e.g.*, a fracture of an articular process in the spine).

2 Repeated films after the passage of a short time. This takes advantage of secondary changes in the fracture line, which may make it more distinct.

3 Radiographs of the opposite side where epiphyseal lines are suspect, or in unusual fractures.

4 Radiographs under strain. Occasionally of value where there is doubt of the firmness of union of long bones or the repair of ligaments. The bone may show bending or displacement under strain.

5 Radiographs in the position of deformity. This is chiefly of value in detecting the rupture of ligaments in the vicinity of joints, but may be useful in determining the presence of diastasis, or the severity of a sprain fracture.

6 Arthrography. Has little place in the treatment of fractures, but may be of value in the diagnosis of difficult lesions of the knee or ankle.

7 Tomography. This is of little value in superficial bones, but may be helpful in doubtful fractures of the spine.

REFERENCES

Joint Mobility

CAVE and ROBERTS. A Method for Measuring and Recording Joint Function. *J Bone and Joint Surg* 1936 18 455 (Forms the introductory chapter to "Scudder. Outlines the normal joint movements and their range and nomenclature").

Radiology

CLARK K. 'Positioning in Radiography'. London, Wm Heinemann 5th Edition 1950.

BRAILSFORD, J F. "The Radiology of Bones and Joints". London J & A Churchill 4th Edition 1949.

LYSHOLM E. 'Apparatus and Technique for the Roentgen Examination of the Skull'. Stockholm 1931.

CHAPTER IV

GENERAL PRINCIPLES OF TREATMENT

With succeeding years the principles of treatment of fractures have altered very little. Reduction, retention and re education have remained the three R's of the traumatic surgeon, but at different periods a different weight has been attached to the importance of each phase. Reduction has always been regarded as necessary except in certain fractures, and some old treatises on the subject contain much elaborate apparatus for the purpose, some crudely anticipating the apparatus now used. Retention and re education, however, have had a see saw existence through surgical history instead of balancing one another. In the years before Champoumire, the insistence on absolute fixation of the limb resulted in many stiff joints, a complication from which we are not entirely free to day. Champoumire substituted early movements and massage for this, and improved the results, so that till recently the removal of splints and massage was an essential part of the treatment. The importance of early and complete fixation in obtaining firm union has not been lost sight of, and it has been the struggle to unite the advantages of both methods, which has resulted in modern developments. While the battle of theory has had its usual ups and downs that of technique has shown a steady advance, and open operation and internal fixation, or skeletal traction with or without plaster, has enabled a better balance between retention and re education to be struck and maintained. To this has been added the more accurate reduction and control of retention made possible by X-rays.

We may summarise the principles of treatment thus

REDUCTION Immediate and accurate

RETENTION Continuous and absolute

RE EDUCATION Active, early, and persistent

We can now proceed to a fuller discussion of the principles which underlie reduction. This should not be carried out till shock has subsided and adequate retentive apparatus is at hand. Before this is possible there is a period in which the patient is in unskilled hands and further damage is liable to occur. The aim of first-aid treatment is to prevent this by the use of whatever is available to prevent movement and soiling of the injured limb, and combat the occurrence of shock. The importance of this emergency treatment was shown during the Great War, when the application of the

Thomas splint on the field to injuries of the leg reduced the mortality for such injuries from 80 to 15 per cent. The combating of shock falls more to the province of the doctor, and of primary importance is the relief of pain. Morphine is unsurpassed for this purpose in relieving the local pain, and the general psychological disturbance. Most effective in combating local pain is the injection of local anæsthetic into the fracture site. This is often a preliminary treatment and will be described in detail later on, but its effect on shock is startlingly satisfactory in many cases. Heat externally by a cradle or the use of hot-water bottles, and a hot drink of coffee, are other sound measures. The restoration of blood loss by transfusion is also important. Shock and its treatment are discussed more fully in Chapter V.

Reduction

The forces producing or maintaining displacement which may have to be overcome are

- 1 Gravity. This produces angulation as a rule.
- 2 The injury itself, if impacted or greenstick.
- 3 The force producing the injury.
- 4 The activities of assistants aiding the injured man.
- 5 Muscle spasm, producing shortening and angulation.

We will not discuss gravity further except to say that its effects must be constantly watched for. To avoid its effect in fractures of the leg Watson Jones has designed an ingenious extension apparatus for use with the leg dependant. In the more usual methods the tension needed to overcome shortening also overcomes sagging.

Disimpaction of the fracture is an essential to complete reposition of the fragments, and must be made before reduction is attempted. In certain cases, such as fracture of the upper end of the humerus, it may be unwise to disimpact.

The most important force to be overcome in correcting the displacement is muscle spasm. This may be overcome in various ways.

- 1 Slow traction without an anæsthetic.
- 2 A general anæsthetic.
- 3 A local anæsthetic.

The spasm being reflex it is partly abolished by the relief of pain, but some muscle tone will remain particularly in the lower limb. It is usually sufficiently abolished for traction to be successful if maintained long enough, i.e., two to three minutes. The length of time necessary for traction is overestimated in most books.

4 The relaxation of the muscles by positioning the limb. Flexion of the knee relaxes the gastrocnemius and enables shortening of the

leg to be pulled out at the same time the muscles are slightly increased in bulk, and it is difficult to apply a plaster with a tight-fitting upper end. For the first plaster in which weight bearing is not as a rule desired, this is unimportant.

5 **Curare** Where reduction has to be achieved and maintained by traction over a long period, *e.g.*, in certain cases of fractured femur, the use of curare (5 cc. of D. tubo curarine, repeated), has occasionally been found helpful.

In order to place traction on any limb arrangements must be made for counter traction. In general these consist of placing a sling around the body or limb being pulled upon, and attaching this to a hook in the wall, so that it will exert a pull in the opposite direction. In other cases the body may be used as a fixed point against which the limb may be extended, such as the extension of a femur against a perineal bar on the orthopedic table. In certain cases of skeletal traction accurate control may only be obtainable by the use of a second pin or Kirschner wire for counter traction. Where continuous traction is used the body is used for counter-traction, by elevating the bed.

In reduction one has to correct

1 **SHORTENING** By traction

2 **ANGULATION** By the direction of traction and manipulation

3 **LATERAL DISPLACEMENT** Traction by increasing the tension in the tissues exerts some lateral pressure, but manipulation is most important

4 **ROTATION** By correcting the position of the limb

Immediate reduction has the following advantages

1 It reduces the size of the hæmatoma

2 It limits and reduces reactionary swelling

3 It removes pressure from soft parts, particularly blood vessels and skin

4 It relieves the patient of pain

5 It can usually be more easily accomplished as the bony points are not obscured by swelling, and the tissues are laxer

Delayed reduction may be necessary for the following reasons

1 The presence of shock

2 The necessity for the treatment of associated injuries first

3 The presence of infection

4 The absence of retentive apparatus

5 Because the method of retention combines slow reduction of the fracture by traction

There are only four methods of reduction to choose from, each suitable to individual cases, and they may be combined to meet various difficulties

MANIPULATION
WEDGING THE PLASTER
CONTINUOUS TRACTION
OPERATIVE METHODS

The choice of method and its application to individual fractures is the theme of the special section of this book.

Retention

The demands made on retentive apparatus are as follows

- 1 That it should produce absolute fixation
- 2 That it should limit movement of the undamaged structure to a minimal degree
- 3 That it should allow the examination of wounds by vision and of the bones by X rays
- 4 That it should be adaptable to various lesions, and, if possible to various sites

These demands are best fulfilled by plaster of Paris, which is being used in increasing amounts in modern methods. Certain fractures require other splintage to control them, and the most important point in determining this is the type of fracture, whether it is oblique, transverse, or comminuted.

Helical or spiral fractures Here the deforming force has been a rotatory one. The displacement in a lateral direction is minimal. On the other hand there is nothing to counteract the pull of muscles tending to shorten the limb, and this must be overcome by continuous traction or fixed distraction. There is also some risk of angulation even in the case of fracture of the tibia with the fibula intact. The shape of the fractured surfaces in a helical fracture often render perfect reduction by ordinary means impossible, if there is any displacement. Perfect reduction and retention are easily accomplished by one or two screws which combine the insertion of a foreign body of minimal size with the attainment of sufficient stability for early exercises.

Oblique and half oblique—transverse fractures These two types of fracture have already been shown (Fig. 6) to be variants of the transverse fracture due to bending violence. The third variant is the "butterfly" fracture in which a single triangular comminuted fragment is produced. All three types show a tendency to shortening and angulation. They are readily, but not perfectly, reduced by traction and manipulation, and retained by traction or distraction. All three lend themselves to fixation with a single or double screw or plating.

Comminuted fractures These suffer the disadvantage mentioned above together with the further disability that lateral movements can occur as there are no interlocking fixed points to prevent it.

Treatment by traction must be supplemented by some form of lateral support, from a splint or from plaster of Paris. If operative treatment is contemplated, a plate, longer than the length of the comminuted fragments, must be employed.

Transverse fractures If the ends can be maintained opposite one another, or reduced so that they engage, there is no fear of shortening. Angulation and rotation only need be feared, and these are best controlled by plaster. In the thigh the muscle bulk makes lateral control difficult, and extension must be used to supplement it. The average transverse fracture is best treated by manipulation and plaster, though some, such as the femur, may require operative fixation.

Retention will also depend on the limb involved, whether upper or lower. In the arm shortening is unimportant, but angulation is important. In the leg shortening and angulation are both very important. Oblique fractures of the leg cannot be allowed to bear weight early owing to the risk of deformity due to the body weight. A transverse fracture can be allowed to bear weight earlier as shortening cannot occur, and lateral control is easier to maintain. Oblique fractures tend to unite more rapidly than transverse fractures, and fractures near the ends of the bones sooner than fractures in the mid-shaft, which influences the time it is necessary to maintain retention.

Traction Emphasis must be laid on the fact that the primary purpose of traction is reduction, and not retention. It is now recognised that skeletal traction has increased the number of ununited fractures. This statement indicates that the great forces available when using skeletal traction have been misapplied, and used for retention or over reduction. Correctly used, skeletal traction is the greatest single blessing provided by the beneficence of "modern technique." It is appropriate here to outline the relative merits of skin and skeletal traction.

DISADVANTAGES OF SKIN TRACTION

- 1 It gives slowly and so requires repeated renewals
- 2 It is painful
- 3 It produces a crop of skin pustules on certain skins
- 4 It covers a large area of skin and so prevents inspection and cannot be applied over abrasions
- 5 It is inaccurate in alignment and cannot be used to control rotatory displacements
- 6 It will only stand a limited weight. In children in whom the skin area relative to the weight is larger this may be unimportant. (See Bryant's method, p. 487.)

ADVANTAGES OF SKELETAL TRACTION

- 1 It is accurate and non-slipping
- 2 It is painless
- 3 It leaves the skin free for inspection, or the application of plaster

- 4 It will take great weights
- 5 Rotatory deformities can be corrected by it
- 6 Its incorporation in the plaster may aid in retention

DISADVANTAGES OF SKELETAL TRACTION

1 The entry and exit wounds of the wire may become infected leading to osteomyelitis. In practice this is rare if care is taken to see that the wire does not rotate in its bed and the skin around the puncture wounds is supported by light pressure to prevent movement and soiling.

2 The method allows long continued traction through joints to be made, with disastrous results to the joint, whose ligaments are stretched, and relaxation is followed by an effusion and subsequent stiffness. Traction should never be made through joints for longer than two to three weeks, and never with great weight.

3 Over reduction and non union are the results of misuse.

4 It cannot be used in young children, owing to the risks of perforating the growing ends of bones, and the fact that the wire cuts out of the soft bone.

Re-education

This is perhaps the most important feature of modern methods. The reduction and retention of a Colles's fracture in an old woman may be perfect, but unless she is instructed to move her fingers and shoulder, and care is taken to see that she does it, she may develop permanent stiffness of the hand and shoulder as a result. The same applies to fractures elsewhere. The exercise of the patient and his co-operation in such exercises is extremely important, and with experience it is quite possible to forecast the duration of a patient's stay in a fracture clinic from his mental make up. An active and interested patient who is not afraid of a little discomfort and "prepared to try anything once" will recover the functional use of the limb in almost half the time it takes a nervous, melancholy and apprehensive patient. The engendering of interest, the encouragement of the patient, and the development of an attitude of confidence is the duty of the doctor. One of the best methods of achieving this is the spirit of competition aroused by competitive exercises with other patients with the same lesion. The association of a fracture clinic with a cheerful gymnasium in which the patient can exercise and be exercised is an essential for good results.

Exercises can be discussed under the general exercises possible to recumbent and ambulatory patients, and the special exercises designed to fit in with the methods of immobilisation of special fractures. In a word almost all patients can be put through general exercises together, special attention then being given to the injured limb. In a forearm plaster the fingers must be carefully exercised, care being taken that they are not prevented by the plaster from going through their full range of movements. The importance of the patients using the muscles of the injured limb and not the fingers of the opposite limb to do this can be brought home by

suggesting that "it is to keep the circulation going beneath the plaster" Exercises to the elbow and the shoulder are deliberately given

Walking is the best exercise in a leg plaster, but the patient is told to move his toes as much as he can, and is given exercises to the knee and hip In plaster jackets general exercises can be done In order to encourage the patient to keep moving, any form of indoor sport may be encouraged Billiards, darts, ping-pong and the punching ball are all valuable adjuncts to more deliberate drill

Some suitable exercises for various plasters will be found in the Appendix of the book

Rehabilitation

It has become clear in recent years that an academic interest in re education alone is not sufficient in an industrialised community to give the maximum return of useful labour in the minimum time following accidents The vast majority of accidents are industrial, or affect the industrial machine indirectly In a nation on a war footing it has become still more important that every available man-hour of labour should be used, and the problems of rehabilitation have therefore been studied more intently and under better statistical conditions in the last few years The problem is a threefold one —

- 1 Physical medicine, the scientific application of measures to restore physical fitness,
- 2 Psychological, the problem of obtaining the patient's co-operation and stimulating the desire to return to normal life,
- 3 Sociological, (a) as it affects the patient — relief from personal financial worries during treatment and a guarantee of employment on recovery, (b) as it affects the community — financing and organising a rehabilitation centre for the area

REHABILITATION IN A HOSPITAL in its widest sense embraces every activity and relationship of the patient while undergoing treatment The stimulating atmosphere of the ward, the relief of the patient's mental anxieties, the quality and regularity of his meals, and the occupations of his spare time are as much the concern of the Rehabilitation Officer, and the patient's own doctor, as the efficiency of the massage staff, the quality of his ward sisters, the provision of adequate exercise space, and the mental drive of the physical training instructor All must be co-ordinated into a harmonious whole, in which the confidence of the patient is echoed in the confidence of those around him and his instinctive desire to recover is fostered and encouraged by all means

REHABILITATION OUTSIDE THE HOSPITAL is often left to the

Almoner, but is as much the concern of the Surgeon as his Ward Round. The atmosphere to which the patient returns on discharge from in-patient treatment, or in which he has to spend his time during out patient treatment, may be quite inimical to his morale, and undo any good done by a short attendance at the hospital waiting to have something "done". It is the conviction that he must do something for himself, that in fact it is almost entirely what he does himself, and not what is done for him, which is important, that must be driven home.

The complexity of the problem and the complete absorption of the patient's time, interest and energy which good rehabilitation demands, makes the combination of acute traumatic surgery and rehabilitation in the one ward difficult. High spirits and energy should not be restrained by a seriously ill case. Rehabilitation commences in the acute ward, but graduates to a stage when the atmosphere of the ward is unsatisfactory for both the bed patient and the ambulant. Further, the routine of the ward conflicts with the routine of rehabilitation exercises and for these reasons it is desirable to separate them. If they cannot be sent to a specially equipped centre they can be segregated in another part of the hospital to which they can graduate as they recover. The most satisfactory results are achieved by a country rehabilitation centre.

The problems of the centre not only include those of staffing, space, feeding and therapy, but the problem of the patient himself. It is still the conviction of many that they go to hospital to be made well, and not to make themselves well. The attainment of the patient's confident belief that the methods recommended are for his own benefit is of the utmost importance. Nothing can be done to rehabilitate a man without his co-operation, and to encourage and develop this is the first care of the staff.

REHABILITATION IN THE WARDS We concern ourselves here particularly with the patients whose confinement to bed limits their range of activities. As soon as is appropriate they are sent to the Rehabilitation Centre, as the first big step in their recovery. The ward morale is dependent on everyone, doctors, sisters, nurses and patients alike, but its tone is set from the top. The tidy ward, the regular routine, the firm convictions of the staff, are breathed in from the moment of the patient's arrival. No more responsive wards are to be found in a hospital than those of a Fracture Unit, where the mental tone of the patient is in the vast majority of patients unimpaired.

Physical therapy in the wards fall into two compartments —

(a) Special exercises, e.g., to fingers and toes, shoulder and knee of a limb immobilised by treatment.

(b) General exercises to the remainder of the body free of restraint, which can be undertaken by the ward as a whole, or in convenient groups, e.g., upper limb injuries, lower limb injuries

In the first group there is considerable scope for inventive imagination in the design of retentive apparatus which allows the maximum freedom, and the invention of exercises to take full advantage of this. A special orderly of suitable personality should be trained in these exercises and spend most of his time in the ward instructing and encouraging patients. The patient should be reminded by a two hourly bell that they are expected to devote the next ten minutes to their exercises. The more general class exercises may be carried out twice a day.

Occupational therapy In many cases this may begin in the ward. Its three aspects are discussed more fully under therapy at the Rehabilitation Centre.

Recreational therapy This is important in the ward where interests are restricted and can be introduced in many ways. The occupational therapist may be able to devote some time to patients not specifically requiring her attention. Adequate library facilities, the organisation of educational groups, cinema shows in the wards and other entertainments are of great value. More important than entertainment given is entertainment made by the men themselves. Discussion groups, small concert performances, or the production of a ward column in the hospital news sheet, may help. Not to be forgotten are the various routine jobs of the ward suitable for untrained workers, and which, being actually of use, may be more stimulating to the right person than many cleverly contrived but useless amusements.

REHABILITATION IN THE SPECIAL CENTRE The Centre may be provided by the hospital gymnasium with some ancillary rooms, but is preferably a small separate institution of around 150 beds. Here all the modern methods of physical re-development are available. Patients may be living in the centre, or attend daily, but the importance of a fully occupied day at the centre must be stressed. The patient must do a full time course. If only trained for a few hours a day his return to his ordinary way of life for the rest of the twenty four hours may effectively undo any mental or physical benefit achieved.

The distribution of the men's time at such a centre is important and needs considerable clerical assistance. Each man should be given a weekly time table of the classes to be attended and his improvement and graduation from class to class should be recorded. The following departments of the centre should be fully harmonised.

1 *Physiotherapy* This is useful in starting off patients with stiff

Almoner, but is as much the concern of the Surgeon as his Ward Round. The atmosphere to which the patient returns on discharge, from in-patient treatment, or in which he has to spend his time during out-patient treatment, may be quite inimical to his morale, and undo any good done by a short attendance at the hospital waiting to have something "done". It is the conviction that he must do something for himself, that in fact it is almost entirely what he does himself, and not what is done for him, which is important, that must be driven home.

The complexity of the problem and the complete absorption of the patient's time, interest and energy which good rehabilitation demands, makes the combination of acute traumatic surgery and rehabilitation in the one ward difficult. High spirits and energy should not be restrained by a seriously ill case. Rehabilitation commences in the acute ward, but graduates to a stage when the atmosphere of the ward is unsatisfactory for both the bed patient and the ambulant. Further, the routine of the ward conflicts with the routine of rehabilitation exercises and for these reasons it is desirable to separate them. If they cannot be sent to a specially equipped centre they can be segregated in another part of the hospital to which they can graduate as they recover. The most satisfactory results are achieved by a country rehabilitation centre.

The problems of the centre not only include those of staffing, space, feeding and therapy, but the problem of the patient himself. It is still the conviction of many that they go to hospital to be made well, and not to make themselves well. The attainment of the patient's confident belief that the methods recommended are for his own benefit is of the utmost importance. Nothing can be done to rehabilitate a man without his co-operation, and to encourage and develop this is the first care of the staff.

REHABILITATION IN THE WARDS We concern ourselves here particularly with the patients whose confinement to bed limits their range of activities. As soon as is appropriate they are sent to the Rehabilitation Centre, as the first big step in their recovery. The ward morale is dependent on everyone, doctors, sisters, nurses and patients alike, but its tone is set from the top. The tidy ward, the regular routine, the firm convictions of the staff, are breathed in from the moment of the patient's arrival. No more responsive wards are to be found in a hospital than those of a Fracture Unit where the mental tone of the patient is in the vast majority of patients unimpaired.

Physical therapy in the wards fall into two compartments —

(a) Special exercises, e.g., to fingers and toes, shoulder and knee of a limb immobilised by treatment.

the P T instructor. Apart from providing a fresh and pleasant way of taking exercise, they have valuable sociological aspects.

3 *Occupational therapy* This takes three forms —

- (a) *Diversional therapy* To maintain patients' interest during tedious periods, and to improve morale and allay anxiety.
- (b) *Functional therapy* Activities specially designed to exercise certain joints and muscles.
- (c) *Pre vocational therapy* Preparation of the disabled for return to his old occupation, or the selection and training for a suitable job if that is out of the question.

It will be appreciated that diversional therapy is particularly needed for the recumbent patient, but that organised games which may be considered a part of P T may also come under this heading. There are a wide variety of communal occupations which for their sociological and character developing potentialities should be included in any complete scheme for rehabilitation. These include dancing, dramatics, debating, formation of small orchestras, publication of a news sheet and the like.

Time cannot be spent here on functional therapy, where great ingenuity can be used in designing exercises to develop specific muscles, or movements. In particular, the employment of the hands in fretwork, weaving, basket work, knotting, leather work, carpentry, etc., is of great importance. The large representation of the hand in the cortex makes it inevitable that many paths of association must be rendered useless in any serious injury, and these can only be replaced by fresh ones by constant application. Suppleness and muscle tone are improved at the same time.

Pre vocational therapy is of extreme importance in an industrialised community. It is only suitable for use at the Special Centre. It demands the development of a close relationship with the employer and the Industrial Medical Officer. Centres have been developed for single industries, in particular mining, where the demands made by the work on the individual are extremely variable, and considerable experience is necessary of the various special jobs inside the industry to return men to suitable employment. In smaller and more specialised industries the industry itself has set apart floor space where its employees can return to work under less exacting conditions and harden themselves for their old job or adapt themselves to new ones. The light engineering workshop is particularly suitable for a graded return to work. Machine tools can be found or adapted to a wide variety of movements of hand or arm, and adjusted to exercise particular muscles. All three variations in muscular activity can be easily achieved, and the stimulation of

joints and limbs, and particularly in the care of cases of nerve injury. It is valuable, but insistence must be made on active voluntary exercises, and the patient made to realise that physiotherapy is only to facilitate this.

For instance, the quadriceps can be best exercised by voluntary contraction which should be taught in preference to the use of Faradism. The vastus medialis, however, can contract only if the knee will finally extend, and screw home, and this condition is not present in the early phases of treatment of most cases of knee injury. It follows that Faradism should be applied in the early stages to the vastus medialis only and the rest of the muscle exercised by voluntary quadriceps contraction. The value of physiotherapy radiant heat, short wave therapy, and diathermy is chiefly to promote relaxation and increased blood supply, which allows an increased range of voluntary movement and promotes absorption of exudates.

2 *Physical training instruction* This is probably the most important single element in rehabilitation, increasing general bodily well-being as well as the muscular power of the affected limb. Classes may be grouped in varying ways, according to the part of the body affected (a) Upper limb injuries, (b) Lower limb injuries, (c) Spinal injuries, (d) Special cases, or according to the severity of the exercises. Obviously the type of cases passing through the centre will govern the arrangement of classes. The fundamental factors governing the progress of the patient is his response to exercises which make increasing demands on his strength. Exercises may be increased in

- (a) Range of movement
- (b) Strength of resistance to effort
- (c) Duration of activity

These three variables are employed in varying proportions to suit each case firstly with regard to general physique, and again with regard to each joint being specially exercised. All activities are alternated with periods of rest and relaxation. Thus in exercising a joint it is not sufficient for the limb merely to come to the end of its range of movement and then retrace its movement under continuous muscle tension. At each end of the range of motion there should be a dead spot, where the resistance is removed entirely, and a period of relaxation given. In pulley and weight exercises this can be arranged easily by suitable knots in the cords, or the introduction of stops against which the weight or limb comes to rest.

The organisation of outdoor and indoor games which add the zest of the competitive spirit to exercises is usually the province of

the P.T. instructor. Apart from providing a fresh and pleasant way of taking exercise, they have valuable sociological aspects.

3. *Occupational therapy*. This takes three forms —

- (a) *Diversional therapy*. To maintain patients' interest during tedious periods, and to improve morale and allay anxiety.
- (b) *Functional therapy*. Activities specially designed to exercise certain joints and muscles.
- (c) *Pre-vocational therapy*. Preparation of the disabled for return to his old occupation, or the selection and training for a suitable job if that is out of the question.

It will be appreciated that diversional therapy is particularly needed for the recumbent patient, but that organised games which may be considered a part of P.T. may also come under this heading. There are a wide variety of communal occupations which for their sociological and character developing potentialities should be included in any complete scheme for rehabilitation. These include dancing, dramatics, debating, formation of small orchestras, publication of a news sheet and the like.

Time cannot be spent here on functional therapy, where great ingenuity can be used in designing exercises to develop specific muscles, or movements. In particular, the employment of the hands in fretwork, weaving, basket work, knotting, leather work, carpentry, etc., is of great importance. The large representation of the hand in the cortex makes it inevitable that many paths of association must be rendered useless in any serious injury, and these can only be replaced by fresh ones by constant application. Suppleness and muscle tone are improved at the same time.

Pre-vocational therapy is of extreme importance in an industrialised community. It is only suitable for use at the Special Centre. It demands the development of a close relationship with the employer and the Industrial Medical Officer. Centres have been developed for single industries, in particular mining, where the demands made by the work on the individual are extremely variable, and considerable experience is necessary of the various special jobs inside the industry to return men to suitable employment. In smaller and more specialised industries the industry itself has set apart floor space where its employees can return to work under less exacting conditions and harden themselves for their old job or adapt themselves to new ones. The light engineering workshop is particularly suitable for a graded return to work. Machine tools can be found or adapted to a wide variety of movements of hand or arm, and adjusted to exercise particular muscles. All these variations in muscular activity can be easily relieved, and the stimulation of

joints and limbs, and particularly in the care of cases of nerve injury. It is valuable, but insistence must be made on active voluntary exercises, and the patient made to realise that physiotherapy is only to facilitate this.

For instance, the quadriceps can be best exercised by voluntary contraction which should be taught in preference to the use of Faradism. The vastus medialis, however, can contract only if the knee will finally extend, and screw home, and this condition is not present in the early phases of treatment of most cases of knee injury. It follows that Faradism should be applied in the early stages to the vastus medialis only and the rest of the muscle exercised by voluntary quadriceps contraction. The value of physiotherapy radiant heat, short wave therapy, and diathermy is chiefly to promote relaxation and increased blood supply, which allows an increased range of voluntary movement and promotes absorption of exudates.

2 Physical training instruction This is probably the most important single element in rehabilitation, increasing general bodily well-being as well as the muscular power of the affected limb. Classes may be grouped in varying ways, according to the part of the body affected: (a) Upper limb injuries, (b) Lower limb injuries, (c) Spinal injuries, (d) Special cases, or according to the severity of the exercises. Obviously the type of cases passing through the centre will govern the arrangement of classes. The fundamental factors governing the progress of the patient is his response to exercises which make increasing demands on his strength. Exercises may be increased in

- (a) Range of movement
- (b) Strength of resistance to effort
- (c) Duration of activity

These three variables are employed in varying proportions to suit each case firstly with regard to general physique, and again with regard to each joint being specially exercised. All activities are alternated with periods of rest and relaxation. Thus in exercising a joint it is not sufficient for the limb merely to come to the end of its range of movement and then retrace its movement under continuous muscle tension. At each end of the range of motion there should be a dead spot, where the resistance is removed entirely, and a period of relaxation given. In pulley and weight exercises this can be arranged easily by suitable knots in the cords, or the introduction of stops against which the weight or limb comes to rest.

The organisation of outdoor and indoor games which add the zest of the competitive spirit to exercises is usually the province of

the P T instructor. Apart from providing a fresh and pleasant way of taking exercise, they have valuable sociological aspects.

3 *Occupational therapy* This takes three forms —

- (a) *Diversional therapy* To maintain patients' interest during tedious periods, and to improve morale and allay anxiety.
- (b) *Functional therapy* Activities specially designed to exercise certain joints and muscles.
- (c) *Pre vocational therapy* Preparation of the disabled for return to his old occupation, or the selection and training for a suitable job if that is out of the question.

It will be appreciated that diversional therapy is particularly needed for the recumbent patient, but that organised games which may be considered a part of P T may also come under this heading. There are a wide variety of communal occupations which for their sociological and character developing potentialities should be included in any complete scheme for rehabilitation. These include dancing, dramatics, debating, formation of small orchestras, publication of a news sheet and the like.

Time cannot be spent here on functional therapy, where great ingenuity can be used in designing exercises to develop specific muscles, or movements. In particular, the employment of the hands in fretwork, weaving, basket work, knotting, leather work, carpentry, etc., is of great importance. The large representation of the hand in the cortex makes it inevitable that many paths of association must be rendered useless in any serious injury, and these can only be replaced by fresh ones by constant application. Suppleness and muscle tone are improved at the same time.

Pre vocational therapy is of extreme importance in an industrialised community. It is only suitable for use at the Special Centre. It demands the development of a close relationship with the employer and the Industrial Medical Officer. Centres have been developed for single industries, in particular mining, where the demands made by the work on the individual are extremely variable, and considerable experience is necessary of the various special jobs inside the industry to return men to suitable employment. In smaller and more specialised industries the industry itself has set apart floor space where its employees can return to work under less exacting conditions and harden themselves for their old job or adapt themselves to new ones. The light engineering workshop is particularly suitable for a graded return to work. Machine tools can be found or adapted to a wide variety of movements of hand or arm, and adjusted to exercise particular muscles. All three variations in muscular activity can be easily relieved and the stimulation of

joints and limbs, and particularly in the care of cases of nerve injury. It is valuable but insistence must be made on active voluntary exercises, and the patient made to realise that physiotherapy is only to facilitate this.

For instance, the quadriceps can be best exercised by voluntary contraction which should be taught in preference to the use of Faradism. The vastus medialis, however, can contract only if the knee will finally extend, and screw home, and this condition is not present in the early phases of treatment of most cases of knee injury. It follows that Faradism should be applied in the early stages to the vastus medialis only and the rest of the muscle exercised by voluntary quadriceps contraction. The value of physiotherapy radiant heat, short wave therapy, and diathermy is chiefly to promote relaxation and increased blood supply, which allows an increased range of voluntary movement and promotes absorption of exudates.

2 *Physical training instruction* This is probably the most important single element in rehabilitation, increasing general bodily well being as well as the muscular power of the affected limb. Classes may be grouped in varying ways, according to the part of the body affected. (a) Upper limb injuries, (b) Lower limb injuries, (c) Spinal injuries, (d) Special cases, or according to the severity of the exercises. Obviously the type of cases passing through the centre will govern the arrangement of classes. The fundamental factors governing the progress of the patient is his response to exercises which make increasing demands on his strength. Exercises may be increased in

- (a) Range of movement
- (b) Strength of resistance to effort
- (c) Duration of activity

These three variables are employed in varying proportions to suit each case firstly with regard to general physique, and again with regard to each joint being specially exercised. All activities are alternated with periods of rest and relaxation. Thus in exercising a joint it is not sufficient for the limb merely to come to the end of its range of movement and then retrace its movement under continuous muscle tension. At each end of the range of motion there should be a dead spot, where the resistance is removed entirely, and a period of relaxation given. In pulley and weight exercises this can be arranged easily by suitable knots in the cords, or the introduction of stops against which the weight or limb comes to rest.

The organisation of outdoor and indoor games which add the zest of the competitive spirit to exercises is usually the province of

CHAPTER V

THE IMMEDIATE COMPLICATIONS OF FRACTURES

General

- 1 Shock
- 2 Traumatic fever
- 3 Hemorrhage (See injuries to vessels)
- 4 Fat embolism
- 5 Delirium
- 6 Bronchopneumonia

Local Due to injury to structures surrounding the bone

- 7 Injury to nerves (Crushing, contusion, concussion, stretching division)
- 8 Injury to vessels (Arteries and veins)
- 9 Injuries to joints
- 10 Injuries to viscera
- 11 Injuries to soft tissues, muscles tendons and skin Discussed under compound fractures

Shock Shock is a condition of depressed vital functions which supervenes on injury after a variable period. Its ætiology is not yet entirely clear, but one important established factor is a general anoxæmia due to disturbed respiratory and circulatory functions. The degree of shock is governed more by the amount of soft tissue damage than the site of fracture.

Shock varies from individual to individual. Highly strung people are more susceptible to the condition. The general health of the patient before the accident, and whether or not he was tired out or hungry also affects his susceptibility. As the pathology of the condition is not yet clear, it is most convenient to discuss shock under the clinical features.

1 *Pain* Painful stimulation of a peripheral nerve will produce a fall in the blood pressure, and this will aid the general reduced oxygenation of the tissues which is a principal factor in the condition. In this connection it is to be noted that great excitement induces a relative anæsthesia. Not till the excitement passes off does shock supervene with the onset of the pain.

The most generally useful anodyne will be found to be morphia given in $\frac{1}{4}$ -grain doses. Local anæsthesia into the fracture is a valuable aid. Early first aid fixation of the fracture is also important.

2 *Temperature* A low temperature is an invariable accompaniment of any degree of shock. It appears to be secondary to a loss of circulatory balance, which results in failure of the skin circulation.

producing something really useful may do much for the patient's morale

SPECIMEN TIME TABLE OF A SPECIAL REHABILITATION CENTRE

Hour	Occupation
0730	Reveille
0800	Breakfast
0830	Bed exercises for recumbent patients Non weight-bearing exercises attended by weight bearing patients
0900	Individual special exercises Class gymnastic games Prevocational Therapy
1000	Break Hot drink
1030	Parade Inspection Complaints Suggestions
1045	General Physical Training
1130	Games Non organised Ping pong, darts, billiards, etc Walk for progressing patients Run, for hardening patients
1230	Lunch Rest period for new and weaker patients
1400	Parade Bed exercises for recumbent patients Organised games
1500	Non weight-bearing } P T Classes, separate Weight-bearing }
1530	Rest period
1545	Tea
1630	Quadriceps Class Occupational Therapy Diversional Therapy
1900	Free time
1900	Supper
1945	Parade Night roll
2000	Entertainment Concert, cinema, ping pong tournament, housey housey, debate, lecture, etc
2130	Hot drink
2200	Lights out

REFERENCES

General

- BOHLER, L "Treatment of Fractures" English edition Edited by E W Hey Groves Bristol 1936 p 2
- BROWNLOW MITCHELL "Spiral Fractures" Robert Jones Birthday Volume 1928, p 189
- PERKINS, G "Fractures in the Region of the Shoulder," *Proc Roy Soc Med*, 1936, 29, 1055
- British Medical Association 'Report of Committee on Fractures' London, February, 1935
- HEY GROVES, E W "Skeletal Traction in the Treatment of Fractures" *Brit J Surg*, 1928, 16 155
- PERKINS, G "Rest versus Activity in the Treatment of a Fracture" *Lancet* 1947, 1, 49-54

has the advantages of being readily determined at the bedside and easily recorded. Nevertheless, taken alone, it may be a source of error, as in the early stages of shock (i.e., within two hours) the blood pressure may be raised, and rare cases are met with in which it is high throughout the whole clinical course. With the development of the full picture of shock (delayed or secondary shock) the blood pressure falls and may be impossible to record. As a general level below which the condition becomes more and more serious, and above which the prognosis is more and more hopeful, the figure of 90 mm may be remembered. No case should be taken to the theatre with a blood pressure below this level unless circumstances force it. Pulse pressure is difficult to determine in the shocked owing to the undefined diastolic sounds. Its easy determination and normal level (45 mm) is a valuable sign of recovery.

6 *Hæmorrhage* Small losses of blood which can be readily made up by contraction of the spleen and peripheral vascular tree are of little importance. When the bulk of fluid lost is sufficient to require the withdrawal of considerable tissue fluid to make up the volume necessary for circulation, shock is induced as a result of blood loss alone. The remaining red cells are slowly diluted by the tissue fluids and concentrated by vasoconstriction in the essential organs. The administration of plasma may do actual harm. In most cases of injury, hæmorrhage and shock are combined in varying proportions. A clinical estimate of the amount of blood lost should always be attempted, based on the amount of blood visible, the severity of the anæmia, and the size of the vessels injured.

7 *Hæmoconcentration* In shock without hæmorrhage hæmoconcentration develops in a few hours' time. In burns the combination of loss of plasma into the tissues and on the burnt surface results in very high figures for percentage hæmoglobin being achieved. In pure hæmorrhage the percentage hæmoglobin is reduced as tissue fluids are absorbed into the vascular system. In the usual mixed lesion due to wounds the accurate determination of the percentage hæmoglobin in the first few hours is not of much clinical value, though as a guide for later transfusion it may be valuable. All cases with a percentage hæmoglobin below 60 should be transfused and a level of 80 per cent maintained if possible.

8 *Toxæmia* The role of tissue products of the histamine type in shock is still debated. The recent elucidation of the crush syndrome shows the important effect of myohæmoglobin in disturbing physiology. It is probable that histamine products play a certain part in the production of shock but that the vicious circle to which they contribute, gains its chief momentum from its own interactions (Fig. 29).

to respond in the normal manner to changes in external temperature, and an actual decrease in heat production due to deficient oxygenation. To this, disturbance of the heat regulating centre may be added. There is thus a marked susceptibility to cold and the avoidance of heat loss forms an essential part of treatment. A warm room, hot bottles or a heat cradle, and warm drinks are simple but important measures to combat a fall of temperature. It is to be noted that excessive heat is as dangerous by producing vaso dilatation and sweating as cold, and in no case should the patient be hurried to perspiration point. The cold sweat which is a variable accompaniment of shock does not come under this consideration, and is frequently localised to the face.

3 *Colour* This is an unreliable guide to the patient's condition, except that satisfactory return of colour may be regarded as a sign of recovery. Pallor is due to peripheral vaso constriction, but it is




FIG. 29 The vicious circle of shock.

difficult to determine whether this is of central origin, in an endeavour to maintain blood pressure and volume, or peripheral spasms due to heat loss and external cold. Cyanosis, indicating anoxæmia, is significant of the severity of the condition but may be due to many causes, or combinations of causes (Fig. 29). As indicated under treatment, it should be rigorously combated.

4 *Pulse rate* This is extremely variable. Of most importance is the general impression given by the pulse where clinical acumen sums up variations in vascular tone, circulating volume, blood pressure and pulse pressure. The whole tone of the vascular tree is thus sampled by the index finger. A rapid fluttering pulse is serious, and is usually combined with a low blood pressure as recovery sets in the pulse slows and the blood pressure rises. Exceptional cases with a slow pulse and low blood pressure are met with.

5 *Blood pressure* The observation of the systolic and diastolic pressure and of the difference between them (pulse pressure) is perhaps the most useful single guide to the condition of the patient. It

has the advantages of being readily determined at the bedside and easily recorded. Nevertheless, taken alone, it may be a source of error, as in the early stages of shock (i.e., within two hours) the blood pressure may be raised, and rare cases are met with in which it is high throughout the whole clinical course. With the development of the full picture of shock (delayed or secondary shock) the blood pressure falls and may be impossible to record. As a general level below which the condition becomes more and more serious, and above which the prognosis is more and more hopeful, the figure of 90 mm. may be remembered. No ease should be taken to the theatre with a blood pressure below this level unless circumstances force it. Pulse pressure is difficult to determine in the shocked owing to the undefined diastolic sounds. Its easy determination and normal level (45 mm.) is a valuable sign of recovery.

6 *Hæmorrhage* Small losses of blood which can be readily made up by contraction of the spleen and peripheral vascular tree are of little importance. When the bulk of fluid lost is sufficient to require the withdrawal of considerable tissue fluid to make up the volume necessary for circulation, shock is induced as a result of blood loss alone. The remaining red cells are slowly diluted by the tissue fluids and concentrated by vasoconstriction in the essential organs. The administration of plasma may do actual harm. In most cases of injury, hæmorrhage and shock are combined in varying proportions. A clinical estimate of the amount of blood lost should always be attempted, based on the amount of blood visible, the severity of the anæmia, and the size of the vessels injured.

7 *Hæmoconcentration* In shock without hæmorrhage hæmoconcentration develops in a few hours' time. In burns the combination of loss of plasma into the tissues and on the burnt surface results in very high figures for percentage hæmoglobin being achieved. In pure hæmorrhage the percentage hæmoglobin is reduced as tissue fluids are absorbed into the vascular system. In the usual mixed lesion due to wounds the accurate determination of the percentage hæmoglobin in the first few hours is not of much clinical value, though as a guide for later transfusion it may be valuable. All cases with a percentage hæmoglobin below 60 should be transfused and a level of 80 per cent. maintained if possible.

8 *Toxæmia* The role of tissue products of the histamine type in shock is still debated. The recent elucidation of the crush syndrome shows the important effect of myohæmoglobin in disturbing physiology. It is probable that histamine products play a certain part in the production of shock but that the vicious circle to which they contribute, gains its chief momentum from its own interactions (Fig. 29).

to respond in the normal manner to changes in external temperature, and an actual decrease in heat production due to deficient oxygenation. To this, disturbance of the heat regulating centre may be added. There is thus a marked susceptibility to cold and the avoidance of heat loss forms an essential part of treatment. A warm room, hot bottles or a heat cradle, and warm drinks are simple but important measures to combat a fall of temperature. It is to be noted that excessive heat is as dangerous by producing vaso dilatation and sweating as cold, and in no case should the patient be heated to perspiration point. The cold sweat which is a variable accompaniment of shock does not come under this consideration, and is frequently localised to the face.

3 *Colour* This is an unreliable guide to the patient's condition, except that satisfactory return of colour may be regarded as a sign of recovery. Pallor is due to peripheral vaso constriction, but it is




FIG. 29 The vicious circle of shock

difficult to determine whether this is of central origin, in an endeavour to maintain blood pressure and volume, or peripheral spasms due to heat loss and external cold. Cyanosis, indicating anoxæmia, is significant of the severity of the condition, but may be due to many causes, or combinations of causes (Fig. 29). As indicated under treatment it should be rigorously combated.

4 *Pulse rate* This is extremely variable. Of most importance is the general impression given by the pulse where clinical acumen sums up variations in vascular tone, circulating volume, blood pressure and pulse pressure. The whole tone of the vascular tree is thus sampled by the index finger. A rapid fluttering pulse is serious, and is usually combined with a low blood pressure, as recovery sets in the pulse slows and the blood pressure rises. Exceptional cases with a slow pulse and low blood pressure are met with.

5 *Blood pressure* The observation of the systolic and diastolic pressure and of the difference between them (pulse pressure) is perhaps the most useful single guide to the condition of the patient. It

the temperature will depend on the amount of the blood effused, but it rarely lasts more than three days. This fever may cause undue anxiety when infection is anticipated.

Fat embolism. This rare condition is usually demonstrated as a post mortem finding. The exact mode of occurrence is not yet clear, the idea that marrow fat is somehow squeezed out into the circulation not being entirely satisfactory. The condition occurs from twelve hours to three days after the accident. At post mortem the fat globules may be demonstrated in the kidneys, brain and lungs, and the symptoms depend on which organ is most involved. Clinically there are two types, cerebral and pulmonary. The cerebral type may show delirium, muscle twitchings, or localised fits, passing into coma. In the pulmonary type there are symptoms of respiratory distress, rising pulse and respiration rate, and later cyanosis. There is a normal precession note all over the chest, but coarse rales and signs of pulmonary oedema may be present. The condition may be confused with shock, delirium tremens, cerebral complications, internal hemorrhage, bronchopneumonia and pulmonary embolism. The latter two conditions are, as a rule, later in onset, occurring after the fifth day. The treatment of the condition is limited to general measures.

Delirium. This may arise in old patients as a result of the trauma alone, and is then usually of the low restive muttering type, which calls for sedatives. More troublesome is the onset of delirium tremens, for the restlessness of the patient will destroy any retentive apparatus used to retain the fracture, other than a plaster cast, and the onset of the condition may be an indication for placing a limb in plaster which was previously being treated by skeletal traction. The onset is never sudden, and warning by hallucinations and insomnia is usually given. The tongue is heavily furred, the temperature 100° to 102° , and the pulse rapid. Delirium persists two to five days. Treatment consists of the minimal restraint necessary and adequate sedatives.

Traumatic delirium (cerebral irritation) may give rise to similar difficulties with retention. Delirium due to fever, or the onset of pneumonia, needs only to be mentioned here.

Bronchopneumonia. It must never be lost sight of that elderly patients or patients in poor general condition, or with chronic bronchitis, may develop bronchopneumonia. The immobility forced on the patient may be the main contributing factor to this, but in certain injuries, such as fracture of the ribs in the old, it may ensue in spite of ambulatory treatment. One must be careful that a patient who is likely to develop the condition has his fracture fixed by the means allowing the greatest amount of freedom in the bed, and

Treatment Some details in symptomatic treatment have been mentioned already. All efforts are directed to the improvement of the circulatory tone and the oxygenation of the tissues. The foot of the bed is elevated and there are sound arguments for bandaging the lower limbs in serious cases. If there is cyanosis or serious shock administration of oxygen by a B.L.B. mask is commenced. Morphia is continued and its effectiveness noted by the pupils. With a sluggish circulation it may be absorbed with difficulty. It should then be given intravenously.

Replacement of fluid loss In cases of shock without hæmorrhage intravenous plasma is given at once, starting off with one or two pints administered rapidly, i.e., within half an hour. The rate is then reduced to half or less. If more than three pints have to be administered the fourth pint should be pure blood, to maintain satisfactory hæmoconcentration. In cases of pure hæmorrhage blood must be given, if possible, in amounts and with a rapidity corresponding to the rapidity of loss. No fear need be felt in giving large amounts rapidly if they have been lost. If it is impossible to provide adequate amounts of blood, blood and plasma should be given in equal amounts together. In the usual case of wound shock and hæmorrhage encountered the plasma infusion is commenced while grouping of blood is carried out for transfusion. Administration of plasma and blood are continued till a satisfactory response occurs. In the later stages the administration may be controlled by percentage hæmoglobin investigations if these are available.

Decision as to operation Nothing may be more difficult to determine than the right moment for operation. As a general rule operations are carried out early, in the recovery phase from primary shock, before secondary shock develops, or after secondary shock has been overcome in part at least by restorative measures. The first period occurs within the first three hours of injury. Appropriate measures to overcome the combined surgical shock and wound shock which will follow are commenced at once, without waiting for specific indications. Plasma and blood are administered on the table from the start of the operation. The second period of operability cannot be confined so easily to time limits. The ideal moment varies from case to case, sometimes it is early, i.e., within five hours, more often late. It is noteworthy that there has been an increasing tendency to postpone interference in seriously shocked cases, so that fifteen to twenty hours' rest and resuscitation may be given.

Traumatic fever Owing to the absorption of the products of autolysed blood from the hæmatoma the temperature may rise as much as 2° (100.8), very rarely more. The height and duration of

injuries, associated with fracture of the medial epicondyle, it is justifiable at the time to transplant the ulnar nerve anterior to the joint, though late ulnar neuritis is not a frequent sequel of this condition, being more common after the fractures of the lateral condyle.

Recently the disappointing results of stretching injuries to nerves have come to light. Although no loss of continuity may be visible to the naked eye, there are multiple lesions scattered through the nerve at different levels. In spite of their approximation these heal exceedingly badly. Such lesions are met with most commonly in the peroneal nerve stretched by adduction at the knee joint, and less commonly in the ulnar nerve.

NERVE LESIONS OCCURRING DURING TREATMENT These may be due to external factors such as the pressure of a splint or crutch. The most common nerves involved are the peroneal as it winds around the head of the fibula from the pressure of a walking plaster and the radial nerve from the pressure of a crutch. These lesions rapidly clear up with the removal of the pressure.

The onset of paralysis in a patient free from such pressure may be confusing and cause the doctor concern as to whether manipulation has not damaged a nerve, or whether he has overlooked a lesion on the first examination. It is for this reason that it is important to make a neurological examination in any likely case when it is first seen. The onset of paralysis due to the involvement of a nerve in callus has been hotly debated, but most people have seen cases in which between the sixth and the tenth day a severe and lasting paralysis has occurred, which may take months to clear up, and the pressure of organising fibrous tissue or callus seems to be the only plausible explanation. Such cases are observed for six months, and if recovery has not occurred by this time the nerve is explored. (See Fig 259.)

LATE LESIONS Where a fracture has resulted in an alteration of the alignment of a limb, or the production of an irregularity causing pressure on a nerve, the nerve is liable to undergo fibrosis, with the slow onset of paralysis. This may not occur till years later and is characteristically seen in the ulnar nerve following lesions of the lateral condyle which have resulted in a valgus deformity of the elbow. More commonly in elbow injuries an ulnar neuritis develops in the third or fourth weeks. This accompanies the commencement of movement in an elbow in which there is still some swelling and bruising around the joint. In these conditions the ulnar nerve has not adapted itself to alterations in its path, and the movements may stretch the nerve in the swollen tissues. This repeated stretching may lead to a palsy or temporary paralysis. To avoid this

which, if possible, will allow the patient to be sat out. Such a medium is plaster, and a complete plaster case should be substituted in many cases where in the normal individual continuous traction would be used. Care must be taken that such a plaster does not restrict respiratory movement, or is of such size as to impede movements in the bed.

A further safeguard is the introduction of general exercises in the bed, particularly deep breathing exercises, which in the very feeble may be promoted by the inhalation of CO_2 for ten minutes every hour. Once symptoms appear as indicated by rise of temperature, nocturnal delirium, and moist sounds in the chest, not necessarily at the bases, every step to increase the movement of the patient and allow free respiratory movement must be taken. This often means dismantling apparatus, but it must be done as the condition is usually progressive if neglected. Where possible the patient is sat out of bed. The use of chemotherapy as a prophylactic and curative must not be neglected.

Injuries to Surrounding Structures

Nerves It is convenient to discuss all the nerve injuries, including late nerve complications, together.

1 Immediate lesions may be due to concussion, stretching, contusion, crushing, or division, which may be partial or total.

2 Lesions arising during treatment.

3 Late neuritis.

IMMEDIATE LESIONS may be complete or incomplete, and these, again, may be temporary or permanent. The more incomplete the lesion on the first examination the more likely it is to be temporary. Complete division of the nerve is uncommon, most of the lesions being due to contusion, stretching or crushing. Concussion is a very rare lesion, which is fleeting and due to the vibration set up in the tissues by the passage of a bullet in the vicinity of the nerve. It is probably a mild variety of contusion.

The indication for immediate operation on a nerve is limited to the suture of a nerve divided in an open fracture. In all other lesions delay is advisable till the diagnosis is accurately established. In most cases the nerve will recover of its own accord. The time of recovery will vary very much, depending on the injury, and in the case of severe damage to the radial nerve may be as long as six months. There is considerable disagreement as to the length of time one should wait before operating, many people preferring to explore earlier, *i.e.*, in the second or third month if recovery has not occurred rather than wait for six months. In brachial plexus injuries no advantage is gained by operation. In ulnar nerve

presence of local injury exploration is necessary, as one is not certain whether one is dealing with a complete rupture. No treatment when



FIG. 30. Diagram of main vessels and collateral circulation showing a vascular laceration without spasm (After Cohen)



FIG. 31. Bruising of the arterial wall with local spasm



FIG. 32. Bruising of the arterial wall with distal spasm

this is found other than local warmth provided by a few hot packs in the wound is necessary.

3. *Bruising of a vessel with distal spasm.* The persistence of this spasm, and its exact mechanism are difficult to explain. The spasm




FIG. 33. Local haemorrhage around a main vessel with bruising. With the limb enclosed in plaster there is grave risk of pressure on the collaterals and of vascular occlusion.



FIG. 34. Complete rupture of a vessel retraction of inner layers and clotting.

may persist till the death of the limb. The acute pain is due to muscle cramp (cf. *Myositis fibrosa*). The association of nerve injuries may be responsible for a few cases which are painless and may be partly responsible for the persistence and failure to redistribute the blood. These demand exploration and the relief of the

complication elbow movements should be commenced gently and actively, and all forced movements avoided. Elbow movements should not be commenced too early if swelling is persistent. Should the condition occur a further period of rest will clear it up.

Vessels Damage to vessels is an inevitable accompaniment of all fractures, but it only becomes serious when there is continuous loss of blood, or a hæmatoma under pressure. Damage to veins may produce a large hæmatoma, which is frequently subcutaneous. It is lax and does not pulsate, and the pressure of the blood being insufficient to overcome the resistance of tissues it ceases after a short time. Damage to a large artery results in the formation of a large pulsating hæmatoma, and, what is far more serious, interference with the blood supply to the rest of the limb. The pressure of displaced bone on a vessel without actual rupture may stop the circulation, and this is more serious as there is then no hæmatoma to draw attention to the condition, and irreparable damage may occur before the pressure is relieved. Circulatory obstruction may also be produced by the pressure of splints, and particularly by the post-traumatic swelling of a limb in a complete plaster. Arteries are very strong and not likely to be ruptured, but they are liable to bruising which because of the autonomic supply carried in their walls may result in marked spasm of the distal vessels and partial obstruction. This is particularly seen in the brachial artery, and may be related to the onset of myositis fibrosa. Gangrene of the distal portion of the limb may follow these lesions.

Pressure on a vessel demands immediate relief by reduction of the fracture, while rupture of a sufficiently large vessel will demand open operation if it has not occurred in an already open fracture. Interference is limited to an incision through the tense fascia, and evacuation of the clot followed by drainage, as it is very unlikely that in the swollen and bruised tissues a bleeding point will be found, unless a main vessel is involved.

Very rarely an aneurysmal varix, or a varicose aneurysm develops from the injury of a nearby vein and artery.

ARTERIOGRAPHY Those who have mastered the simple technique of contrast arteriography, may be saved much anxiety, as the method enables the situation in the limb vessels to be assessed without operation and in a more reliable manner.

To sum up. The vascular changes met with may be —

- 1 *Bruising of an arterial wall without spasm* (Fig. 30)
- 2 *Bruising of an artery with local spasm*. This may occur to the brachial artery in dislocations of the shoulder, or in gunshot wounds of the limbs. The pulse is variable usually reduced in volume sometimes absent. It returns to normal in two to six hours. In the

to assume large proportions, and aspiration is advisable. This is necessary as a preliminary to any manipulations, and to the accurate fitting of a plaster, while the removal of the blood probably decreases the adhesions which may form. Much the most important features of the injury are the later sequelæ, limitation of movement and traumatic arthritis.

In open wounds the escape of a few drops of synovial fluid into the wound, which can readily be appreciated by rubbing the fingers dipped in the exudate, may help to decide whether a joint is involved. A somewhat similar slippery sensation may be imparted by marrow fat, so that in the presence of a fracture below the wound the test may be unreliable. A more valuable test, if a decision has to be made, is to inject penicillin into the joint, and see if it escapes into the wound.

It must not be forgotten that cartilage injury alone will show no irregularity or shadow in the X-ray. Only if a flake of bone is torn off with the cartilage (as in arthritis desiccans) will the damage be seen in the radiograph. Thus in fracture of the head of the radius, damage to the cartilage of the capitellum (as shown by operation) frequently occurs, and is overlooked and unsuspected till recovery fails to occur in the usual time.

Dislocation associated with a fracture is an added source of trouble. The fracture may make adequate reduction of the dislocation difficult as in fracture dislocation of the shoulder, or *vice versa*, as in fracture dislocations of the spine.

Viscera. The viscera liable to damage are discussed in the complications of special fractures. The principal dangers are due to infection or to hemorrhage.

REFERENCES

Shock

- HUSTON "Shock its Prevention and Treatment" *S Clin North America*, April 1935, 287 (Contains a summary of the American work.)
- BOND and WRIGHT "Treatment of Hemorrhage and Traumatic Shock by the intravenous use of Lyophile Serum" *Ann Surg*, 1938, 107, 500
- FRAZIER "The Modern Treatment of Surgical Shock," *J A M A*, 1935, 105, 1731
- RIDDOCH, J. W. "Surgical Shock" *Birmingham Med Rev*, 1936, 11, 131
- MAHONEY, E. B. "A Study of Experimental and Clinical Shock with Special Reference to its treatment by the intravenous injection of preserved plasma," *Ann Surg* 1938, 108, 178
- CANNON, W. B. "Studies in Experimental Traumatic Shock" *Arch Surg* 1922, 4, 1, and on p. 300
- BLALOCK "Acute Circulatory Failure as Exemplified by Shock and Hemorrhage" *Surg Gynec and Obst*, 1934, 58, 551
- LEVINSON, NOWELT and NECHELES "Human Serum as a Blood Substitute in the Treatment of Hemorrhage and Shock" *J A M A*, 1940, 114, 455

collateral circulation from all pressure. At operation, excision of a segment of the artery has been recommended. The rationale of this is not clear. Any effects on the distal circulation, presumably occur through the peri arterial sympathetic, and peri-arterial sympathectomy by stripping the outer coats would seem more logical. Whether anything is done locally or not, immediate paravertebral sympathetic block should be carried out, not only to try and dilate the affected vessel, but to dilate the collateral circulation as well.

4 *Local bruising and pressure with pressure on collaterals* This may occur in gunshot wounds, especially if put in plaster. The collateral circulation around joints is to allow for the occlusion of the main vessel in extremes of movement. It is at the joint levels that particularly large areas of a cross section of the limb are occupied by bone and pressure may readily be exerted on the collaterals. The hematoma should be evacuated and drained if necessary, or the wound lightly packed.

5 *Complete rupture of a vessel* If the vessel ends can retract there is often little bleeding. Danger arises from thrombosis in the distal end or pressure on the collaterals. If a vessel cannot retract, e.g., it is bound down by branches, or only partly torn, bleeding may be severe. The vessel ends should be ligated.

AFTER TREATMENT Never use traction where there is any question of the impairment of the blood supply. Plaster also should be avoided, but it may be necessary to use padded plasters or plaster gutter splints. Always elevate the limb, a slung skeleton splint is usually most convenient. Keep the limb cool rather than over-heat it. Remember that the circulation in the deep tissues is what counts, and the skin circulation is an unreliable guide to this.

Joints Joints may be injured in association with fractures in the following ways

1 The fracture may run into the joint, or be entirely intra articular.

2 The fracture may result in the normal alignment of the limb being altered, with subsequent strain on the joint.

3 A dislocation may be associated with a fracture.

4 A mal united fracture in one leg may throw so much strain on the other that a traumatic arthritis may develop on the uninjured side from repeated minor strains.

It has been emphasised before and will be emphasised again, that the serious feature of a fracture is the damage to soft parts and the alteration of joint alignment, and not the fracture itself. It is still more serious when the fracture involves a joint and to altered alignment is added an irregularity of the joint surface. An effusion of blood into the joint is inevitable. In the knee it is liable

CHAPTER VI

THE LATE COMPLICATIONS OF FRACTURES

Late Complications

- 1 Infection (See compound fractures, Chapter VIII)
- 2 Non union (See Chapter IX)
- 3 Mal union (See Chapter IX)
- 4 Late neuritis (See Chapter V)
- 5 Myositis ossificans and ossifying hæmatoma
- 6 Myositis fibrosa (Volkman's ischæmic contracture)
- 7 Acute traumatic bony atrophy
- 8 Joint stiffness and adhesions
- 9 Traumatic arthritis
- 10 Avascular necrosis (See Chapter II)
- 11 Œdema and vascular disturbances
- 12 Nephrolithiasis

Myositis Ossificans and Ossifying Hæmatoma

It is customary to apply the term myositis ossificans to any flake of bone found in the vicinity of, but distinct from, an injured bone. This is an equivocal use of the term, which was once limited to a single clinical entity in which some inflammatory features were present. It now covers several conditions:

- 1 New bone formed in the vicinity of displaced fragments of bone or cartilage
- 2 Extensive new bone formation in tissues in the vicinity of a fracture which were involved in the fracture hæmatoma
- 3 Patchy new bone formation in muscles at some distance from the fracture and not directly involved in the fracture hæmatoma
- 4 True myositis ossificans, the formation of new bone accompanied by pain and other features of inflammation, and now less commonly seen than under old methods of treatment

The formation of callus commences first at the junction of the stripped periosteum and the shaft, and slowly extends into the hæmatoma, gradually encroaching on the fracture site till it joins the callus extending from the opposite side. At the same time there is a tendency for the hæmatoma to diminish in size. If the hæmatoma is very large, or the periosteum is torn and displaced into the muscles around the bone, the ossifying process may extend into the surrounding tissues, and this is particularly marked in comminuted fractures. We have stated that ossification is not a specific property of the cambium cells of the periosteum, but that any fibroblast may under certain conditions become an osteoblast and lay down collagen fibrils, among which calcium and phosphorus are

- MEAKINS, J C "Shock, its Cause and Treatment," *Canad Med Ass Jour*, 1940, 93, 201
- MOON V H "Early Recognition of Shock Differentiation from Hemorrhage," *Ann Surg*, 1939, 110, 260

Fat Embolism

- SCUDERI, C S "The Present Status of Fat Embolism," *Internat Surg Digest*, 1934 October, No 4, Vol 18
- ROWLANDS and WAKELEY "Fat Embolism" *Lancet*, 1941, 1, 502
- SCOTT and KEMP "Pulmonary Fat Embolism," *Lancet*, 1942, 1, 228

Nerve Injuries

- PLATT, H "Peripheral Nerve Complications of Fractures and Dislocations of the Elbow" Robert Jones Birthday Volume London, 1928, p 195
- PLATT and BRISTOW "Remote Results in Operations for Injuries of the Peripheral Nerves," *Brit J Surg*, 1923, 11, 535
- PLATT, H "Traumatic Neuritis of the Ulnar Nerve in the Post condylar Groove," *Brit J Surg* 1925, 13, 409
- PLATT, H "Peripheral Nerve Complications of Certain Fractures," *J Bone and Joint Surg*, 1928, 10 403
- DAVIDSON and HOROWITZ "Late or Tardy Ulnar Nerve Paralysis," *J Bone and Joint Surg*, 1935 17 844

Injuries to Vessels

- DODD, H "Gangrene following Fractures (excluding Gas Gangrene)," *Brit J Surg*, 1934 22, 246 (Summary of the types of injury, the vessel liable to injury, and symptoms)
- COHEN S A "Traumatic Arterial Spasm" *Lancet*, 1944, 1, 1

elsewhere, such as " rider's bone " in the adductor longus, or bone formation in fibrotic scars, but the formation is in this case related to the repair process which is going on in the vicinity. According to Leriche and Polierard, whose theory is related to the facts, but is not the whole truth, under these circumstances we have the essential conditions present in which ossification occurs

- 1 We have an active blood supply in the organising hæmatoma
- 2 An ossifiable medium, that of the growing fibroblasts
- 3 Excessive calcium from absorption in the vicinity

Any damage to a muscle in the vicinity resulting in a slight fibrosis may become involved in this cycle. The stimulus changing the direction of the fibroblast from fibrous tissue formation to bone is considered in this hypothesis to be the local calcium excess, but though this is part of the truth it is not all of it. Observation of many cases and the study of the repair of bone makes one certain that any further tissue injury in the vicinity of the repair process will result in the rapid extension of the ossification, and many cases in which the condition develops give a history of early forced movements. The condition is particularly common in the elbow region, and is to be avoided by giving adequate rest to the joint before movements are attempted, usually a period of three to four weeks, and then to commence gentle active movements. In all cases forced or violent active or passive movements are to be avoided. The effect of such movement can be seen readily if the angle of the elbow in extension and flexion is measured weekly. If, following an elbow injury such as a supracondylar fracture, there is a progressive decrease in the range of movement, it is almost certain that inquiry will reveal forced movements, such as the carrying of a school satchel or the well meant effort of a parent to get the arm straight.

TREATMENT This falls into two stages. In recent cases, in which the outline of the callus in the radiograph is soft, time will usually result in absorption of the deposit altogether or in part. The degree of fixation necessary to encourage this is debated. If there are any acute symptoms such as swelling or pain, the joint must be completely rested. If the joint is painless the advantage of absolute fixation in plaster is doubtful, and equally satisfactory results are achieved by merely avoiding heavy work and forced movements, while leaving the arm free for lesser activities.

If the lesion is old and the bone well organised with a sharp dense outline (Fig 35), operative removal is required if it is obstructing movement. In many cases there will be little disability in spite of its presence, and there is then no call to interfere. Care must be taken during the operation to do as little damage to soft tissues as possible and avoid the formation of a fresh hæmatoma.

deposited to form new bone. The cambium cells of the periosteum merely serve as a store of readily available cells which rapidly produce fibroblasts. In the first two conditions mentioned the muscle is involved because it forms part of the fracture hæmatoma. This may be serious, as, for example, in the thigh, where the quadriceps may develop extensive adhesions to the femur, limiting knee movements. Such hæmatomas show a rounded and definite outline and usually some connection with the callus at the fracture site. Occasionally only small areas of the hæmatoma undergo calcification due perhaps to the presence of a bone fragment, or the displacement




FIG. 3. Ossifying hæmatoma in the brachialis anticus following fracture of the ulna with anterior dislocation of the head of the radius. (Sequel to the fracture shown in FIG. 364. The outlines of the new bone are now sharp and well defined due to the organisation of a fine layer of compact bone on the periphery, indicating that all activity has ceased and light active exercises can be indulged in without fear of extension of the new bone formation.)

of periosteum and show no connection in the radiograph with the shadow of the callus.

Such an ossifying hæmatoma should be left, and will gradually decrease, particularly in the young. Occasionally, when in the neighbourhood of a joint, it will limit movement and when well organised, which takes some twelve to eighteen months, may be better removed. Early interference is contra-indicated in all cases as it produces a fresh hæmatoma and fresh bone formation.

The conditions resemble those of heterotopic bone formation.

open to an action for malpractice. Such a risk makes it important that the various factors related to the condition be fully discussed.

The deformity is due to shortening of the flexor pronator group of forearm muscles secondary to a replacement fibrosis of the muscles with subsequent contraction. It is invariably associated with circulatory changes of the limb in both the onset stage and the late stage. The association of the condition with vascular and nervous features has led to a thorough examination of both these factors as the possible causative agents—the nervous damage appears to be an associated phenomenon due to either nerve damage at the time of the injury, or secondary to ischaemia of the limb. Of the vascular possibilities both the venous and the arterial sides have been held responsible but the etiology of the condition is not yet clear.

Clinically the condition may be divided into three stages

- 1 Threatening stage
- 2 Developed acute inflammatory stage
- 3 Stage of fibrosis and contracture

First stage In this stage, which is not uncommonly seen, the patient will complain of severe pain in the limb, the fingers will be swollen and engorged and the movements limited. There may be some interference with the radial pulse. With correct treatment (to be discussed later) this will pass off and the condition may completely recover. Partial recovery may occur with a slight degree of contraction later in one or two fingers, indicating that the second stage has developed in a few muscle bellies.

Second stage The symptoms and signs mentioned above are present in an aggravated form. In the actual muscles involved changes of an acute inflammatory nature occur. The muscles are tense, swollen and oedematous, of a bluish colour, due to congestion combined with multiple capillary ruptures and hemorrhage into the muscles. This is followed by an invasion of lymphocytes and phagocytes among the muscle fibres, which soon lose their characteristics and degenerate. At this stage the fascia of the forearm is very tense and frequently the skin is almost equally tense, due to the gross swelling. Finger movements are impossible and, if passively made, excessively painful. The fingers are held flexed. Symptoms of nerve pressure or paralysis may be apparent.

Third stage This is the stage which characterises the condition. In the fibrosis which follows arterial obstruction and nerve degeneration the contracture which characterises myositis fibrosa does not occur. We must therefore seek for the special factors which produce this contraction, and it has been suggested that they are vascular or neurological, or a combination of both. The acute symptoms subside and at the end of three days early contraction can be noted.



FIG. 35a Myositis ossificans in the brachialis anticus. This specimen of true myositis ossificans shows extensive involvement of the muscle with calcification occurring along the lines of the smaller intramuscular septa.

MYOSITIS OSSIFICANS
The condition to which this was first applied is most commonly seen in the elbow region. It takes the form of a fairly acute inflammatory reaction with heat, pain, redness, swelling and tenderness in the vicinity of the fracture, which is obviously a much more active lesion than the repair processes on which it supervenes. It occurs at any time after the first three days up till the end of the third week. It is rapidly followed by calcification and ossification in the involved tissues. The exact aetiology of the condition is not clear, it may be sub-acute inflammatory in nature, or more probably chemico-pathological, following vaso-motor changes. It produces larger masses of new bone

than is usually found with the more passive processes previously described, and organisation is slower. Characteristically the new bone formed indicates the outline and direction of the bundles of muscle fibres of which the muscle is composed (Fig. 35a). The treatment, which consists of complete rest in the acute stage, must be prolonged. Removal of organised fragments is very likely to be followed by a recurrence, and the extent of the condition usually renders this impossible. Slow recovery over a long period may occur, but some permanent disability is the rule.

Myositis Fibrosa (Volkmann's Ischæmic Contracture)

The decrease in the incidence of this condition is due to the widespread recognition of the risks of certain forms of treatment in fractures in the elbow region. This care must not be relaxed by the profession because the condition may also be found apart from all treatment. The responsibility for the condition is so frequently laid at the door of treatment that a surgeon who neglects the warning signs and allows the condition to develop will lay himself

arise from the rupture of a small artery into the space, the pressure of displaced fragments of bone, or the anteriorly displaced end of the humerus, or from traumatic swelling and edema.

Brooks' theory has however not explained the loss of radial pulse often noticed, or the occurrence of the condition, apart from the ante cubital swellings and in other regions.

Arterial theory—Contusion or pressure on the brachial artery by a fragment of bone has been seen at operation to cause intense spasm of the vessel, which is continued into the distal branches. This spasm is sufficient to reduce the blood flow through them to almost nil, and is persistent. The long continued partial or complete obstruction to the circulation in the limb thus accounts for the loss of the radial pulse, and the peripheral vascular features which characterise the condition. The subsequent microscopical changes fit in satisfactorily with an avascular necrosis of the muscle cells, followed by a peculiarly active fibroblastic replacement. Clinically it has been shown that the vasospasm can only be undone by novocaine infiltration of the vessel wall or complete division of the vessel. This latter procedure being the most effective is the usual procedure adopted, as the vessel is usually damaged at the point of spasm. Absence of a radial pulse is thus a justification for exploration of the radial artery, with which may be combined the release of tension in the ante cubital fossa and the flexor group by a long fascial incision.

CLINICAL In watching suspected cases it must be remembered that certain signs may be absent. For example, the condition may develop without loss of the radial pulse, which cannot alone be used as a criterion of safety. Loss of the radial pulse from the beginning suggests pressure on the brachial artery from the fracture, and should the reduction of the fracture fail to restore this, it is an indication for operative exploration, especially if accompanied by other signs of circulatory failure in the hand. Myositis fibrosa may also develop in an arm without complaint of pain, though this is usually severe and bitterly complained of. Swelling, loss of function of the flexor muscles, and circulatory disturbances such as pallor, cyanosis, and coldness are found in all cases, and these are sufficient to justify active interference. It must be remembered that nerve symptoms are present in 50 per cent. of cases, the median and ulna being the more commonly affected nerves. Involvement of these nerves may account for a few cases in which there is no complaint of pain. The time of onset of the condition is most commonly within eight to forty eight hours of the fracture, but in a few cases it has apparently occurred later, but such cases usually give a history of some manipulation or change of treatment some days

This becomes more and more marked so that the fingers are first flexed, then the wrist, and in severe cases even the elbow. In the fully developed state the lesion is easily diagnosed. The wrist is flexed and the fingers extended at the metacarpo-phalangeal joints, due to the action of the extensor digitorum communis, and flexed at the inter-phalangeal joints due to the inability of the lumbricals and interossei to oppose the contraction. The forearm in severe cases is flexed and pronated. The fingers can be extended if the wrist is fully flexed, but on extending it the fingers forcibly flex again. The condition reaches a maximum ten to twenty weeks after the injury. Fully developed cases are not overlooked, but the mild cases may be very readily missed. They come up some time after the injury, usually to a different doctor, and with no story suggestive of myositis. They are confused with nerve lesions, contracture of the palmar fascia, tenosynovitis, and contractions of the fingers. Careful history taking and examination should suggest the cause.

PATHOLOGY The pathological peculiarity which characterises myositis fibrosa is the contraction of the fibrous tissue which forms in the muscles affected. It is highly probable that this is due to some unusual trophic disturbance of the muscle as similar contractions may be seen in other vasomotor disturbances. It is theoretically possible that this change may be produced by either venous obstruction or arterial occlusion, and it would seem that this is the only possible explanation of the divergent views expressed as to its aetiology.

Brooks' theory This theory, of old standing, states that the obstruction is venous in origin, and was based on experimental work. It was found that the blocking of the artery to a muscle alone produced no contracture. That the blocking of artery and vein were equally without effect but that contraction followed the blocking of the vein alone. Further support was lent to the idea by the fact that the venous return from the forearm muscles which are most commonly affected occurs through one large vein. As this vein crossed the anti cubital fossa it was susceptible to pressure, and as a rise in pressure in this space seemed to be an inevitable accompaniment of the condition here was a convenient explanation.

In observed cases the condition has arisen following tight bandaging of the arm to the chest for fractures of the clavicle, also in unsplinted fractures in the elbow region. Cases of prolonged use of the tourniquet, various crushing injuries of the forearm, rupture of the brachial artery, and, most frequently, splinted fractures of the elbow region, have all given rise to cases of contracture. Assuming Brooks' theory to be correct, pressure in the ante cubital fossa may

after the injury, and the lesion develops within eight to twenty-four hours after this, so that the primary cause in these cases was the second manipulation. Such reported cases are probably not due to the contracture being overlooked, as there was no pain noted in the first instance, and this is an almost inseparable accompaniment of the inflammatory stage. As contraction sets in after forty-eight hours, and such reported cases have occurred after intervals of several days contraction would be certain to be established, and could hardly be overlooked.

The condition is not uncommonly seen in the leg, either as the result of too tight plastering, or, more commonly, following lesions of the upper end of the tibia, in which the posterior tibial vessels are injured. They are peculiarly susceptible to pressure where they lie under the fibrous arch of the popliteus, and pierce the interosseous membrane. The changes are similar to those in the hand, persistent vascular disturbance being even more troublesome in the foot.

TREATMENT *Prophylactic or precautionary* As the condition is most commonly associated with lesions in the elbow region it is important to observe such cases for twenty-four hours after treatment. As pressure on either vein or artery will persist if the fracture is unreduced, early reduction is important in all cases. This can usually be done by manipulation, which should be the minimal necessary, to avoid further damage and hæmorrhage. Retention should also be the minimal necessary. A plaster slab bound on with a gauze bandage is sufficient, the elbow being maintained at right angles, as acute flexion is liable to produce pressure. Morphia should not be given as it may mask the pain, which is an important premonitory symptom, and the pulse and circulation should be regularly observed. The patient is better in bed to avoid the increased swelling due to a dependant arm.

Traumatic swelling and œdema will not as a rule cause trouble if there is room for the swelling to occur, but if the arm is tightly splinted, or acutely flexed, the swelling may cause pressure, first on the veins and then on the arteries, with, in severe cases, the total obstruction of the circulation of the limb. Before such a condition is arrived at, however, the signs of threatening myositis fibrosa will have occurred.

In the threatening stage All apparatus must be removed at once, and the situation considered. If the fracture has not been reduced this is done at once and the progress observed afterward. If possible the arm is placed in Zeno's position (Fig. 248), and held there with a plaster slab and a sling, or a wire through the olecranon. If the fracture has been reduced the limb is similarly suspended. It is then carefully watched and if within one and a half hours no change

is noted in the condition of the circulation the fascia of the forearm is incised and the lower third of the brachial artery explored. The incision, 6 inches long, lies over the muscle group and the artery. Spurring vessels are tied and the wound drained and lightly sutured. The arm is then slung up in Zeno's position. The fracture is not exposed during this procedure if possible.

The developed condition The treatment of this is not the province of this book, but in the earlier cases care must be taken to prevent contraction occurring by adequate splintage. This is best done by incorporating a frame of Crumer wire in plaster so that it overhangs the dorsum of the hand. From this the fingers are suspended by strings and a small volar pad. The spring of the Crumer wire exerts a continued pull on the fingers and this can be tightened daily by retying the suspensory tapes. Early contraction can be counteracted by this method and old contraction to some degree corrected. As the damaged muscles do not regenerate there is no possibility of the return of function, but the fingers are much more useful if they are not excessively flexed (Fig. 37).

Ultimate outlook In early cases which are rapidly relieved by the removal of splints the outlook is good. In slight cases the disability is not very crippling. In severe cases, especially with nerve complications, the outlook is poor, and in the established case there is little hope of improvement, some diminution in flexion of the fingers is all that operative interference other than muscle transplants produces.

Acute Traumatic Bony Atrophy

Following the immobilisation of any limb there is a certain degree of decalcification of the bone as shown by the X-ray (disuse atrophy). In certain cases in which the pathology is not at all clear this decalcification progresses at an abnormal rate. It may further show the abnormality of being confined to a comparatively limited area, such as the hand. It may follow a very minor lesion and be out of all proportion to it. Sudeck, who first drew attention to the condition, regarded it as an inflammatory condition. It is now regarded as a neuro-trophic manifestation as is suggested by the skin changes, circulatory disturbances and impaired sensation. The condition most commonly affects the hands and feet. Two conditions are recognised as predisposing to its development, a period of partial vascular obstruction under a tight plaster, and multiple attempts at reduction in elderly patients. Both should therefore be avoided. In the hands there will be complaint of disproportionate pain and stiffness. The skin will become shiny and red and susceptible to cold, when it turns a cyanotic blue. An X-ray distinguishes the



FIG. 36 Acute bony atrophy (Sudeck's) of the hand. Note the concentration of the maximum rarefaction around the joints.



3" A simple method of preventing finger contraction. The fingers wrapped in cardboard are tied by tapes to a piece of cramer wire incorporated in a forearm plaster. One must be careful by exercising the fingers that one does not substitute stiffness in extension for stiffness in flexion.

condition from the pure neurotrophic manifestations. The bones will be found to have a mottled appearance, with marked decalcification in the regions of the joints. There will be a general decalcification of all portions of the bone in comparison with the normal side. Variable degrees of soft tissue contraction accompany the condition, particularly affecting the capsular ligaments of the inter phalangeal joints, and in certain cases this is marked and resistant. The severe case is very rare, but the mild case in which the bony atrophy progresses past the normal is not uncommon. In this latter group the soft tissue contraction is small, possibly only preventing full extension of the fingers, and with use the normal calcification is restored. In the serious cases there is no more disappointing lesion to treat. Recently paravertebral sympathetic block has been suggested for the early case, but as the lesion is accompanied by vasodilatation it is not obvious how this would act. In the absence of any other method of attack, it is however worth trying. In the established case vitamin concentrates and calcium in the diet are given, together with local treatment in the form of radiant heat, contrast baths, massage, exercises, and electrical stimulation of the muscles. In the less severe cases movements will return to some extent, but in the majority of cases the hand is crippled for life.

Joint Stiffness and Adhesions

This is one of the most disabling conditions following fracture, and one which should be more frequently avoided than is the case. The borderline between these cases and traumatic arthritis is not sharp. The condition may arise from

- 1 Actual fracture into the joint (Traumatic arthritis later)
- 2 Bruising of the joint with no X-ray evidence of fracture. Possibly osteochondritis desiccans later
- 3 Bruising and damage to peri articular structures
- 4 Degeneration and fibrosis around a joint immobilised in treatment, particularly so if there is any previous tendency to arthritis
- 5 Sepsis in the region of the joint
- 6 Burying foreign bodies near the joint
- 7 Ossifying hematomas and myositis ossificans
- 8 Flare up in a joint disease due to injury or immobilisation
- 9 Excessive skeletal traction through a joint (p 33)

Most of the conditions outlined above have been discussed elsewhere. In a general discussion it is important to emphasise that joints should only be fixed for a reasonable period. This period varies with each fracture and each joint. Generally speaking fractures near joints should be given time to become firm before the

condition from the pure neurotrophic manifestations. The bones will be found to have a mottled appearance, with marked decalcification in the regions of the joints. There will be a general decalcification of all portions of the bone in comparison with the normal side. Variable degrees of soft tissue contraction accompany the condition, particularly affecting the capsular ligaments of the interphalangeal joints, and in certain cases this is marked and resistant. The severe case is very rare, but the mild case in which the bony atrophy progresses past the normal is not uncommon. In this latter group the soft tissue contraction is small, possibly only preventing full extension of the fingers, and with use the normal calcification is restored. In the serious cases there is no more disappointing lesion to treat. Recently paravertebral sympathetic block has been suggested for the early case, but as the lesion is accompanied by vasodilatation it is not obvious how this would act. In the absence of any other method of attack, it is however worth trying. In the established case vitamin concentrates and calcium in the diet are given, together with local treatment in the form of radiant heat, contrast baths, massage, exercises, and electrical stimulation of the muscles. In the less severe cases movements will return to some extent, but in the majority of cases the hand is crippled for life.

Joint Stiffness and Adhesions

This is one of the most disabling conditions following fracture, and one which should be more frequently avoided than is the case. The borderline between these cases and traumatic arthritis is not sharp. The condition may arise from

- 1 Actual fracture into the joint (Traumatic arthritis later)
- 2 Bruising of the joint with no X ray evidence of fracture. Possibly osteochondritis desiccans later.
- 3 Bruising and damage to periarticular structures.
- 4 Degeneration and fibrosis around a joint immobilised in treatment, particularly so if there is any previous tendency to arthritis.
- 5 Sepsis in the region of the joint.
- 6 Burying foreign bodies near the joint.
- 7 Ossifying hematomas and myositis ossificans.
- 8 Flare up in a joint disease due to injury or immobilisation.
- 9 Excessive skeletal traction through a joint (p. 33).

Most of the conditions outlined above have been discussed elsewhere. In a general discussion it is important to emphasise that joints should only be fixed for a reasonable period. This period varies with each fracture and each joint. Generally speaking fractures near joints should be given time to become firm before the



FIG 78 Early traumatic arthritis of the elbow, following fracture of the head of the radius showing lifting of the sigmoid notch, small loose body in the joint, and rarefaction of the capitellum

3 Arthritis developing in joints which are some distance from the fracture due to alteration in the lines of force passing through the joint from malunion of the fracture. Such arthritis may occur in the opposite lower limb to that injured from the excessive use of the uninjured limb in an attempt to protect the injured one. Such cases are really an osteoarthritis from excessive strain.

The condition is usually a low grade chronic inflammatory one without of course any bacterial basis, the

pathology resembling that of monarticular osteoarthritis. It is accompanied by pain and swelling, and progressive deterioration of the joint with loss of cartilage, flaking and eburnation of bone, and later the formation of osteophytes. Any of the factors mentioned in the etiology of adhesions may be an associated or primary cause of the condition. It is commonly found in the hip after fractures of the neck of the femur, and in the elbow and knee after fractures into the joint.

The condition is in general relieved by rest and aggravated by exercise. Patients with arthritic lesions elsewhere are particularly prone to develop the condition, and it may be difficult to decide if it is the original arthritis or the accident which is more to blame for the condition. These cases are unsuitable for any but palliative physiotherapeutic treatment or if severe for some radical surgical interference.

The aim of treatment is to avoid the development of the condition, which once developed shows a strong tendency to progress, even if the original cause is removed. Thus if a displaced head of the radius is left *in situ*, and gives rise to a traumatic arthritis, its late removal may result in very little improvement in the condition. Early removal to avoid the complication is indicated. No one was more

istent on the need for perfect reduction to avoid this complication than Arbuthnot Lane, and time has proved his contention. Post-traumatic strain from malunion is most important in the lower limb, where the disturbance of the line of transmission of the body-weight throws unequal strains on either side of a joint. This may apply to the leg involved, or to the opposite leg, which may be subjected to strain to balance the affected limb. Where a joint is involved in damage the subsequent traumatic arthritis develops as a result of frictional strain as well of intra-articular strains. The importance of perfect reduction of fractures in the vicinity of all joints, and of any fracture of the lower limb, is thus a strong argument for the use of open operative methods of reduction in fractures.

Treatment In early cases this may be difficult to decide. If the deformity is gross, operative restoration of the normal may be attempted. In the young this is obviously desirable, but in the old, especially if the deformity has been established any length of time, a certain amount of adaptation has occurred and a fresh alignment merely substitutes a fresh series of strains for the old. Often palliative measures are all that can be prescribed, such as firm bandaging or the wearing of a moulded support. A course of physiotherapy may give symptomatic relief. The possibility of temporary relief and improvement by manipulation must be kept in mind.

In well-established cases the treatment is similar to that of osteoarthritis. Palliative measures like massage and other forms of physiotherapy are used, together with a support to the joint such as a caliper or knee cage. If this does not relieve the patient recourse must be had to cup arthroplasty, osteotomy to alter lines of strain or arthrodesis.

Œdema and Vascular Disturbances

Following the removal of any plaster which has been worn for a week or more there is a reactionary œdema, particularly in the lower limb, which varies with the age of the patient, the type of plaster and the lesion. Such an œdema limits the movement and use of the limb leading to stiffness of joints, and requires to be controlled. This is best done by applying some form of elastic stocking to the limb immediately after removal of the plaster and before the swelling has time to occur. It will be necessary to keep this stocking on for approximately half the length of time the plaster was worn. Unna's paste, elastoplast, or "Viscopaste" bandages are suitable for long cases, and crepe bandages for milder and shorter cases.

In contradistinction to this group of patients in whom there is a controllable œdema, usually of the lower limb and lasting only for a short time, while the vascular tone returns to normal, there is a rare

but more troublesome group of persistent œdemas. These may be secondary to a number of causes

- 1 Deep thrombosis of the tibial veins during treatment
- 2 Extensive subcutaneous scarring with diminished venous return
- 3 Chronic lymphangitis from an attack of streptococcal lymphangitis ("Wound erysipelas")

4 Vasomotor disturbances of an unexplained type, sometimes associated with nerve lesions, but occurring in their absence and often following comparatively trivial injuries, e.g., sprains

These forms may be distinguished from the "physiological types" by their persistence, the failure of the œdema to subside with rest, or elevation of the part, its localised site in certain cases, the firm resistant quality of the œdema, and the occasional obvious ætiology. Deep thrombosis of the tibial veins may be demonstrated by a venogram, and is followed by the development of varicose veins. The treatment of these is unwise while the deeper veins remain blocked. Where lymphatics are blocked and there is extensive scarring, full thickness grafts of skin and subcutaneous tissues (tubed pedicle grafts of flaps), may restore normal lymphatic and venous channels. Vasomotor disturbances being of uncertain pathology are naturally the most unsatisfactory to treat. The localised forms may be treated by regular weekly infiltrations with novocaine, and physiotherapeutic measures to improve vascular tone, contrast baths, short wave therapy. The more generalised forms, affecting the whole limb, or the distal portion of it, may respond to sympathetic block, or to sympathectomy. This group remains both the most unsatisfactory and the most interesting on account of their indeterminate nature.

Nephrolithiasis

The development of renal stone in cases recumbent for a long period has been observed for many years. It is due to a combination of defective renal drainage from the position, and the decalcification of the skeleton due to disuse. Thus decalcification is greatly increased by sepsis in the neighbourhood of the bone, or in the bone itself, and this is an important factor in the ætiology. In 90 per cent of cases the stones are of calcium phosphate, and the chief factors in their formation seem to be physico-chemical rather than infective, as renal infection is uncommon in the early stages of their development. The calculus is discovered by X ray, usually accidentally, in a film of the spine, or from an attack of renal colic when the patient moves in the bed.

To avoid this development patients who are to be recumbent for

a long period should be given fluids freely, and turned regularly in bed to get complete drainage of the renal pelvis. The urinary reaction may be altered for a period now and then by a course of sodium citrate, or phosphate. In likely cases the renal tract should be watched by X rays.

When developed a number will be found to absorb on assuming the upright posture. Others may continue to develop or produce symptoms which will demand their surgical removal.

REFERENCES

Myositis Ossificans

- BOWERS, R. P. "Myositis Ossificans Traumatica," *J Bone and Joint Surg*, 1937, 19, 215.
 BRISTOW, R. "Myositis Ossificans," *Brit J Surg*, 1922-23, 11, 475.
 THORNDIKE, A. "Myositis Ossificans Traumatica," *J Bone and Joint Surg*, 1940, 22, 315.
 GESCHICKTER and MASEBARTZ. "Myositis Ossificans," *J Bone and Joint Surg*, 1938, 20, 661.
 MORLEY. "Traumatic Myositis resulting from Gunshot Wounds," *Brit J Surg*, 1919, 7, 178.

Myositis Fibrosa (Volkmann's)

- BROOKS. "Pathologic Changes in Muscle as a Result of Disturbances of Circulation," *Arch Surg*, 1922, 5, 188.
 GARDER, J. N. "Volkmann's Contracture as a Complication of Fractures of the Forearm and Elbow," *J Bone and Joint Surg*, 1939, 21, 154.
 GRIFFITHS, D. L. "Volkmann's Ischemic Contracture," *Brit J Surg*, 1940, 28, 239. (Able article, accompanied by full references, supporting the arterial theory of origin.)
 JONES, ROBERT. "Volkmann's Ischemic Contracture," *Brit M J*, 1928, 2, 639.
 KING, T. "Treatment in Fractures of the Lower End of the Humerus," *Gen Practitioner*, 1934, 5, 42.

Acute Traumatic Bony Atrophy

- SUDECK. "Über die akute entzündliche Knochenatrophie," *Arch f Klinische Chirurgie*, 1900, 62, 147.
 OPPENHEIMER. "The Swollen Atrophic Hand," *Surg Gynec and Obst*, 1938, 57, 440.
 FRAZER GURD. "Post traumatic Acute Bone Atrophy," *Ann Surg*, 1934, 99, 449. (With further references.)

Nephrolithiasis

- PULVERTAFT. "Nephrolithiasis occurring in Recumbency," *J Bone and Joint Surg*, 1939, 21, 559.
 WINSBURY WHITE. "The Aetiology of Urinary Calculus," *Brit J Urol*, 1935, 7, 103.
 PYRAH and FOWWEATHER. "Urinary Calculi in Recumbent Patients," *Brit J Surg*, 1938, 26, 98.

CHAPTER VII

THE TREATMENT OF WOUNDS

APART from compound fractures wounds are commonly associated with fractures, and the two must often be treated simultaneously. The assurance of *primary union in a wound is always important*, and doubly so if the wound communicates with a fracture. A detailed description of the treatment of wounds is thus not only a part of the description of the treatment of compound fractures, but it is deemed sufficiently important to merit a chapter to itself.

The history of the treatment of wounds from the days when pus was "laudable" to the days when it became "damnable" is the history of surgery itself. Medieval superstition first shows the impact of common sense observation with Ambrose Pare's description of the improved condition of the soldiers whose wounds he had been unable to cauterise. From this time on we can trace a gradual development of modern principles, first one man grasping one aspect of treatment, and making a name for himself, only to be forgotten as another achieves successful results by his discovery of another important principle. The synthesis of a completely rational outlook on the subject has thus been the product of many minds, in which few stand out as milestones. With the discovery of bacteria by Pasteur, and the development of antisepsis by Lister, we approach the era in which the 1914-18 war was fought. The object at this time was the elimination of bacteria by the use of antiseptic media. Wounds as a result were treated by the introduction of a solid and persistent antiseptic such as BIPP or an attempt to keep them clean was made by continuous irrigation as in the Carrel-Dakin method. The frequent dressings employed were distressing to patients and nurses alike, and the tired and exhausted faces of the patients contrasted markedly with the odourous but cheerful and trolley-free wards of the modern fracture unit.

The change is not so much to be attributed to the end of the antiseptic era as to the end of a campaign for the recognition of the defensive powers of the body, when aided to the utmost by surgical ability. To this has been added the new weapon of chemotherapy, which gives just the little time longer for the body to organise its defences, which may make all the difference in the loss of life or the loss of a limb, in the severely wounded. The essential principles remain the same whether chemotherapy is used or not, and will not be altered by the addition of penicillin to the armoury. Each point in technique is directed towards reducing the available nutrient material for bacteria, and assuring that the wound cavity is lined

with viable cells among which no pocketing or pressure on retained products can develop. The principles concerned will be pointed by the discussion of their practical application, but may be theoretically set out as follows.

1 TIME. The stabilisation of the defences of a wound occurs in thirty six to forty eight hours. After this time any interference with a wound which is at all extensive may open up new paths for the spread of infection. Bacterial infection is lowest immediately after the infliction of a wound, and it therefore follows that this is the best time for surgical treatment, and with increasing delay it becomes less and less propitious, till when defence and infection are balanced it becomes unwise.

2 REDUCTION OF BACTERIAL MULTIPLICATION. The avoidance of further soiling of the wound is merely common sense. The more subtle part of surgical technique is the deprivation of the bacteria of any nutrient media. For this reason the soiled walls of the wound are excised and damaged tissues removed. Haemostasis must be perfect, for clotted blood becomes a fine breeding ground, and excessive moisture is to be avoided as being equally necessary to bacterial reproduction.

3 AVOIDANCE OF BACTERIAL SPREAD. The spread of organisms is aided by the movement of tissue planes on each other preventing a fixed line of granulation tissue defence being formed. The pressure of retained products and the re-infection of the wound with fresh strains of organisms may also be important. For this reason wounds in which infection is likely to develop must not be closed, but lightly packed and enclosed in a plaster cast.

Wounds fall into two great classes, those in which closure of the skin is possible and those in which it is impossible. In the latter group, excluding those cases in which immediate skin grafting can be employed, there is no alternative but to leave the wound open. Although infection will follow, when treated by the closed plaster method and early skin grafting the result will in the end be highly satisfactory.

The group of cases in which the skin can be closed may provide controversial material. It is obvious that this is the ideal to aim at and is the correct line of treatment in a clean wound seen and treated early. In a contused wound seen some hours later, or in a compound fracture with marked muscle damage, it may be unwise. This group of cases may therefore be subdivided into —

1 Those in which primary closure is safe and should be carried out.

2 Those in which it is unwise owing to the risk of infection, such cases being treated by the closed plaster method, with light packing of the wound.

The practical points which are determined by these principles will now be discussed

1 **TIME** The time factor already mentioned must be enlarged upon. The earlier the treatment of a wound under surgical conditions the better, but it has been found that treatment can be carried out with benefit many hours after the infliction of the wound. The absolute limit of time at which it can be carried out cannot be stated, but is somewhere between thirty-six and forty-eight hours. Joints, whose importance merits complete treatment, are very resistant to infection and show a satisfactory response to adequate debridement, suture of the synovial membrane and drainage down to the suture line, twenty-four to thirty hours after wound infliction. The use of chemotherapy has been in part responsible for the ability to interfere effectively later than was thought wise before. A wound adequately treated with penicillin and sulphonamide in a patient who has had adequate parenteral chemotherapy, will be less seriously infected on arrival at the theatre, and a wound more seriously infected will be given a breathing space after excision in which to organise its defences. In dirty, late, untreated wounds treatment is limited to removal of foreign bodies and the excision of dead tissue to improve drainage. Local and general chemotherapy are then continued.

2 **ANTISEPTICS** The application of any chemical substance or solution other than normal saline, or small quantities of the chemotherapeutic drugs, to the walls of a wound which is to be sutured is to be condemned. They can do nothing but harm. If watery, they increase the oedema of the tissues, which absorb water, if hyperosmotic, such as spirit or iodine, they are equally dangerous to the cells by dehydration. On the surfaces of a wound to be excised they are less open to objection. Iodine is a useful antiseptic for the skin, but in the wound it must be used sparingly. The use of a moist swab dripping with iodine is to be avoided, but a well wrung out swab has the advantage of dyeing the damaged tissues a deep brown while viable tissue remains a pale yellow. The use of a "frosting" of sulphonamides and penicillin on the wound surface is not strictly to be compared to the use of an antiseptic.

3 **DRYNESS** In order to combat the development of bacteria which flourish in a moist medium it is advantageous to keep the wound as dry as possible under all circumstances. It is further important in encouraging clotting. This fundamental will be referred to again, but it is placed here on account of its importance, and that an early paragraph may be used to cry out against the prevalent practice of soaking a wound as soon as it is seen in a solution of acriflavine, saline or water. This can do nothing but harm. Firstly, it washes more dirt as a rule into the wound than out of it. Secondly,

it results in the death of the living cells on the surface of the wound, which absorb the water by osmosis and burst their cell membranes. Further absorption in the wound makes it oedematous and this favours bacterial multiplication. To these points may be added the washing away of the blood which is bactericidal for a short time, and the increase in blood loss if the water is warm, and so dilates the blood vessels. If strong antiseptics are used the damage may be more serious. All these points are potent arguments against the use of water in any form near a fresh wound, and it will be found that a casualty department working on the dry principle will reduce the incidence of infected lacerations by 30 to 40 per cent.

A wound when freshly seen should have any very gross dirt wiped away from it by dry gauze, and then have a dry gauze dressing applied to it till the case can be taken to a theatre and the correct treatment instituted. Should the wound be haemorrhaging seriously a tourniquet may be applied, or the vessel caught with forceps if it can be seen, or the pressure of the dressing may be relied upon to stop it.

4 PREPARATION POINTS The use of a clean set of dissecting instruments for every major wound is essential and for every minor one desirable. The disturbance of the patient by transfer to the ward, from stretcher to bed, undressing, bed to stretcher, and finally stretcher to theatre table is best avoided by sending the patient to the theatre at once, and utilising the anaesthetic room as resuscitation ward.

With larger numbers of injured the use of a multi bedded resuscitation ward amply proves its value. The preparation of the skin for operation, and the final removal of clothes can often best be done under the operation anaesthetic. Under certain circumstances it may be desirable to use a small injection of pentothal in the ward if there is to be much pain or disturbance of the patient.

A separate preparation trolley should be available containing a bowl of ether soap, a bowl of methyl-ether if the contamination is greasy, a bowl of sterile saline, iodine or spirit. Shaving the skin is unnecessary unless the part is particularly hairy. Even in the scalp close clipping is satisfactory. The wound is then packed with sterile swabs (Fig 39) and the surrounding area of skin cleaned, wiping away from the wound. Soap is first used, this is washed off



FIG 39 Cleaning up a wound. A roll of gauze is placed in the wound and the skin cleaned away from the edges of the wound with a swab held in forceps.

with water or saline and the skin then dried. A final application of spirit or iodine completes the preparation. The wound swabs prevent contamination of the wound with the washings and the exudation of blood which makes cleaning impossible. At the end of the skin toilet the swabs are replaced by fresh ones and the limb wrapped in a sterile towel. In many cases an Esmarch's bandage, by producing complete hæmostasis, facilitates the identification of injured




FIG 40 With a roll of gauze still in position the skin almost up to the edges of the wound is painted with iodine. Small blebs are raised in the skin with local anæsthetic and then the edges of the wound infiltrated by injections along the lines indicated by the arrows.




FIG 41 The protective gauze roll is now removed and the whole wound may be swabbed with iodine. The area is towelled. The shaded area indicates the margin of skin on the edge of the wound which is excised.

tissues, and their accurate debridement. After cleaning the wound it is released and hæmostasis assumed. The surgeon then scrubs up preparatory to the complete excision of the wound. The towelling off of the area is completed and the removal of the swab is the first step before commencing.

5 LOCAL ANÆSTHESIA For most small wounds this is very satisfactory. It is however a time consuming method for multiple injuries and is contra indicated in wounds in which chemotherapy is subsequently to be used. The length of time added to the operation must be weighed against its useful effects on shock.

LOCAL TECHNIQUE With a fine hypodermic syringe weals are raised on the iodined skin $\frac{3}{4}$ to 1 inch from the wound edge, at spots

appropriate to the infiltration of the edges of the wound. Novocaine, 1 to 2 per cent, is satisfactory, and it is better not to add adrenalin to it. Excess local anaesthesia entering the tissue spaces washes out of the wound, but this is washing the debris in the right direction, out of the wound. Under no circumstances is the needle entered into the tissues through the wound surface. In spite of the increased water content of the tissues near the wound local anaesthetic does not make the wound sodden as there is no cell destruction and it is rapidly absorbed. No adverse influence on healing can be detected. The wound surface is now anaesthetised, and if desired it can be lightly painted with iodine before towelling the wound up preparatory to excision.

6 EXCISION OF THE WOUND This commences at the skin edge, which is removed for a distance of $\frac{1}{8}$ to $\frac{1}{4}$ inch all round, avoiding making small indentations, so that a smooth clean edge is left. In most areas, particularly the scalp, this can best be done with the knife, but in certain areas where the skin is fine the scissors will be most useful. Where possible the incision will be carried through the subcutaneous fat to the fascia, so that the whole soiled surface of the skin and subcutaneous fat is excised at once.

Loose tags of fibrous tissue, tendon, and muscle will be seen and excised, till all the tissues seen have a fresh and clean appearance. In perforating wounds it will be necessary to enlarge the skin wound to allow it to be explored to the bottom. This is essential to avoid leaving foreign bodies in the depths of the wound.

7 AVOIDANCE OF BURIED FOREIGN BODIES Not only must no debris be left in the depths of the wound, but it is advisable not to leave any catgut or other suture material buried in the wound unless it is absolutely necessary. This can usually be avoided, unless a large vessel is cut, by the judicious use of deep silk worm tension sutures. Tendons, in a wound which cannot be closed or is likely to become infected, are best left to a set operation when the wound has healed and merely tacked down to avoid retraction. In clean wounds nerves and tendons should be sutured. In wounds which are to be left open they may be tacked down to avoid retraction. Risk of damage to nerves from excessive local use of sulphamylamide should be remembered.

8 HÆMATOMA This must be reduced to the minimum possible by the careful suture of the wound, in which deep tension sutures will play an important part. Where it is impossible to stop oozing a small drain must be placed in the wound. The choice of the site for drainage must depend on the shape of the laceration, the most dependent point, and the site of the laceration. It is not always wise to drain through the wound itself, and a small puncture wound

at a chosen spot in a skin flap is often more satisfactory. Where only a small amount of oozing is expected a few strands of folded silkworm gut will be a sufficient drain. For larger drainage some rubber dam may be used. Such drains should be removed at the end of twenty-four hours.

9 SUTURING Of the many materials suitable for suture the most satisfactory will be found to be silkworm gut, stainless steel wire, or waxed thread. Such sutures are strong, non absorbable, but above all, non absorbent, and do not carry moisture and with it infection from the surface into the deeper tissues.

It is extremely important that the skin edges be brought as closely together as possible, that the blood may clot between them rapidly and so seal the deeper layers of the skin off. One of the most satisfactory sutures for doing this is a mattress suture passed deeply through the tissues on either side and then back through the skin edges and tied. Such a suture obliterates any space which may be present in the tissues by pressure and at the same time brings the skin edges accurately together, while slightly everting them, so that there is no infolding and accurate apposition is possible. It also relieves

the skin edge of strain and exerts sufficient pressure on the subcuticular vessels to control hæmorrhage. The appropriate number of these stitches for a wound varies with the type and site of the wound. No fixed distance can be given, the number being determined by the readiness with which the skin is approximated, and sufficient being inserted to get the accurate apposition required. In between the mattress suture a few smaller stitches are placed to bring the skin edges into still more complete apposition. Suturing under any great tension is to be avoided. The relaxed position of the limb, undercutting the flaps, and appropriate incisions may make the union of the skin easier. When the wound is sutured it is dried well with a swab wrung out in spirit, and a dressing of dry gauze applied to it and bandaged on. The use of an air-tight dressing such as strapping completely covering the




FIG. 42 The finished suturing showing the everted skin edges

- A Deep retention and approximating sutures
- B Finer suture for close approximation of the skin edges

wound is to be condemned as it keeps the wound moist. Strips of strapping over gauze have not this objection. There is not always the necessity for a bandage dressing, but it helps to control oozing and absorbs the discharge which occurs in the first few hours. In small wounds this is unnecessary and sticking one or two layers

of gauze over the wound with tinct Benzoin Co is sufficient. If a bandage is used it should be removed in four to six hours and the wound left exposed to the air.

10 ABSOLUTE REST In order to avoid disturbance of the tissue spaces which are being repaired, and the formation of fresh hæmatomas in the wound, absolute rest is essential. Inadequate fixation is useless, and it will be found that in the majority of cases only plaster gives that immobilisation which is necessary. This absolute immobilisation does not need to be maintained for more than forty-eight to seventy-two hours as a rule. If the wound is dry and satisfactory at the end of this period then some movement may be allowed, but if there is any suspicion of infection or moisture it is kept at absolute rest.

A further important point is the avoidance of swelling. This is best done by elevation of the part. An injured leg is rested on a



FIG 44 Padded wire finger splint bandaged in position to immobilise the fourth finger after a compound fracture of the terminal phalanx (See Fig 102)




FIG 43 Diagrammatic section of the sutured wound

- A Fine approximating suture
- B Deep mattress suture for retention and hæmorrhage
- C Hæmatoma
- D Small blood vessel controlled by the mattress suture
- E Muscle
- F Fascial sheath
- G Subcutaneous fat
- H Skin

Braun's splint in bed Arm injuries if mild may be merely kept recumbent, but if there is a serious lesion of the forearm Zeno's position should be used (Fig 248)

11 FRESH AIR TO THE WOUND It is essential for sound clotting on the skin that the blood poured out be able to lose some of its water content. The necessity for a dressing for the first hour or two

has been emphasised, but after this the wound is best exposed to the air. If the limb is in plaster, a window may be cut, but plaster being porous allows very satisfactory circulation of air, and unless the discharge is profuse, windowing is unnecessary. Under no circumstances should an airtight dressing be applied as may easily be done if strapping is not carefully used. Only dressings should never be used if primary union is anticipated. Thus, of course, applies only to wounds which can be closed.

If these comparatively simple rules are followed it will be found that the number of septic wounds in any casualty clinic is greatly reduced with a corresponding absence of stiff fingers, granulating




FIG 45 The correct method of applying strapping dressings to provide ventilation A = Gauze B = Strapping

wounds, and persistent sepsis, which wastes so much of the time of a casualty staff.

Chemotherapy

The opportunities provided by the war have enabled the chemotherapeutic agents to establish themselves on a rational basis in much less time than many equally revolutionary innovations. They have been viewed by some as a return to the era of antiseptics, but their action is far more subtle than the sledge hammer blows of mercury or carbolic.

Sulphonamides The sulphonamides are more bacteriostatic than bactericidal, delaying by the deprivation of *p*-amino benzoic acid the reproduction of the organisms in the tissues and so allowing time for the deployment of the forces of defence. The chemical structure of the sulphonamides resembles that of *p* ammo-benzoic acid. The enzyme group in the bacterium responsible for the absorption of the amino acid attaches itself to the useless sulphonamide and its activity ceases. Unfortunately the organisms have a greater affinity for the *p* amino-benzoic acid and the sulphonamide to be effective must be present in far greater concentration than the amino acid. Thus 1 part of *p* ammo benzoic acid requires 1 600 parts of sulphanilamide,

36 parts of sulphathiazole, or 100 parts of sulphaguanidine to neutralise it. It follows from this that the question of the availability of the drug in the infected tissues is of paramount importance to its effectiveness, and questions of local application, solubility and rate of excretion of the drug have to be considered. Certain substances have also been found to inhibit the action of the drug. Of these there are two it is necessary to mention. 1. The presence of pus and necrotic tissue are inhibiting and the effects in established and inadequately incised wounds will be less than in the freshly excised wound. 2. Other chemicals containing the *p* amino benzoic acid group may form a source of supply neutralising the action of the drug. Of these the local anæsthetic known as "novocaine" or "procaine" and by many other proprietary names is an example. It follows that the use of this anæsthetic in wounds subsequently to be treated with sulphonamide is contradictory, if not absolutely contra indicated.

Two other situations in which it is undesirable to use sulphonamides should be mentioned here. In wounds of the cerebral tissues it produces irritation with subsequent scarring and risk of epileptiform convulsions, and should not be used. In wounds with exposed nerves it is similarly deleterious, producing an interruption of the nerve path, with subsequent intraneural fibrosis and permanent nerve damage.

Specific action. The greater effectiveness of certain of the sulphonamides against certain organisms is probably due to the achievement of more effective concentrations, due to different physico chemical properties rather than to any specificity between any organism and the drug. Thus the greater solubility of sulphamylamide renders it useful in fresh wounds where immediate effective concentrations can be obtained. At the same time the rapid absorption reduces its time of action. Sulphathiazole, which has a greater bacteriostatic power, is less soluble and may be used with sulphamylamide to prolong the action of the drugs against the organisms. A proportion of three parts of sulphamylamide to one of sulphathiazole is recommended. This should be done up in sterile containers and be available in the theatre, where it is lightly "frosted" over the wound surfaces with a blower or dusted through gauze on to the wound. Under no circumstances should lumps of the powder be left in the wound or the wound actually packed with the drug. The total amount used in a large wound should not be great, but in any case should not exceed 15 grams. It is convenient to have the drug weighed out in this amount in each container. Care must also be taken that the rise in blood sulphonamide which follows six hours after its implantation into the wound must not be followed too soon.

by the rise from the oral administration of the drug, otherwise a dangerous level may be reached. Maintenance of an adequate level of the drug in the blood is essential as there is some evidence that micro organisms may become drug resistant if exposed to low concentrations.

The wide range of organisms encountered in infected wounds (see p. 93) makes the non-specificity of the sulphonamides important. Were they more specific the difficulty in establishing the appropriate drug might be troublesome. Nevertheless some specificity is present. Sulphanilamide is more potent against hæmolytic streptococcal infections than any other member of the group, and much less effective against staphylococci than sulphathiazole. Hence the value of the combined use of the drugs. If one drug is to be used alone sulphathiazole should be chosen. The non-hæmolytic streptococci are as a rule insensitive to the sulphonamides, and when encountered as the chief element in an infection must be submitted to a sensitivity test *in vitro*. A course of treatment may be begun in the meantime, as it can do no harm. The relatively lower antibacterial effect on the staphylococci than on other organisms has been the weak spot in the chemotherapeutic armour, now, it is hoped, happily covered by the discovery of penicillin, which is almost specific in its action against these organisms.

Dosage. The attainment of an effective concentration of the drug in the blood may be rapid or slow, according to the urgency of the case. In severe infections a blood concentration of 6-7 mgms is aimed at. In milder conditions 3-5 mgms is satisfactory. These are roughly achieved by the dosages set out below. Having achieved the right level it is maintained by a series of reduced doses. Prolonged administration of the drug is dangerous, and to avoid this it is important that the total amount to be given in grams should be written on the temperature chart, together with the day the course will end. The amount given daily is also written in grams (not in tablets, which normally contain half a gram).

Severe infections. Dosage is commenced with the administration of 2-4 grams intravenously and 1.5 grams by mouth. Maintenance doses are given on the following days —

First and second days, 1.5 gms four-hourly

Third and fourth days, 1 gm four-hourly

Fifth and sixth days, 1 gm six-hourly. Total, 4.4 gms

Milder infections. Dosage is started by the oral administration of 2 gms, followed by —

First and second days, 1 gm four hourly

Third and fourth days, 1 gm six hourly

Fourth and fifth days, 1 gm eight hourly. Total, 28 gms

For the children the dosage may be calculated by multiplying the adult dosage $\frac{\text{age}}{15}$, remembering that the young tolerate the drug very well, and that at the ages of one to three the dose should be doubled

TOXIC REACTIONS Serious toxic reactions are uncommon. The **CYANOSIS** produced by the formation of methæmoglobin or sulph-hæmoglobin may be disregarded. **VOMITING** is an annoying complication, rendering even dosage difficult. It may be met by reducing the dosage, or combining it with alkalis, or by changing the type of sulphonamide used. In serious cases a change from oral to intravenous or intramuscular administration may be made. **DRUG FEVER** may be confusing if not recognised. It occurs during or just after the administration of the drug, usually about the eighth day. As this often corresponds to the cessation of a course of treatment, the rise may be confused with a recurrence of infection. The withdrawal of the drug produces a dramatic fall in temperature. **LEUCOPENIA**. A mild degree of this is not uncommon, and the use of the drug nullifies to some extent the value of the white blood count. Serious leucopenia, *i.e.*, below 2,500 w b c's, is rare but very important. Premontory signs may be lassitude, pyrexia, and an ulcerative pharyngitis. **RENAL COLIC**. This may be easily produced if an adequate fluid intake is not insisted on. Four to six pmts daily should accompany the taking of the drug. **HÆMATURIA** and **ANURIA** are less frequent if more serious complications.

Penicillin. The discovery of penicillin by Sir Alexander Fleming in 1929, is one of the most dramatic chapters of modern medical history. If its discovery was the flash of genius, its re-discovery and evaluation by Sir Howard Florey and his co-workers represents the more patient side of medical research. Its peculiar effectiveness against the staphylococcus and the clostridia make it an invaluable ally against infection of wounds, particularly the compound fracture. Its freedom from toxic side effects is particularly helpful. Its use has rendered some surgical re-orientation necessary with regard to osteomyelitis, and infected wounds, and this is not yet complete. The drug is readily tolerated, but as readily excreted, and difficulty is met with in maintaining an adequate concentration in the blood. It is unsuitable for oral administration and has to be given by intramuscular or intravenous routes. Systemic administration may be combined with local application as in the case of the sulphonamides.

The drug comes as a dry brown powder, soluble in water or normal saline. Packed in glass ampoules it can be stored at low temperatures for some time without deterioration. In solution kept at 1-4° C it can be kept four days.

Three forms of Penicillin are at present available —

- | | |
|------------------------|---|
| (1) Barium Penicillin | Used as the standardising agent |
| (2) Sodium Penicillin | Used for intravenous and intramuscular administration |
| (3) Calcium Penicillin | Used for powders and ointments as it does not deliquesce and is more stable
It is unsuitable for intravenous and intramuscular use, being irritating |

In general, the drug acts as a bacteriostatic agent on the Gram-positive organisms. A wound effectively treated with the drug will thus show a Gram-negative flora.

Sensitive Organisms

Staphylococcus, aureus, albus

Streptococcus, hæmolyticus

Streptococcus, pyogenes

Clostridia Welchii

Clostridia Oedematiens

Clostridia Septique

Clostridia Tetani

Bacillus Anthrax, etc

Clostridia

of

Gas Gangrene

Insensitive Organisms

Streptococcus Viridans

Proteus

Pyocyaneus

Bacillus Coli

Streptococcus Fæcalis,

etc

Complications from treatment are rare as the drug is non-toxic. There is a tendency to venous thrombosis when the intravenous route is employed. Pain may be complained of after intramuscular injection. Fever is occasionally due to impurities. Urticaria is the only mild toxic reaction at present noted.

MODES OF ADMINISTRATION 1 *Powder form* This has been applied to wound surfaces in the same manner as sulphonamides, with which it may be conveniently combined. The penicillin being in concentrated form is spread more evenly by the dilution of the other powder. Dosage varies according to the size of the wound up to 200,000 units.*

2 *Local application of the solution* Very satisfactory results have been achieved by this method. The penicillin is made up in a strength of 250 units per c.c. of normal saline, and the wound irrigated by tubes buried under light packing in the depths of the wound after the manner of the Carrel-Dakin method (p. 99). Wounds involving bone and heavily infected with staphylococcus aureus heal rapidly. No reduction in sequestration is to be expected in fresh wounds, but more rapid localisation of infection may restrict spread to decrease secondary bone involvement.

* The drug not being clinically pure is standardised according to its effect on an organism of known type and virulence and its effect expressed in units of activity. Doses of equal unit value may therefore not be equal in size and its unit value will alter with its age.

3 *With an ointment* Combined with lanoline, and if desired, sulphathiazole, in quantities of 500 units per gram Useful for burns and plaster dermatitis

4 *Continuous intramuscular drip* The rapidity of excretion renders dosage by intramuscular injection unsatisfactory, as the serum level falls below the effective minimum before the next injection unless these are unpleasantly frequent Continuous intramuscular drip either subpectorally or into the thigh is most satisfactory A dosage of 4,000 to 6,000 units an hour is required, and this is made up in normal saline, 100,000 units or more in 600 c.c. of saline Administered accurately at the rate of 5-8 drops per minute this amount will provide accurate dosage for a day

If the interrupted intramuscular route is adopted, 20,000 to 50,000 units are given every three hours At longer intervals the blood concentration falls below an effective level if the dosage is not much increased To save the patient discomfort, and to avoid wasting the time of the staff, a little more than double the three-hourly dosage may be given six hourly—(50-100,000 units)

5 *Intra articular* The drug appears slowly in the synovial fluid after parenteral administration and requires a higher blood-level to maintain an effective concentration Where there is risk of joint infection e.g., from neighbouring osteomyelitis or from penetrating wounds, local injection into the joint is the most rapid and effective way of treating the case Sodium Penicillin* is employed in varying amounts For the knee 50,000-100,000 units in 10 c.c. of normal saline is a suitable dose Its duration in the joint is not accurately known, being affected by the presence of blood, fractures into the joint, whether or not the synovial fluid is increasing and the like, but it remains for at least twenty four hours Daily re-institutions are therefore satisfactory

A course of treatment by any route lasts several days to four weeks It is varied in length and strength according to the clinical condition of the patient Thus it may be given for forty eight hours after a wound and discontinued if there is no rise in temperature In the presence of infection it should be continued longer, but its effectiveness is much reduced in a granulating wound, and once an effective localisation of the infection has occurred, may be discontinued and recommenced when any interference is contemplated One of its most valuable advantages is the reduced risk of a flare of infection after any early attack on an infected bone, its facilitation of secondary suture, and skin grafting There is much to be said clinically and bacteriologically for interrupting the course with an occasional day's rest It relieves the patient, allows assessment of

* In crystalline form

the patient's condition without a bacteriostatic, and as penicillin attacks young forms of bacilli, may by permitting fission of older organisms aid its effectiveness. At the end of a course the drug is discontinued and the results assessed. Another course may, if desired, be commenced after a short interval. Causes of failure may be (1) Inadequate dosage, (2) Insufficiently frequent dosage, (3) Non-susceptible organisms, (4) Old and inactive penicillin, (5) Failure to reach the site of infection with the penicillin.

Effects of Penicillin Either combined with sulphonamide or used alone the drug will not prevent infection of a wound. It will alter the bacterial flora, and tip the balance in some infected wounds towards primary union, while the serious sequelæ are diminished. The percentage of cases suitable for early secondary suture is far higher in cases treated with penicillin, due to an absence of serious infection. It is an adjunct to good wound surgery but does not replace it. The drug may be used as a prophylactic in the later treatment of the wounded when fresh dressings or operation is required, e.g., a secondary amputation, in the hope of reducing the complications. One hundred thousand units are then given in the twenty four hours before operation and continued for two days or more afterwards.

In chronic osteomyelitis the drug is extremely useful in healing old wounds with a heavy staphylococcal infection. It is then used locally as an irrigant and may be combined with systemic administration. In staphylococcal septicæmia it may be life-saving in massive doses. No serious complications have been reported from its administration in large quantities. In grafting its use on the granulating surface results in a disappearance of the Gram-positive organisms and an increased percentage of "takes."

Proflavine This is a member of the acridine compounds, of which the most familiar is acriflavine. Acriflavine has achieved little success, but the application of proflavine in solid form seems to hold distinct possibilities and has been proved successful in the treatment of chronic wound sepsis. Applied in large amounts to a wound the substance produces necrosis, it therefore has to be used carefully, and a combination with sulphathiazole of one part to 100, provided adequate dilution with the reinforcement of the sulphonamide. The value of the drug lies in its slow solubility, local concentrations of proflavine remaining in the tissues for some time. Such a powder is used in an analogous way to that described for the sulphathiazole sulphanilamide mixture.

PROPAMIDINE This has similar actions to proflavine and its specific uses have not yet been worked out. It appears to be beneficial in the treatment of tubercular abscesses and is effective in chronic infections.

STREPTOMYCIN While this is specifically designed for attack on the tubercle bacillus, it exerts remarkable effects when applied locally to chronically infected wounds, such as varicose ulcers. It may thus prove valuable in the chronically infected traumatic wound.

Chemotherapy in Wounds

Prophylactic The immediate dusting of the flesh wound with the combination of sulphonamide and sulphathiazole recommended, is good first aid treatment, and if available should be applied under the first or "shell" dressing. The limit of 15 gms. previously mentioned should be observed. The introduction of the powder into the depths of the wound is impossible under first aid conditions and should not be attempted. For this reason, and in an attempt to reach the depths of the wound, the oral administration of the drug to the freshly wounded has been employed. This method can be used as a less desirable alternative.

Combined powders The use of powdered calcium penicillin in wounds is rendered difficult by its concentration and rapid absorption. To prevent this the drug has been enclosed in a semi-permeable membrane to allow slow diffusion. More convenient and logical, however, is its use mixed with a powder of the sulphonamide group, dilution of the penicillin and combined action against organisms is thus obtained.

Common combinations used are —

- (1) Sulphathiazole, 1 gm., penicillin, 5,000 units
- (2) Sulphathiazole, 1 gm., penicillin, 5,000 units, proflavine, 1 per cent
- (3) Sulphanilamide, 3 gms., sulphathiazole, 1 gm., penicillin, 20,000 units

Curative After excision of a wound the sterile powder should be scattered over the surface of the wound to produce a light "frosting". The wound may then be sutured, or packed and the "closed plaster" method of treatment may be proceeded with. In general, under battle conditions, the latter is the safer procedure. Where the risk of infection is considered high, local application should be supplemented by oral administration. Care should be taken that the oral administration of sulphonamide should not be commenced till the peak of absorption from the wound is on the decline, i.e., after six hours. The value of the drugs in avoiding infection altogether, or in reducing the seriousness of infection, has been commented on before. Thus it enables amputation in the presence of sepsis to be carried out more safely and at a lower level.

TREATMENT OF GRANULATING SURFACES The powdering of the surface of a granulating wound with a sulphonamide penicillin mix-

the patient's condition without a bacteriostatic, and as penicillin attacks young forms of bacilli, may by permitting fission of older organisms aid its effectiveness. At the end of a course the drug is discontinued and the results assessed. Another course may, if desired, be commenced after a short interval. Causes of failure may be (1) Inadequate dosage, (2) Insufficiently frequent dosage, (3) Non susceptible organisms, (4) Old and inactive penicillin, (5) Failure to reach the site of infection with the penicillin.

Effects of Penicillin Either combined with sulphonamide or used alone the drug will not prevent infection of a wound. It will alter the bacterial flora, and tip the balance in some infected wounds towards primary union, while the serious sequelæ are diminished. The percentage of cases suitable for early secondary suture is far higher in cases treated with penicillin, due to an absence of serious infection. It is an adjunct to good wound surgery but does not replace it. The drug may be used as a prophylactic in the later treatment of the wounded when fresh dressings or operation is required, *e.g.*, a secondary amputation, in the hope of reducing the complications. One hundred thousand units are then given in the twenty four hours before operation and continued for two days or more afterwards.

In chronic osteomyelitis the drug is extremely useful in healing old wounds with a heavy staphylococcal infection. It is then used locally as an irrigant and may be combined with systemic administration. In staphylococcal septicæmia it may be life saving in massive doses. No serious complications have been reported from its administration in large quantities. In grafting its use on the granulating surface results in a disappearance of the Gram positive organisms and an increased percentage of "takes."

Proflavine This is a member of the acridine compounds, of which the most familiar is acriflavine. Acriflavine has achieved little success, but the application of proflavine in solid form seems to hold distinct possibilities and has been proved successful in the treatment of chronic wound sepsis. Applied in large amounts to a wound the substance produces necrosis, it therefore has to be used carefully, and a combination with sulphathiazole of one part to 100, provided adequate dilution with the reinforcement of the sulphonamide. The value of the drug lies in its slow solubility, local concentrations of proflavine remaining in the tissues for some time. Such a powder is used in an analogous way to that described for the sulphathiazole sulphamylamide mixture.

PROPAMIDINE This has similar actions to proflavine and its specific uses have not yet been worked out. It appears to be beneficial in the treatment of tubercular abscesses and is effective in chronic infections.

STREPTOMYCIN While this is specifically designed for attack on the tubercle bacillus, it exerts remarkable effects when applied locally to chronically infected wounds, such as varicose ulcers. It may thus prove valuable in the chronically infected traumatic wound.

Chemotherapy in Wounds

Prophylactic The immediate dusting of the flesh wound with the combination of sulphonamide and sulphathiazole recommended, is good first aid treatment, and if available should be applied under the first or "shell" dressing. The limit of 15 gms previously mentioned should be observed. The introduction of the powder into the depths of the wound is impossible under first aid conditions and should not be attempted. For this reason, and in an attempt to reach the depths of the wound, the oral administration of the drug to the freshly wounded has been employed. This method can be used as a less desirable alternative.

Combined powders The use of powdered calcium penicillin in wounds is rendered difficult by its concentration and rapid absorption. To prevent this the drug has been enclosed in a semi-permeable membrane to allow slow diffusion. More convenient and logical, however, is its use mixed with a powder of the sulphonamide group, dilution of the penicillin and combined action against organisms is thus obtained.

Common combinations used are —

- (1) Sulphathiazole, 1 gm, penicillin, 5,000 units
- (2) Sulphathiazole, 1 gm, penicillin, 5,000 units, proflavine, 1 per cent
- (3) Sulphanilamide, 3 gms, sulphathiazole, 1 gm, penicillin, 20,000 units

Curative After excision of a wound the sterile powder should be scattered over the surface of the wound to produce a light "frosting". The wound may then be sutured, or packing and the "closed plaster" method of treatment may be proceeded with. In general, under battle conditions, the latter is the safer procedure. Where the risk of infection is considered high, local application should be supplemented by oral administration. Care should be taken that the oral administration of sulphonamide should not be commenced till the peak of absorption from the wound is on the decline, i.e., after six hours. The value of the drugs in avoiding infection altogether, or in reducing the seriousness of infection, has been commented on before. Thus it enables amputation in the presence of sepsis to be carried out more safely and at a lower level.

TREATMENT OF GRANULATING SURFACES The powdering of the surface of a granulating wound with a sulphonamide penicillin mix-

ture for five or six days will reduce the number of organisms present very considerably and so facilitate secondary suture of the wound or skin grafting. It is most conveniently applied direct to the wound by insufflation and the whole covered by tulle gras and moist gauze.

The use of chemotherapy in the treatment of gas gangrene is described on p. 103. The common association of burns and fractures




FIG. 46 Powder insufflator for sulphonamide or penicillin sulphonamide mixtures

demands that attention be drawn here to the value of a sulphanilamide penicillin cream in the treatment of burns. It may be conveniently applied and the whole limb encased in plaster, a combination impossible with other methods.

The treatment of abrasions. There are two types of abrasion, firstly the excoriated type, in which an area of superficial epithelial loss is furrowed by incomplete lacerations of the epidermis due to gravel and the like, and secondly the superficial type, in which the lesion is a smooth loss of epithelium resembling a second degree burn. It is important to eradicate dirt from such abrasions particularly on the face as it may be incorporated in the skin as a tattoo.

The first type is an exceedingly difficult type to clear up, requiring a superficial debridement combined with a number of excisions of small wounds. The second type is more readily cleaned up by the use of swabs well wrung out in saline. For large areas an anæsthetic of some kind will be necessary. After satisfactory cleaning up in small areas a coat of preliminary coagulant is given, such as iodine, or tinct. Benzoin Co. The important treatment, however, is the after-treatment. The area is left open to the air under a heat cradle, or in the vicinity of a radiant heat bulb. Under these conditions there is rapid drying of the surface serous exudate, producing a layer similar to that produced by tannic acid on burns. This layer is resistant to infection but has the disadvantage common to tanning that once infection has commenced it offers such resistance to its discharge that the infection tracks underneath it. For this reason it is advisable to aim at as thin a layer of inspissated serum as possible, and this is obtained by using iodine or dilute tinct. Benzoin Co. to commence with, and only making one application. The use of any moist compress over such an area usually destroys any chance of healing by primary intention. For large areas of abrasion the treatment must resemble that of a burn. After gentle cleaning with saline penicillin cream, or penicillin, sulphonamide powder and 'tulle gras' are applied and bandaged firmly on. Systemic penicillin is continued. Any infection of the

area will need a change over to hot saline compresses applied over the "tulle gras", several times a day, and with a dry dressing at night. The "tulle gras" is changed once a day only.

The treatment of large areas of skin loss This frequently presents a difficult problem. Where it is associated with gross damage to muscle and bone, and any possibility of covering the lesion with flaps is excluded, the limb may be enclosed in plaster after packing the wound with gauze, as described in the next chapter. Where the skin is stripped cleanly from the fascia of the limb, as is often seen in run over accidents due to the abrasion of the tyre, there is a temptation to stitch the skin back and hope for its survival, in spite of its doubtful vitality. Under these circumstances the skin should be cut away until bleeding occurs from the skin edge, and pressure on the margin of the flap shows some capillary response. These edges are then lightly stitched in position to the fascia. The rest of the raw area may be covered with Thiersch graft at once, if the patient is in fit condition, or if not the wound may be packed with "tulle gras" bound on under even pressure, obtained by packing the area with pledgets of cotton wool wrung out in liquid paraffin. Such a dressing may be left undisturbed for several days in the absence of any reaction of the patient. At the end of four to ten days the area is grafted. As an intermediate dressing for such areas gauze dipped in eusol and wrung out in paraffin is satisfactory.

REFERENCES

- ANDERSON, D. P. "The Problem of Wound Healing," *Ann Surg*, 1938, 108, 918.
- HARTWELL, S. "Surgical Wounds in Human Beings," *Arch Surg*, 1930, 21, 76.
- TRUETA and BARNES. "The Rationale of Complete Immobilisation in Treatment of Infected Wounds," *Brit M J*, 1940, 2, 46.
- GARROD, L. P. "Recent Advances in the Antiseptic Treatment of Wounds," *Bull War Med*, 1943, 3, 589. Useful summary with further references.
- THROWER, W. R., and VALENTINE, E. C. O. "Propamidine in Chronic Wound Sepsis. An Experimental and Clinical Study," *Lancet*, 1943, 1, 133.
- MITCHELL, G. A. G., and BUTTLE, G. A. H. "Proflavine Powder in Wound Therapy," *Lancet* 1942, 2, 416.
- TRUETA, J. "The Principles and Practice of War Surgery," London, 2nd ed., 1944 (Wm Heinemann and Hamish Hamilton).
- "Penicillin in Warfare" *Special issue of Brit Jour Surg*, 1944, Vol 32.
- JONES, G. BLUNDELL. "The Behaviour of Penicillin in Synovial Cavities," *Jour Bone and Joint Surg*, 1948, 30b, 106.

CHAPTER VIII

THE TREATMENT OF COMPOUND FRACTURES

Historical The compound fracture has been the occasional result of accident and the inevitable result of war since gunpowder was invented. The peculiar severity of the gunshot wound led to the suspicion that the bullet was poisoned, and when this was proved incorrect, to a still firmer grip on the public mind, of the superstitions with which the formation of pus, mortification and gangrene were surrounded. The rôle of Ambrose Pare (1510-90), who started the long work of clearing the dead weight of mediæval superstition from the shoulders of the experimentalist, is interesting reading in his own words. The process is nearly complete. It is interesting however to note the general reluctance of the public to leave a wound to nature. Everyone has their ointment or lotion guaranteed to heal better than their neighbours'. The popularity of the new chemotherapeutic agents is as much due to the fact that a magic remedy is available as to their proved clinical value.

The great strides in the treatment of compound fractures are not due to the sudden discovery of new principles. Excision of wounds was practised centuries ago, and was well described by Charles Bell 100 years ago, plaster is still more antiquated. The developments are due to a slow discovery that the powers of nature, when given ideal conditions to work under, are enormous, and can be relied upon as a defence mechanism. This attitude is the result of the work of physiologist, surgeon and bacteriologist, who have produced a continuous picture of wound pathology. Outstanding names in this story are few or many according to the wish of the selector. It is perhaps easier to fix a few dates marking progress than to attempt any analysis of credit.

1744-95 P. J. DESAULT Surgeon to the Hotel Dieu in Paris at the time of the French Revolution. He thus gained considerable experience in trauma and was responsible for advances in the treatment of fractures and wounds. His most important contribution was his insistence on the debridement of wounds, which though lacking a scientific basis till the work of Pasteur proved so successful that it was widely adopted.

1766-1842 D. J. LARREY He gained his experience as a pupil of Desault, and as surgeon to Napoleon who left 100 000 francs to "Larrey, the most virtuous man I have ever known". A humanitarian, beloved by his men, he sought to bring the wounded treatment as early as possible, and to this end developed the use of ambulances taking the hospital to the wounded. So efficient was his organisation that in the Egyptian Campaign he was able to boast that no patient remained more than fifteen minutes without attention. He thus carried on the tradition of excision and appreciated the value of early treatment. In addition, he made observations on the value of maggots in wounds, the onset of gas gangrene and trench foot.

1822-95 L. PASTEUR The work of Pasteur and his followers has provided the rational basis on which the pathology and treatment of wounds is based. The son of a soldier in Napoleon's army now settled as a tanner in the Jura. Pasteur started life in a humble fashion. The trail of his researches starting with crystallography and progressing through fermentation, spontaneous generation, diseases of wine and beer, diseases of silkworms to human disease is one of the most moving in medical history. Rarely has such affection for humanity, courage and devotion been combined with such intellectual

power and achievement. Affected by a stroke in the last years of his life, Pasteur died the most honoured "layman" in the profession.

1843-1910 **Koch** The work of Pasteur was nobly seconded by Robert Koch, who in 1876 was able to describe the complete life history of the anthrax bacillus. In 1878, his paper on infectious diseases of wounds appeared, in which he described the clinical and bacteriological findings in infections with six different types of micro organisms.

1827-1912 **J Lister** Following Pasteur's researches, Lister on August 12th, 1865, carried out the first successful operation on a compound fracture by his "antiseptic" method. This was dependent entirely on the use of carbolic acid. Lister paid great attention to the type of dressing used (double cyanide gauze is a relic of his work), and the arguments which grew around them, and his priority in the use of carbolic, would have embittered a man of less nobility of character.

1914-18 **FIRST WORLD WAR** This was still the era of antiseptics. Wound excision had been lost sight of, and the surgical tragedies of the first six months of the war necessitated a revision of technique. Excision was rediscovered, and its early success led to the attempt of universal primary suture. This produced a second crop of tragedies, and was responsible for the development of the Carrel-Dakin methods, and other less successful ideas such as the bismuth iodine paraffin paste, known as Bipp. Robert Jones, by insisting on the immediate immobilisation of the limb on a Thomas' splint, re-emphasised the principle of early treatment and rest. Lorenz Böhler, as the result of his experiences during the war, developed the principle of excision, complete rest, and the windowing of the plaster over the wound. Thus wounds lay in a bath of pus, but this was not disturbed more than necessary. He thus approached closely to the "closed plaster" method. Böhler's chief contribution to the surgery of fractures is, however, regarded as the development of mechanical methods of reduction and the organisation and segregation of fracture cases. Böhler first proved that this had an economic as well as a therapeutic value and so laid the foundation stone of all accident hospitals.

1929 **WINNETT** Oan, as a result of his experience with osteomyelitis which he successfully treated by pack and immobilisation in plaster, applied the same principles to the treatment of infected compound fractures with great success. The infrequency of dressing, the comfort of the patient, and the satisfactory progress were impressive. It was not long before it was used as an immediate line of treatment for compound fractures with impressive results. In England, after Orr's visit in 1930, the method made little progress, probably because of the difficulty of evaluating any method without individual experience of large numbers of cases.

1933 First reports of the value of the sulphonamides began to appear in Germany. In 1935 its value was experimentally assessed in England against puerperal sepsis, and since then there has been a steady increase in numbers of the sulphonamide family synthesised and their use.

1936-39 **The Spanish War** provided the first large field for the use of new methods. **J TRUETA**, who had been working with this technique in civil surgery with good results, slowly popularised the method which became known as the "Closed plaster method". His efforts in this country at the outbreak of the present war were largely responsible for the dissemination of the fundamental principles underlying the method, and the insistence that it was no simple and infallible road to success but demanded qualities of experience, and judgment in the surgeon of the highest order.

1939-45 **SECOND WORLD WAR** In spite of the experiences of the past,

and the recent lessons of the Spanish War, much remained to be re learned and re discovered. Excision was not firmly established. Abortive methods to apply the "closed plaster" technique without adequate debridement were made with disastrous results. Slowly the experience gained, coupled with a better organisation for the diffusion of knowledge, led to the complete evaluation of methods and improvements in technique. Coupled with the use of transfusion, intravenous salines, and the new chemotherapeutic agents, a survival rate unexampled in previous wars was achieved.

1940 SIR HOWARD FLOREY decided to investigate afresh the properties of the available antibiotics. Unknown, Penicillin was lying to hand, having been discovered by Sir Alexander Fleming in 1929, following the accidental contamination of a petri dish containing staphylococci with the mould. A re examination of its promising properties was undertaken, which established its enormous clinical value. With Britain fully extended, it was impossible to set aside the necessary machinery and manpower for its preparation. Its first commercial manufacture was thus begun in America. Neither it nor the sulphonamides affect the standard principles of wound treatment. The best they do, and it is much, is to modify the method chiefly with regard to the time factor, and the risks of its application.

THE principles of treatment of compound fractures are exactly similar to those outlined for the treatment of wounds of the soft tissues. It is merely necessary to analyse the complications added to a wound by the fracture of a bone to complete a discussion of compound fractures. The added complexities are as follows —

1 *Increased shock*, with greater depth of wound, and increased soft tissue damage.

2 *Loss of rigidity of the limb*. This is the most important feature and leads to several secondary complications. There is first a loss of fixity of soft tissue planes which results in spread of infection by the exposure of new planes to infection on movement. Drainage is also impaired. Secondly there is the necessity for fixing the fracture, which modifies, and usually complicates the fixation of the soft tissues.

3 *Sepsis* is more frequent due to the factors outlined and the susceptibility of bone to infection is greater, due to its slow mobilisation of defence.

4 *Persistence of infection*. Due to the slow changes in bone the soft tissues are apt to overcome infection first and fibrose down with the formation of sinuses and the retention of sequestra.

5 *Adhesions of soft tissues*. From the functional point of view this is most important and is the bugbear of all traumatic work. It is particularly troublesome if infection persists.

The same considerations of time of shock, and of suture govern a compound fracture as govern a large wound, and will not be repeated here. The treatment of the various structures met with in excision may be summarised as follows —

Skin and subcutaneous tissues Excision of the contaminated surfaces of these tissues down to the level of the fascia, avoiding excessive removal of skin, and leaving a regular clean edge

Fascia and fibrous tissue Removal of all loose tags Where the fascia is soiled an attempt may be made to clean it and if this fails it must be excised One must often weigh the chance of spread of infection by removal of a fascial barrier against the chance of infection by leaving soiled tissues More important is the barrier offered by fascial planes to efficient drainage in the wound which is left open It is often safer to divide the fascia transversely where this risk exists, so that retraction of the ends offers a wide path of escape for exudates An essential part of excision is incision to allow free drainage and saucerisation of the wound No fear must be felt of a wide and free opening of all tissue spaces

Muscle All seriously bruised muscle must be removed, and all loose portions, so that fresh living cells only remain

Tendons All loose tags are cleared up The answer to the vexed question of tendon suture is dependent on the risk of infection of the wound The importance of the tendon has also to be considered In a laceration tendons should certainly be sutured In a contused wound the tendons should be sutured to an underlying structure to avoid the subsequent retraction which may make secondary suture impossible Fine stainless steel wire is the most satisfactory suture material where infection is not anticipated

Nerves Nerve ends are freshened and sutured together by the nerve sheath with a few fine silk sutures

Blood vessels These are caught early and left clamped if possible during the rest of the operation At the end of the operation they are tied if necessary Large vessels must obviously be tied, and this may be done at once

Bone Only the soiled surfaces are removed by the use of the nibbling forceps or the chisel and hammer, this normally applies to the soiled sharp ends of bone only Small fragments of bone are removed if they are severed from all soft tissue connection Large fragments are always retained as there is a definite risk of non union if a large gap is left between the bone ends Even if completely detached they may act as bone grafts in a clean wound In an infected wound they may also lead to some new bone formation around them before being thrown off as sequestra

In general, all non-viable tissue is removed and an attempt made without the sacrifice of living tissue to make the wound a flat and shallow one into which the gauze can be easily packed if the wound is to be left open If it is to be sutured these considerations do not hold There is no objection to draining a sutured wound for twenty-

four to forty eight hours, and where there is much bleeding from bone ends this is often desirable

Compound fractures fall into two great groups —

(A) THOSE WHICH CAN BE COMPLETELY CLOSED, as the skin loss is negligible This is ideal but may not be desirable, as in the case of war wounds of any severity Accordingly these may be divided into

- 1 Those in which closure and primary union is aimed at
- 2 Those in which the wound is left open

(B) THOSE WHICH CANNOT BE CLOSED DUE TO LOSS OF SKIN This loss may be accepted and the wound left open, or the wound may be covered by a skin graft or flap, or by appropriate incision the wound over the bone may be closed, and a wound in a less important area left open

- 1 Those in which the wound is covered leaving a raw area at some distance from the fracture
- 2 Those in which the wound is packed and left open

We may discuss a few important points concerning these in more detail

Wounds with primary closure The opportunity is provided here for the first and last time of obtaining perfect reduction under visual control, and great care should be taken to make sure that reduction is satisfactory and retention sound It is undesirable to re-manipulate a compound fracture within fourteen days of its infliction, as infection which was localised may be spread Should a compound fracture be met with healing by primary union with the bones in mal-position correction by gradual methods such as traction may be undertaken, but it is often safer not to disturb them until four to six weeks when they may be reset by a secondary operation

Absolute fixation of the soft tissues and the bone is essential and is best provided by the application of plaster, or by plaster and skeletal traction The use of internal fixation in the "clean" compound fracture is not to be forgotten (p 123) The use of traction for reduction may be necessary, but continuous traction alone plays no part in the immobilisation of a compound fracture It does not provide sufficient lateral stability and tensions tissue planes in an undesirable manner Fixation by the incorporation of the wire or pin in the plaster is preferable to continuous traction in compound fractures

Windowing the plaster There are certain objections to this, notably the tendency of the tissues to prolapse through the opening if there is any swelling of the limb In wounds adequately excised with adequate hæmostasis there should be little swelling as all products can drain away Observation of the wound is unnecessary,

as the general condition of the patient is a sufficient guide to it. Where a drain has been inserted a window may be incompletely cut through the plaster and completed at the time the drain is removed. Plaster being porous allows wounds to dry under it satisfactorily, though it is undesirable over large raw areas.

Absolute rest of the whole part and the elevation of the limb to avoid swelling are important. To obtain this the patient is usually best in bed, with the lower limb placed on a Braun's splint. The upper limb may be placed on an abduction splint, or attached to a lateral bed frame as shown in Chapter XXI.

Sutures The most useful material is provided by stainless steel wire which, because of its uniform strength and easy tying, enables hair-line sutures of wounds to be quickly and accurately carried out. They have the advantage of holding if only a single knot is tied when tissues are not under tension. On the face this fact may be used to lightly approximate tissues which may become infected. On the face sutures should be removed as soon as possible to avoid scarring, and as the healing of the face, hands and scalp is rapid this can usually be carried out before the fifth day. Under no circumstances should suturing be carried out under excessive tension, and on the face the tissues should be merely gently laid together. There is no objection to leaving skin sutures below a plaster for several weeks. It is usually convenient to remove the sutures at the end of the second week when the subsidence of swelling of the limb usually compels re-plaster.

Compound fractures in which the wound is closed by secondary measures A classical if minor example of this is the use of a whole thickness pinch graft in cases of partial amputation of the terminal phalanx, where preservation of length is important. Having completed a neat guillotine amputation through the pulp, and after adequate hæmostasis a fat free pinch graft is sewn over the raw area (Fig 47). Such grafts do remarkably well in most cases and not only save length of finger, but avoid the unpleasant consequences of infection.

In serious accidents time cannot be spent in placing large grafts over raw areas, but in small accidents, particularly involving the hand, this always has to be borne in mind. The immediate placing of the hand under an abdominal flap may be of tremendous value in avoiding subse-



FIG 47 Whole thickness pinch graft applied to the amputated tip of the pulp of a finger

quent contracture The important area to be covered is the area over the fracture, and in the leg the subcutaneous surface of the tibia may be covered by the skin of the calf mobilised by a posterior incision The raw area left may be covered later with Thiersch grafts

Closed plaster method In open compound fractures in which infection is to be expected, or in which the wound cannot be closed, firm immobilisation and free drainage under plaster is the safest and most satisfactory method of dealing with the case Care is taken that no pockets liable to infection are left, and, in particular, fascial barriers which tend to close so rapidly, if incised longitudinally, are incised widely in a *transverse* direction The skin wound and that in the superficial fascia are extended widely so that when the wound is lightly packed there is no question of the wound being plugged Dependent drainage is provided as far as possible This is of particular importance in the thigh

Having excised the damaged tissue, saucerised the wound and controlled the hæmorrhage, the wound surfaces are lightly "frosted" with a mixed powder (see p 83) and then packed lightly ("with the firmness you would hold a lady's hand on greeting her") to the surface level with gauze The packing holds the surfaces of the wound widely but lightly apart The value of impregnating the gauze with vaseline and other substances has been maintained by many observers, but in practice the profuse discharge which arises soon impregnates the material with pus and nullifies the value of most added drugs Experiments with gauze containing penicillin, or special bacterial flora to reduce odour have yet to be completed Of more value is the covering of the skin in the immediate vicinity of the wound with vaseline gauze which prevents it becoming waterlogged, and the seat of follicular abscesses from its enforced bath in pus The whole limb is then placed in a lightly padded or non-padded plaster, making sure that the immobilisation of the limb is complete In all places but the thigh this is easily accomplished In correctly excised wounds no danger should arise from enclosing the limb in a complete plaster, as the hæmorrhage and œdema which produce dangerous pressure in the closed fracture should be reduced by the excision and have an opportunity to escape into the plaster

The value of the gauze pack is fourfold —

(a) It steadies and closes up tissue planes enabling rapid adhesions to be formed

(b) It exerts an even pressure on the walls of the wound preventing their prolapse and the pocketing of material, and the development of œdema It also reacts in an unknown manner on the local circulation which responds much more satisfactorily under light pressure

(c) It adsorbs and absorbs discharges which work their way readily to the surface without undue pressure, and aids at first in the control of capillary hæmorrhage

(d) It prevents the loss of heat and moisture from the wound surface and gross soiling of the wound from external organisms

Under these conditions the wound is rapidly lined with granulation tissue, effectively localising infection to the surface of the wound. Considerable discharge is produced and the plaster is rapidly soiled. The activity of saprophytic organisms in the pus produces an unpleasant odour which is the only objectionable feature of the method. It is most satisfactorily combated by enclosing the plaster in an air tight bag. The material composing the bag is of little importance. As a general rule, the development of a ripe odour corresponds to a full development of granulation tissue and indicates the moment for redressing the wound and reducing the amount of packing.

Organisms Nothing is more remarkable than the variety of organisms which can be cultured from below a plaster, varying from the most innocent saprophyte to the most virulent coccus, and each apparently interfering little with each other and less with the patient. The material available is an ideal breeding ground for organisms, and the success of the method is the organisation of the defences before heavy growth of organisms occurs, hence the value of the bacteriostatic effect of chemotherapy. Organisms commonly met with under plaster are —

<i>Staph Albus</i>	}	May be present in the early stages in a wound which will heal by primary union
<i>Diphtheroids</i>		
<i>Micrococci</i>		
<i>Staph Aureus</i>	}	Responsible for serious infections, the streptococcus in particular because of its invasive powers
<i>Strep Hæmolyticus</i> (Pyogenes)		
Aerobic		
<i>Strep Hæmolyticus</i> (Pyogenes)		
Anaerobic	}	Present without invasion and serious effects, or together and acting symbiotically, often with the <i>Streptococcus hæmolyticus</i> , in gas gangrene
<i>Strep Viridans</i>		
<i>Cl Welchii</i>		
<i>Cl Œdematiens</i>		
<i>Cl Septique</i>	}	Saprophytes and contaminants appearing and disappearing from the pus
<i>Proteus Vulgaris</i>		
<i>Ps Pyocyaneus</i>		
<i>Ps Fluorescens</i>		
<i>Cl Bifermentans</i>		
<i>Enterococci</i>		

The source of infection in most cases is soiling of the wound at the time of injury with outside organisms, or organisms from the skin of the patient. Air-borne contamination from naso pharyngeal secretions should be guarded against by only opening the wound after it has been covered under theatre conditions. Change of dressing and of plaster should similarly be made under aseptic ritual and not in the general ward if it can be avoided, though once a well-developed granulation tissue surface is developed cross infection is as a rule of no serious significance.

Post operative course Nothing is more satisfactory than the post operative course of a patient progressing normally under closed plaster treatment. His temperature may be raised for the first three days even as high as 104 degrees, but his general condition remains satisfactory, that is to say, his tongue is clean, he has a fair appetite, sleeps soundly, looks bright, and, most important, is free from pain. Persistent pain, which is more than discomfort and is obviously not due to any localised pressure of the plaster, is due to the development of some complication, either vascular obstruction, the most urgent and serious condition, or the extension of an inflammatory process, and steps should at once be taken to find the cause.

Complications

VASCULAR OBSTRUCTION The development of pressure inside the plaster in cases with open wounds is not common if the wound has been correctly excised and lightly packed, as the products of hæmorrhage and infection escape under the plaster. A complete plaster on an open wound is far safer than on a closed wound, where it should not be applied within the first twenty-four hours. Oedema from crushing or infection may however produce pressure, and it is safer if the wound cannot be continuously supervised to split the first plaster in a single line throughout its length. Any appearance of congestion or oedema of the toes demands the same precaution, as the circulation fails slowly and irregularly, and delay may result in some covered portion of the limb being completely deprived of its blood supply.

LYMPHANGITIS AND ADENITIS This is due to the invasion of the tissues by streptococci and the initial temperature is often high. The wound has a bright red edge which shows a firm oedema, and streaks of erythema run up to the nearest group of lymph glands which may be enlarged and tender. Sulphathiazole chemotherapy is commenced at once, if not already being administered. Free drainage is assured to the wound, and in the case of smaller wounds heat in the shape of fomentations may be applied to the wound and the glands. The condition usually settles satisfactorily, but may leave abscesses in

the glands and between the superficial fascia and the skin which require to be opened.

CHILBLITIS The onset is often slower than in streptococcal infections, and is due to poor resistance to a mixed infection, assisted perhaps by pocketing and inefficient drainage. The wound is dirty, shows pale unhealthy edges and a free mucopurulent watery discharge. The tissues around the wound are tender and turgid and an area of superficial oedema frequently accompanies the tracking of underlying pus. Free drainage must be obtained by the removal of any sutures or picking and the establishment of dependent drainage. The use of a window in the plaster however undesirable must often be necessary to maintain soft tissue fixation as far as possible and yet allow inspection of the wound. Wounds which can be readily dressed and where the limb is stable may be lightly packed, covered with "tulle gras" and the whole covered by hot saline packs renewed regularly. Tracking of pus is usually due to defective drainage and demands opening of the track and light packing. The wound usually settles satisfactorily with this treatment, but the presence of an inflammation with its added complications, such as increased length of treatment, severe adhesions, vascular changes and causalgia, may in a doubtful case tip the balance in favour of amputation. In the case of most compound fractures, where an amputation at the site of election through uninfected tissues is not possible, the amputation should be through the site of fracture and open up as little fresh tissue as possible. No pockets should be left and the surface of the wound left wide open. Occasionally amputation through the knee or elbow, with minimal exposure of muscle planes, may be of value in minimising spread of infection.

GAS GANGRENE This rare complication is described together with tetanus at the end of the chapter.

Later Complications

PERSISTENCE OF INFECTION This is nearly always due to the development of a complication and not to the low general resistance of the patient. It may and often is due to defective drainage. A compound fracture of the thigh never drains satisfactorily through an anterior incision, and a posterior wound for gravitational drainage must be provided. More commonly, it is the presence of sequestra, easily recognised radiologically because of their excessive density, which delay healing. Removal of dead fragments of bone by the most convenient approach through the wound is usually rapidly effective. The after treatment of such a procedure may be similar to the closed plaster treatment in the beginning. The clinical signs of sequestra, apart from delay in healing, are the persistence of

The source of infection in most cases is soiling of the wound at the time of injury with outside organisms, or organisms from the skin of the patient. Air-borne contamination from naso-pharyngeal secretions should be guarded against by only opening the wound after it has been covered under theatre conditions. Change of dressing and of plaster should similarly be made under aseptic ritual and not in the general ward if it can be avoided, though once a well-developed granulation tissue surface is developed cross infection is as a rule of no serious significance.

Post operative course Nothing is more satisfactory than the post operative course of a patient progressing normally under closed plaster treatment. His temperature may be raised for the first three days even as high as 104 degrees, but his general condition remains satisfactory, that is to say, his tongue is clean, he has a fair appetite, sleeps soundly, looks bright, and, most important, is free from pain. Persistent pain, which is more than discomfort and is obviously not due to any localised pressure of the plaster, is due to the development of some complication, either vascular obstruction, the most urgent and serious condition, or the extension of an inflammatory process, and steps should at once be taken to find the cause.

Complications

VASCULAR OBSTRUCTION The development of pressure inside the plaster in cases with open wounds is not common if the wound has been correctly excised and lightly packed, as the products of hæmorrhage and infection escape under the plaster. A complete plaster on an open wound is far safer than on a closed wound, where it should not be applied within the first twenty-four hours. Edema from crushing or infection may however produce pressure, and it is safer if the wound cannot be continuously supervised to split the first plaster in a single line throughout its length. Any appearance of congestion or cedema of the toes demands the same precaution, as the circulation fails slowly and irregularly, and delay may result in some covered portion of the limb being completely deprived of its blood supply.

LYMPHANGITIS AND ADENITIS This is due to the invasion of the tissues by streptococci and the initial temperature is often high. The wound has a bright red edge which shows a firm cedema, and streaks of erythema run up to the nearest group of lymph glands which may be enlarged and tender. Sulphathiazole chemotherapy is commenced at once, if not already being administered. Free drainage is assured to the wound, and in the case of smaller wounds heat in the shape of fomenta may be applied to the wound and the glands. The condition usually settles satisfactorily but may leave abscesses in

UNHEALTHY SURROUNDING SKIN Wounds are often met with in which the surrounding skin becomes the seat of multiple follicular



FIG 50 Compound comminuted fracture of both bones of the leg after reduction by traction and operative excision of the wound



FIG 51 Same case as FIG 50 Sepsis followed After a period of immobilization in non weight bearing plasters a walking iron is fitted and weight bearing allowed

abscesses, is oedematous and the wound edges unhealthy Mere plastering results in a continuation of the condition Such wounds often respond satisfactorily to exposure to air, which may be arranged by windowing the plaster, or the change to a skeleton form

sinuses, a profuse watery sero purulent discharge, and the presence of profuse rather cedematous and pointing granulation tissue around the wound edge. After long established infection the walls of the wound may become very fibrous and thickened and may fail to close in one cavity, producing a persistence sinus. Wide excision of the




FIG 48 Carrel's instillation apparatus for the irrigation of infected wounds




FIG 49 The Carrel Dakin method of wound irrigation. The tubes are passed into the depths of the wound. The skin edges are protected by a layer of vaseline gauze and outside this is packed cotton wool to absorb excess fluid. It is better still if dependent drainage allows the fluid to be drained off. The wound is flushed with a few cubic centimetres of Dakin's solution every two to three hours.

sinus and saucerising the wound will usually produce rapid healing of the wound. It is particularly in areas where there are awkward arrangements of tissue planes from the point of view of drainage, such as around the hip, that sinuses are apt to persist and may require very wide excision for their cure.

PLASTER DERMATITIS All varieties of irritation may be met with below a plaster from a dry eczema to an acute desquamating dermatitis. In susceptible subjects it may be met with below a dry plaster, but is more commonly met with in the presence of an infected wound. To avoid irritation of the skin the application of vaseline gauze below the plaster in "closed plaster" cases is often effective. A short period of freedom from plaster is usually the most effective remedy. In intractable conditions the painting of the skin with triple dye may be helpful, or the use of sulphathiazole powder and tulle gras covered by saline packs.

WOUND IRRIGATION The Carrel-Dakin method of treatment, which was developed in the 1914-18 war, consisted in the burial of tubes in the depths of the wound, held in place by sutures or tight packing. The tubes were flushed through every few hours with a neutral or mildly antiseptic solution such as eusol. Though originating as an extension of the "antiseptic" methods then in vogue it had much success because of its adherence to the principles of immobilisation and freedom of disturbance of the wound. Only in a few cases is the removal of the discharge by this method of value, but there are possibilities in the method if the irrigating substance is bacteriostatic, as in the case of penicillin, which has given good results in old standing staphylococcal lesions. Recently a revival of the method by the use of a watertight envelope (Bunyan Staunard) has been employed, primarily for burns. Under certain circumstances, such as the combination of a burn and a fracture, it may be useful and may be used in cases of severe plaster dermatitis. Combined with skeletal traction, it may clear up rapidly superficial skin infections enabling an early graft to be carried out, or minimising the delay before plaster can be employed.

EPITHELIAL LOSS Large areas of epithelial loss may delay the healing of a compound fracture. It must never be forgotten that as soon as deep infection of bone or soft tissue is cleared up, and a satisfactory granulation tissue bed obtained, a skin graft will hurry up healing, and, more important, provide a better skin surface. If subsequent procedures have to be carried out on the bone healthy skin over the fracture is essential, and a pedicle graft may be necessary to make the approach satisfactory. Time should not be wasted in waiting for skin repair, but this should be encouraged by the use of Thiersch, chip or pedicle grafts.

Special Infections Gas Gangrene and Tetanus

The risks of these infections are not particularly the risks of fractures, but the depth of wounds involving bone provides the ideal situation under which these infections develop, and so they show a

of splintage such as a Thomas splint. It must not be forgotten that exposure to air and thorough washing may be of great benefit to



FIG 52 Union follows slowly but a sequestrum develops, which requires removal now that it is well demarcated



FIG 53 Final result after removal of the sequestrum

the general health of the skin below a plaster, and a few days may be allowed for this between changes of plaster in long standing cases

Treatment

PROPHYLACTIC Tetanus toxoid Injection of 1 c.c. of the toxoid, followed by 2 c.c. in three to six weeks' time, and 2 c.c. in six months, gives an immunity which lasts three years. Omission of the third dose reduces the immunity to one year's duration.

For wounded patients antitoxin offers limited protection for three weeks. Three thousand units are given, followed by a further 3,000 units in twenty one days if suspicious factors are present. The two methods of active and passive immunity can be practised together in a fresh case if desired. Anaphylactic phenomena will be avoided if the injection is made while the patient is under ether anaesthesia. In any case adrenalin should be at hand to combat it.

CURATIVE The wound if draining freely should be left alone. Indications for treatment of the wound are provided by general factors, previously discussed, and not by the presence of tetanus alone.

Antitoxin forms the basis of treatment and is given by all routes except the intrathecal. When it was believed that the absorption of the toxin was neural, this route was thought to have advantages. One hundred thousand units are given intravenously at once, and followed by maintenance doses of 20,000 units intramuscularly, or intravenously. Over 500,000 units may be used in such treatment. The effect of the antitoxin may be increased by the administration of light ether anaesthesia, the toxin being soluble in ether. Anaesthesia may enable control of the spasm to be obtained, and is a safeguard against anaphylaxis. This is likely to develop in ten days from the first injection, and should be guarded against by a small test intradermal dose.

GENERAL TREATMENT Sedatives are necessary to control the fits, and any surgical procedure must be given under some form of general anaesthesia, or the stimulation will provoke another fit. Complete quiet and absence of all disturbance must be assured in the nursing. The sedatives must be adapted to suit the case. Large doses of chloral, paraldehyde by mouth and rectally, intramuscular luminal, morphia, or even intravenous pentothal have all been used, according to the severity of the case. Morphia is probably the most useful standby, but cannot be used over long periods. Maintaining the patient's general condition by adequate nourishment is often difficult, and intravenous fluids and glucose may be given, combined with nasal feeds when the patient is under suitable sedatives.

PROGNOSIS This varies with the date of onset of the symptoms. The more delayed this is the better the outlook. The more localised

higher incidence in such lesions. The soiling of the wound with dirt is the prime cause of the condition, and it is to be noted that the well-manured soil of the field is richer in such organisms than is street dirt. The resistance of the spores of the tetanus bacillus is well known, and they survive a great length of time in the soil once it is infected. In gas gangrene the infection is a double one, but again due to spore forming anaerobes. The characteristic organism is the *Clostridium Welchii* (*Bacillus perfringens*), which is saccharolytic, and splits the glycogen in the muscles into simpler sugars and ultimately CO_2 and water. This action is followed by the activities of a proteolytic group, *B. sporogenes*, *B. aerogenes capsulatus*, and *Clostridium septicum*, which break down the muscle protein with further gas production.

Prophylaxis. The best and most certain prophylaxis is the excision and treatment of wounds on the principles outlined. If this is carefully done the incidence of either condition will be almost negligible in peace time conditions.

In serving soldiers active immunisation with tetanus toxoid is practised, and the immediate use of anti-toxin is insisted on in all suspicious wounds. For gas gangrene massive doses of antitoxic serum are given to all cases with much muscle damage as soon after wounding as possible.

Tetanus

The symptoms of this condition are due to the absorption of exotoxin from the region of the wound via the lymphatics. Symptoms may vary from those of (1) local tetanus, in which the spasms are confined to the muscles around the wound, (2) tetanus of a limb, to (3) generalised tetanus, according to the degree and rate of absorption of the exotoxin.

The date of onset of the symptoms varies from two days to two months after the injury, depending on the rate of production and of absorption of exotoxin. Associated sepsis increases both considerably. The slowest development is thus seen in wounds infected by spore containing catgut, where the wound may heal by primary intention. The local signs are not peculiar to the condition, being those common to any septic infection. General features such as rise in pulse, and increased nervousness, and apprehension of the patient may be noted, but usually the first feature is the occurrence of spasm in a voluntary muscle. In local tetanus this may be in the neighbourhood of the wound. In limb tetanus one limb may be involved, but the most common manifestation is that from generalised toxæmia when stiffness in the jaw (trismus) and back is complained of. These features are followed in a variable time by the clonic and tonic spasms.

reveal gas, but must not lead to an erroneous diagnosis from the inclusion of outside air in the wound. The general features are a toxæmia out of proportion to that to be expected. The temperature is variable, but the pulse is running and rises rapidly and disproportionately to the temperature. Pain from the pressure of swollen tissues is severe. Colour changes in the skin of a necrotic type may be seen at a little distance from the wound edges. The patient is often mentally disturbed and restless. The diagnosis of the condition under closed plasters is obviously important and may be indicated by early and severe signs of pressure inside the plaster and severe pain of a burning character at the site of injury.

Generalised infections Severe toxæmia may be rapidly followed by septicæmia, but fulminating forms are seen, in which a general septicæmia develops so rapidly that few changes may be noted in the wound. These patients are pale, cold and mentally alert. There is a subnormal temperature and a running pulse. Vomiting, dilated pupils and air hunger usher in the end.

Treatment **PROPHYLACTIC** Cases which are likely to develop the condition, i.e., those in which there is muscle damage, contamination or delay in surgical treatment or associated vascular damage, should receive as soon as possible after wounding a dose of antitoxic serum. This should contain 9,000 units of *Cl Welchii*, 4,500 units of *Cl Septicum*, and 3,000 units of *Cl Edematiens* antitoxin. This is given intramuscularly or intravenously.

The immediate treatment of the wound by excision is followed by the local application of sulphonamide and a general course of sulphathiazole and penicillin suitable to severe infections (p. 79). Massive doses of serum are given intravenously. Doses of 27,000 units of *Cl Welchii* antitoxin with other antitoxins in proportion are given every six hours.

SURGERY This is of value only in the localised forms, and its prime object is the excision of all infected tissue, leaving the minimum of muscle tissue exposed. For this reason the whole muscle belly is excised in infection confined to one muscle. In muscle group infections the fascial boundaries of the group are the limits of dissection. In limb infections amputation through the knee or elbow may be needed to avoid exposure of muscle. Excision is followed by light powdering of the wound with sulphonamides and penicillin, light packing of the wound, and immobilisation.

PROGNOSIS The prognosis varies with the amount of muscle infected before treatment is introduced, and the constitution and general condition of the patient. In localised infection it is hopeful, but in any widespread condition the outlook, in spite of blood transfusion and adequate serum, is poor.

the spasms also the better the outlook. Generalised tetanus is always of grave significance, but not necessarily fatal.

Gas Gangrene

Cl. welchii is a spore-forming anaerobe like tetanus and has a similar habitat. It is invariably present in gas gangrene and is accompanied by a variety of other anaerobes, some capable of symbiotic activity, and by the more common aerobes. It is the chief producer of gas, being mainly saccharolytic, but is also proteolytic. It can only live under anaerobic conditions, and an effective blood supply is the best barrier to its progress. It follows that the effective blood supply of the wound area is most important, and any local vascular damage or general vascular failure from shock may be of great significance in the spread of the condition.

Clostridium oedematiens though non-invasive, produces extensive oedema, and an absorbable exotoxin. *Clostridium septicum* similarly produces oedema and an exotoxin, but can actively invade the tissues. *Cl. Fallax*, *Cl. Histolyticum*, *Cl. Sporogenes* are spore-bearing anaerobes commonly found in association with gas gangrene infections.

The extension of the disease is dependent on the invasion of muscle, and fascial barriers offer a short check to its course. The importance of the blood supply, long ago pointed out by Larrey, is seen in the increased incidence in severe contused and crushed wounds. The disease may localise itself in

- 1 A wound area {Contamination
 {Anaerobic cellulitis
- 2 A muscle belly
- 3 A muscle group
- 4 A segment of a limb,

each giving opportunity for surgical treatment.

The wound area. The organism may be found in a granulating wound as a harmless contaminant. If active there is the formation of local gas, but on account of reduced virulence or active granulation tissue there is no further spread and an absence of systemic effects. The characteristics of the wound are those of gas gangrene in a sub-acute form. These are pallor, swelling and oedema of the wound edges, a thin evil smelling, brownish discharge, with a peculiar foetid odour, some crepitations in the surrounding tissues, and bubbles in the wound. The condition is confined to the subcutaneous tissues and requires adequate drainage and general therapy.

Localised infections in muscles. The discharge and odour are present. Gas formation is increased and the muscle colour varies from a dark red to a greenish black. The tissues are swollen and oedematous, tense and crepitant. Radiological examination may

reveal gas, but must not lead to an erroneous diagnosis from the inclusion of outside air in the wound. The general features are a toxæmia out of proportion to that to be expected. The temperature is variable, but the pulse is running and rises rapidly and disproportionately to the temperature. Pain from the pressure of swollen tissues is severe. Colour changes in the skin of a necrotic type may be seen at a little distance from the wound edges. The patient is often mentally disturbed and restless. The diagnosis of the condition under closed plasters is obviously important and may be indicated by early and severe signs of pressure inside the plaster and severe pain of a burning character at the site of injury.

Generalised infections Severe toxæmia may be rapidly followed by septicæmia, but fulminating forms are seen, in which a general septicæmia develops so rapidly that few changes may be noted in the wound. These patients are pale, cold and mentally alert. There is a subnormal temperature and a running pulse. Vomiting, dilated pupils and air hunger usher in the end.

Treatment **PROPHYLACTIC** Cases which are likely to develop the condition, i.e., those in which there is muscle damage, contamination or delay in surgical treatment or associated vascular damage, should receive as soon as possible after wounding a dose of antitoxic serum. This should contain 9,000 units of *Cl Welchii*, 4,500 units of *Cl Septicum*, and 3,000 units of *Cl Œdematiens* antitoxin. This is given intramuscularly or intravenously.

The immediate treatment of the wound by excision is followed by the local application of sulphonamide and a general course of sulphathiazole and penicillin suitable to severe infections (p. 79). Massive doses of serum are given intravenously. Doses of 27,000 units of *Cl Welchii* antitoxin with other antitoxins in proportion are given every six hours.

SURGERY This is of value only in the localised forms, and its prime object is the excision of all infected tissue, leaving the minimum of muscle tissue exposed. For this reason the whole muscle belly is excised in infection confined to one muscle. In muscle group infections the fascial boundaries of the group are the limits of dissection. In limb infections amputation through the knee or elbow may be needed to avoid exposure of muscle. Excision is followed by light powdering of the wound with sulphonamides and penicillin, light packing of the wound, and immobilisation.

Prognosis The prognosis varies with the amount of muscle infected before treatment is introduced, and the constitution and general condition of the patient. In localised infection it is hopeful, but in any widespread condition the outlook, in spite of blood transfusion and adequate serum, is poor.

REFERENCES

Compound Fractures

- EHALT, W "Behandlung der offenen Bruch der Langen Rohrenknochen"
Wilhelm Maudrich, Vienna, 1938
- WATSON JONES "Fractures" E & S Livingstone, Edinburgh, 2nd ed,
1943
- HUDSON, O C "Multiple Fractures," *J Bone and Joint Surg*, 1940,
22, 354
- HEY GROVES "Treatment of Infected Open Fractures," *Brit J Surg*,
1930, 18, 294
- TRUETA J "The Principles and Practice of War Surgery," London, 2nd ed
1943 (Hamish Hamilton and Wm Heinemann)

Chemotherapy

- GARROD L P "Recent Advances in the Antiseptic Treatment of Wounds,"
Bull War Med, 1943 3, 589
- MEDICAL RESEARCH COUNCIL "The Medical Use of the Sulphonamides,"
London 1943 (H M Stationery Office)
- JENSEN, LUVERNE, JOHNSRUD and NELSON "The Local Implantation of
Sulphanilamide in Compound Fractures," *Surgery*, 1939, 6, 1
(With further references concerning sulphanilamide therapy)

Infection

- MACLENNAN, J D "An aerobic Infection of War Wounds in the Middle
East," *Lancet*, 1943 ii, 63
- TOPLEY and WILSON "Principles of Bacteriology and Immunity" London,
Edward Arnold & Co, 3rd Ed 1946, ii 1746
- DE WALL H L "Wound Infection A preliminary Note on the Combined
Clinical and Bacteriological Investigation of 708 Wounds," *Ed Med
Jour* 1943 50 571

Tetanus

- COLE "Treatment and Prognosis in Tetanus" *Proc Roy Soc Med*, 1938,
31, 1205
- BOYCE and McFETRIDGE "An Analysis of 185 Cases of Tetanus from the
New Orleans Charity Hospital with a Special Note on Avertin," *New
Orleans M and S J* 1935, 87, 825
- EARLE, K V "Evipan Sodium in the Treatment of Tetanus," *Lancet*,
1938, i, 435
- HUNTINGTON THOMPSON and GORDON "The Treatment of Tetanus with
Antitoxin," *Ann Surg* 1937 105 93
- TIDSWELL, F "Treatment of Tetanus Experiences at the Royal Alexander
Hospital for Children Sydney," *M J Australia* 1938, 1, 198
- COLE L "Treatment of Tetanus" Ministry of Health E M S Instructions,
Part 1, Supplement 31 1942

Gas Gangrene

- ECKHOFF N L "Gas Gangrene in Civil Surgery" *Brit J Surg*, 1938,
18, 38
- BLAND, F K "Gas Gangrene in Compound Fractures," *Ann Surg*, 1929,
90, 603
- GHORMLEY, R K "Gas Gangrene and Gas Infections" *J Bone and Joint
Surg*, 1935 17, 907

- LOWER and TORREY "Gas Gangrene and its Treatment," *Surg Clin N America* 1937 17, 1385
- MEDICAL RESEARCH COUNCIL "Notes on Gas Gangrene Prevention," *War Memorandum No 2*, 2nd ed 1943
- WAR OFFICE "Use of Gas Gangrene Antitoxin," *Army Med Dept Bull*, No 30
- PATTERSON, KEATING AND CLIG "Experiences in the Prophylaxis and Treatment of Clostridial Infections in Casualties from the Invasion of Europe," *Brit J Surg*, 1945, 33, 74-79
- JEFFREY AND SCOTT THOMSON "Gas Gangrene in Italy, a Study of 33 Cases Treated with Penicillin," *Brit J Surg*, 1944, 32, 159-167
- CUTLER AND SANDUSKY "Treatment of Clostridial Infections with Penicillin," *Brit J Surg*, 1944 32, 168-176
- TOPLEY AND WILSON "Principles of Bacteriology and Immunity " London, Edward Arnold & Co, 3rd Ed, 1946, ii, 1770

CHAPTER IX

DELAYED UNION, NON-UNION, MAL-UNION

Union **CLINICAL UNION** When a bone is rigid to bending stress in all directions, and this stress produces no pain at the site of fracture, and the callus is no longer tender, the bone is clinically united. This does not necessarily correspond to the appearance of union radiographically and to wait for this confirmatory evidence is to lose valuable time. The radiograph may, however, be of value in judging the strength of union present and its ability to yield under the continued action of body weight. If satisfactory, all support can be abandoned. If uncertain, support may be maintained under strain and reduced when strain is absent. A lesser degree of fixation may be allowed. Thus in the case of fractures of the leg, when there is no fear of rotatory strain, there is no need to fix the knee, and active exercises of the joint may be commenced. Clinical union is the sign for more active employment of the limb.

RADIOLOGICAL UNION This may be obvious at the time of clinical union, but more often lags behind it. It is often difficult to determine, e.g., in the case of the navicular, and when obvious usually indicates that clinical union has been long established. It is a valuable aid to the assessment of the strength of union and of the occurrence of non union.

Delayed union The time which a fracture takes to unite depends on many factors. Thus the particular bone fractured, the particular site involved, the age and general condition of the patient all influence the time taken for repair. We cannot, therefore, assign any fixed period beyond which we can say the union is delayed, for all fractures, but there are periods for each fracture in which union should occur and beyond which we can say that union is delayed.

Non-union With the passage of time and the development of further change in the bones this may definitely become "non-union." Here we have a visible change in the bone pathology which can be detected in the X ray, and this can be considered a criterion of non union. There is however no fixed boundary between the two conditions and one merges into the other. The causes influencing the development of either condition are the same, and are as follows.

1 **WIDENING OF THE FRACTURE ENDS** Several factors may produce this. Loss of bony tissue in compound comminuted fractures is important. Gross displacement of the parts if left unreduced may produce it. With skeletal traction there is a definite risk that excessive traction may over separate the bone ends and

cause failure of union, while continuous distraction is an even more potent cause of failure

2 **INTERPOSITION OF SOFT PARTS** Muscle and fascia may be turned in between the bone ends, thus preventing their approximation, and forming a barrier to callus formation. Even the blocking of the medullary canal by the impaction of a fragment of compact bone across it may prevent union

3 **CONSTANT MOVEMENT** This is an important point. The influence of movement on the development of callus has been mentioned. A small degree of movement does not delay healing, but gross degrees of movement will. Movement of the impaction type will actually hurry the process. The ribs are always cited as an example where constant movement does not prevent union. In the ribs the actual movement of the rib ends on each other is small, owing to their fibromuscular attachments. This degree of movement may result in excessive callus, but never in non union

A restless patient who will not remain quiet under skeletal traction may cause such bones as the femur to fail to unite, and in certain cases may justify operative fixation and plaster

4 **INFECTION** The disastrous effects of infection in delaying union need no reiteration here

5 **LOSS OF THE BLOOD SUPPLY** In certain bones this may produce avascular necrosis of a fragment of bone. This commonly occurs to small fragments in comminuted fractures and is of no importance. In certain bones such as the navicular and the upper end of the femur the loss of blood supply may involve the whole of one surface of the fracture, and then delay in union must occur while the bone is revascularising, or, if this fails to occur, non-union of an absolute type will be established. Double fractures of a long bone inevitably delay the healing of one fracture, usually that fracture separated by the other from the nutrient artery, which thus has a reduced blood supply

6 **LOCAL OR GENERAL DISEASE** This may influence union. A positive Wassermann may delay union till adequate treatment has been carried out. Most local conditions of bone, such as cysts, tumours, and the other conditions outlined under the causes of pathological fractures do not cause non-union, though they cause delay in union. Scurvy, tabes and advanced malignancy seem to be the only conditions causing absolute non-union

7 **BURIED FOREIGN BODIES** In certain cases the use of Lanes' plates or wire leads to a mild inflammatory reaction around them with hyperemia of the bones and decalcification. This may be the cause of failure to unite. The reaction is not so noticeable with bone pegs or grafts and is due to some specific effect of the metal

CHAPTER IX

DELAYED UNION, NON-UNION, MAL-UNION

Union **CLINICAL UNION** When a bone is rigid to bending stress in all directions, and this stress produces no pain at the site of fracture, and the callus is no longer tender, the bone is clinically united. This does not necessarily correspond to the appearance of union radiographically and to wait for this confirmatory evidence is to lose valuable time. The radiograph may, however, be of value in judging the strength of union present and its liability to yield under the continued action of bodyweight. If satisfactory, all support can be abandoned. If uncertain, support may be maintained under strain and reduced when strain is absent. A lesser degree of fixation may be allowed. Thus in the case of fractures of the leg, when there is no fear of rotatory strain, there is no need to fix the knee, and active exercises of the joint may be commenced. Clinical union is the sign for more active employment of the limb.

RADIOLOGICAL UNION This may be obvious at the time of clinical union, but more often lags behind it. It is often difficult to determine, e.g., in the case of the navicular, and when obvious usually indicates that clinical union has been long established. It is a valuable aid to the assessment of the strength of union and of the occurrence of non-union.

Delayed union The time which a fracture takes to unite depends on many factors. Thus the particular bone fractured, the particular site involved, the age and general condition of the patient all influence the time taken for repair. We cannot, therefore, assign any fixed period beyond which we can say the union is delayed, for all fractures, but there are periods for each fracture in which union should occur and beyond which we can say that union is delayed.

Non-union With the passage of time and the development of further change in the bones this may definitely become "non union". Here we have a visible change in the bone pathology which can be detected in the X ray, and this can be considered a criterion of non union. There is, however, no fixed boundary between the two conditions and one merges into the other. The causes influencing the development of either condition are the same, and are as follows.

1 **WIDE SEPARATION OF THE BONE ENDS** Several factors may produce this. Loss of bony tissue in compound comminuted fractures is important. Gross displacement of the parts if left unreduced may produce it. With skeletal traction there is a definite risk that excessive traction may over separate the bone ends and

False joint formation It has been mentioned in the chapter on the healing of fractures that the amount of cartilage at the fracture site is related to the amount of shearing strain which the fracture undergoes while callus is forming. Excessive movement may produce excessive cartilage, and under the influence of further movement this may form itself into a false joint with a central cavity containing fluid, and surrounding thickening in the fibrous tissue resembling a capsule. It is to be noted that only shearing strains produce this



FIG 5b Atrophic type of non union. There is little callus reaction and the bone ends have rounded off and been partly absorbed. This is unsuitable for Beck's drilling but may be bone grafted.



FIG 5b_a Established non union with false joint formation following a fracture of the clavicle. The condition was consistent with excellent function.

effect. Compression strain encourages union. False joint formation occurs commonly in tabetics in whom the loss of sensation encourages abnormal movements at the fracture site. False joint formation is much more common in active young men than in old men, and is very rare in women. If the limb is used the modifications which occur in the bone ends and the surrounding structures make it very closely resemble a normal joint. The bone end rounds off on one side, and expands on the other to form a bearing surface. These surfaces are large and fluid appears between them, while the surrounding tissue comes to resemble

On the other hand compound fractures due to bullet wounds often heal well in spite of metal being scattered through the bone, if no infection occurs

The effect of synovial fluid on union has been called in to explain non-union in navicular and patella fractures but it can be said with confidence that it does not delay or prevent union

The influence of the type of fracture must be mentioned ✓ Transverse fractures have a small area of bone in contact, have often less periosteal disturbance, and so throw out less callus and unite more slowly than oblique fractures

Types of Non-union

- 1 FIBROUS
- 2 FALSE JOINT FORMATION
- 3 ABSOLUTE

Fibrous union occurs normally in certain bones such as the skull and the patella, and it may occur in many other fractures and allow of full function, e g, fractures of the clavicle and the navicular In



FIG 54 False joint formation in fracture of the lower third of the tibia. The bony sclerosis on the distal side is well marked and into this the rounded proximal end fits



FIG 55 Hypertrophic type of non union. There is a good callus reaction but there is a line of non union across this. This is the type of non union suitable for Beck's bone drilling

certain bones, such as the long bones, it is insufficient and bony union must be obtained. Fibrous union can only be satisfactory where there is no serious bending strain

bone ends, absolute non union is established and operative interference will be necessary to procure union

ABSOLUTE NON UNION All operative interference is directed to three ends

- 1 The opening up of the bone ends
- 2 The formation of a fresh hematoma
- 3 Improved fixation of the parts

Certain treatments such as the injection of whole blood around the bone ends, or of dilute hydrochloric acid have occasionally been successful, because they have fulfilled these conditions in part, but in general they are unreliable

The simplest method of producing the conditions above is to retraumatise the fracture area by manipulation and hammering under an anæsthetic This may be combined with a tourniquet above the fracture site compressing the veins only, which is main-




FIG 59 Beck's bone drilling Through two small skin incisions made to avoid soiling the drill by contact with the skin the bone is drilled in the directions indicated by the interrupted lines

tained for some twenty to thirty minutes to encourage the formation of a larger hæmatoma After such treatment adequate fixation is secured by plaster, and in suitable patients weight bearing is encouraged This will cause union in a few cases, but it is better regarded as a method of hastening delayed union than a method of treating non union

If this method fails or is unsuitable, the next grade of interference is provided by Beck's bone drilling This can be done under local anæsthesia if necessary, and is considerably aided by the use of a mechanical drill, either pneumatic or electric The skin over the fracture is satisfactorily sterilised and anæsthetised Two incisions are made at suitable sites A small bone drill is then inserted at a convenient point, and by repeated drillings and partial withdrawals the bone ends are perforated in numerous directions The number of perforations made will depend on the size of the bones and their accessibility Both ends of the bone are dealt with in the same way, and the fracture then treated as a fresh fracture, and reset in a

Absolute non-union This is usually a very weak type of fibrous union. In the atrophic type (Fig 56) it is shown radiologically by the rounding off of the bone ends, and the closure of the marrow cavity with a thin layer of compact bone while a considerable gap separates the bones. In the hypertrophic group of cases the marrow cavity closes off with a layer of sclerotic cancellous bone and a broader softened line is left between the two fractured surfaces. In the hypertrophic type (Fig 55) there has been a good callus reaction and the ends of the bones are surrounded as a rule by excess callus, but for some reason the callus fails to unite. In the atrophic type there is very little callus reaction at all, and the outlook is more serious. This condition is fortunately the less common of the two. When either of these conditions is established any hope of union by other than operative means must be abandoned.

Treatment DELAYED UNION General treatment is the same in all cases, and consists of efficient nursing, together with an adequate diet in which all the vitamins are present. To stimulate union a variety of agents from egg-shell to parathormone have been tried and vaunted, but on clinical and experimental grounds it is extremely unlikely that they have the slightest effect. Adequate calcium and phosphorus are, for example, obtained from the decalcification of the rest of the skeleton, the amount stored there, compared with the amount required for the callus and the amount ingested from any special diet, being enormous.

Special treatment This is directed to the discovery of the cause and, if possible, its removal. The treatment of a positive Wassermann reaction will usually result

in union in a short time. In the lower limb the use of a walking plaster, or some form of weight bearing, will often promote rapid union. In the femur the release of the traction weights is often the signal for union to commence. Adequate length of immobilisation will result in the union of most fractures of the navicular.

Where possible the use of the affected limb should be encouraged. The arm should be given the appropriate plaster, and the leg fitted with a walking plaster or a calliper. If after some time there is no union and the X ray shows increasing sclerosis of the



FIG 57 Long standing ununited fracture of the body of the navicular showing the smooth surfaces and well marked sclerosis on either side of the fracture line

method to be successful the fibula must be divided first to allow the two ends of the tibia to come into contact. Cases of atrophic non-union or in which there is an obvious inclusion of soft parts are unsuitable for this method of treatment, and in cases in which it has failed other methods must be adopted. The next step usually considered is the amputation of the bone ends, and their approximation, which can only be considered if one is prepared to sacrifice the length of the bone to some extent. This is only possible in the arm, and here, owing to technical difficulties with grafts and plates, it is often a useful manoeuvre. Re-union of the bones is accomplished by the "step cut" method (Fig 59) or by cutting both ends obliquely (Fig 60) and screwing them together.

Rarely when mere separation of the bone end has been the cause of non-union, placing the bones in correct relation and plating them may be sufficient. Plates may be combined with grafts to obtain the advantages of both. In general, pure grafts will be found most satisfactory.

BONE GRAFTING

The final resort, and the most satisfactory method in most cases, is bone grafting. This provides fresh bony material, demands an adequate opening up of the bone ends and the formation of a fresh hæmatoma around them, and provides internal fixation. The success of bone grafting as a method of obtaining union has led to its wide use under other conditions. Indications for its use are present when —

- 1 Absolute non union is established (atrophic or hypertrophic)
- 2 Failure to obtain adequate reduction and failure of retention occurs, *e g*, in fractures of both bones of the forearm, where alignment must be as perfect as in the leg
- 3 Obvious loss of bone which will delay or prevent union is present
- 4 Fractures in which difficulty is expected or non-union is common, *e g*, fractures of the medial malleolus with displacement or of the femoral neck
- 5 Delayed union in certain cases

The material used for grafting may be obtained from the bone as that grafted or from another limb. The increased operating time taken by making a second incision is offset by the added strength of the material gained and the fact that the injured limb is not further weakened, but has osteogenic material added to it. In covering large defects these advantages are important.

Bone grafts may be,

- 1 Cancellous chip

plaster cast This method is very successful in selected cases, notably the hypertrophic type of non union For it to succeed the



FIG 59 Step cut operation



FIG 60 Double oblique method of joining bones

bone ends must be capable of being brought into apposition Where there are two bones to be considered this may mean that an osteo-



FIG 61 Usual method of inserting a sliding tibial graft The long and short portions of the bone freed by the saw cut are reversed in their bed



FIG 62 Correct method of grafting One saw cut is slanted leaving a wedge of bone free which is slid down wards and fixed firmly into the lower part of the bed

my must be done on one of them This is often necessary in the leg, where the fibula unites well and the tibia does not For any

bone or the wing of the ilium. A modified form has been used in arthrodesis with success.

INLAY GRAFTS The sliding graft is the principal example of this method. Here a long channel is cut in the bone crossing the fracture line so that two thirds of its length lies to one side of the line and one




FIG. 66 The sliding graft—the small lower fragment is replaced above the graft and fixed with a single screw.




FIG. 67 The Masque graft —
A Complete division of bone by saw
B Area split and removed



FIG. 68 The sections reversed and screwed in position

third to the other. The fragments are freed and then reversed and screwed into position. The disadvantage of the method is the fact that the curves of the graft do not correspond to the curves where it is moved, and so one end of the graft must always be sunken. Further in order to get firm fixation of the graft it is necessary to taper the graft (Fig. 62), both from above down, and from side to

- 2 Inlay grafts
- 3 Onlay grafts
- 4 Massive sliding grafts

The cancellous chip method has been derived logically from the fact that the earlier the graft is revascularised the sooner sound



FIG 63 Non union Compound comminuted fracture of tibia



FIG 64 Union obtained by sliding bone graft fixed by two screws AP view (inlay graft)



FIG 65 Lateral view of same case

union of graft and bone will occur. In a compact graft only surface cells survive. In a chip graft the surfaces are large, and many more cells survive, with a consequent rapid formation of new bone and consolidation of the chips. The disadvantages are the absence of the rigidity provided by other methods and its consequent unsuitability in many situations. The chips are usually derived from the injured

use of an electric or compressed air driven saw and drill is essential. "No touch" technique should be employed throughout. All the methods are successful. Clinical union is established in a varying time after three months from the operation. The fate of the graft has already been discussed (p. 20).

Grafts should not be carried out on infected fractures until at least six months from the date of healing of the wound. Preliminary skin grafts may be necessary to obtain suitable skin through which to work. The advantages of employing plates in addition to the graft are few. The advantages of freedom from the necessity of external support are discussed on p. 128. Where Lane used plates for non-union, Beck's bone drilling is often equally effective. Where non-union and displacement co-exist grafts alone are not always satisfactory.

FAILURES OF GRAFTING The chief causes of failure in bone grafting will be found among the following errors or accidents.

1 **Sepsis** To be avoided by awaiting an adequate time for tissue infection to subside, i.e., three to six months. Obtaining sound skin cover through which to operate, the use of chemotherapy.

2 **Application of the graft under strain** Notably in grafting the bones of the forearm. To avoid this the use of a plate and graft together are advised.

3 **Inadequate nutrition of the graft** Failure to prepare the graft bed adequately and excise avascular bone and fibrous tissue. Chip grafts of cancellous bone survive best and may be used preparatory to a cortical graft in difficult situations.

4 **Failure to immobilise the graft efficiently**

5 **Lack of protection of the graft before union is solid**

Mal-union

This may take the form of

1 **SHORTENING** Due to loss of bone or overlap of the bone ends

2 **ANGULATION** Due to too early use or incomplete reduction

3 **ROTATION** Due to failure to align the limb correctly

4 **EXCESSIVE CALLUS**

The importance of these various deformities depends to a great extent on whether the lesion is in the upper or lower limb. Accurate alignment is much more necessary in the lower limb, where the relation of the bones to the line of transmission of the body weight is of great importance. In the arm shortening, rotation, and angulation may be overlooked if they are not gross. In the forearm these defects will lead to loss of pronation and supination. Rotation produces a serious disability in the fingers.

A fracture may be mal-united, but produce no interference with

side, so that it may be firmly impacted into its bed by the screws employed to hold it (Figs 64, 66)

ONLAY GRAFT This graft is screwed to the surface of the bone. This has the slight disadvantage of increasing the bulk of the bone, but does not necessitate the weakening of the bone with saw cuts. By proper trimming of the graft and of the bed on which it is to lie it can be adapted to any surface. By reversing the graft so that the cancellous surface lies outwards, flat surfaces of compact bone can



FIG. 65a Non union of a fracture of the tibial shaft treated by massive sliding graft

be obtained to work with and the cancellous outer surface provides better osteogenesis

MASSIVE SLIDING GRAFT This has been worked out in an endeavour to obtain a mechanically sound method. It is essentially similar in principle to the sliding graft, but the whole thickness of the bone is split in section and not as a groove. By this means a level surface of bone is obtained to work with, and reversal of the bone fragments does not upset alignment (Figs 67, 68). It is the soundest method mechanically, though a rather extensive procedure.

All methods should be done under radiological control to be certain that alignment is perfect before being finally closed. The

at the level of the fracture and then wedging the plaster at the appropriate spot. When the correction is shown to be radiologically correct the wedges and gap are plastered over.

OPERATIVE CORRECTION This is reserved as a rule for solidly united cases. An osteotomy at the site of an old fracture is apt to be followed by non union, especially if treated by any form of traction, so care must be taken in the selection of cases. Oblique osteotomies are to be preferred to transverse ones in which the usual difficulties of transverse fractures are likely to complicate matters, i.e., lateral displacement and slow union.

LATE CASES After a period of six to twelve months the joints become adapted to their new positions, joint surfaces alter in outline and ligaments elongate and contract. Any attempt to alter the alignment results in the imposition of a further strain on the joint similar to the first to which it must adapt itself once again. This will aggravate rather than relieve any traumatic arthritis already present, so where this is a genuine disability an arthrodesis is to be preferred to any attempt to correct the alignment.

In young patients these arguments do not hold, as the joints are more adaptable, and serious deformities should be corrected, leaving the finer details of correction to growth.

Shortening may be corrected by an oblique osteotomy and traction, or by the insertion of a bone graft. Rotation is the most difficult to correct as it requires a transverse osteotomy with its disadvantages, or a very well-planned oblique one.

Various complicated orthopaedic procedures to improve the function in late lesions of the hip, ankle, and other joint, are outside the scope of this book.

Excessive Callus

The amount of callus formed depends on

- 1 The size of the hæmatoma
- 2 The amount of comminution of the bones
- 3 The amount of movement at the fracture site during retention
- 4 The bone fractured. Membrane bones repair by fibrous tissue

Excessive callus is rarely a drawback, but it may be cosmetically undesirable in such bones as the clavicle. In the arm the radial nerve may be involved in the organising callus and paralysis produced. Either of these reasons may call for surgical interference. In the neighbourhood of joints excessive callus may interfere with the joint movement. It usually slowly adapts itself to the situation and full movement is restored.

function, in which case before treatment is decided upon one must ascertain if the deformity is likely to increase, or to produce other disabilities, such as traumatic arthritis. In the young the bones will spontaneously correct quite large deformities, and unless the lesion is very gross it is wise to postpone interference till growth has ceased. In adults there is little spontaneous correction.

TREATMENT This may be necessary at the following stages

- 1 Early, when the callus is soft
- 2 After consolidation of the callus
- 3 In late cases when secondary effects have arisen

In the early stages the correction of the deformity may be brought about by any of the methods used for fresh fractures, i.e., manipulation, continuous traction, or open operation.

MANIPULATION The length of time during which this can be carried out varies with different lesions. In the wrist one may refracture and reset a Colles's fracture up to ten weeks after the original injury. The callus around a femur will not be firm for six to eight weeks, and similarly a fracture of the tibia and fibula may be bent up to five weeks after the injury. The best gauge to the possibility of manipulation is the X-ray. The nearer the fracture is to the joint the more difficult it is to manipulate, and also the more rapid union is likely to be. It is very important to get correct alignment of a third degree abduction fracture of the ankle at once and not allow early weight bearing which may disturb it. Following a manipulative correction for recurrent deformity, a fresh plaster is applied which need not be left on for quite as long after this as after the original fracture and reduction.

Manipulation can be carried out under the screen, which is a great help in correcting the angulation of long bones accurately. In fresh cases the freedom of mobility of the fracture ends on each other may cause some trouble in manipulation, but if a period of two to three weeks is allowed to elapse with the ends in contact, sufficient fixation will have occurred to prevent the bones moving laterally on each other, but not sufficient to prevent correction of angulation, which may then be done with great precision.

A very satisfactory method of correction in suitable cases is provided by wedging the plaster. This enables an angular deformity to be corrected with almost mathematical precision. The application of the method to the tibia is shown on page 521.

GRADUAL CORRECTION This is difficult to control in many cases but it may be attempted by corrective padding inside a plaster cast, or using heavy skeletal traction for a short time, or the use of adjustable pressure pads, and suchlike manoeuvres. In the long bones it may be done by making a circular cut in the plaster case

CHAPTER X

THE IMMEDIATE OPERATIVE TREATMENT OF FRACTURES

AFTER the first successful open reduction and suture of the patella, in 1874 by Lister, the door opened on a new vista in fracture treatment. Arbuthnot Lane saw farthest across this attractive prospect and saw more than most. His emphasis on the abnormal strains placed on a joint by mal union is as important to day as ever, and is the fundamental fact justifying operative interference. The popularity of Lane's methods were their undoing. Plating became the fashion, doomed by this to become unfashionable. So absurd were the lengths to which his methods were carried that a birth fracture of the femur in an infant was plated on the second day of life, with distressing results. The wholesale fixing of fractures under unsuitable conditions and with that lack of judgment and selection which had made Lane successful, made plating so unpopular that within fifteen years, to mention it in an examination, was to court disaster.

The return of operative methods to favour is based on sound convictions. It is to be hoped that the influence of those returning to such methods will prevent a further wave of unpopularity. The basis of dissatisfaction with present methods is the inability of surgeons, even with a mechanical distractor (Fig 70), to get perfect reduction. Exposure of a few fractures will soon show that the irregularity of many fractures is such that no surgeon could hope to interlock the ends blindly, even given all the control available by skeletal traction. Recognition of the defects of skeletal traction has led to the use of beaded wires to provide lateral pressure on fractured bone ends, but this is open to other objections. The interposition of soft parts is often another immediate obstruction. Further the use of skeletal traction in itself has disadvantages. This is particularly so if traction is persisted in over any length of time. Stiffness of joints through which force is employed is an inevitable sequel, only varying in degree. Traction is not fixation, but a balance of forces, which exert a continual opposition to each other,




FIG 69 Showing the method of reduction of an oblique fracture using beaded wires

REFERENCES

- GALLIE and ROBERTSON "The Repair of Bone," *Brit J Surg*, 1919, 7, 211
- WATSON JONES "Inadequate Immobilisation and Non union of Fractures," *Brit M J*, 1934, 1, 936
- CAMPBELL "Malunited Fractures," *Surg Gynec and Obst*, 1938, 66 466
- KING, T "Matti's Spongiosa Bone Transplant for Ununited Fractures," *M J Australia*, 1938, 1, 526
- HEY GROVES "Methods of Bone Transplantation," *Brit J Surg*, 1917, 5, 185
- KELL, R E "Application of Wedge Principle in Fashioning a Tibial Bridge Graft," *Brit J Surg*, 1923, 10, 232
- BANCROFT "Bone Repair following Injury and Infection," *Arch Surg*, 1922, 5, 646
- ALBEE "Bone Graft Surgery" New York, 1915
- WILDEY "Ununited Fractures Treated by Long axial Drilling of the Fractured Bone Ends" *Brit J Surg*, 1914, 2 423 (Anticipated Beck, but drilled axially with wide exposure)
- BECK, A "Zur Behandlung der verzögerten Konsolidation bei Unterschenkelbrüchen," *Zentralbl f Chir*, 1929, 56-2, 2690
- LANE W ARBUTHNOT "The Operative Treatment of Fractures," London 1914, 2nd ed The Medical Publishing Company
- ARMSTRONG, J H "Bone Grafting in the Treatment of Fractured Tibia and Fibula," *Lancet* 1943, ii, 188
- ARMSTRONG J H 'Bone Grafting in the Treatment of Fractures,' Edinburgh 1945 E & S Livingstone
- ELLIS V H, LANGSTON, C H and ELLIS, J S 'Failures in Cortical Bone Grafting,' *Lancet* 1947, 2, 128

3 The immediate comfort of the patient who finds that the one operation, apart from the removal of the stitches, is the only uncomfortable procedure to which he must be subjected

It should be scarcely necessary to add that the operative fixation of fractures plays little part in the treatment of fractures during the growing period, when bones automatically realign themselves

THE DISADVANTAGES OF OPERATIVE REDUCTION The method can only be carried out by the experienced, working under good conditions, and this limits the general usefulness of the method. The method itself introduces new complications and difficulties —

1 *Sepsis* That this is slightly increased by the method cannot be denied. In the most skilled hands an odd case will become infected. Whether this can be regarded as a complete contraindication to the method is a personal decision. Such sepsis as occurs in carefully selected cases is usually of the subacute type and has no serious consequences. It may delay union and result in excessive new bone formation, but rarely increases the sequestration. Its occurrence is undoubtedly related to the conditions under which the method is carried out and the skill of the surgeon. The amount of metal used in fixation is also of importance, sepsis being more common with large plates than with single screws. With a single screw secondary infection produces little further damage, but with a plate the removal of the whole appliance may become necessary.

The most common cause of infection is inadequate hæmostasis which alone, or by interfering with the blood supply of a portion of skin, produces infection of the wound. Excessive tension in suturing a wound is also a common cause of trouble.

The use of plates in open compound fractures has been given up as it definitely increases the sequestration, but occasionally a single screw may be used with advantage.

2 *Sinus formation* Although related to infection this complication deserves special mention. It appears to be due to the escape of fluid exudate around the plate and through the suture line at some date after partial healing of the wound has occurred. As a result there is little tendency for infection to pass along the track and a watery serous discharge may persist for weeks. The majority of cases heal of their own accord in time. In a limited number of cases removal of the metal will be necessary.

3 *Non union* Like infection, which may be responsible for the condition, this is most commonly the result of faulty technique. A classical example is the separation of the surfaces of a transverse fracture by a plate which has been screwed in position holding the bone slightly apart. A secondary factor is the deleterious effect on callus formation exerted by some plates. This is due to —

varying with every movement of the patient. Fixed distraction is equally undesirable in many fractures leading to non-union and soft tissue adhesions. The movements of tissues around pins and wires leads to infection of the pin tracks, so that early mobilisation of limbs fixed by these methods cannot be safely carried out. If the




FIG. 70 The lower limb ready for distraction lying on a mechanical distractor (London Splint Co)

fractures can be fixed internally no track is left open to the skin and this objection is overcome.

THE ADVANTAGES OF OPERATIVE REDUCTION may be stated as follows —

1 Early, complete, and perfect reduction of the fracture with resultant benefits

(a) Immediate Avoidance of further soft tissue damage from pressure or manipulation.

(b) Intermediate Possibilities of earlier mobilisation due to greater early rigidity of the limb. With this is bound up the patient's confidence in the limb which he once again feels is solid.

(c) Late Absence of secondary effects on the joints at either end of the bone due to abnormal strains from mal-alignment.

2 The evacuation of part of the hæmatoma, with a decrease in the adhesions formed among the tissues. This is counterbalanced to a slight extent by a delay of approximately a fortnight in the establishment of clinical union.

be repaid by the development of a subsequent traumatic arthritis from the uneven distribution of the strains and stresses around the joint. Mal union in the leg is therefore serious in its consequences and must be avoided. Bearing these points in mind it will be seen that open operative reduction and fixation of fractures of the following bones is indicated if there is more than minimal displacement.

- 1 Fractures of the lower end of the humerus and around the elbow (Fig 284)
- 2 Fractures of the radius (Fig 313)
- 3 Fractures of both bones of the forearm (Fig 380)
- 4 Fractures of the posterior margin of the acetabulum, making the hip unstable
- 5 Fractures of the upper third of the femur




FIG 71 Lano's Plate. The original design in which the holes were in alignment and the metal carrying them in sufficiently strong (Down Bros)




FIG 72 Stamin's Plate. A plate designed to have greater rigidity in the centre and holes out of alignment (Down Bros)

- 6 Fractures of the femoral condyles and tibial plateau involving the knee
- 7 Fractures of both bones of the leg (Fig 546)
- 8 Fractures of the tibia alone
- 9 Fractures with displacement at the ankle joint (Fig 591)

Supporting these assertions is the fact that these fractures are those which give the least satisfactory results when treated by ordinary measures.

Materials used in internal fixation. The search for a non-corrosive material was soon ended, that for a non electrolytic material continues. Vitalium, which is non electrolytic, has the disadvantage of not being ductile and has to be cast. Stainless steel shows some electrolytic features, but is stronger and can be more readily worked.

WIRE. The early use of wire in fracture of the patella was found to be valuable, owing to its durability. Secondary changes were frequently noted around the iron wires used and silver wire often

- (a) Subacute infection around the plate, not sufficiently acute to affect the temperature chart, but indicated by radiological signs of rarefaction at the fracture line
- (b) Electrolytic effects of the metal. Currents of action develop between the metal and the surrounding cells. This is prevented by the use of a non electrolytic material such as vitallium, or stainless steel
- (c) The size of the plates. Apart from increased electrolysis, there is a greater intolerance displayed by the tissues the larger the foreign body present. This is independent of the material used, and encourages one to reduce the amount of material inserted to the smallest possible proportions

4 *Technical difficulties* Skin damage in the vicinity may prevent operation. It is desirable in the case of an abrasion to operate at once, rather than to wait till the abrasion has healed, as delay is undesirable, and infection unlikely to occur if immediate operation is carried out. The line of incision must of course be clear of all abrasions, though if these are very small they may be cut across.

5 *Rate of union* If a small amount of metal is inserted no effect on the rate of union can be noticed. The strength of union, however, depends on the area of callus formed as well as the rigidity of the callus present. The area of callus formed is reduced when the fresh hæmatoma is evacuated by early operation. Clinical union is thus delayed. In the case of the tibia the delay amounts to a fortnight.

Fractures in which Operative Reduction may be Indicated

A more detailed consideration of this subject will be found in the chapters concerning each special bone, but a few general remarks and an outline of the suitable fractures seem appropriate here. Generally speaking, the fractures which involve the surfaces of joints, particularly those of the lower extremity, require the most perfect reduction if the later development of traumatic arthritis is to be obviated. Such fractures require open operative reduction. Fractures of bones which have a complex movement due to the presence of joints at either end of the bone, such as the radius, require perfect reduction for perfect function. The nearer a fracture is to a joint the more strain on the joint mal union will impose and the greater need for perfect reduction. The bones of the upper limb, if mal aligned, are subject to the strains of abnormal muscular contractions and incongruous joint surfaces. These are often trivial and, as a consequence, the alignment of such a bone as the humerus need not be perfect for sound function. In the leg the line of transmission of the body-weight through the limb balances the pressures on either side of the joints and any deviation from the normal will

preference to Lane's plates, which not infrequently snapped after use of the limb (Figs 71, 72)

SCREWS Screws have the advantage of producing strong fixation with minimum bulk of material where it is possible to use them alone. They may be supplemented with plates. Two main designs of screw are available —

(a) Machine thread (Sherman pattern),

(b) Wood thread (Venable pattern)

In the latter screw the depth and width of the thread enable a better grip to be obtained on cancellous bone. In compact bone both screws are equally efficacious if the compact bone on the opposite side is penetrated by the screw. The Venable pattern screw is the more generally useful pattern. Screws should be accurately gauged, and a drill one sixty-fourth to one thirty-second of an inch smaller be used to drill the preliminary hole. The length




FIG 74a Three varieties of the Kuntscher nail, the upper being used for the femur, the middle one for tibial fractures and the lower one for fractures of the forearm. Other varieties with different cross sections have been developed and are perhaps more frequently employed.

of the screw should be calculated as nearly as possible, but excess is often of little moment and may sometimes be nipped off.

Parham's bands These may still be employed for fixing spiral or oblique fractures. They are not available at present in any satisfactory metal, but if manufactured there would be no objection to their use other than their large surface area. Single or double screws can usually be employed to do the same work.

NAILS OR PINS The most effective of these is the trifin pin of Smith Petersen used for fractures of the femoral neck (p 457). But smaller pins and nails have been used in many other situations.

KUNTSCHER NAIL This is a long, light, slightly flexible nail, inserted in the intramedullary cavity. Entrance to this is gained at one end of the bone, e.g., the great trochanter in femoral fractures, the olecranon, the tibial tuberosity. The nail is sufficiently wide to press on the inner surface of the cortex and thus obtains good fixation by its width and excessive length. Open reduction and end-

broke after a time. Stainless steel wire is now available and is technically suitable for the few cases in which wire is advisable.




FIG 72a The slotted plate which permits end to end apposition of the bones and variable placements of the screws (Egger's plate)

PLATES The use of plates and screws provides the most satisfactory method of rigid fixation. Against them are their bulk, their frequent unsuitability of design, and the fact that if not carefully applied they may hold the bone ends apart. In order to impact the bone ends an oblique screw across the fracture site has been employed in addition to the plate. Recently plates of more suitable design than those of Lane, with their greatest strength at the centre, and with slotted holes, have been designed and should be used in



FIG 73 Plating gone mad—excessive plating in a comminuted fracture of the leg from Arbuthnot Lane's book



FIG 74 The two usual varieties of screws employed

- A The venerable screw with wide thread and taper end (Wood screw)
- B The Shurman screw with self-clearing tip and fine thread (Machine screw)

operative time and exposure. The external fixation necessary restricts the early use of the joints, but these never become as stiff as joints which have been under continuous traction. If the operation has only controlled the shortening, angulation may be controlled by wedging the plaster. Early weight bearing in a fresh plaster is dependent on the type of fracture present and the degree of fixation obtained. Thus a spiral fracture fixed with two screws may show the rigidity of a transverse fracture fixed by a plate. Active use of the upper limb can always be encouraged and the lightest of external supports be employed.

INTERMEDIATE METHODS This is an endeavour to combine the advantages of both methods. Light internal fixation is used and supplemented by external fixation for a fortnight. This is removed and the stitches taken out and a plaster back slab substituted. This is removed daily for non-weight bearing exercises to knee and ankle. Activity on crutches is permitted in the case of the lower limb. At the end of six weeks the principal advantages to be gained from early movement of the limb have been established, and fixation of the knee and ankle, or any other joint concerned, will not be followed by serious stiffness. A weight bearing plaster may thus be applied and the patient encouraged to get about. Stiffness is thus avoided, but not at the cost of long periods of inactive recumbency.

General operative technique Open operative reduction is only the method of choice where the facilities for operation approach the ideal. It should be carried out with scrupulous care and "no touch" technique. A general outline of the steps necessary will be given here and are applicable to all fractures.

It will be found convenient in early cases to combine the preparation of the skin with the operation and utilise the one anaesthetic. Preparation in the ward is painful, difficult and apt to be incomplete. In the presence of a gently continuing hæmorrhage it becomes almost impossible. The details of the skin toilet are given on p. 71, where wound excision is discussed. Shaving of the skin is unnecessary. The use of a tourniquet is convenient. In the arm an Esmarch's bandage and a manometer are used, in the leg two Esmarch bandages are applied. These are put on over a sterile towel in which the leg is wrapped at the end of the skin preparation.

The skin is incised in the appropriate position, or the incision is designed to incorporate the excised edges of a wound if this is convenient. Care is taken to see that the vitality of the skin is not impaired by the lines of the incisions. The incision, if possible, does not cross or communicate directly with the fracture site. Curved flaps are thus usual or long incisions to one side which permit approach by adequate retraction. Tissues are then sewn or clipped

to end apposition of the bones is usually a necessary preliminary It is particularly helpful in the difficult fracture of the upper third of the femur (Page 483)

BONE GRAFTS The use of grafts has been discussed elsewhere It must be remembered that they may be used as an immediate method of fixation where there is bone loss, or bone pegs may be used in the fixation of fractures near a joint

Selection of suitable cases The complication to avoid at all costs is sepsis, and for this reason any infection of the skin in the vicinity, or any serious infective process elsewhere, is a contra indication to operation Any risk of failure of wound healing from skin damage must be carefully watched For these reasons grossly compound fractures are usually unsuitable for primary fixation Indirect compound fractures should heal by primary union and excision of the wound may well be combined with single screw fixation (p 557) Simple fractures of the types indicated previously, where a good result cannot be obtained by other methods, should be fixed There are two periods at which this fixation may be carried out —

1 *Immediately* This has many advantages but does not allow any preparation of the skin If there is an abrasion immediate operation is the method of choice, as infection of the abrasion may prevent later operation

2 *Delayed* Between the fourth and the fourteenth day This gives time for the hæmatoma and local swelling to subside a little Adequate skin preparation may be carried out

Immediate operation relieves the patient, avoids hæmatoma, and is generally easier, because of the absence of tissue contraction and the ease with which the sharp edges of the bone interlock

General Aspects of Internal Fixation

The degree of internal fixation and the degree to which it is supplemented by external fixation are capable of much variation The limb may be so fixed by plates as to require no external support, or it may be so lightly fixed as to demand rigid external support Each method has its advantages and disadvantages and must be adapted to the individual case

COMPLETE INTERNAL FIXATION The advantages offered by this method are the simplicity of the dressings and the opportunity given for early use of the limb for non weight bearing and weight bearing exercises The disadvantage is the bulk of metal which must be inserted and the consequent complications

LIGHT INTERNAL FIXATION AND EXTERNAL SUPPORT This utilises the simplest degree of internal fixation with a reduction in

5 *Unsatisfactory position or excessive length of screw* This may not be realised till later radiographs are taken. The screws should be left in till union is established and then removed.

Combined Internal-External Fixation Methods

It seems appropriate in this chapter to describe some of the methods which have been adopted to facilitate early use of the limb. The most important of these is the crossed-pin technique (anatomic splint of Roger Anderson) for the long bones, but more profitably applied by our dental colleagues to fractures of the mandible. Pins are inserted in the bones on either side of the fracture at a suitable distance, and at such an angle to one another that they control the movements of the bone completely. By fixing the pins rigidly to an external support complete mechanical control of the fracture may be obtained and it may be aligned and held in alignment. If the apparatus is sufficiently rigid, weight bearing through the appliance is possible. While dramatic in its immediate results there are several drawbacks to the method. It needs considerable experience to apply, it is not always painless when applied due to slight movement being permitted, but its chief disadvantage is the liability to infection of the pins. This is present with any pin, but is reduced in amount by using as fine a pin or wire as possible (hence the advantage of Kirschner wires over Steinmann's pins), and by having little or no movement of the tissues relative to the pin. The early movements made possible by the apparatus thus sow its seeds of failure. In the jaw, where there is relatively little movement of soft parts compared to bone and delicate pins can be used, the method is effective and useful.

The use of a pin which screws into the bone and leaves a handle extending through the skin for incorporation in plaster may be helpful in fractures of the radius.

Intramedullary Kirschner wires This method may be of value in fractures of the forearm, as it is comparatively simple to introduce it into the ulna. Its application to the radius is less satisfactory. In the ulna the




FIG. 75. Anatomic splint. Fixation of the fracture by mechanical clamping to an external bar. Alternative methods of angling the pins to obtain rigidity are shown (Roger Anderson splint).

very accurately to the skin edges so that all contact with external skin is excluded

With fresh instruments the tissues are dissected and the bone ends exposed. Periosteal stripping is confined to the minimum. The bone ends are then grasped in Lane's forceps and accurate alignment of the limb restored and the bone ends interlocked. A decision as to the appropriate method of fixation of the fracture will now have been arrived at. If transverse a plate may be needed. If oblique or, helical, single or double screw fixation may be satisfactory. The insertion of the screws is much facilitated by the use of a mechanical drill, either electric or pneumatic. In general, the type and position of the fracture will determine the position of the fixing agent, but where possible the deeper surface of the bone should be employed. Screws should always obtain a grip on the cortex of the bone on the opposite side, and to avoid splitting the bone they should not be put in line.

The soft tissues may be closed over the bone with a few interrupted sutures. The skin is carefully and accurately closed by interrupted skin stitches as described on p 74. Haemostasis is important and if there is any fear of haemorrhage, either the tourniquet must be relaxed and the haemorrhage controlled or a small drain must be put in for the first twenty-four hours. The limb is then enclosed in a firm dressing of cotton wool evenly bandaged on, and the whole encased in plaster. If the internal fixation provides sufficient stability the plaster is omitted and the leg supported on a Cramer wire splint for the first few days.

REMOVAL OF FIXATIVE AGENTS. This is not always necessary and is dependent on several factors.

1 *Infection.* Usually subacute, it does not necessarily demand immediate removal with resultant loss or control of the fracture, but may be postponed till there is no lateral instability. In the rare acute cases a decompression of the wound is necessary to provide adequate drainage. Later on the foreign bodies may be removed.

2 *Atrophic non union.* Following the insertion of large amounts of metal this may occur, and is characterised by a complete lack of new bone formation. Removal of the plates and external support is often followed by satisfactory osteogenesis. Freshening of the fractured ends of the bone may be carried out at the same time. Rarely a bone graft may be necessary.

3 *Palpable metal.* A screw head which is subcutaneous may become tender.

4 *Formation of sinuses.* These often close in the course of time without removal of the metal if they are not due to acute infection (see p 123).

has been found to be an unsatisfactory procedure in the treatment of fractures of the long bones, with the exception of the olecranon process of the ulna

'(9) Operative treatment should not be regarded as a method to be employed in consequence of the failure of non operative measures, as the results of secondary operations compare very unfavourably with those of immediate operations

'In order to secure the most satisfactory results from operative treatment, it should be resorted to as soon after the accident as practicable

'(10) It is necessary to insist that the operative treatment of fractures requires special skill and experience, and such facilities and surroundings as will ensure asepsis. It is therefore, not a method to be undertaken except by those who have constant practice and experience in such surgical procedures

"(11) A considerable proportion of the failures of operative treatment are due to infection of the wound, a possibility which may occur even with the best technique

'(12) The mortality directly due to the operative treatment of simple fractures of the long bones has been found to be so small that it cannot be urged as a sufficient reason against operative treatment

"(13) For surgeons and practitioners who are unable to avail themselves of the operative method, the non operative procedures are likely to remain for some time yet the more safe and serviceable "

Instruments Used in the Operative Treatment of Fractures

A. CLEANING UP TROLLEY

- 1 Bowl of etl or soap
- 2 Bowl of sterile water
- 3 Bowl of iodine or spirit
- 4 Dry gauze swabs
- 5 Scissors
- 6 Dissecting forceps
- 7 Sterile towels
- 8 Esmarch's bandages (2)

B. OPERATING SET Plating of fractures, Screw fixation, or Grafts

- 1 Scaupels (2)
- 2 Dissecting forceps, toothed (2)
- 3 Dissecting forceps, untoothed (2)
- 4 Blunt dissector, Macewan's
- 5 Spoon, Vollmann's
- 6 Retractors, single hook
- 7 Retractors double hook
- 8 Retractors, Langenbeck's
- 9 Levers, bone, Lane's (2)
- 10 Periosteal elevator, Fraiboenf's
- 11 Periosteal elevator, Macewan's
- 12 Scissors, Mayo's curved, Straight (2)
- 13 Bone holding forceps, Lane's serrated (2)
- 14 Bone holding forceps, Lane's toothed (2)
- 15 Plate holding forceps
- 16 Screw holding forceps
- 17 Plates

fracture is exposed and the Kirschner wire passed down the shaft of the bone towards the olecranon. It is drilled through this till it protrudes behind and is then withdrawn into the end of the proximal fragment. The fracture is then aligned and the Kirschner wire pushed across into the distal fragment. In the radius a Kirschner wire may be introduced into the radial styloid and down the shaft but it is technically difficult. Usually other methods of fixing the radius are more satisfactory (see Chapter XXII)

B M A Report on the Operative Treatment of Fractures

In 1910, as a result of the acute controversy around the subject of the operative fixation of fractures, a committee of the B M A was appointed to report on the subject. The high standard of this committee needs only the names of Victor Horsley, Wilfred Trotter and Rutherford Morrison to be mentioned to testify it. It is appropriate here that their findings should be reported as the passage of thirty years has not altered their validity in any degree, and they balance nicely the position of the immediate operative reduction of fractures.

"(1) The statistics relative to the non operative treatment of fractures of the shafts of the long bones in children (under the age of fifteen years), with the exception of fractures of both bones of the forearm show as a rule, a high percentage of good results. These are unlikely to be improved upon materially by any other method of treatment. Operative results in children, expressed in percentages are approximately the same as non operative.

(2) It is possible either by non operative or by operative treatment to obtain a high percentage of good results in children.

(3) In comparison with the non operative results in children, the aggregate results of non operative treatment in those past childhood (i.e. over the age of fifteen years) are not satisfactory.

"(4) From the analysis of the age groups it is clear that there is a progressive depreciation of the functional result of non operative treatment as age advances that is to say the older the patient the worse the result.

(5) In cases treated by immediate operation the deleterious influence of age upon the functional result is less marked.

(6) In nearly all age groups operative cases show a higher percentage of good results than non operative cases.

(7) Although the functional result may be good with an indifferent anatomical result the most certain way to obtain a good functional result is to secure a good anatomical result.

"(8) No method whether non operative or operative which does not definitely promise a good anatomical result should be accepted as the method of choice. For this reason mobilisation and massage by themselves have not been found to secure a high percentage of good results. They are however valuable supplementary methods of treatment.

'Similarly, of operative methods those which secure reposition and absolute fixation of the fragments yield better results than methods which fall short of this imperfect fixation of the fragments by wire or other suture

CHAPTER XI

THE WAR SURGERY OF FRACTURES

OF the unholy profits of war the least contemptible and the most direct is the advance in the knowledge of wound surgery. From the days when Ambrosio Pare first noted that the wounds of the uncauterised were in better condition than those treated with sealding oil and up to the present day the advance has been steady. The incidence of war has paradoxically increased with the knowledge gained, and the last two wars with their wealth of clinical material have brought the most startling advances. The war of 1914-18 fought in the era of dressings and antisepsis has given way to the era of no dressings and asepsis. In 1914-18 the knowledge of wound shock and its treatment—and the development of skeletal traction, are the two greatest advances. In this war the use of the closed plaster and the development of the chemotherapeutic drugs are the vanguards. In between the wars, the organisation, segregation and specialisation of treatment of fractures has gradually advanced, growing in great part from the work of Böhler, who first emphasised the economic advantages of segregation and early correct treatment. The widespread improvement in technique and treatment in this war is due as much to the body of organised men on which it was possible to draw as to the newer methods.

Modifications of method entailed by war. The object of a fracture service is the provision of the most highly skilled service available, at the earliest possible moment after injury. It is in the first few hours after the infliction of a wound that surgical treatment is decisive. No amount of after treatment in skilled hands can alter the after effects of preliminary disasters. Though this ideal remains the same in war, it remains more remote by reason of delays and difficulties. The lack of sufficient trained personnel makes it necessary to ensure that the methods adopted and taught to the less specialised are safe and simple and give the best results in the aggregate of cases. Necessarily this is not always ideal, but is ideal under the prevailing conditions of war.

Of paramount importance in handling casualties is evacuation, and attention is rightly concentrated on this. No treatment other than that necessary to forward a man along the chain of evacuation should be carried out until the conditions for interference and after-care are stable and satisfactory, in other words, until a man has reached a stable unit. Methods which are quite safe and comfortable have to be worked out and in this there has been a tremendous advance.

- 18 Screws
- 19 Screwdriver
- 20 Drill, pneumatic, electric, or hand (For grafting must be motor driven)
- 21 Bits One thirty second to one sixty fourth smaller than screws
- 22 Circular saws on spindles To fit drill chuck, of which Jacobs is best type
- 23 Counter sink bit
- 24 Bone nibbling forceps
- 25 Gouges, bone, $\frac{1}{4}$ and $\frac{1}{2}$ inch, deeply curved
- 26 Chisel, $\frac{1}{4}$ and $\frac{1}{2}$ inch wide
- 27 Hammer
- 28 Sequestrum forceps
- 29 Needles round bodied and cutting edge
- 30 Needle holder
- 31 Suture material, thread catgut and stainless steel wire
- 32 Spencer Wells' forceps (6)
- 33 Allis' forceps (6)
- 34 Moynihan's towel clips (2)

REFERENCES

- LANE W. ARBUTHNOT "The Operative Treatment of Fractures" London 1914 2nd Ed The Medical Publishing Company
- INGELTRANS P "Biologie de l'ostéosynthèse Méthallique" L'echo Médical du Nord 1944, 15 185
- SPEED AND SMITH "Campbell's Operative Orthopaedics" London 1922 2nd Ed Henry Kimpton

includes incision, that is, the opening up of possible pockets of the wound so that a widely open saucerised wound is the result. In cutting fascia for this purpose it is often desirable to incise it transversely so that the ends will retract, and not longitudinally, when the cut edges may pull together with extension and rapidly close off the space below. This is particularly important in wounds of the thigh and calf.

Delayed or secondary suture. The undesirable waste of time between the establishment of a granulation tissue bed and epithelialisation can be greatly reduced in many cases by the use of skin grafts, either free or pedicle, or the secondary suture of the wound. In cases returned from "forward areas," this can often be carried out with success before the end of the first week. The stages at which a wound may be suitable for closure may be outlined as follows —

1 Within the first week. The wound looks clean. There is no active granulation tissue bed and there is minimal discharge. Secondary suture with limited excision is carried out (or skin graft).

2 Between ten to fourteen days. There is a well established granulation tissue bed but adhesions are not firm. Discharge is moderate in amount. The wound may be prepared by saline compresses and powdering with penicillin and sulphathiazole for two or three days.

Bacteriological examination may be of assistance to exclude heavy infection with streptococcus hæmolyticus or staphylococcus aureus unsuitable to taking of grafts and satisfactory suture. Moderate excision and removal of granulation tissue is necessary to approximate the wound.

3 After twenty-eight days. A firm granulation tissue bed and adhesions are found, and wider excision and mobilisation of tissue will be needed, or the surface of the wound may be grafted.

CAUSES OF FAILURE WITH SECONDARY SUTURE. 1 Excessive tension in the skin flaps.

2 Inadequate hæmestasis.

3 Heavily infected wounds. Do not suture when the patient has a temperature or when œdema is present around the wound.

4 Poor general condition of a patient. Maintain the hæmoglobin above 80 per cent and give full diet.

The advantages to be gained from the early closure of a wound are many, chiefly the avoidance of undesirable adhesions, the healthier scar obtained, and the possibility of earlier and safer interference if subsequent procedures such as bone grafting have to be carried out.

The time for surgical interference is the time between the infliction of a wound and the invasive stage of organised bacterial warfare. Any medium which delays the invasion of bacteria will therefore be of paramount importance in lengthening the time in which interference is safe and giving longer time for transfer. The sulphonamides and penicillin have proved of tremendous value in this respect—both the internal administration and the direct application of the drug to the wound being of value. By this means, it has been found possible to excise wounds thirty-six to forty eight hours after infliction, where normally twenty four hours would be regarded as a reasonable limit. A second and equally important effect has been the reduction of dangerous sepsis and the complications therefrom. The delay in bacterial multiplication produced by the surface application of the drugs gives a little longer for the tissues to organise their own defence and reduces the spread of infection. As a result of this, wounds which would have previously required amputation may be given a trial on conservative treatment and should this fail and amputation prove necessary, the amputation, though in the presence of sepsis, can be carried out safely at the most suitable level. On the secondary advantages of chemotherapy in infected wounds, we have not time to speak here, but a little more will be found on p. 82.

Closure of wounds. In a compound fracture without serious loss of skin, it is often a point of fine judgment whether or not the wound should be closed. Primary union may save months of open drainage from an osteomyelitis. Closure may result in infection spreading under pressure and complications which threaten the limb or even life. Especially is this likely to be so where no rest and no continuity of treatment can be given the patient. It is therefore incorrect under war conditions to close any but the most trifling wounds. This is not to be accepted as proving that under different conditions in civil practice, with early interference, ideal operating conditions and immediate rest, the same thing should be done. If the wound has been dusted with sulphathiazole and drained, no damage will ensue even if primary union does not take place, and observation will soon show whether an undue risk has been taken and a change to packing and open treatment is advisable.

Under battle conditions comfort, safety during transport and uniformity and speed of treatment are best secured by adequate excision of wounds 'frosting' with a mixture of sulphanilamide and penicillin (p. 83), light packing of the wound with gauze and a closed plaster. This may be removed at any period along the line of evacuation that seems desirable or is indicated by any alteration in the patient's condition.

Emphasis must once again be laid on the fact that excision also

The arm and forearm In the upper limb there was a tendency in compound fractures of the humerus to immobilise the arm on a thoraco brachial plaster in abduction. Experience has shown that this is undesirable from the point of transport and surgically seldom necessary. Fractures of the arm are better immobilised by a U-shaped slab, with the arm lying against the thorax. The side of the thorax is then padded to make it lie comfortably and the whole arm fixed to the side by plaster (Fig 78). In less complicated cases circular bandages and a sling can be used to replace the thoracic plaster. Fixation of the forearm will depend on the degree of immobility desired. It may be supported by the sling, or a continuation of the arm plaster to the metacarpal heads may be incorporated in the plaster turns around the chest.

The forearm alone is satisfactorily immobilised by a plaster slab.

The thigh and hip It is always difficult to apply a satisfactory plaster spica under anaesthesia, padded or unpadded. Being awkward to nurse, it is particularly undesirable when the patient must be transported. The plaster spica has its place in treatment, but that place is not far forward in the line of evacuation. Methods have necessarily been sought to replace it and these have been much modified individually.

The femur THE TOBRUK PLASTER, AND MODIFICATIONS This is a combination of the Thomas splint and plaster. After adequate toilet of the wound, skin traction is applied by one-way stretch Elastoplast, pads being placed over the malleolus. Stockinette and cotton wool or stockinette alone may be placed over the leg to prevent adhesion of the plaster to the strapping. The leg is then placed on a Thomas splint in the ordinary manner. The slings being in position, a large pad of cotton wool, 8 inches by 6 inches by 3 inches, is placed behind the knee. Care is taken in the case of anterior wounds to see that the slings are tight and that the whole leg lies well in front of the bars of the Thomas splint. This enables inspection of anterior wounds to be carried out subsequently without the bars obscuring the sides of the limb. If the wound is a posterior one the limb may be allowed to fall through the bars to some extent to facilitate inspection of the posterior aspect of the limb. The fracture is then set in as satisfactory a position as is possible by traction and adjustment of the pad and sling, and the traction tapes tied firmly around the lower end of the splint. If a large ring Thomas' splint is being used, difficulty may be met with, as it rides off the ischium and presses on the perineum. This may even cause retention of urine, a serious disability during transport. To offset this the diameter of the ring may be decreased by one of two methods —

Transport Plasters

The plaster which is ideal for transport must comply with certain conditions —

- 1 It must be sufficiently stable to prevent movement of the bones and soft tissues ,
- 2 It must offer no possibility of constriction ,




FIG 76 Transport methods of fracture of the humerus—fixation of the humerus by a U shaped slab running over the shoulder. If there is an accompanying radial nerve lesion or a fracture of the forearm a slab may be laid along the forearm as shown by the dotted lines




FIG 77 For simple fractures of the arm after fixation, it is sufficient to support the forearm in a sling and bandage the arm firmly to the chest with a wool pad in the axilla

- 3 It must be readily removable for inspection if possible without disturbing the fracture ,

- 4 It must be marked with the details of the lesion and treatment for ready reference




FIG 78 In compound fractures or in fractures of the arm and forearm the slabs are covered by plaster padded lightly and moulded around the arm

Under these conditions the skin-tight plaster is unsuitable and has to be replaced by the padded plaster. Padding should be judiciously used, confined chiefly to the area where swelling is expected and to the bony prominences. It should be evenly applied and compressed to about $\frac{1}{2}$ to $\frac{3}{4}$ inch in thickness. A clumsy, ill padded plaster fails to grip the limb and provide adequate fixation. Where a tighter plaster has to be applied for fixative purposes it should be split down its full length.

No circular bandages should be applied

below the plaster as they may not be divided in splitting the plaster and so act as a cause of constriction

It is important that the foot be held at right angles to the limb and that the toes be protected from the weight of the blankets. If




FIG. 81 Section of the femur lying in a transport plaster

- A Cotton wool pad
- B Femur
- C Plaster
- D Side bar of Thomas splint
- E Sling

the leg has been enclosed in a short plaster for other injuries the plaster should extend beyond the toes. This will provide sufficient support. If the leg is uninjured a Thomas' footpiece is strapped on




FIG. 82 Section of Thomas splint at plane of ring, showing one method of narrowing the ring of the splint to obtain a better fit

- A Ring of splint
- B Folded over plaster slab
- C Felt strip on skin over trochanter
- D Section of trochanter
- E Ischial protruberance

to the splint. This should be high enough to take the pressure of the blankets off the toes. A piece of gamgee is placed on either side of the foot and the gamgee, foot, and side bars of the footpiece incor-

(a) It may be filled with a large pad made of cotton wool wrapped in a few turns of plaster. The plaster must not be sufficiently thick to make a hard surface on setting and is used merely as a covering. This pad is placed between the trochanter and ilium and the ring of the splint. It moulds itself to the tissues and the ring and so does not slip out or alter its position, the setting of plaster assisting in retaining it in place.

(b) A felt pad may be placed over the trochanter and outer part of the thigh. A plaster slab 15 to 20 inches in length is then placed




FIG. 79. A fracture of the femur lying in slings in a Thomas splint. Note pad over trochanter to decrease the diameter of the ring of the splint; pad behind knee and the skin traction on the leg. In the case of an associated fracture of the leg, this can be replaced by a short padded leg plaster.



FIG. 80. The complete transport plaster—a modified Tobruk type. The leg as shown in Fig. 79 is covered with a layer of wool before the application of the plaster. Note the punching in of the plaster (Fig. 81) on either side. The foot is supported by a plaster cuff.

over the outer portion of the ring and splint opposite the side bar of the Thomas' splint. It is then moulded over the ring on both sides so that it fills the gap between the ring and the felt (Fig. 82).

Having fixed the limb firmly on the splint the front of the thigh, knee and leg is padded with cotton wool. The whole limb and splint is then enclosed in plaster which is moulded in at either side (Fig. 81) so that the side bars are included in a plaster U and the cross section of the limb resembles a ball of plasticine pinched out on each side. To do this the plaster must be left slack anteriorly. It is then well moulded around the limb as it sets.

ments do not hinder union and may be incorporated in the callus (Fig 83) Larger metallic fragments should be removed if they are readily accessible They should be sought for specially if —

1 There is progressive hemorrhage in the soft tissues around them

2 The fragment lies in a joint

3 The fragment is in the vicinity of a large vessel or nerve

4 If it is excessively large

5 If it is palpable

Wounds from larger foreign bodies fall roughly into two main categories Those with a clean entry and exit wound and little evidence of tissue damage Those with a jagged entry or exit wound and obvious tissue destruction below The first group, i.e., the clean bullet wound, merely require toilet of the entry and exit wounds, and dressing, unless there is continued hemorrhage Infection is rare in such wounds and usually not serious In the second group of cases the exposure of the damaged soft parts which is necessary, usually results in the finding and extraction of the foreign body Where small fragments have produced considerable tissue damage, and then ricocheted to a position where their extraction would be difficult, they may be safely left (Fig 84)



FIG 83 Satisfactory union of fracture in spite of the inclusion of many foreign bodies



FIG 84 Compound comminuted fracture of ulna due to a bullet seen lying over the radius Note Union has occurred though there is a sequestrum present the marked osteoporosis of the carpal bones

Care must be taken to conserve fragments of bone with any attachment or if huge and lying free, is removal of too many such

porated in a few circular turns of plaster. In other words, the foot is maintained in dorsiflexion by a similar means to that used for fixing the limb.

At the end of the proceeding brief diagrammatic and written notes of the injury and its treatment should be recorded in indelible pencil on the plaster.

THE HIP Immobilisation of injuries in the region of the hip joint is difficult to carry out satisfactorily. The plaster spica is unsatisfactory for reasons previously given. A useful temporary method for transport is provided by the abduction frame for the hip. This enables rapid fixation of injured lower limbs and so shortens operating time. It may be invaluable for transport or for fractures of the femur complicated by other injuries. Various combinations of traction on the lower limb and plaster may be used with it.

Amputations Closure of an amputation wound is similar to the closure of a compound fracture, and for the same reasons is inadvisable in forward areas. If the tissues are left widely open there is little to limit their movement and patients with a guillotine amputation protected only by a dressing travel badly. For this reason where possible flaps should be cut and lightly stitched together over a gauze pad which may protrude at either end for drainage. The fixation of the soft tissues by this means greatly increases the comfort of the patient.

As secondary amputation may be required all amputations should be carried out at the lowest possible level. It is often convenient to amputate through a fracture site, and amputations through joints should not be scorned as they expose a much smaller area of soft tissue to infection (see also p. 103).

War Fractures and their Complications

1 *Compound fractures from missiles* No new complications are raised by this form of injury, but the common complications of compound fractures are met with in an exaggerated form. Soft tissue damage may be heavy, particularly on the side of the exit wound. Comminution in injuries to the shaft of a bone may be marked and there may be considerable loss of bone, while foreign bodies may be widely scattered through the soft tissues. In contrast to this a neat hole may be drilled by a high velocity bullet through the cancellous end of a bone with relatively little damage. In general, small metallic foreign bodies without gross tissue injury may be neglected. They should be removed if visible or palpable in the general debridement of the wound but should not be specially sought for in tissues at a distance from the wound. Metallic frag

chemistry suggests that other factors than mere interference with filtration are damaging renal action. Treatment is directed towards slowing the release of the toxic products from the limb into the general circulation. If a limb is to be amputated the tourniquet should be left on until the last moment to avoid absorption from the limb. Cooling the limb to prevent rapid revascularisation may be maintained at the same time as the general body warmth is raised. The immediate intravenous administration of plasma and saline with alkalis is essential in severe cases.

6 The increased use of blood transfusion and of plasma have been of enormous advantage in saving life. These materials have been brought up sufficiently close to the front line and in sufficient quantities to make the impossible possible. The use of two pints of plasma to one of whole blood has become established as a proportionate dose to avoid corpuscular dilution. In cases of pure hæmorrhage whole blood should be used, but a small proportion of plasma may be given to supplement it. Recognition of sub groups as the cause of minor degrees of incompatibility has been greatly advanced. Scientific control of the condition of the blood can be greatly assisted by pathological reports from the laboratory.

End results. The opportunity to assess the functional results following injuries and the desire for an early return of function has led to a closer study of the effects of various forms of treatment. This has been facilitated by the preliminary knowledge of the patient's physical fitness, as provided by his medical category before injury.

Comparison with his category subsequent to injury enables the recent and remote results of injury to be carefully checked. In certain cases, such as that of trauma to the knee, this has resulted in undue criticism of treatment. Damage to a meniscus is not likely to be the only injury following trauma to the knee. Closer follow up has shown the frequent association of ligamentous injury and it is this factor which usually compels re-categorisation, not the results of the operative removal of the cartilage as is frequently suggested.

The reconsideration of cases from the functional standpoint has demanded an absence of sequelæ and an early return to duty. In the following injuries some modifications of older methods have been found necessary to attain this goal —

1 *Fractures of the fingers and metacarpals.* As early use of the hand as is compatible with the injury is essential. This has been insisted on before, but is now carried to the extreme of avoiding all splinting unless absolutely necessary and insisting on active movements of the fingers from the commencement of treatment. Thus no attempt is made to fix single oblique fractures of the metacarpal

fragments may establish a complete non union with a wide loss of bone tissue. Excluding these cases the average case unites firmly and rapidly with satisfactory and early callus if infection has not supervened. When infection is established progress is slow, but ultimate union is usually satisfactory. In the region of the hip drainage is apt to be unsatisfactory, due to the depth of tissue and complicated fascial planes. For such cases a wide wedge excision of tissues, often including the head and neck of the femur may eventually be necessary.

2 *Fatigue fractures* A much higher incidence of these fractures in the metatarsals has been noted due to the strain of heavy training on the adolescent. Similar fractures in the tibia, the lower third of the femur, and the neck of the femur have been noted (see p 514).

3 *Fractures of the talus and tarsus* The high incidence of fractures of this bone amongst airmen has always been recognised, and the large number of cases occurring in the R A F has shed new light on the mechanism and treatment (see p 573). Mine explosions produce complicated compound foot injuries, often best amputated (see p 594).

4 *Burns and fractures* The unpleasant combinations of these injuries in airmen and tank crews may set difficult problems in treatment. Skeletal traction is unwise if the burnt area is likely to become secondarily infected around the pin. The use of a sulphonamide wax dressing under a plaster cast may be helpful. Where skeletal traction can be used, encircling burns of limbs may be enclosed in an envelope of the Bunnell Stannard type between or distal to the pins. Should a compound wound be surrounded with a burnt area the same treatment may be employed. Irrigation with saline hypochloride or penicillin solution replaces the vaseline pack.

5 *The crush syndrome* In civilian injuries from falling buildings and in the prolonged use of the tourniquet this syndrome may be met with. It has certain similarities to the syndrome which follows incompatible blood transfusion. It is characterised by general features due to disturbed renal function and local changes in the injured limb of a circulatory nature. Thus the limb may become swollen, pale, and tense. Arterial pulsation is reduced or absent and distal gangrene not uncommon. The blood pressure rises, the patient is liable to frequent vomiting and there is a variable mental disturbance. The output of urine is rapidly reduced, is highly acid, and in early specimens myohæmoglobin makes its appearance. Recovery is ushered in by diuresis. In fatal cases the renal failure continues and the blood urea rises. Proof that the damage to the kidney is due entirely to the deposition of hæmatin in an acid urine, with resultant tubular blocking is lacking and the disturbed blood

alleged late vascular disturbances in the skin of the stump. In general the weight and efficiency of artificial limbs has been so much improved that the contrast between retaining a damaged limb and being limbless is no longer so prejudicial to amputation. Where it is obvious that the patient's general condition may deteriorate as the result of prolonged sepsis, or the efficiency of the limb if retained will be low from muscular adhesions, vascular disturbance or associated nerve injury then amputation is to be urged. After amputation the functional use of the stump is to be insisted on rigorously as it would have been in the digits of the affected limb.

REFERENCES

- "The Official History of the War, 1914-1918," *Surgery of the War*, Volumes 1 and 2, London, 1923. H.M. Stationery Office.
- PORRIT, A. E. "Military Surgery in the Middle East," *Brit J Surg*, 1944, 31, 208.
- BUXTON, J. D. "Surgical Experiences in the Middle East," *Brit J Surg* 1943, 30, 111.
- McKEE, G. K. "The Use of Irrigation Envelopes in the Treatment of Lacerated Wounds and Compound Fractures," *Brit J Surg*, 1943, 30, 328.
- BYWATERS, E. G. L. "Crushing Injury," *Brit Med J*, 1942, 11, 643.
- "Memorandum on Skin Cover for Wounds and Burns" London, 1944. War Office.

even if slight shortening results. Fractures of multiple metacarpals never have the individual fingers splinted unless the displacement is gross. Sufficient support can be given to them by a plaster extending to the metacarpal heads on the dorsum of the hand. In fractures of the fingers it has been found unnecessary to splint the majority as there is little tendency to redisplacement after reduction. Where deformity recurs splinting for a minimal period is used.

2 *Fractures of the metatarsals* The stiffness of the tarsus and foot is generally so apt to follow immobilisation it is best avoided by allowing early active use of the foot. This is a natural deduction from the success met with in treating march fracture by light activity in boots. Under such treatment the patient is soon capable of light duty and the total disability time is much reduced.

3 *Fractures of the calcaneus* The conclusion that this fracture is best treated by early active exercise of the foot and ankle without weight bearing was gaining ground before the war and has been reinforced by experience during it. No indication for active interference is provided by anything other than gross anatomical deformity. This is reduced by any of the available methods and retained by a plaster. Treatment by continuous traction is avoided if possible.

4 *Fractures of both bones of the leg* In spite of the great improvement in the position obtained by reduction with modern methods, this has not been found sufficiently good judged by the high standards of physical efficiency demanded by the Army. Open operative reduction has therefore gained much in popularity and is described in full on p. 124.

5 *Skin graft* The increased use of skin grafts in the healing of wounds is directed towards hastening functional recovery. The desirable co-operation of orthopaedic and plastic surgeons is growing and it is becoming clear that traumatic surgeons must have considerable plastic knowledge to gain the best results. The uses of grafts are numerous. The immediate whole thickness graft over the pulp of the finger may save amputation of the terminal phalanx. Later the cleanly granulating wound may be rapidly closed by a Thiersch graft. The early use of Thiersch grafts in open wounds which remain uninfected between the fourth and the tenth day may produce a dramatic hastening in the time of repair. Large areas of scar tissue preventing adequate approach for orthopaedic operations may be replaced by pedicle grafts, enabling secondary operations through healthy skin to be carried out.

6 *Amputations* The elective sites remain. The opinion is to which sites should be elective varies. The Syme amputation though found effective by the Canadians is unpopular in England from its

demands of all fractures. The apparatus necessary for the operative treatment of fractures is listed at the end of Chapter 10.

1 THE BED For the patient's comfort and nursing convenience it is important that this should be satisfactory. Most of the advantages of complicated beds can be obtained more cheaply and equally satisfactorily by additions to an ordinary iron bedstead. Such a bed should have a firm iron frame and wire mattress on which fracture boards can be placed. A convenient height for this mattress is 26 inches from floor to wire. The stuffed mattress should be firm and even, and for this horsehair mattresses cannot be bettered.




FIG. 85. Suitable fracture bed arranged with hand pulley, iron Balkan beams (now only occasionally required) and fracture boards. The end of the bed is elevated on wooden steps, the most suitable assistance for high elevation. For low elevation the blocks on the floor may be used.

If a divided mattress is available, with a removable central portion, the use of the bedpan will be facilitated. All beds must have an attachment at the back so that the overhanging pulley may be provided for the patient to elevate himself. In place of this a fairly low Balkan beam may be used which has the advantage of allowing the patient to run hand over hand down it and so flex himself to any degree, and thus obtain valuable exercise for the spinal and other muscles.

2 BLOCKS The elevation of the end of the bed to obtain counter traction from the body weight is constantly required and may be made on blocks of varying height (6, 9, 12 and 15 inches are useful heights), adjusted to the pull required and the weight of the

CHAPTER XII

APPARATUS

THE following is a short list of the necessary general apparatus for the handling of cases according to the methods outlined in this book. The apparatus is described in more detail in the paragraphs following.

- 1 Sutable bed
- 2 Bed blocks or stand, pulleys, fracture boards
- 3 Orthopaedic table or pelvic rest and apparatus to use as a substitute
- 4 Counter traction bands and wall hooks for their fixation
- 5 Kirschner wires and apparatus for their introduction and retention
- 6 Steinmann's pins, and apparatus for their introduction and retention
- 7 Screw traction apparatus for the leg, Böhler's or Watson Jones
- 8 Screw traction apparatus for the arm (Böhler's) This is not absolutely necessary as the leg apparatus may be used instead
- 9 Braun's splints With single and multiple pulleys
- 10 Thomas splints For the leg and arm
- 11 Abduction splints for the arm
- 12 Cramer wire in assorted widths
- 13 Finger wires
- 14 Felt, plam and adhesive
- 15 Walking irons, rocker soles or plaster overshoes
- 16 Sponge rubber 1 inch thick for heels
- 17 Mastisol
- 18 Unna's paste
- 19 Stockinette
- 20 Strapping, single and double stretch
- 21 Wooden tongue spatulas and spreaders
- 22 Cord, hooks, separate pulleys and weights
- 23 A spring balance (0 to 60 lbs.)
- 24 Starch bandages
- 25 Elbow goniometer
- 26 Copper wire
- 27 Osteoclast Only occasionally used not a necessity
- 28 Calcaneal clamp
- 29 Indelible pencils
- 30 Plaster scissors, Stockholm plaster shears, plaster case openers and old scalpels
- 31 Knee exercise bar
- 32 An arm abduction apparatus for traction on the arm with the bent elbow
- 33 Plaster as described in the subsequent chapter on that subject

With the exception of the objects commented upon the other requirements may be regarded as absolute necessities if one is to be equipped to meet the

simplest form consists of a metal horseshoe with two clamping screws at either end, and adapted to take a strainer. With one screw




Fig 87 An effective variety of Kirschner wire drill

clamped down the wire is tightened and is held true by tightening the second screw. Strainer and excess wire are then removed.

For cutting Kirschner wires a specially strong type of wire cutter is required.

6 STEINMANN'S PINS These are stainless steel rods of varying diameter from 2 to 4 millimetres. One end is sharply pointed and the other squared for the introducing handle. They may be hammered through bones like the calcaneus, or drilled through as though using a bradawl by the introducer. We have found



Fig 88 A Kirschner wire strainer and tractor combined

the most satisfactory method is to drill the bone first with a small wood twist drill of smaller diameter, and then insert the pin through this hole. It gives one accurate control over the direction of the pin and is comfortable for the patient. The pins are held in stirrups which are attached to either end by a collar and screw so that the stirrup can rotate without rotating the pin. A rotating pin is a common cause of sepsis in the pin hole.




Fig 89 Steinmann's pin and stirrup



Fig 90 Steinmann's pin and introducer

patient, or on a wooden step ladder on which both legs of the bed are placed. This is the more stable arrangement when the foot of the bed is elevated over one foot.

3 **ORTHOPÆDIC TABLE** The possession of an orthopædic table of the Hawley or Putti type is almost a necessity if much work on the hip is to be done, but for plasters without extension a pelvic rest with a small stool to go under the shoulders can be used. The feet in this case are supported by assistants. A very convenient pelvic rest is made for attachment to the Böhler leg traction splint,




FIG. 56. Hawley table

and this gives almost all the conveniences of an orthopædic table including leg traction, at considerably less cost. (Fig. 56.)

4 **COUNTER-TRACTION BANDS** For many methods of reduction and the retention of a fracture while plaster is being applied, counter-traction is necessary and this is best provided by webbing bands attached to a hook in the wall some 6 inches above the table height. The use of such a band is almost a necessity in forearm fracture. (See Chapter XXII for illustrations of its use.)

5 **KIRSCHNER WIRE APPARATUS** This consists of a drill, which there are many types, both hand and electric, and so apparatus for tightening the wire and maintaining its stretch. There are many stirrups (or tractors) designed for this purpose, more convenient consisting of tractor and strainer combined. 7

increasing pull can be put on the leg and registered on the spring balance. A third detachable upright is important as it can be used to support the lower third of the leg which is hung from it by a bandage. This frame can be combined with a pelvic rest and adjustable foot piece, and so be used for traction on the straight leg. It can be used also for forearm and arm fractures. This piece of apparatus, with the addition of a pelvic rest piece, can replace a Hawley table, or be used instead of an arm traction frame. It can thus be a very useful and economical addition to one's apparatus. Watson Jones' apparatus is designed to avoid the action of gravity, traction being applied to the leg in the dependent position (Fig 93). The apparatus is convenient for the leg, but not so adaptable.

8 BOHLER'S SCREW TRACTION APPARATUS FOR THE ARM. This is occasionally useful, but the apparatus described above can be used in place of it.

9 BRAUN'S SPLINT. This skeleton splint is a modification of Pettit's trough leg splint, and is a very convenient and adaptable splint for most fractures below the pelvis. It consists of a rigid iron frame which sits on the mattress of the bed, and from this two




FIG 93 Watson Jones Extension Apparatus for the leg which offsets the effect of gravity (Doun Bros)




FIG 94 Bohler's modification of Braun's splint

7 BOHLER'S SCREW TRACTION APPARATUS FOR THE LEG This consists of a rectangular tubular steel frame with uprights carrying




FIG 91 The Böhler leg extension frame A Extension screw B Pelvic support used only with additional leg piece C Bar for support under the knee D Another variety of bent knee rest E Upright support used in calcaneal fractures (See Fig. 644)

cross-bars One bar is placed under the flexed knee The other bar carries a screw with a wing nut, which has a hook attached, and to




FIG 92 Showing the use of a pelvic support and leg extension piece added to the Böhler leg extension frame which makes it suitable for hip plasters

this the stirrup of a Steinmann's pin is attached by copper wire, with a spring balance intervening By tightening the wing nut an

first aid splint, and is used where it is desirable to treat the leg with the knee extended. With the knee-flexion piece it can be used in the same manner as the Braun's splint, or it may be bent at the level of the knee to obtain knee flexion. Its chief disadvantages are the discomfort of the ring, particularly at the shoulder, and the fact that it needs some support, such as a Balkan frame to carry it. When




FIG 97 Thomas splint used as described in method (a)




FIG 98 Thomas splint used as described in method (b)




FIG 99 Thomas splint used as described in method (c)

the splint is slung, however, it responds to the patient's movements in the bed, without disturbing the fracture. It therefore provides a degree of comfort which no splint firmly attached to the bed can do, and this alone justifies its use in any long term case, in preference to the Braun's frame. There are several methods of application of the splint.

(a) The strapping or skeletal traction is tied to the splint and both pulled on together. This releases the ring from pressure, and the bed must be elevated for counter traction.

parallel iron bars slope up to support the thigh, and then run parallel to the bed to support the calf and leg. Over the foot runs a steel arch, and to this are attached pulleys in the line of the femur. The two leg bars are prolonged, and end in a pulley on the level of the leg. By bandaging the parallel bars a trough for the leg may be made.




FIG. 95 The use of a Thomas splint with a knee flexion piece
Skeletal traction in the lower end of the femur

The thigh portion should be bandaged firmly to make a flat surface, and the leg portion more loosely to allow the calf to sag into it. The bandage should stop before the heel to prevent pressure sores. The foot is conveniently supported by stockinette bandaged over mastisol, or by strapping and a spreader attached to the bar of the




FIG. 96 Straight arm Thomas splint

arch or pulled on lightly by a 1 lb weight passing over the upper pulley. This is essential to steady the foot, and prevent foot drop.

10 THOMAS SPLINT This is another skeleton splint of an adaptable nature particularly if it has a knee flexion attachment. The leg Thomas consists of a padded leather ring attached at the angle of the groin to two iron bars which run, narrowing towards one another, till joined transversely, at a variable distance from the ring. In the arm splint the leather ring lies at right angles to the line of the side bars, and is hinged on them. In the leg splint it is placed obliquely to adapt it to the angle of the groin. This is a most useful

While an assistant holds the splint firmly up into the axilla. Over these an oblique bandage is placed, running over the opposite shoulder and around the bottom of the vertical bar of the splint, around which one twist is taken with every turn of the bandage to lock it. These bandages need reapplication in two to three days when they have stretched. If they are now re-applied and covered with two starch bandages the splint may be made firm for



FIG 101 Abduction splint made of Cramer wire strips wired together with copper wire and padded. A cheap and adaptable splint

two to three weeks. It is very difficult to apply an abduction splint to an unconscious patient, and it is advisable to apply the splint before manipulations are commenced in cases in which a general anæsthetic is to be used.

12 CRAMER WIRE This skeleton wire, consisting of strong wire uprights with lighter wire cross bars resembling a ladder, is very convenient material for making temporary splints. The most comfortable of back splints may be made by wiring two lengths



FIG 102 Cramer's wire ladder splinting

together to give rigidity and then moulding them to the shape of the posterior aspect of the knee, calf and heel, and padding them. This makes an ideal resting splint for sprains, lacerations and cases such as fractured patellas awaiting operation. Similar short splints for the hand, elbow, and forearm can readily be made.

13 FINER WIRES These consist of light iron wires bent as shown, and approximately 10 inches long with $1\frac{1}{2}$ inch side pieces. They can be incorporated in a forearm plaster when traction is

(b) The splint may be used as a support only, and the extension be taken from the skin or skeletal traction apparatus. This is the most useful and satisfactory method.

(c) The extension may be made to run through a pulley attached to the splint so that there is an equal counter pressure on the ring of the splint. If this is done the bed need not be elevated.

11 ABDUCTION SPLINTS. A great variety of these have been produced. The greatest difficulty with this splint is maintaining it in position. This is attained by the use of straps or bandages, and these need constant attention to prevent dropping of the splint, which then drags on the arm, and may produce the deformity it is desired to correct. Their correct application, so that the hand is




FIG. 100 Bohler's arm abduction splint

in front of the face and the arm at an angle of 45° to the frontal plane, to relax the pectorals is also not easy to attain. The splints used fall into three types: (1) those used for support only, (2) those used for support together with continuous traction on the arm, provided by a separate spring (see Fig. 247), (3) those in which the elasticity of the splint provides some traction on the arm.

An effective and useful splint of the combined first and third types may be made from 3 or 4 inch Cramer wire suitably bent and wired together with copper wire (see Fig. 101). The splint is padded carefully with tow or wool. It has the advantage of being cheap, light, and readily adaptable to varying bodily habitus. It is applied by bandaging the two body pieces firmly to the chest,

on of Colles's fractures, or in the application of plaster for continuous skin traction. Here it is advisable to paint the skin once before the application of the strapping, and then paint over the strapping when it is applied and cover the whole with a few turns of gauze bandage.

18 **UNNA'S PASTE** (Zinc oxide 150 grams, gelatin 150 grams, glycerine 350 grams, water 350 cc. Soak the gelatin in the water till soft, add the glycerine, heat and adjust the weight with water to 850 grams. Sift in the zinc oxide and stir till even. Allow to set in a tray, and cut into blocks to be melted for use.) This is used in the treatment of varicose veins, but it can be used for skin traction or making elastic stockings. It is applied with a large brush and painted warm on the skin. A layer of gauze bandage is then wound evenly over this, and another coat of paste applied.



Fig. 107 Materials for the application of Unna's paste stockings

This is repeated till three layers are evenly applied. The application is finished by wiping the surface with 6 per cent formalin in spirit and covering the resultant moist surface with a fine layer of cellulose wool. "Viscopaste" bandages are a convenient proprietary preparation, from which elastic stockings may be made. Elastoplast serves the same purpose, but is more expensive.

19 **STOCKINETTE** This is a useful material for obtaining a smooth lining to plasters such as spinal jackets. In limb plasters, by pulling it down over the end of a moist plaster satisfactory smooth, rounded ends may be obtained (see Fig. 126, also 501).

20 **STRAPPING** The ordinary zinc oxide strapping sticks better if the skin is painted with mastisol first. Where close application with increased flexibility is desired, *e.g.*, in supporting a joint, strapping with a single or double elastic weave (elastoplast) is more satisfactory, though there are certain situations where this increased

required on a finger, and are then used unpadded, being covered with strapping after incorporation in the plaster. Where it is only required to rest the finger it is sufficient to use a padded splint curved to fit the flexed finger and palm, and bound on with a gauze bandage covered with a starch bandage (Fig 44)




FIG 103 Wire finger splint, unpadded and padded Compare Fig 44

14 FELT is a very useful padding material. That with a sticky surface has its uses, but mastisol painted on the skin will enable plain felt to be put to a similar use. It is used to cover pressure points in such plasters as that for a fractured spine, or to make a comfortable bearing surface in a walking plaster.

15 **ROCKER SOLES** These consist of a simple wooden or iron section of a small circle attached usually to a wooden base plate. They are made in variable sizes. For an adult the base measures 7 inches by 3 inches and the attached curved portion, 5 inches with a maximum depth of $1\frac{1}{2}$ inches. They are cheap, easily made, and permit a more normal gait, avoiding the screwing action frequently seen with the walking iron (Fig 134).

WALKING IRONS These consist of a bent light metal bar to which a rubber heel is attached. They are bent in the shape of a U and incorporated in a leg plaster to bear the weight. They are best applied by a separate plaster bandage after the leg plaster has set, to avoid the metal making pressure marks in the fresh plaster. They are applied so that the centre of the bar is two fingers' breadth below the plaster on the heel, and in line with the tibia and fibula (see Fig 134 and page 182).

16 **SPONGE RUBBER** Sponge rubber pads, 1 inch thick and cut to a size of 3 by 6 inches, may be attached to the leg plaster by a few turns of bandage over the foot. They have the advantage of allowing a more natural gait, but they must be protected by an overshoe of some description.

17 **MASTISOL** (Gum mastie 40 parts, Oil Ricin 12 parts, benzine 100 parts). This varnish provides a sticky skin surface which improves any grip on the skin, such as required in the reduc




FIG 104 Walking iron with attached rubber stud

tion of Colles's fractures, or in the application of plaster for continuous skin traction. Here it is advisable to paint the skin once before the application of the strapping, and then paint over the strapping when it is applied and cover the whole with a few turns of gauze bandage.

18 UNNA'S PASTE (Zinc oxide 150 grams, gelatin 150 grams, glycerine 350 grams, water 350 c.c. Soak the gelatin in the water till soft, add the glycerine, heat and adjust the weight with water to 850 grams. Sift in the zinc oxide and stir till even. Allow to set in a tray, and cut into blocks to be melted for use.) This is used in the treatment of varicose veins, but it can be used for skin traction or making elastic stockings. It is applied with a large brush and painted warm on the skin. A layer of gauze bandage is then wound evenly over this, and another coat of paste applied.



FIG. 107 Materials for the application of Unna's paste stockings

This is repeated till three layers are evenly applied. The application is finished by wiping the surface with 6 per cent formalin in spirit and covering the resultant moist surface with a fine layer of cellulose wool. "Viscopaste" bandages are a convenient proprietary preparation, from which elastic stockings may be made. Elastoplast serves the same purpose, but is more expensive.

19 STOCKINETTE This is a useful material for obtaining a smooth lining to plasters such as spinal jackets. In limb plasters, by pulling it down over the end of a moist plaster satisfactory smooth, rounded ends may be obtained (see Fig. 126, also 301).

20 STRAPPING The ordinary zinc oxide strapping sticks better if the skin is painted with mastisol first. Where close application with increased flexibility is desired, e.g., in supporting a joint, strapping with a single or double elastic weave (elastoplast) is more satisfactory, though there are certain situations where this increased

required on a finger, and are then used unpadded, being covered with strapping after incorporation in the plaster. Where it is only required to rest the finger it is sufficient to use a padded splint curved to fit the flexed finger and palm, and bound on with a gauze bandage covered with a starch bandage (Fig 44)




FIG 103 Wire finger splint unpadded and padded Compare Fig 44

14 FELT is a very useful padding material. That with a sticky surface has its uses, but mastisol painted on the skin will enable plain felt to be put to a similar use. It is used to cover pressure points in such plasters as that for a fractured spine, or to make a comfortable bearing surface in a walking plaster.

15 ROCKEN SOLES These consist of a simple wooden or iron section of a small circle attached usually to a wooden base plate. They are made in variable sizes. For an adult the base measures 7 inches by 3 inches and the attached curved portion, 5 inches with a maximum depth of $1\frac{1}{4}$ inches. They are cheap, easily made, and permit a more normal gait, avoiding the screwing action frequently seen with the walking iron (Fig 134).

WALKING IRONS These consist of a bent light metal bar to which a rubber heel is attached. They are bent in the shape of a U and incorporated in a leg plaster to bear the weight. They are best applied by a separate plaster bandage after the leg plaster has set, to avoid the metal making pressure marks in the fresh plaster. They are applied so that the centre of the bar is two fingers' breadth below the plaster on the heel, and in line with the tibia and fibula (see Fig 134 and page 182).

16 SPONGE RUBBER Sponge rubber pads, 1 inch thick and cut to a size of 3 by 6 inches, may be attached to the leg plaster by a few turns of bandage over the foot. They have the advantage of allowing a more natural gait, but they must be protected by an overshoe of some description.

17 MASTISOL (Gum mastic 40 parts, Oil Ricini 12 parts, benzine 100 parts) This varnish provides a sticky skin surface which improves any grip on the skin, such as required in the reduc-



FIG 104 Walking iron with attached rubber stud

variation, depending on how firmly it is pressed into the muscles, it gives a more consistent accuracy than other instruments. It is adaptable to other joints such as the knee and hip.

26 COPPER WIRE This is necessary for binding Cramer wire




FIG. 108 The Phelps Gocht osteoclast

splints together and for connecting up parts of the extension apparatus, especially if a spring balance is not used.

27 OSTEOCLAST This is a necessity for breaking down firmly united fractures, and is useful for the reduction of some fractures. The Phelps Gocht apparatus shown is the most generally useful. It is a luxury only needed in a busy clinic.

28 CALCANEAL CLAMP This is necessary for the complete reduction of a fracture of the calcaneus with broadening of the bone. It can also be adapted for compressing the upper end of the tibia, or the lower end of the femur if special pads are used. It is a




FIG. 109 The Bohler redresseur, or calcaneal compression clamp

strongly made clamp tightening the jaws evenly, over a bar on which the distances between the clamp faces are measured. In use the convex pad is applied to the outer aspect of the calcaneus, and the reniform pad to the inner aspect so that it clears the sustentaculum tali.

29 INDELIBLE PENCILS

These are the most suitable for recording on the plaster the dates of fracture, reduction, and approximate removal of the plaster, together with a diagram of the fracture.

31 PLASTER INSTRUMENTS The most generally useful instruments are

Stockholm plaster shears

Plaster scissors

Plaster case openers

Round pointed scissors

Old scalpels or ankle knives

elasticity is a disadvantage. The single stretch strapping is the more generally useful (see Figs 79, 425)

21 **WOODEN SPATULAS** These are useful in holding apart the ends of ready made strapping extensions and enable the strapping to be applied with the minimum of disturbance. Wooden spreaders



FIG 106 Skin extension made from ordinary strapping torn ready for use. Central spreader attached and the ends held apart by attachment to tongue spatulas

are necessary to obtain an even pull on the plaster and to prevent pressure on bony points, such as the malleoli

22 **CORD, HOOKS AND WEIGHTS** are essential. Two pound weights will be found most useful. Hooks are necessary as an attachment to the stirrup, and a second hook on which the weights are hung facilitates adjustment

23 A **SPRING BALANCE** placed between the screw of the saw traction apparatus and the stirrup will record the pull applied. A balance registering to 60 lbs is most useful. Smaller balances may be used for registering the traction on the arm in an abduction splint



FIG 107 A goniometer particularly useful for measuring elbow movements

24 **STARCH BANDAGES** These consist of ordinary gauze impregnated with starch. They are boiled for a few minutes and then placed in cold water. As soon as they are cool they are applied. They contract slightly in setting and so obtain a firm grip, accentuated by the fact that each layer sticks to the next. They are useful to maintain splints and bandages in position over a long period

25 **GONIOMETER** Some simple apparatus for keeping a check on the movement possible at the elbow is essential to accurate observation of that joint. The one illustrated is of personal design, the flat surfaces lying along the surfaces of the ulna and the triceps. While giving a few degrees




FIG 112 Diagram of the apparatus described for traction on the arm with the elbow bent Compare Figs 113, 114



FIG 113 View from the end of the bed of the apparatus shown diagrammatically in Fig 112 The wooden foot piece is seen resting on the floor while the main lateral support lies between the wire mattress and the fracture boards Above this lies the oblique arm support, lying on top of the mattress




FIG 110 Stockholm plaster shear, large and small plaster case openers, plaster scissors, probe point scissors

32 KNEE EXERCISE BAR This consists of an adjustable transverse bar whose height can be varied. It can be placed on the bed so that the recumbent patient may bend his knee over it and so exercise his quadriceps. It can be used very early in treatment and aids materially in the maintenance of movement in the knee.




FIG 111 Knee exercise bar

33 ARM SPIINT FOR TRACTION WITH THE BENT ELBOW This simple apparatus consists of a vertical upright standing on a wooden base to which is attached at the height of the top of the wire mattress a strong lateral bar. This bar is laid between the wire mattress and the fracture board, where it is well gripped by the patient's weight, but allows free variation of its position so that the pull can take place at any angle to the central line of the bed. The vertical upright, thus firmly held, is slotted above this level, and through this slot runs a clamping screw with a wooden block on either side. To one block is attached a pulley, to the other a hinged board $4\frac{1}{2}$ inches wide, which stretches to the approximate level of the centre of the bed, where it tapers off. On the top of the upright at a height of 5 feet from the floor, is another cross beam which projects 2 feet on the bed side and 1 foot on the opposite side. To it pulleys are attached, the one




FIG. 112 Diagram of the apparatus described for traction on the arm with the elbow bent Compare Figs. 113, 114



FIG. 113 View from the end of the bed of the apparatus shown diagrammatically in Fig. 112. The wooden foot piece is seen resting on the floor while the main lateral support lies between the wire mattress and the fracture boards. Above this lies the oblique arm support, lying on top of the mattress.

over the bed moving in a groove in a similar manner to the arm rest piece. The cords for traction are run over the lower pulley for the arm and over the upper two pulleys for the forearm. It will be seen that any position of the arm in relation to the trunk can be obtained, as the apparatus is movable in both the horizontal and vertical planes, and that the angle of the elbow can be varied very considerably by adjusting the angle of the arm piece, and the position of the upper pulley. The apparatus is simply made by



FIG 114 Details of the apparatus shown in the previous figure. The strapping extension on the forearm requires a pull of 4 lbs. to maintain it vertical. The arm lies along the sloping support board, and is undergoing skeletal traction through a pin in the olecranon, the average pull required being between 6 and 10 lbs.

any carpenter, is inexpensive, effective, and does not occupy valuable space around a bed, nor look untidy.

34 PLASTER This is fully described in the next chapter.

REFERENCES

- SINCLAIR, M. "The Thomas Splint and its Modifications" Oxford Medical Publications 1927.
 BÖHLER, L. "The Treatment of Fractures" English Edition, 1936 4th Edition, p 34.
 KEEL and CONWELL "The Management of Fractures, Dislocations and Sprains" London, Henry Kimpton 2nd Edition 1937.

CHAPTER XIII

PLASTER TECHNIQUE

THE age old use of plaster for the fixation of broken limbs has received a fresh impetus from the aims of modern treatment, with which the accurate fixation afforded by plaster falls more into line. The successful application of plaster demands the use of plaster bandages of constant standards and a speed of handling only given by constant practice. It is essential that where the plaster cannot be applied single handed a team of assistants familiar with plaster technique be employed, and that they observe a number of simple rules scrupulously.

Material Plaster of Paris, or gypsum, is calcium sulphate which has been heated and so deprived of its water of crystallisation. Soaking and setting result in the recrystallisation of the material in a solid form. The quality of the plaster is important, as it is obvious that one not deprived of its water content as efficiently as another will not be so good. Again it may be contaminated by admixture with inactive powders. Once a suitable plaster is found, and one becomes familiar with its strength, its setting time, and speed of water absorption, one should not lightly change it. Much of the efficiency of plastering depends on easy familiarity with these points.

Bought plaster bandages differ from home-made ones, for in them the plaster is attached by an adhesive medium to the meshes of the material, while in home-made bandages it is only scattered through the meshes of the material and will shake out. The disadvantages of this are that plaster slabs cannot be made dry, as in doing so the plaster washes out, and that there is usually less plaster at the beginning of the bandage and more at the end, while in bought bandages it is evenly distributed. In the making of small and delicate plasters, such as for the fingers, bought material is an asset, but for most other work home made material is equally satisfactory. For certain plasters, such as plaster jackets, the rapid setting and high water-retaining qualities of bought material are a disadvantage. Bought bandages are wound more loosely and so soak more rapidly, and the plasters are lighter when finished. Owing to expense they will not be found suitable for large limbs, and the technique discussed in the following chapter is based on the use of home made bandages, but can always be carried out with bought material.

Home made plaster bandages must be made of good quality plaster, and the maintenance of uniform tension and weight of plaster

in each bandage can only be obtained by practice and experience. It is consequently advisable to have only one or two people making the bandages constantly rather than fresh relays of people. To commence with, they are taught to weigh the bandages after rolling and discard those over or under a certain weight. A little practice and they will be found to roll them so consistently near this weight that weighing may be suspended. Bandages of 4, 6 and 8 inches width will be found the most generally useful, and should be 5 to 6 yards in length. A 6-yard bandage impregnated with plaster

weighs approximately 9½, 14 and 17 ounces for the three respective widths.




FIG. 115 A convenient method of rolling plaster bandages

Rolling The bandages used are muslin sized with starch, and of a mesh of 14 to 24 strands to the inch. They must be plucked at the edge to avoid loose threads. Plaster is placed on a flat tray and the bandage settled

into this so that a foot length of it lies flat on the plaster covered floor of the tray. The bandage is then rolled toward one with the right or left hand and the other hand employed (with a flat spatula if desired) in spreading an even layer of plaster on top of the bandage. This portion is then rolled up, and the action repeated again and again till the bandage is completely impregnated. The tightness of the bandage is important for if wound too tightly the centre of the bandage will not be penetrated by water during soaking, while if too loose the plaster falls out and it is awkward to handle when making slabs.

Handling When used the bandages are dropped evenly into a basin of water which is deep enough to cover the bandage completely. It is ready for removal only when the water has ceased bubbling. If increased speed of setting is desired the water may be hot, and salt (a tablespoon to a quart) may be added. With good plaster this latter expedient is unnecessary. The bandage is then picked up with the hand over either end and squeezed toward the centre till it is devoid of loose water. The free end of the bandage is then undone for a turn and the bandage landed to the surgeon. If a plaster slab is to be made some smooth metal or glass surface is chosen and the appropriate length marked off on it.

Holding the loose end of the bandage down to the slab it is unrolled beyond the length required, and then allowed to fall back to the desired length. The fingers are placed on this end and the bandage rolled to the opposite end and the same action repeated. This will demand a change of hands and if there is an assistant available to hold one end of the plaster down it can be done much more rapidly without changing grip. When a suitable thickness is achieved it is smoothed out and lifted off the slab. If a second bandage is to be used it should be placed in the water just before the removal of the first. After several bandages have been soaked the water becomes impregnated with loose plaster and fails to enter the fresh bandages, so fresh water must be used. It is also unwise to use the same water twice if there has been any delay, as plaster sets in the basin and makes unpleasant loose fragments, which are often picked up by the second bandage.



FIG 116 The correct method of wringing the bandage out

Once a cast is commenced it should be completed as quickly as




FIG 117 Making a plaster slab

possible so that it may set together, and not, as often happens, in separate layers. In large casts this will demand a suitable number of assistants. A forearm plaster may be applied single handed, a plaster jacket will require one assistant to soak the bandages, remove them as soon as required and hand them to the other assistants, one assistant making plaster slabs and one assistant aiding the surgeon in the application of the jacket.

Setting This is a chemical process and continues whether the plaster is under water or drying in the air. It is independent of all factors except the quality of the plaster, and takes place in the following stages

Adsorption of the water of crystallisation together with absorption of water by the bandage and excess water by the plaster

Recrystallisation of the calcium sulphate, accompanied by the generation of heat and consolidation of the plaster. This commences in four to seven minutes, and is complete in ten to twenty minutes

Drying The excess water absorbed is slowly given off. Excessive water can later soften the set plaster, and it must be dried out as quickly as possible. The length of time necessary for this depends mainly on the thickness of the plaster. The placing of the plaster in an airtight space, e.g., under the bedclothes, does not encourage it to dry, and it is best treated in a draught of warm dry air, most conveniently obtained under a well-ventilated heat cradle

Padded and Non-padded Plaster Casts

Much discussion has arisen as to the advantages and disadvantages of the two methods. Where great argument has arisen truth lies as a rule midway between the two extremes. Many so called non-padded casts have padding over the pressure points and so are, strictly speaking, padded. Padded casts are only difficult to handle when excessive and unsuitable padding is used. In this condition they are to be heartily condemned as they do not fit the parts and the padding becomes loose under the plaster, resulting in uneven pressure and pressure sores. The plaster will, as a rule, be unnecessarily large and clumsy, and quite unsuitable for weight bearing. There are many advantages to the unpadded plaster cast, and its use is recommended. It is applied close to the skin, the actual hairs being incorporated and helping in close retention. The plaster can therefore be smaller and more accurately moulded, giving better visual control of position and much better plaster fixation. The absence of padding results in an even pressure on the skin if care is taken to wind the plaster bandage evenly, and the hands are kept moving to avoid pressure points being formed. Plasters should always be held with the flat of the hand and not the fingers, to avoid pressure points. With unpadded plasters pressure sores are less frequent than with padded plasters. Unpadded plasters are more suitable for windowing so that wounds can be observed. Their closer application allows exercise of joints near the fracture with no disturbance of the injured part.

The one great difficulty with them is their inelasticity. In certain areas, such as the wrist and above the ankle, the small amount

of fleshy tissue allows little room for expansion before a dangerous pressure on vessels is reached. For this reason circular plasters have been condemned, but it is not the plaster which is at fault, but the judgment of the person using it. To avoid this risk no circular unpadded plaster should be applied to a fracture within twenty-four hours of its occurrence when further reactionary swelling can be expected. Control of the swelling by even pressure is desirable, and this is best accomplished by the use of a plaster slab for retention, and a circular gauze bandage over it. Later, if desired, a circular plaster bandage can be applied over this. In many cases the presence of swelling prevents the application of a plaster suitable for weight bearing and time must elapse with the limb elevated for this to subside. At the end of this period a circular bandage may be applied skintight, with no risk at all. Similar precautions must be taken after any fresh manipulation of a fracture or any treatment from which reactionary swelling may be anticipated. If these precautions are observed unpadded plasters are devoid of danger.

Plaster difficulties 1 **SWELLING** This may occur in spite of precautions and falls into three stages

- (a) *No obstruction to the circulation or pain* This subsides with exercise of the muscles below the plaster and elevation of the part. All fresh plaster cases should be instructed in the immediate use of fingers and toes and the unfixed joints.
- (b) *Venous obstruction, with an engorged hand* Arterial circulation good. There is no pain, but a feeling of tightness. To relieve this the plaster must be split down, the part elevated and exercises encouraged.
- (c) *Arterial obstruction* This should never be allowed to occur. There is gross swelling and cyanosis or pallor of the skin. Capillary circulation is impaired under the nails and there may be loss of arterial pulsation. This condition is always painful in the early stages, and should never be neglected. The cast must be split and spread, the part warmed and elevated, and if no benefit follows in one and a half hours the cast must be removed.

2 **PAIN** Some aching pain may be expected, but in a well-reduced fracture it is small and relieved by aspirin. Incompletely reduced fractures are frequently more painful. Severe aching pain of a generalised type should raise suspicion of pressure, and demands careful investigation and treatment, as outlined above. It is an important sign not to be neglected and certainly not to be controlled by morphia without investigation.

LOCAL PAIN If the patient can place his finger on a point which is constantly painful, or localises pressure always to a certain spot, he

is always right, and removal of the plaster will reveal the commencement of a pressure sore if not a more fully established lesion. To avoid removal a temporary expedient is to cut a window over the point complained of. If the patient cannot localise the pain definitely it may be due to some roughness or to fragments of plaster falling between the plaster and the skin. This can be neglected unless with the passage of time it turns into more definitely localised pain or pressure.

3 DISCHARGE Unless there has been an open wound discharge always means a moist pressure sore, and demands treatment. Such pressure sores are best treated by fresh air and radiant heat with dry dressings between the applications.

4 PARESIS OF MUSCLES Rarely a walking plaster may press on the peroneal nerve as it winds around the neck of the fibula, and produce foot drop, which is usually not noted till the plaster is removed. It recovers in a variable time with rest, support and faradism to the paralysed muscles.

5 LOOSENESS This is more uncomfortable for the patient than tightness, and in most cases demands replaster. In certain situations such as the first degree external rotation fracture of the fibula, it does not matter as the important movements of inversion and eversion are controlled by a loose plaster as well as a tight one, and weight bearing does no harm. To avoid frequent replastering the necessity for the abolition of swelling by early recumbency and elevation of the limb cannot be too seriously stressed.

Plaster Casts and their Construction

The treatment of fractures demands the use of several standard plasters, the construction of which will be outlined here. These plasters are the base of all work, and more complicated plasters are built up on them. Plasters most commonly used are

Upper limb	1	Arm plaster
	2	Forearm plaster with fixation of the elbow
	3	Standard forearm plaster
	4	Thoraco brachial plaster
Lower limb	1	Whitman's plaster
	2	Long hip spica
	3	Short hip spica
	4	Long walking plaster (Ischial bearing)
	5	Knee fixation plaster
	6	Walking plaster with fixation of the knee
	7	Short walking plaster
Trunk	1	Plaster jacket
	2	Plaster bed

The most adaptable method of construction is the combination of the slab and the circular bandage. Strength is given where strength is required, and the plaster should be lighter in construction than when any uniform thickness of plaster is employed. Given time work the method is quite rapid enough for ordinary purposes. Certain plasters such as the thoraco brachial plaster are troublesome to apply by this method, and the pattern method may be employed. In the pattern method sheets of plaster impregnated muslin are employed. They may be bought in standard pattern form, or patterns cut from sheets to suit the case. Six to eight pattern sheets are placed together and soaked, and then applied as a unit to the limb to be plastered. They are time saving, but unless one is familiar




FIG 118 The Pattern method of plastering for the leg

with them apt to be as troublesome in application as any other method. They are heavier than necessary and the sheets of material are not so easy to store for any length of time. Only bought material can be used and the method is therefore expensive. A pattern for a short leg plaster is shown in Fig 118.

Arm plaster Used for fractures of the shaft of the humerus. This plaster is most conveniently applied with the patient sitting or standing so that the assistance of gravity may be obtained. A 4 inch bandage is made into a plaster slab equal in length to double the length of the arm. This is placed in U-shaped fashion along the inside of the arm, around the elbow, and up the outer side. Cuts in the bandage are made just above the forearm, and over the olecranon to mould it around these points. It is then bandaged in position with a gauze bandage, and the arm held in the desired

position till set. In cases where swelling is expected it is left so. If swelling is not anticipated it can be reinforced with a circular plaster bandage. The plaster is worn with a sling, and can be steadied with a circular bandage around the arm and thorax, including the sling. If a starch bandage is used for this purpose and passed over the sling the arm is kept very firmly fixed.

Forearm plaster, with fixation of the elbow. This is used for fractures of the elbow region and fractures of both bones of the forearm. Where extension is being used in a fracture of the forearm the plaster can often be applied more satisfactorily in two stages.




FIG. 119. The application of a U shaped slab in fractures of the humerus. In high fractures the ends of the slabs can be overlapped on the shoulder.

Where the extension must be maintained while the plaster is setting one stage is used.

(a) **WITH EXTENSION.** The long slab of the forearm plaster is carried up behind the elbow and between the straps of the webbing extension. Plaster is applied overlying the band slightly, but leaving a narrow gap anteriorly through which the extension band is later withdrawn. This gap is then filled in with plaster. (Fig. 326.)

(b) **WITHOUT EXTENSION.** The forearm plaster is applied as usual, but the long slab is continued to the lateral condyle and curved around behind it. When set the extension is removed and a short U-shaped slab placed around the elbow, as in the arm plaster, and bandaged on with a circular bandage while the patient holds the arm at right angles.

(c) **FOR FIXATION OF THE ELBOW ALONE** A dorsal slab is run down behind the elbow from axilla to wrist, or to the metacarpal heads if pronation and supination are to be avoided. This is cut opposite the elbow for moulding, and covered with short reinforcing strips. The whole may then be bound on with a circular plaster or gauze bandage. In adults a 6 inch bandage will be found the best and a 4 inch bandage in children.

Where swelling is anticipated the posterior slab should be increased in thickness and gauze only used to bind it on. This can be covered later with a starch or a plaster bandage.

Forearm plaster This is a standard plaster used with a slight




FIG. 120 Immobilising the arm and forearm in fractures of both bones of the forearm. Retention of the forearm fracture has been satisfactory with a short forearm plaster, and over this a U shaped slab to fix the elbow has been added.

modification for a Colles's fracture or a navicular fracture. A dorsal slab of 6 inch bandage is laid on the dorsum of the mid-pronated hand up to the elbow. It is trimmed or folded back along the line of the metacarpals heads and cut obliquely at the opposite end to allow flexion of the elbow. A vertical cut is made $1\frac{1}{2}$ inches deep parallel with the second metacarpal and the narrow portion folded back over the thumb metacarpal, or cut off. The other side of the plaster is then moulded around the lateral side of the fifth metacarpal and the whole covered with a circular gauze bandage. (Fig. 328.)

Where the fracture is not fresh a circular plaster bandage is used, and then care must be taken that it reaches only to the level of the most proximal portion of the distal line of the palm to allow full flexion of the fingers. Most commonly flexion of the index finger is incomplete, due to excessive plaster. This turn of plaster holding

the metacarpals back against the dorsal slab must not be too loose, but as swelling is often maximal in this region it must not be too tight to commence with. If it becomes loose or has to be cut away it can be replaced with a few turns of strapping or starch bandage. The use of a small piece of iron wire covered in rubber and moulded to the palm, and then incorporated in the plaster is a satisfactory addition as it allows free movements and can be bent tighter as swelling subsides.

For forearm plasters incorporating finger wires, volar slabs are used, which are best applied with the patient leaning the elbow on the table and allowing the hand to fall back. The wires are placed between the slab and circular turns of bandage. (See Fig 43.)

To attain the resting position of the wrist the patient is instructed to clench the fist lightly and then lay forearm and knuckles on the table. The dorsal slab is then placed on top of the forearm if the



FIG 121 The resting position of the hand in which plasters for carpal and metacarpal fractures and foundation plasters for wire finger splints should be applied

plaster can be applied without extension. This is the most comfortable position in which to plaster any wrist.

Thoraco-brachial plaster It is perhaps true to state that the elbow cannot be completely immobilised without fixing the shoulder, but it would be an error of judgment to carry this too far. Having immobilised the arm and forearm it is usually only necessary to bind the arm to the side of the chest, either temporarily with bandages or more permanently by plaster (Fig 78). This is more convenient for transport and for the patient. The application of a thoraco brachial plaster with the arm in abduction is not lightly to be undertaken, especially if the patient is lying down and under general anaesthesia. In the sitting position it is more satisfactory. In the recumbent patient the back must be supported by a strip of metal along the vertebral column which can be later withdrawn from the jacket. Some connection between the hand portion and the thorax is desirable in order to strengthen the support of the limb. The plaster is often conveniently applied in two parts. The jacket

may be done first while the patient is conscious and the arm subsequently fixed to it. In view of the difficulties in its application the pattern method will be found to save valuable time and is easier than the slab and circular bandage method. The plaster is occasionally necessary in wounds of the shoulder region and of the upper third of the arm, but the majority of fractures affecting the shoulder region can be handled with the arm at the side.

Whitman's plaster. To apply this satisfactorily three assistants will be required, one to soak the bandages, one to make slabs, and one to aid the surgeon in smoothing on the plaster. Some form of




FIG. 122 The padding applied for the application of a Whitman plaster. Note the thin roll in the groin held in place by knotting the gauze over the opposite shoulder and the pad over the anterior superior iliac spine. Note also the slight flexion of the knee.

pelvic rest must be available, preferably an orthopaedic table, but the other substitutes previously described may be used.

PADDING. Several layers of flannel bandage are wound around the chest at the level of the armpits. A felt pad is placed over each anterior superior iliac spine, and held in place by painting the skin with mastisol. A roll of cotton wool 12 inches long and 1 inch in diameter rolled up in a long piece of gauze is placed in the gluteal fold and extending over the ischial tuberosity into the groin. This is held in place by crossing the ends of the gauze over the pad on the anterior spine and tying the ends of the gauze over the opposite shoulder. This padding is then covered by a single layer of calico bandage in the form of a hip spica extending up to the chest bandage.

PLASTERING Bandages 6 inches in width are most convenient, though 8-inch bandages may be used for the trunk. The plaster is applied in two stages (unless there is a multiplicity of assistants), first the trunk and short hip spica together, and then the leg from thigh to toes. Four plaster bandages are wound on evenly covering the calico bandages, these are then reinforced with plaster slabs. The first is laid vertically down the side of the leg. The second is placed posteriorly and winds from the back over the sacrum and around the great trochanter to the anterior




FIG. 123 Diagram illustrating the reinforcements used for a Whitman's plaster and which can be used with modification in any hip spica



FIG. 124 The completed plaster being used by an ambulatory patient

aspect of the thigh. The third slab reverses this passing from the anterior aspect of the trunk over the groin to the back of the thigh. The length of all these slabs is approximately 30 inches. A short vertical reinforcing slab made by cutting a longer slab in two may be laid down the anterior and medial aspect of the thigh if desired. These slabs are covered with three circular bandages and the whole well moulded around the pelvis and upper end of the femur.

The leg is then completed with a long dorsal slab overlying the thigh plaster and continued down to the toes. This is cut on either side of the heel and moulded around it. The sides of the knee are strengthened with two short slabs and the whole covered with three circular bandages. In all fifteen 6 inch plaster bandages will be used, and the total weight of the plaster will be 13 to 15 lbs.

Long hip spica This is used for walking when fixation of the hip is desired, the weight being taken on the ischial tuberosity. It can be used for certain fractures of the femur, both shaft and condyles. It is applied in a similar manner to the Whitman's plaster except that the plaster is not carried so far up the trunk. It is well moulded around the pelvis to obtain good fixation.



FIG 125 A short walking spica

Short hip spica This is used for fixation of the hip without avoidance of weight bearing, such as may be required in abduction fractures of the neck of the femur. It is applied in a similar manner to the long hip spica, but terminates above the knee. It is




FIG 126 Illustrating the use of stockinette in finishing off the ends of a cylindrical plaster cast

very difficult to apply either of these plasters in a satisfactory manner to an exceptionally fat patient. The weight necessary to obtain sufficient strength makes the plaster a handicap rather than an aid.

Long walking plaster This is used in lesions of the knee region which require fixation and freedom from weight bearing. It is applied by placing the narrow roll of wool previously described in the gluteal fold, and over the ischium and tying it as before. A long plaster slab is then applied from this to the tips of the toes. It is cut over the ankle and moulded. This is then held in place with the requisite number of circular bandages. Two short slabs are placed on either side of the knee to reinforce it, and covered with further circular bandages. The knee is then held slightly flexed (5° to 10°)

and the foot at right angles till the plaster sets. The roll of wool forms a satisfactory upper limit to the plaster and the ischium sits on this. The plaster is trimmed in front to trochanter level. A rubber heel or walking iron may be applied when desired. This can be used to replace a walking calliper if desired.

Knee fixation plaster. This is used for lesions in the region of the knee where weight bearing is harmless but flexion is undesirable, such as a case of fracture of the patella. It is most conveniently applied with the patient on a pelvic rest and the heel on an object



FIG. 127. The knee fixation plaster as used for a fracture of the patella. Note the elastoplast continued below the lower felt pad to prevent swelling of the foot.

at the same level. The use of a layer of stockinette against the skin will make the finishing of the plaster ends easier. The foot and ankle are strapped in elastoplast to avoid subsequent oedema of the foot. A layer of felt $1\frac{1}{2}$ inches wide is placed over this 3 inches above the malleolus. A dorsal plaster slab is applied extending from the groin level to this, and bound on with a circular bandage. Two 18-inch slabs are placed on either side of the knee and bound on, and circular bandages added till the desired stability is achieved. The stockinette is then pulled back over the ends of the plaster before the final turns and enclosed under them, thus providing a rounded finish.

Short walking plaster This plaster is the most commonly used leg plaster, as it is the only method of completely relieving the foot of strain. It is important that it should be as light as convenient, and not clumsy, being well moulded around the ankle, and fitting firmly around the knee at the level of the fibula head and the tibial condyles. It must be cut out behind the knee to allow flexion beyond a right angle. The foot must be at right angles to the line of the leg and in the neutral position as far as inversion and eversion are concerned, except in special cases. The plaster must continue to the ends of the toes on the sole, but stop short of the webs of the toes on the dorsum of the foot, so that toe movements are free.



FIG 128 The method of applying a plaster for immobilising the knee. The foot is strapped in elastoplast up to the lower felt pad on which the lower margin of the plaster ends. The knee is held slightly flexed as the plaster sets.

The walking iron must not be applied till the plaster has set, to avoid the risk of producing pressure by the metal on the soft plaster.

There are several methods of applying this plaster and it is advisable to familiarise oneself with one and use it alone. These methods are applicable to fractures in which there is moderate union, or to fractures in the ankle region, in which pressure in the long axis of the leg is painless. For fresh fractures, skeletal traction or manipulation and manual retention till the plaster sets, are required.

(a) **THE STANDING METHOD** The patient lies on the couch and flexes the knee and hip so that he can place the foot against the surgeon's chest. By this means the foot is retained at a right angle, and the hands are left free. A circular pad of felt $1\frac{1}{2}$ inches wide is bound on over the head of the fibula and at the level of the tibial condyle. A second piece may be put over the dorsum of the toes.

to prevent rubbing and excessive tightness in plastering. A 6 inch plaster slab is now run from the upper margin of the felt to the




FIG 129 The standing method of applying a walking plaster showing the method of obtaining dorsiflexion against the chest, and the necessary padding of felt

tips of the toes. A cut is made on either side of the ankle and the plaster moulded in. Circular plaster bandages are then applied




FIG 130 The dorsal slab applied. Commencing the circular bandage

around the slab including heel and foot, two 6-inch plaster bandages being as a rule sufficient. To plaster the heel the surgeon leans forward, thus pushing on the ball of the great toe, and leaving the

heel free. To plaster the toes satisfactorily he must have an assistant to support the heel unless he waits till the plaster has set firmly enough to maintain the ankle at right angles and then turns the toes with a small bandage.

(b) **THE SITTING METHOD.** The technique of padding and plastering are unchanged. The patient sits on the table with the operator before him on a low stool. The leg to be plastered is allowed to hang over the edge of the table, and dorsiflexion is maintained by



FIG. 111. The seated method of applying a walking plaster. Dorsiflexion of the foot is maintained by resting it on the knee.



FIG. 112. Application of a short leg plaster with the patient lying on his back. The slab shows no tendency to fall away.

resting the toes on the knee of the surgeon. This is a very comfortable and satisfactory method of application.

(c) **WITH SKELETAL TRACTION** the problem of support to the leg does not arise, but dorsiflexion of the foot must be maintained. The plaster includes the wire through the calcaneus, which is removed later if desired. No padding is placed around the wire or pin and the plaster is in direct contact with it. The pin is often retained for a combination of skeletal traction with plaster retention.

(d) **WITH SKELETAL TRACTION** IS NOT AVAILABLE the limb

is best handled under local anæsthesia which enables the patient to co operate, and makes plastering much more simple than when there is a completely flaccid knee. Manipulative reduction is followed by plastering with the help of an assistant, so that the limb may be maintained in the desired position.

(e) **THE FACE DOWN METHOD** By laying the patient over on his face, and then flexing the knee the foot can be easily kept at right angles, and the plaster slab placed on it does not tend to fall off by gravity. It is a position easily maintained by the patient and comfortable for work. It can, of course, only be used for stable limbs (Fig 132).

APPLICATION OF A WALKING HEEL This may consist of either




FIG 133 The application of a sponge rubber sole and heel to a walking plaster




FIG 134 Rocker sole plate To a wooden base a curved metal section preferably covered with rubber or leather is fitted

(1) Rubber sole of sponge rubber 1 inch thick and 3 by 6 inches in size. It is held under the sole by a few turns of a plaster bandage. This gives the patient a more natural gait than a walking iron, and is more comfortable, but requires the use of an overshoe to prevent it being worn out. (2) Overshoes with thick sponge rubber heels and soles may be bought and laced over the foot of the plaster. In clinics they will do for several patients. (3) Böhler walking iron. This is applied over the leg plaster so that the heel lies two fingers' breadth below the heel of the plaster and in the line of the tibia and fibula. It is satisfactory but does not give a good gait, as the patient tends to screw his foot out in taking off with the plastered foot. It will stand up to rough usage, and does not require an over shoe (Fig 104). A modification of the

Böhler iron giving a better gait is the rocker sole (Fig 134). This consists of a curved steel band covered in leather which is attached to a sole plate. The sole plate alone is attached to the plaster and it may be used over and over again. A rocking heel and too gait results.

Freedom of the toes. There has been considerable discussion as to the advisability of extending the plaster sole to the tips of the toes to provide a platform for the toes. This restricts the flexion exercises of the toes. There is no doubt that all cases of injury to the foot itself should have a platform, owing to the danger of flexion contracture of the toes. This risk is especially marked in cases of pes cavus. On the other hand, patients who are merely lying in bed with the foot fixed as the result of a leg injury can have the plaster discontinued below the ball of the great toe to give adequate exercise to the toes. Similarly when the short walking plaster is used with an overshoe, the softening of the fore part of the foot to allow normal toe and metatarsal action should be encouraged. In all cases the exercises should be regularly instituted. Where the bed clothes are likely to press on the toes, during transport, the plaster should be continued beyond the toes.

Removal of plasters. The most suitable shears for removing plasters are the Stockholm shears. They should always be introduced in the fleshy side of the limb so as not to produce painful pressure between the bone and the plaster. Forearm plasters should thus be split down the volar aspect. To remove a leg plaster the patient is turned over on his face, and the plaster split over the calf and then over the sole.

The plaster jacket. This is used for fractures or other non-traumatic lesions of the spine. There are various positions in which it may be applied (see Chapter XVII), but the aim of all of them is to produce satisfactory hyper-extension of the spine, and maintain it while allowing the patient freedom of movement. The careful padding of the plaster is necessary to avoid pressure sores. The areas of pressure under such a plaster are, the sternum above, the iliac spines, crest and pubis below, and posteriorly the highest point of the curve of the extended spine, corresponding to the spinal kyphosis. Padding of orthopaedic felt is placed over these areas. In the method recommended for plastering the dorsal pad is an essential part of the technique and consists of a gamgee pad 15 inches by 4 inches (Fig 209). Satisfactory padding of the iliac crest may be obtained by painting the skin with mastisol, and running a piece of felt 2 inches wide right around the pelvis, folding the two ends over the pubes anteriorly.

Over these pads a stockinette jacket is applied pinned over the

shoulders to keep it smooth. The plaster is then applied. Eight 7-inch bandages are used for encirclement and 6-inch bandages for reinforcing slabs. Five to six of each will be found necessary. The arrangement of assistants is as for a hip plaster. It is important that all the plaster be applied in a short period (five to ten minutes) so that it may set evenly. A circular layer is first laid carefully over the stockinette, and over this the reinforcing slabs and bandages are applied, the slabs running in the following directions:

1 Horizontally around the anterior and posterior margin of the jacket at the level of the iliac crest. (One long, or two short slabs)




FIG 135 Diagrammatic illustration of the reinforcing slabs used in the construction of a plaster jacket. First layer




FIG 136 Second layer

2 Vertically posteriorly in the midline from the sacrum to the seventh dorsal vertebra. (One)

3 Obliquely from the top of the sternum around the chest and under the arm to the midline posteriorly. (Two)

4 Vertically from the trochanter to the axilla on either side. (Two)

5 Obliquely from the symphysis pubis upwards and around the iliac crest to the midline posteriorly. (Two)

These slabs are best made from single 6 inch bandages rolled into 30 to 40 inch long slabs and cut in half. They are incorporated

under the circular turns which are continued steadily throughout the whole proceeding

As soon as the plaster has set the patient is placed on a flat bed and after half an hour it will be ready for trimming. The armpits are first cut out so that the arms can be placed comfortably at the sides. Anteriorly the plaster is cut a little below the level of the sternal notch, and in the groins so that full flexion of the legs can occur. Here the tendency is not to cut away sufficient plaster. Extension can be maintained by a plaster which comes only to the level of the anterior superior iliac spines, though usually one removes less than this, leaving a tongue anteriorly to press over the pubes. A circular window is cut anteriorly over the stomach. A longitudinal window is cut posteriorly over the pad covering the lumbar spines. The pad is left in place under this. This is a particularly important spot to relieve pressure.

The application of a plaster jacket is much more satisfactory in a conscious patient. Under anaesthesia one tends to get too great hyper-extension and the patient is difficult to control. Morphine and hyoscine are satisfactory sedatives and usually all that is required. Bought plaster is unsatisfactory to work with, for spinal jackets home made bandages being the best. After any jacket is applied the patient may vomit during the first twenty four hours, but this settles down at the end of that time. It is best to get the patient up and about on the first day, as he settles into the jacket more readily. Trimming is usually needed again at the end of twenty-four hours. The plaster should be dried under a heat cradle for the first night, plenty of circulating air being allowed.

AFTER-TREATMENT This is important and consists of active general bodily exercises, including exercises specially designed for the abdominal muscles. After a fracture of the spine correctly treated the patient should emerge in better physical condition than before the injury. (See Appendix III p 644.)

Plaster beds These can be made either by applying bandages to and fro over the back of the recumbent patient, or by using sheets of muslin of the size required soaked in plaster cream and laying them layer by layer on the back of the patient. The first method is quite satisfactory, and demands no new technique. The number of assistants required is as for a hip plaster. The patient is laid on his back with appropriate extension, and is covered with a stockinette singlet. Over this bandages are criss-crossed and slabs laid between them till a reasonably strong shell has been built up. This must be done quickly to obtain uniform setting. The second method demands team work for a satisfactory result. Ten to fourteen sheets of muslin are cut to a size approximately 4 feet 6 inches by 2 feet

Fourteen pounds of plaster are mixed in a deep bucket to a smooth cream. The sheets of muslin are then quickly soaked in this and laid layer by layer on top of the patient, and smoothed into position. If the muslin is slightly moist before it is dipped into the cream it will facilitate its absorption. The plaster is allowed to set, then removed and trimmed. Drying will take two to three days.

Such a plaster bed may or may not include a portion for the head. It is most comfortable if carried down to the mid thighs, and should have a central portion between the thighs which are thus slightly separated. If the plaster is intended for continuous use a window is cut out over the buttocks and the shell held up on a wooden frame to permit the passage of a bedpan underneath.

REFERENCES

- SCHNEK, F. "The technique of the Non padded Plaster Cast" English Translation Vienna, Wilhelm Maudrich, 1932.
MONRO "The History of Plaster of Paris in the Treatment of Fractures," *Brit J Surg*, 1935, 23, 257.

CHAPTER XIV

ANÆSTHESIA

THOUGH intravenous anæsthesia has largely displaced the many alternative anæsthetics, on account of its great advantages, there are still a few cases for which it is unsuitable, and for these there is a wide choice of anæsthetics. Local anæsthesia is unsatisfactory in children, gas does not give sufficient relaxation in many cases, and ether allows too great a relaxation and makes plastering difficult. These and many other points make the choice of a suitable anæsthetic from one of the following not as simple as it may seem at first sight.

1 LOCAL ANÆSTHESIA

2 REGIONAL AND BLOCK ANÆSTHESIA

3 SPINAL ANÆSTHESIA

4 GENERAL ANÆSTHESIA

(a) *Gas and oxygen*

(b) *Intravenous anæsthesia*

(c) *Ethyl chloride*

(d) *Ether and chloroform*

The factors influencing the choice of the anæsthetic will be (1) the site and type of fracture, (2) the duration of the anæsthetic required, (3) the degree of relaxation required, (4) the age and mentality of the patient, (5) the presence of other complications, and (6) the anæsthetics available.

Local Anæsthesia

Local anæsthesia has many advantages, which are set out briefly in the following paragraphs (After Bailey and Love)

1 The fracture may be reduced single-banded

2 It can be used in patients in whom a general anæsthetic is dangerous

3 It relieves shock and pain

4 The patient can co-operate with the surgeon. This may be seen in the application of a plaster jacket, or in setting a fracture of the humerus with the patient sitting up.

5 Reduction can be confirmed by X-rays and if unsatisfactory, the fracture can be reduced again before the local anæsthesia has worn off.

6 The patient does not require any period of recovery

7 It is particularly useful in compound fractures where the length of time required for operation is often very great, and the patient's condition unsuitable for a general anæsthetic.

Local anæsthesia has, however, its disadvantages. It cannot be used in children, who will not tolerate the prick of the needle. Further, it is unsuitable for greenstick fractures as there is often insufficient hæmatoma into which the anæsthetic can be introduced and diffuse. In fractures of over forty-eight hours' duration in which some clotting has occurred the same difficulty with diffusion will be met with, and it will not prove satisfactory. The more recent the fracture the more satisfactorily local anæsthesia works. Skin abrasions over the site of the fracture are a




FIG. 137. Tray set up for local anæsthesia.

contra-indication to puncture of the skin, which cannot be adequately sterilised.

TECHNIQUE OF LOCAL ANÆSTHESIA. A sterile tray is set up containing the following instruments:

A 10 c.c. record syringe, preferably dry sterilised.

Four to six needles. Two fine hypodermic needles for the skin, and larger ones to penetrate into the hæmatomas.

A pair of sterile forceps.

Iodine.

Small swabs, alone or, more conveniently, on sterile swabsticks.

Skin towels.

Two per cent. Novocaine, preferably in small sterile ampoules of 20, 40 and 60 c.c. one of which is completely used at a time.

Apart from the handling of the outside of the syringe with the hand the remainder of the manipulations are done with the forceps.

No needle is used to penetrate the skin twice. The needle is not withdrawn to fill the syringe, but the syringe is detached.

A careful examination is made, which includes a consideration of the X ray to decide where the hæmatoma is most easily entered, and with least danger to the soft tissues. This may necessitate several points of entry, *e.g.*, one for a fibula fracture, and two for either end of a comminuted fracture of the tibia in a fracture of the ankle. Having decided this the skin over the appropriate spots is painted with iodine, and skin blebs raised with the hypodermic needle. A larger needle is now inserted, and manipulation of syringe and needle, or more delicately of the needle alone, held in a gauze swab will enable one to determine if one is in contact with the bare fractured surface of the bone, or a part covered with periosteum. When satisfied that the fracture bone has been found some 5 c c of anæsthetic are injected. The syringe is detached and if the hæmatoma has been successfully entered bloodstained local anæsthetic will regurgitate along the needle (Fig 322). If this is the case the appropriate amount of local anæsthetic is injected and the needle withdrawn. If the hæmatoma has not been entered none, or little, fluid escapes, and it must be sought for again. Quite large amounts of novocaine may be used without danger, up to 60 to 80 c c. Success is shown by the cessation of pain in two to five minutes. The duration of anæsthesia varies from thirty minutes to two hours. In rare or complicated fractures it sometimes fails to relieve the pain, or relieves it only partially.

Regional Anæsthesia

This is suitable for cases in which the injection of local anæsthetics over many sites would be tedious or impossible, and in which the advantages of local anæsthesia are not desired. Its use is limited to the brachial plexus for the upper limb, and the sciatic nerve for the leg.

Brachial plexus anæsthesia. A similar tray is set out as for local anæsthesia. With the patient's head slightly turned to the opposite side a point is selected in the supraclavicular fossa where the subclavian artery can be felt pulsating in the angle between the clavicle and the sternomastoid. The outermost point of this small area is noted, and a spot $\frac{1}{2}$ inch above and $\frac{1}{2}$ inch medial to it chosen. A skin bleb is raised here after painting the skin with iodine. A fresh needle is then entered in a dorso-medial direction, till the patient complains of a stabbing sensation down the arm, indicating that the plexus has been entered. If bone is reached then the needle has been passed too directly back on to the first rib, and must be withdrawn and re-inserted. The plexus lies around and above the artery.

at a distance from the skin which varies largely with the build and fatness of the individual. In a thin patient it will only be necessary to enter the needle $\frac{1}{2}$ to $\frac{3}{4}$ inch, in a fat sthenic individual the plexus may be 2 to 2½ inches deep. If no blood has escaped into the syringe 20 to 30 c c of novocaine are injected. Loss of sensation in the arm follows at a varying interval some times as long as fifteen minutes, and lasts two to three hours. Muscular power is abolished to a variable extent. Combined with a basal narcotic this is an ideal anæsthetic for long operations including skeletal traction on the arm.

RISKS AND COMPLICATIONS (1) *Perforation of an artery* This is impossible if due care is exercised and the needle pushed in carefully before the syringe is attached. A hæmothorax has been caused by this.

2 *Perforation of a vein* This may occur, and merely demands withdrawal of the syringe. It is important not to inject the anæsthetic into the vein.

3 *Paralysis of the phrenic* This may occur, and is unimportant. There may be cough and shortness of breath.

4 *Involvement of the cervical sympathetic* This may produce headache, giddiness and a feeling of faintness, and it may be necessary to lay the patient flat. It passes off with no ill effects.

Sciatic anæsthesia This may be used for operations on the leg and foot. It is less reliable, and more difficult to achieve than brachial anæsthesia. It is a convenient anæsthetic for the reduction of a fractured calcaneus on one side. If the condition is bilateral a spinal anæsthetic is more suitable.

TECHNIQUE The most difficult matter is the localisation of the sciatic nerve. This is most readily found in thin patients by rolling it between the fingers and that curved portion of the ischium just above the tuberosity, in the line of the gap between the hamstrings and just above the point where these are covered by the gluteal fold. A skin bleb is raised here, and the needle introduced directly forwards till the nerve is found, and the complaint of pain referred down the leg is made. Twenty to 30 c c of novocaine are then injected.

In fat patients the nerve is so difficult to find that it is reasonable to use spinal anæsthesia at once. Should it be sought for the same landmarks are used, but the nerve cannot be rolled and must be sought for blindly.

Anæsthesia of a similar duration to brachial anæsthesia will ensue, but it extends only two thirds up the leg.

Block anæsthesia This is suitable for lesions of the hand which may be blocked at the wrist, or of the fingers and toes, which may be blocked by injection of the nerves at their bases. It is most

commonly employed for the fingers, and the description of the technique personally employed will be given, the more complicated techniques of other block methods being left to text-books on the subject. A tray similar to that previously described is set up. The skin at the base of the finger is painted with iodine, and two small skin blebs of novocaine are made on either side of the knuckle posteriorly. A slightly longer needle is then used, and is made to penetrate forward on the side of the phalanx till it lies just below the palmar skin. By infiltrating as the needle is advanced and withdrawn, the anterior aspect and the digital nerves on the antero-lateral aspect of the phalanx can be anaesthetised. The needle only requires to be pushed laterally toward the opposite bleb and the dorsum of the finger infiltrated to have complete anaesthesia of the finger. This method by utilising an approach through the finer skin on the dorsum of the hand is easier and much more comfortable for the patient.

Spinal anaesthesia This is particularly useful for cases in which both legs have been injured, such as bilateral fractures of the os calcis. It must be used with care if the patient has been shocked, or has not fully recovered from shock. Where shock is present local anaesthesia is to be preferred.

General anaesthesia (a) **GAS AND OXYGEN** This is very useful for short manipulations and plasters which require a period of under fifteen minutes. If it is decided to prolong the manipulations over this time ether must be added. Thus anaesthetic is useful for handling a large number of Colles's fractures together. Relaxation varies considerably from individual to individual. Its chief advantage is that it enables the patient to go home shortly after the manipulation.

(b) **INTRAVENOUS ANÆSTHETICS** These are also useful for manipulations which may last a little longer than ten minutes. Relaxation varies, and a few patients may be restless. This is disturbing if one is applying a plaster, and retentive apparatus may be disturbed on the return to the ward.

(c) **ETHYL CHLORIDE** This is particularly useful for children, in whom it is quite unnecessary to obtain deep anaesthesia to reduce a greenstick fracture. With the child doped and just insensible the fracture may be quickly straightened, and the subsequent plaster applied when the child has come back to consciousness. It is surprising how good children will be under such circumstances setting most adults a very good example.

(d) **ETHER AND CHLOROFORM** These are only used when complete relaxation is required. The addition of ether to a gas and oxygen preliminary anaesthetic is a satisfactory way of obtaining

relaxation when it is required without giving the patient very much ether. The disabilities attendant on having a completely relaxed patient for plastering have already been outlined.

The most generally useful anæsthetic for fracture and orthopædic work will be found to be a combination of intravenous pentothal and gas oxygen anæsthesia. Combined with a basal narcotic, this enables most procedures to be carried out under very light anæsthesia, and where more relaxation is required a further small injection of pentothal may be given. This method has the advantage of speedy induction and is comfortable for the patient.

Continuous intravenous pentothal has many of the same advantages and is very satisfactory.

REFERENCES

- HOSFORD, J. P. "The Use of Local Anæsthesia in the Treatment of Fractures with Conclusions drawn from Fifty Cases," *Brit J Surg*, 1930, 18, 546.
PATRICK, J. "The Technique of Brachial Plexus Block Anæsthesia" *Brit J Surg*, 1940, 27, 734. (Full article with references.)

CHAPTER XV

FRACTURES OF THE SKULL

Surgical anatomy

From the point of view of violence applied to the skull it must be regarded as a hollow ellipsoid, the bony vault, crossed by various suture lines, which increase its natural elasticity in one direction while decreasing it in the direction in which they run. This rests on a base of more dense and irregularly thickened bone, which is weakened by numerous foramina and fissures, but is made more rigid by the support of the bones of the face. The posterior aspect of the vault rests on the cervical vertebrae as on a pedestal.

The vault behaves as a spheroid in compression injuries to all points on its circumference, but the inelastic base is incapable of reacting evenly to the




FIG 138 Diagram to illustrate the basic mechanical construction of the skull

strain so that internal stresses are set up, which frequently fracture the base or junction of base and vault, such cracks running complicated paths through fissures and foramina. The bone of the vault consists of two compact layers, the inner and outer tables united by cancellous bone the diploë. The outer table is stronger than the inner, which is grooved by the meningeal vessels, and so in perforating injuries the inner table is often most damaged. The mechanical forces generated by a bullet passing out of the skull after perforating it are such that at the point of exit the outer table is more damaged. In other words the outer table lends support to the inner table which is cleanly perforated and the unsupported outer table is shattered, the reverse being the case at the point of entry.

General considerations Fractures of the skull derive their importance and interest from the associated damage to the brain and other structures in the skull. It must be remembered that any form of brain damage can co exist with any type of skull fracture, though they are usually relative, the more severe the fracture, the more severe is the brain injury. In 80 per cent of cases of severe brain damage there is a fracture of the skull.

Discussion of fractures of the skull must therefore differ from that of fractures elsewhere in that consideration of soft tissue injury must overshadow the bone injury completely. Fractured skulls must be considered in the light of the trauma to the brain, and the discussion of treatment falls into a discussion of the treatment of cerebral injuries. In order to regiment one's thoughts the actual fractures must be grouped and the possible brain injuries discussed as separate entities, though it must be always borne in mind that they run into one another, as may be seen in Fig 139 which represents the common sequence of events.




FIG 139 Sequence of events after severe fracture

Bony Lesions in Fractures of the Skull

Type of violence (1) **DIRECT** (a) Puncture wound with sharp instrument. Stellate fracture. Most frequent through nose or orbit. Limited perforation when in vault.

(b) Large force on limited area, *e.g.*, hammer blow, bullet. Produces a depressed fracture, often with comminution.

(c) Large force on large area. Blows with blunt weapons, or falls in which the skull strikes a hard surface. Produces fracture of the base and fissure fractures of the vault.

(d) Glancing blows with a sharp edge, *e.g.*, a sword, produce elevated fractures of the outer table. The tendency of the spherical skull to glance off a blow protects it from much direct violence.

2 **INDIRECT** Falls on the buttocks, in which the force is transmitted up the spine to the occipital bone, and blows on the point of the chin, which may drive the condyle through the base.

Usually these lesions and their associated damage are grouped as follows

- 1 **VAULT** Fractures may be fissured, stellate, punctured, depressed, comminuted or elevated. Intracranial signs and symptoms tend to be general. Readily seen in X-rays.

2. BASI

Fissured or punctate fractures

Intracranial symptoms are both local and general

Not easy to see in the X-ray

More common

More commonly compound

Fractures of the Vault

Mechanism Any blow on the skull of a severity sufficient to deform the skull at the point struck produces a series of changes in the skull and its contents, which varies only in magnitude. Blows




FIG 140 Illustrating the various possible effects following a blow on the skull

restricted to small areas tend to damage the scalp tissues, and therefore are often compound. They produce severe damage at the point struck, i.e., perforation or depression with irradiating cracks. Should the object be a tapering one, the skull may be split as with a wedge. The inner table, as mentioned, is more severely damaged, being weaker, more brittle, grooved by the meningeal arteries, and subject to the spread of the lines of force. Blows over larger areas produce flattening at the point struck, with narrowing of the skull along the diameter represented by the direction of the force, and a corresponding increase in diameter at right angles to this. In spite of this there is a decrease in the volume of the skull, which

produces an enormous rise of pressure in it, transmitted by the CSF to the brain and its blood vessels. This results first in the emptying of the veins, then a rise in CSF pressure, and compression of the brain, emptying of the arteries, and a further rise of CSF pressure. The brain, though semi-fluid, behaves as a solid under these conditions, and partakes of the skull damage at the point of impact, and is damaged by internal stress to a varying degree along the line of force of the blow, and most severely damaged at the point of exit of the line of force from the brain, where the brain is thrown against the opposite side of the skull ("Contre coup").

The skull itself tends to fracture at the point of impact from the compression, and this may take the form of a fissure, though it would be more characteristically shown by a depressed fracture with some irradiating fissures. The bursting strain which occurs in the skull in a plane at right angles to that of compression (see Fig 140) is probably a very rare cause of fracture, and more commonly the fracture is seen to run in the same direction as the line of force. This is due to the fact that the vault is not a true sphere, but is only two thirds of one, with a firm and rigid base (Fig 138). Force applied in an A P direction to the skull is unable to compress the base, and the skull tends to split in two halves opening outwards on this, much the same as an orange when cut half through tends to open up when squeezed from end to end of the cut. Transversely applied force tends to produce a transverse fissure. A careful analysis of the line of force and the X ray will often enable one to deduce the type of stress which caused the fracture.

Fractures may occur at some distance from the point of impact, when the blow itself may produce no local damage. Except in the infantile skull the tentorium and falx play little part. Rarely the great vein of Galen may be torn from its junction with the straight sinus. Tearing of the falx is only associated with severe trauma. The most important trauma, however, is that which may occur to the brain after the blow, from the continued hæmorrhage of a torn vessel, which sets up a series of reactions to be described later.

Mode of Brain Damage

1 **PENETRATING INJURIES** (Fig 142) The penetration of a bullet or a fragment of shrapnel produces an explosive effect inside the skull and damage scattered along the track. Foreign bodies, both bony and metallic, may be distributed among the bruised tissues and vascular damage may be severe.

2 **LOCAL DEFORMATION** (Fig 143) The degree of damage permitted by this is dependent on the elasticity of the skull. In the



FIG 141 Fine fissure fracture of the occipital bone running into the foramen magnum following a fall on the back of the skull

produces an enormous rise of pressure in it, transmitted by the CSF to the brain and its blood vessels. This results first in the emptying of the veins, then a rise in CSF pressure, and compression of the brain, emptying of the arteries, and a further rise of CSF pressure. The brain, though semi fluid, behaves as a solid under these conditions, and partakes of the skull damage at the point of impact, and is damaged by internal stress to a varying degree along the line of force of the blow, and most severely damaged at the point of exit of the line of force from the brain, where the brain is thrown against the opposite side of the skull ("Contre coup")

The skull itself tends to fracture at the point of impact from the compression, and this may take the form of a fissure, though it would be more characteristically shown by a depressed fracture with some irradiating fissures. The bursting strain which occurs in the skull in a plane at right angles to that of compression (see Fig 140) is probably a very rare cause of fracture, and more commonly the fracture is seen to run in the same direction as the line of force. This is due to the fact that the vault is not a true sphere, but is only two-thirds of one, with a firm and rigid base (Fig 138). Force applied in an A P direction to the skull is unable to compress the base, and the skull tends to split in two halves opening outwards on this, much the same as an orange when cut half through tends to open up when squeezed from end to end of the cut. Transversely applied force tends to produce a transverse fissure. A careful analysis of the line of force and the X-ray will often enable one to deduce the type of stress which caused the fracture.

Fractures may occur at some distance from the point of impact, when the blow itself may produce no local damage. Except in the infantile skull the tentorium and falx play little part. Rarely the great vein of Galen may be torn from its junction with the straight sinus. Tearing of the falx is only associated with severe trauma. The most important trauma, however, is that which may occur to the brain after the blow, from the continued hæmorrhage of a torn vessel, which sets up a series of reactions to be described later.

Mode of Brain Damage

1 PENETRATING INJURIES (Fig 142) The penetration of a bullet or a fragment of shrapnel produces an explosive effect inside the skull and damage scattered along the track. Foreign bodies, both bony and metallic may be distributed among the bruised tissues and vascular damage may be severe.

2 LOCAL DEFORMATION (Fig 143) The degree of damage permitted by this is dependent on the elasticity of the skull. In the




FIG 142 The damage produced by a bullet wound of the skull. Note the scattering of fragments of bone through the brain tissue (After Makins)



FIG 143 Compound depressed fracture of the frontal bone.

infant brain damage may occur without fracture of the skull. In the adult 70 per cent of cases of severe brain injury will show fractures



of the brain remote from the side of injury to the skull Damage there may be due to,

- 1 Deceleration
- 2 Traction from acceleration (suction)
- 3 The compression of an opposite pole in gross deformations of the skull

Fractures of the Base

Mechanism This may be

- 1 Perforation, e.g., a pencil pushed through the orbital plate
- 2 Irradiation from a fracture of the vault
- 3 Bursting fracture, due to stress set up in the bone in a plane at right angles to the direction of the force
- 4 Indirect violence transmitted along the spine to the occipital condyles Produces fissure fractures in the region of the foramen magnum
- 5 Indirect violence applied to the point of the jaw may drive the condyle of the mandible through the glenoid, or fissure the middle fossa

The areas of the base most liable to damage are the cribriform plate, the orbital plate, the body of the sphenoid, the petrous bone, and the thin areas of the cerebellar fossæ. The dangers arise due to the fissures communicating with potentially infected cavities, such as the ear, nose and sinuses

The Clinical Examination of Cases of Fracture of the Skull

This may be extremely difficult in an irritable patient. X-ray may be impossible without an anæsthetic, as may lumbar puncture. One must decide how important the information to be obtained from these proceedings is, relative to the condition of the case before carrying them out, but when in doubt it is better to investigate further.

HISTORY This usually has to be obtained from an associate in acute cases. The patient may be able to help, but his amnesia covers the most important period, and its length is some measure of the severity of the accident.

One must ascertain,

Type of injury, i.e., blow, fall, bullet, etc

Severity of the force, i.e., height of fall

Length of time since accident

Mental condition of patient since accident

If vomiting has occurred, a sign of recovery

of the skull, and fractures will be found in 90 per cent of autopsies for brain injuries. Local deformation produces local brain damage. It is perhaps most important as a cause of injury to the meningeal vessels.

3 MECHANICAL CAUSES The brain having inertia and not occupying fully the skull cavity, is liable to injuries from acceleration and deceleration. Although lying in a fluid bath, the ready displacement of the CSF can offer little softening effect to such forces.

(a) *Acceleration* (Fig 140) When struck violently the force transmitted to the skull may cause it to strike against the brain on the side of impact as the brain lags behind owing to its inertia. Damage may thus occur at the point of impact without a depressed




FIG 144 Effect of deceleration on the skull—single arrow indicates direction of motion multiple arrows resistance. The dark areas represent areas of compression the dotted areas those of damage by tension and rupture.

fracture occurring, though general deformation of the skull and possibly a fissure fracture may be present.

(b) *Deceleration* (Fig 144) In a similar manner, when the skull is suddenly brought to rest by striking a hard surface such as a metal road, the brain travels on for a fraction of a second and strikes against the surface of impact. At the same time the brain separates from the opposite side of the skull and damage from traction or suction may occur there.

(c) *Rotational acceleration and deceleration* If the head is violently spun by a blow at one or other end of its axis the contents may be swung against the tentorium or falx. This accounts for the damage frequently found in these regions for both structures oppose acceleration or deceleration.

Contrecoup This term is used to describe damage on the surface

It is difficult to recognise the palsy, but the patient may complain of diplopia on looking down and in

5 *Trigeminal* Rarely injured Loss of perception of touch and pain over face and forehead according to the divisions injured Corneal reflex may go Paralysis of muscles of mastication

6 *Abducent* Long intracranial course, liable to damage Paralysis of the lateral rectus with loss of lateral movement of the eye Convergent squint, with diplopia on looking to affected side

7 *Facial* Lesion is usually infranuclear, at the base of the brain or in the temporal bone Produces facial asymmetry and loss of response of facial muscles to irritation Unconscious patient may blow the cheek out

8 *Auditory* Accurate test requires co operation Patient may not respond to sounds on that side May be associated with lesions of the 7th nerve Vertigo Tinnitus Nystagmus

9 *Glossopharyngeal* Very rarely involved Loss of taste over posterior third of tongue

10 *Vagus* Paralysis produces palatal paralysis, some difficulty in swallowing, and alteration in voice The vocal cord assumes the cadaveric position Very rarely injured, and then usually incompletely

11 *Accessory* Trapezius paralysed, and patient cannot shrug the shoulder

12 *Hypoglossal* Paralysis of the tongue on one side so that on protrusion the unparalysed muscles force tip over to the side of lesion

EXAMINATION OF THE MUSCULAR SYSTEM In the unconscious, pick up the arms and allow to fall, estimating the muscular tone Endeavour to obtain the withdrawal reflex by pricking the sole of the foot Attempt to open the eyes This is easier on the paralysed side Pricking the face or pressure on the supraorbital nerve may produce a grimace The knee jerks are absent in concussion, in which there is complete loss of tone In cerebral irritation all the reflexes are hyperactive The plantar reflex and abdominal reflexes may show changes as in cerebral hæmorrhage, i.e., changed or lost due to loss of the cerebral path

In cerebral compression, in the first stage of irritation the reflexes on the side of the body opposite to the lesion are hyperactive With the development of the second stage of paralysis, or in trauma to the motor area, loss of upper motor neurone control again produces, or continues, the hypertonicity of the muscles on the same side of the body, which become spastic

X RAY EXAMINATION This is very important Often the patient is too restless in the early stages, and the examination has to be postponed If necessary an anæsthetic may be given when it

One may be able to learn,

If there is any history of previous skull injury

If there is any nerve palsy or nervous disease

If the B P is higher than normal

Whether the patient has been drinking

If there is a history of fits or previous coma

If there is no history available the diagnosis from a cerebral hæmorrhage or other lesion may be impossible, especially if there are facial or other injuries

EXAMINATION This should be carried out preferably in a separate room, warm, and with a good light, so that the patient may be safely stripped. Associated injuries should be excluded and dealt with temporarily to enable the surgeon to concentrate on the cerebral injury

Inspection,

Position of the patient Colour Respiration

Site of laceration, abrasion, hæmatoma

Type of movements if any, of the extremities, facial muscles

Bleeding from the mouth, nose or ears

Presence of an orbital hæmatoma

Depth of coma

Palpation,

Symmetry of the skull

Resilience of tissues below the hæmatoma, or abrasion

Presence of a hæmatoma in neck muscles

Neck rigidity, or Kernig's sign

Record the B P, pulse and respirations, and continue to do so hourly

Proceed to a thorough clinical examination of the C N S if the patient's condition will allow it

CRANIAL NERVES (1) *Olfactory* Impossible to test in usual case. Anosmia complained of later

2 *Optic* Requires patient's co operation, except for the light reflexes. Important, but less so than ophthalmoscopic examination

3 *Oculomotor* Supplies all ocular muscles but the superior oblique (4) and the lateral rectus (6). Conveys fibres to sphincter pupillæ from the cavernous plexus through the short ciliary nerves. A lesion may be partial or complete. Complete paralysis gives a divergent squint, ptosis, and a dilated pupil with no reaction to light or accommodation. A dilated pupil alone is more likely to be due to injury to the sympathetic fibres around the internal carotid

4 *Trochlear* Supplies the superior oblique. Rarely injured

baller In order to distinguish the degrees of confusion more accurately the Medical Research Council suggest that the findings be recorded under the following heads —

Mild A state in which the patient, though presenting the characteristic feature of confusion in some degree, is capable of coherent conversation and appropriate behaviour

Moderate A state in which the patient, though out of touch with his surroundings, can give relevant answers to simple questions, such as "What work do you do?", "How old are you?", "Where do you live?"

Severe A state in which the patient, though for the most part inaccessible, will occasionally show adequate response to simple commands forcibly given and, if necessary, reinforced by appropriate gestures, e.g., "Put out your tongue," "Take my hand"

The next stage is the stage of semi-coma in which the patient may be made to give some response, e.g., to screw up the face when pressure is placed on the supraorbital nerve. The swallowing and corneal reflexes are present, and the patient will usually evacuate a full bladder when discomfort occurs incontinently

In coma, the deepest state of unconsciousness, the patient is completely inert and does not respond to any stimulus. Retention of urine and overflow are usual. The corneal and swallowing reflexes may or may not be present. It is indicative of severe damage to the brain and the longer it lasts the more serious the outlook. A change in the patient's state of consciousness is a most important prognostic sign for good or ill

POSITION OF THE PATIENT This is dependent in the unconscious on the distribution of muscle tone throughout the body, and is profoundly modified by damage to the various centres whose pathways control the lower motor neurone. Damage may occur at various levels in the brain and brain stem, and in various combinations which account for the complicated and changeable features met with. Hemiplegia, monoplegia, convulsive twitching, changes in muscle tone and in muscle spasm should all be analysed as far as possible in relation to experimental physiology. Here division of the motor tracts below the levels indicated produces the following changes —

LEVEL

OBSERVED CHANGES

Motor cortex	Hemiplegias and monoplegias (Irritation produces twitching and convulsions)
Basal ganglia	Slowness of movement, tremors and rigidity, expressionless face
Red nucleus	Decerebrate rigidity Extensors in spasm, flexors relaxed (may be confused with meningitis)
Deiters nucleus	Extensors relaxed and flexors in spasm

is thought that the information is important. In addition to the fissures which may be seen, in rare cases, particularly fractures of the frontal region, air may escape into the skull or scalp and cast a shadow in the X-ray.

Confusion with the various other lines visible on the skull should be avoided. Generally speaking, the fracture line will be sharp and clear cut in at least one view of the skull. It shows no relation to other lines present, which it usually crosses, and it may angle sharply. Suture lines rarely cause confusion on account of their serrations. Meningeal vessels and diploic veins have fairly sharp margins, but they occur in recognised situations. The meningeal




FIG. 145 The radiological markings of the vault of the skull —

- A The parieto-occipital suture
- B The grooves of the meningeal veins and arteries
- C The fronto-parietal suture
- D The diploic venous sinuses
- E The frontal sinus
- F The sella turcica

vessels branch like a tree and the diploic veins run an irregular course producing patterns with a large mesh (Fig. 145).

Analysis of Clinical Findings

The analysis of the signs and symptoms of cerebral injury is not simple. This is due to the uneven and widespread distribution of the lesions and the uncertain mechanism underlying cerebral states such as concussion. Over the whole is placed the blanketing action of unconsciousness in most cases.

UNCONSCIOUSNESS is the most conspicuous feature of any severe head injury, and varies considerably in depth. In the mildest forms the patient is merely dazed and may be able to continue his activity with merely some impairment of efficiency, *e.g.*, the stunned foot

2 There is no posterior limit to the conjunctival hæmorrhage

3 The conjunctiva itself is not injured or œdematous

ESCAPE OF CSF It may escape from the nose due to cribriform damage, giving rise to the condition known as traumatic rhinorrhœa

BRAIN MATTER may also escape, in either case the importance of the observation is due to the attendant risk of infection

ESCAPE OF AIR Air from the ethmoids or the frontal sinus may form localised crepitant collections under the scalp

INJURY TO NERVES The nerves involved may be the olfactory, optic, the oculomotor, the trochlea, the abducent, and the ophthalmic division of the trigeminal

Middle fessa HÆMORRHAGE *From the nose and mouth* Due to comminution of the sphenoid body Both the cavernous sinus and




FIG 146 The appearance of subconjunctival hæmorrhage in fracture of the skull




FIG 147 The appearance of subconjunctival hæmorrhage due to a blow directly over the eye

the internal carotid may be injured, giving rise in some cases to an arteriovenous aneurysm

Aural This is pathognomonic of middle fessa fracture, if damage to the external auditory meatus is excluded

CSF may also escape from the ear

BRAIN MATTER has also been observed to discharge from the ear

AIR may escape from damage to the mastoid air cells

INJURY TO NERVES due to involvement in the fissuring of the petrous temporal may occur to the trigeminal, the abducent, the facial, and the auditory In injuries the hæmorrhage may so damage the drum that the impairment of hearing cannot be assessed till later Disturbances of the vestibular division are common

Posterior fessa HÆMORRHAGE May occur into the tissues of the neck, with stiffness and the late appearance of bruising, or into the scalp in the mastoid region

THE CSF and brain matter have no channels for escape, except in severe compound injuries

AIR may escape from the mastoid region

Eye muscles These may be thrown out of action by other causes than nerve palsy, and watch has to be kept for the effects of damage to the orbital cavity and hæmorrhages into the orbit. The majority of squints are due to brain stem lesions of a transient type, probably vascular, and recovery is rapid and complete.

Pupils Rapid change in size of pupil and varying size of pupil are common, and indicate brain stem lesions of a similar type to the transient oculomotor palsies. The pupillary change indicating pressure is the fixed dilated pupil, which does not respond to light shone into it, or into the opposite eye (consensual reflex), and may be reached by the series of steps shown in Fig 150. This indicates that the oculomotor nerve is being stretched, by depression of the brain stem, from a rise in supra tentorial pressure. This is also the most common cause of decerebrate rigidity which occurs after an interval (immediate decerebrate rigidity is due to local brain stem damage). It demands relief from pressure by decompression. It is in these cases that serious complications may follow lumbar puncture, which allows the medulla to prolapse further with resultant increased pressure on it.

Special Clinical Features of Fractures of the Base

These may be due to

- 1 External hæmorrhage
- 2 Escape of cerebrospinal fluid
- 3 Involvement of cranial nerves
- 4 Escape of brain matter
- 5 Escape of air from the air sinuses

These features can be grouped according to the fossa affected

Anterior fossa **HÆMORRHAGE** *Nasal* Have to exclude blows on the nose or hæmorrhage into the antrum. Occurs from rupture of the cribriform plate.

Oral Hæmorrhage from the post nasal region may trickle out of the mouth. Have to exclude oral damage. In this and preceding case the blood may be swallowed and later vomited.

Orbital Hæmorrhage into the muscles may result in squint. If more severe there may be proptosis, with a dilated inactive pupil. Hæmorrhage into the lids may occur from damage to the ethmoidal, frontal sinus, or from blows on the eye. Hæmorrhage from fractures shows itself after a lapse of time, and trickles first into the lower lid. There is no sign of external damage, and when it passes below the conjunctivæ it forms a wedge with its base in the lateral fornix, and extending inferiorly, and with the following characteristics—

- 1 The hæmorrhage is limited by the palpebral fæcia to the orbital margins and tends to be circular

The face is pale and the temperature subnormal
 The pupils are dilated and may not react
 Respiration may cease momentarily, then is shallow and barely perceptible

The pulso may be imperceptible, and is usually quickened

2 RECOVERY Sets in in the uncomplicated case in a few moments

The pulso and respirations improve

The pupils react sluggishly to light Eyes remain closed and open on recovery

The patient may stir a little or react to disturbance

The visceral reflexes return and the patient usually vomits

3 REACTION Accompanies recovery and persists some time
 Headache, restlessness and irritability

Mental clouding

Giddiness and tremulousness

Nausea and a feeling of weakness

Loss of memory for a period shortly before, during, and for a short time after the accident, the length of time usually being related to the severity of the blow As time elapses the interval of forgetfulness decreases, but there is absolute loss of memory for some period

If the patient passes into cerebral irritation the reactionary period is delayed, and occurs after an interval which may last weeks, but is correspondingly modified

Physiology of concussion and theories to account for it The sudden loss of consciousness and the generalised muscular collapse suggest cerebral involvement, while the cardiac and respiratory disturbance suggest that the midbrain is compressed All features are most readily explained by the hypothesis that the sudden rise of pressure in the skull produces a transient anæmia of the brain by driving the blood out of skull In addition to this the rise of pressure in the CSF in the lateral and third ventricles may force an excessive amount of fluid through the iter into the fourth ventricle and by compressing the midbrain centres around the iter, aid in the disturbance

OTHER THEORIES 1 *Multiple microscopic lesions* These would not be likely to cause such uniform and widespread features, but may be associated in certain cases

2 *Molecular derangement* This is an old theory which supposes that the neurones are mechanically jarred out of position The complete recovery is not explainable on this hypothesis

3 "*Tillman's hypothesis*" This is based on the different SG of the white and grey matter It is supposed that a separation

INJURY TO NERVES may involve the facial from a crack across the petrous temporal, the hypoglossal, or the auditory

A typical fracture of the posterior fossa involves the jugular foramen, but the nerves in this foramen are rarely injured

Special Treatment of these Symptoms

Hæmorrhage or the discharge of CSF from the nose If small, leave alone Syringing is absolutely contra-indicated owing to the risk of infection If severe, one may be forced to pack A post nasal pack is put in first, and then the anterior nares packed The patient must then be watched for the development of compression, from blocking the escape of blood

A bleeding ear may need cleansing on the exterior to be certain that the blood has not run into it from outside If bleeding is coming from the drum it should be cleaned with spirit and left Syringing is dangerous If there is a free discharge of blood there is a rare possibility of a middle meningeal hæmorrhage being externalised A pad over the ear to absorb the discharge, whether CSF or blood, is all that is allowable

CEREBRAL STATES ASSOCIATED WITH BRAIN DAMAGE

- 1 Concussion
- 2 Cerebral Irritation or traumatic delirium
- 3 Coma or traumatic stupor

CONCUSSION

This is a rather ill-defined condition owing to its uncertain pathology which is stated to have occurred after all blows sufficient to cause loss of consciousness Some authors add a rider to this, that it must leave no permanent effects, and is always followed by recovery When the mechanism of concussion is discussed it will be seen that it may occur and be followed by cerebral irritation and later traumatic stupor It is therefore considered here as an entity which may exist alone, or have superimposed on it a further series of changes producing cerebral irritation and traumatic stupor The persistence of any sequelæ following concussion indicate that more than simple concussion has occurred

The symptoms of concussion may be divided into three stages

- 1 ONSET Instantaneous following the blow

The loss of consciousness is absolute, and there is no response to any stimulus, and a loss of all reflexes

The limbs are flaccid and relaxed, and the sphincters may

Patient is often noisy and may have a cry resembling the meningeal cry
Delirious at nights



FIG 148 The posture in cerebral irritation. The body lies curled up and the face is turned away from the light. A fracture of the lower end of the tibia has been immobilised in plaster.




FIG 149 The temperature chart in a case of cerebral irritation

When roused may be violent

May refuse all feeding

Incontinent, often of both bladder and bowel

Pulse is usually variable, of regular and moderate volume, becoming weaker with deterioration in the patient's general condition

occurs between them on account of this, when they are jarred. This is again incompatible with the complete recovery.

The reaction stage is characterised by a return of blood to the brain, and a reactionary hyperactivity and irritability, of which one obvious feature is the vomiting.

Treatment of concussion without fracture At the time of the accident all that can be done is to see that the patient lies in a comfortable position with a free airway till he can be put to bed. Stimulants are usually forced on the unconscious by the larynx and may later form the grounds for an accusation of drunkenness. As concussion without further complication recovers spontaneously in a short period at the most, the only treatment to be discussed is that of the rest necessary afterward. The length of this must be governed by the length of time concussion lasted, the association of other injuries, the age and general condition of the patient, the type of mental work the patient does, and the patient's general mental type. Thus a sensitive highly strung, intelligent brain worker will require the maximum period of rest compared with a dull, heavy labourer who feels fit for work the next day. A period of rest of from one to two weeks should be insisted upon and a longer period is often desirable.

PROGNOSIS At the time of accident it must be guarded, as the development of further vascular damage cannot be forecast. If the reactionary stage sets in rapidly and the blow has not been severe, the outlook is good. If the injury has been severe, concussion may be very short with small depressed fractures, and though recovery has set in the outlook is still very uncertain.

SEQUELÆ These will only be mentioned here, and discussed more fully later.

Headache Loss of memory [Some period of loss is certain, but it may reach back before the accident for some time, and return later.] **Impaired concentration** **Vertigo** **Increased susceptibility to alcohol** Alterations in character are usually associated with more severe injuries.

CEREBRAL IRRITATION OR TRAUMATIC DELIRIUM

A condition characterised by increased excitability of all nervous tissue, i.e. increased knee jerks, and in the higher centres photophobia and dislike of any interference. It follows on concussion with no intermediate period of recovery. It may persist for a few hours, or may last for several weeks.

SYMPTOMS The patient lies curled up with knees flexed and head turned into the pillow (see Fig 148).

Photophobia Pupils normal

Disorientation

CSF pressure is raised in most cases has given rise to the use of lumbar puncture as a therapeutic method. It is difficult to explain its rationale, as the removal of CSF can have little effect on the oedema of the brain, and the small amount removed to bring the pressure to normal will very rapidly be made up again. It is a fact, however, that the patient's general condition may improve rapidly after lumbar puncture, and as the LP is usually warranted as a clinical investigation to further the diagnosis, it is a justifiable line of treatment. Some small risk is run in severe head injuries of compressing the medulla by its being forced into the foramen magnum, with collapse, and possibly death if more than a few cc are withdrawn.

Attempts have been made to reduce the oedema of the brain by the use of hypertonic saline and glucose. The use of these intravenous methods seems to have arisen from a mistaken idea of the physiology of the brain. The hypertonic saline in the vessels rapidly withdraws the fluid from the tissue spaces to reduce the osmotic pressure of the blood, and has been shown clinically and experimentally to reduce the oedema of the brain. Later on, however, some of the salt being dialysable passes into the cells themselves, and when the salt content of the blood is reduced by renal action, may withdraw fluid from the blood, to bring the cell protoplasm back into an isotonic condition. The temporary dehydration may thus be followed by a wave of oedema as bad or worse than before. The same objection holds to the use of glucose, but not to sucrose (cane sugar), which is not dialysable and has to wait for reduction in the liver before being absorbed. It may thus exert a prolonged dehydrating effect on the oedematous tissues.

Simple dehydration alone may accomplish much. Often the patient by refusing food and drink accomplishes this for himself. If he is taking fluids they should be cut down to 30 ounces a day, and if possible these should be of a hypertonic nature, such as glucose, saline, or salty broths. To aid this magnesium sulphate may be given by mouth, or, if the patient cannot swallow, by rectum.

As the perivascular spaces may be damaged by the trauma, and the CSF is absorbed by them, another disturbing feature is introduced into the picture. On physiological grounds, therefore, the use of dehydration should be restricted to patients with a raised CSF pressure, and the use of intravenous sucrose to patients in whom unconsciousness has persisted for some time. (See treatment.) As to its action we can only suppose that it acts by disturbing the disordered mechanism, and that the readjustments which are then made favour the normal side rather than the abnormal, and may start a return to normal, or if repeated, may summate.

Temperature also variable Normal at first May then get a rise in forty-eight hours persisting for two or three days, and then becoming normal again (see Fig 149)

Respirations are normal

The blood pressure is normal

The CSF pressure is raised in most cases, but is subnormal in some

The condition can be discussed in three stages

1 Onset Following shock or concussion

2 Developed state

3 Recovery period

Pathology May be defined as that of general cerebral contusion with which may exist lesions due to direct laceration of the brain, and hæmorrhage Microscopically the brain is often swollen and œdematous Minute multiple punctate hæmorrhages are scattered throughout the cerebral tissues in the white and grey matter Larger hæmorrhages may be present in the frontal, temporal and occipital lobes (Polar contusion)

The lesion of "contrecoup" is usually a subarachnoid hæmorrhage, and may be due to the brain being torn away from the meninges by its own inertia, when the skull is struck, or possibly its own momentum carrying it against the skull when the force of the blow has ceased This is the usual cause of polar contusion

Microscopically the minute hæmorrhages tend to have a perivascular distribution, i.e., ringed round the blood vessels, while the perivascular spaces are œdematous and contain red blood corpuscles

Physiology The variability of the pulse rate is marked, and may be due to upset of the heart regulating centre in the hypothalamus Usually rapid at first it falls as recovery occurs, but later on it may rise again as the patient's general condition deteriorates from inability to provide adequate food, and the continual restlessness

The rise of temperature which occurs may be similar to that occurring after hæmorrhage elsewhere, i.e., due to absorption of products of autolysed blood The blood in the CSF disappears very rapidly, being absent at the end of the third day and only leaving a slight decreasing discoloration for the next ten days or so Persistence of blood in the CSF beyond this period indicates that fresh hæmorrhage is occurring

CSF PRESSURE This is also variable, which makes the theory, that cerebral irritation is due to increased pressure only, untenable It is admittedly usually raised, and if very high, i.e., in the neighbourhood of 300 mm of water, there is cerebral compression In the majority of cases it is between 120 and 200 mm The fact that the

RESTLESSNESS AND CEREBRAL IRRITABILITY This can be controlled by a variety of sedatives, which are adjusted to suit the needs of the case. Chloral and pot. bromide, paraldehyde, and Dover's powder may be used by mouth. Where the patient is intolerant of this mode of administration he is usually more intolerant of rectal administration of bromides or paraldehyde, and one has to have recourse to intramuscular injections. Sodium luminal in 2 to 4 gr. doses may be given and repeated when necessary. In acute phases intramuscular evipan is useful. Morphua should be avoided as it has an effect on the pupils, and has been shown to raise the C S F pressure, as well as depress respiration. Morphua, however, is better than a strait jacket and should be used if the condition warrants it.

LUMBAR PUNCTURE This should not be done as a routine. It may be necessary to establish the diagnosis accurately, or to exclude suspicions of brain trauma in the unconscious. At the end of eighteen hours if the patient has not regained consciousness lumbar puncture is carried out. A general anaesthetic may be necessary and the moment may be seized to feed the patient at the same time. The C S F pressure should be recorded and if raised it is lowered to one third of the raised pressure thus a pressure of 240 mm. of water would be reduced to 80 mm. This is done regardless as to whether the fluid is blood stained or not, and is done slowly using the manometer as a control. The amount of blood in the C S F is noted. If small it is evidence of damage which is probably settling. If large there is severe damage, and a repeat L P must be made in six hours and, if necessary, made again, to see if the amount is decreasing. If not, hemorrhage is continuing and this will generally be shown by the accompanying signs of increased intracranial pressure.

If the C S F is normal in colour and pressure, the outlook is reasonable in the absence of other features, and no further benefit is to be obtained from L P. If the C S F is raised in pressure, then L P is repeated in twelve hours. A fall of pressure in subsequent punctures is a good omen. The value of lumbar puncture as a therapeutic method is undoubted, though its rationale is difficult to explain. For the same reasons the use of dehydration therapy is debatable. There can be little harm in supplementing the lumbar puncture with the use of 3 ounces of magnesium sulphate in 6 ounces of water per rectum in an endeavour to reduce cerebral oedema, and if progress is still unsatisfactory the use of intravenous sacroso. Amounts varying from 25 to 100 c.c.s. of a 50 per cent solution may be given intravenously.

After forty-eight hours if the patient has not regained conscious-

Treatment As a preliminary for accurate information, records of the following are made and continued

The B P

Hourly pulse chart

Food intake The patient is put on a daily 30 ounce intake at once

Food intake

Sedative chart

Passage of urine (to exclude a full bladder)

GENERAL The nursing of certain cases of cerebral irritation may tax every ounce of energy of the nurse, and for certain cases it is necessary to have male nurses. The patient is intolerant of every interference, and may be quite dangerous. He tolerates the bed clothes badly and is better dressed in warm clothes, which allow freedom of movement. Generally the patient is best left to himself, when he will curl up and remain quiet. It is interference which promotes struggle, and the more force used on the patient the more resistant he will become. This may be well seen in attempts to force a patient to drink, which are usually quite unsuccessful. If the patient is given the cup in his hand, and suggestions made by action and word he will often drink as an almost automatic action. Successful results along similar lines may be obtained when there is difficulty with micturition.

A quiet dark room, a bed preferably against one wall, and with some padding on the head rails and in some cases a cot bed, are a *sine qua non*.

To give an unconscious patient an aperient is to give hostages to fortune. If not already incontinent with its attendant nursing troubles, nothing is more likely to produce it. Control of the bowels should be retained by enemata. No anxiety need be felt in leaving the bowels closed for the first three days.

Incontinence of urine is trying and common. Frequent changes of bed linen will be necessary to keep the skin healthy. In the male a piece of colostomy tubing may be strapped over the penis and led to a bottle. Unfortunately the restless patient usually pulls it off. Catheterisation is necessary every six hours in the case of retention as a patient with a full bladder is restless and disturbed by it.

Feeding is difficult. For the first twenty-four hours glucose and water in limited quantities (1 pint) suffice. After this some attempt to introduce protein and more carbohydrate must be made. If the patient will swallow this may be in the form of milk foods, junkets, or custards. If the patient will not swallow a stomach tube must be introduced through the nose and food sufficient to run through used.

HYPERPARALIA can only be treated on general lines by sponging an icebag to the head or wrapping the limbs in cloths soaked in water. It is of bad prognostic significance.

RISTLESSNESS AND GENERAL IRRITABILITY This can be controlled by a variety of sedatives, which are adjusted to suit the needs of the case. Chloral and pot. bromide, paraldehyde, and Dover's powder may be used by mouth. While the patient is intolerant of this mode of administration he is usually more intolerant of rectal administration of bromides or paraldehyde, and one has to have recourse to intramuscular injections. Sodium luminal in 2 to 4 gr. doses may be given and repeated when necessary. In acute phases intramuscular evipan is useful. Morphine should be avoided as it has an effect on the pupils, and has been shown to raise the CSF pressure, as well as depress respiration. Morphine, however, is better than a strait jacket, and should be used if the condition warrants it.

LUMBAR PUNCTURE This should not be done as a routine. It may be necessary to establish the diagnosis accurately, or to exclude suspicions of brain trauma in the unconscious. At the end of eighteen hours if the patient has not regained consciousness lumbar puncture is carried out. A general anaesthetic may be necessary, and the moment may be seized to feed the patient at the same time. The CSF pressure should be recorded and if raised it is lowered to one third of the raised pressure, thus a pressure of 240 mm. of water would be reduced to 80 mm. This is done regardless as to whether the fluid is blood stained or not, and is done slowly, using the manometer as a control. The amount of blood in the CSF is noted. If small it is evidence of damage which is probably settling. If large there is severe damage, and a repeat L.P. must be made in six hours, and, if necessary, made again, to see if the amount is decreasing. If not, hemorrhage is continuing and this will generally be shown by the accompanying signs of increased intracranial pressure.

If the CSF is normal in colour and pressure, the outlook is reasonable in the absence of other features, and no further benefit is to be obtained from L.P. If the CSF is raised in pressure, then L.P. is repeated in twelve hours. A fall of pressure in subsequent punctures is a good omen. The value of lumbar puncture as a therapeutic method is undoubted, though its rationale is difficult to explain. For the same reasons the use of dehydration therapy is debatable. There can be little harm in supplementing the lumbar puncture with the use of 3 ounces of magnesium sulphate in 6 ounces of water per rectum in an endeavour to reduce cerebral oedema, and if progress is still unsatisfactory the use of intravenous sucrose. Amounts varying from 25 to 100 c.c.s. of a 50 per cent solution may be given intravenously.

After forty-eight hours, if the patient has not regained conscious-

ness and the CSF pressure is persistently high, the question of a subtemporal decompression will have to be considered to break the vicious circle present. A fixed dilated pupil, the late onset of decerebrate rigidity, or retrogression following a period of improvement, may be additional factors in deciding the time and side for a decompression.

RECOVERY This is an interesting period, in which the patient seems to familiarise himself with various things which he has apparently forgotten. It may be a dramatic moment when the patient first takes a cup for himself and uses it, however clumsily, for drinking. Once one chain of ideas is established recovery is usually rapid.

A long period of rest is to be recommended after this, the length of time varying with the circumstances of the case, as previously described, and it may vary in length from two months to two years. The criteria of recovery can be deduced from a perusal of the sequelæ of the condition, and not till the patient is free from all these is recovery complete. This may cause some difficulty where there are mental changes as a result of the blow, but here we tread on the province of the alienist.

Prognosis. The same uncertainty applies to cerebral irritation as to concussion, and it is only after some time has elapsed and repeated observations of the patient made, that a prognosis can be given. The severity of the blow, the X-ray evidence of the fracture, the amount of blood in the CSF, the length of time cerebral irritation has lasted, all play a part in deciding as to the outcome. In the absence of features of compression it can always be hopeful. With regard to the sequelæ one must usually hedge. In cases of quite short duration the sequelæ may be very severe, while in cases who have lain days unconscious no ill-effects may be noted. In general, of course, the longer the irritability persists the worse the sequelæ. After twenty-four hours the longer the patient lasts the greater the hope of the recovery of life, but the more likelihood there is of sequelæ.

It may be useful here to list the causes of death in cases of head injury, as a guide to the complications to be expected, and avoided if possible.

Due to massive brain injury, shock and hemorrhage in severe fractures, the patients dying under ten hours	Per cent 25
Cerebral compression. Death usually in twenty-four hours	46
Pneumonia	5
Exhaustion	3
Meningitis	8
Other lesions and associated injuries	14

TRAUMATIC STUPOR OR CEREBRAL COMPRESSION

A certain percentage of these cases have not a raised CSF pressure, and so the term cerebral compression is not strictly accurate. The mechanism of cerebral compression is, however, the most common cause of the symptoms to be described. Where the CSF pressure is not raised we must postulate damage to vital centres, widespread areas of thrombosis, and little hæmorrhage as the cause of the coma. This is perhaps more commonly due to direct brain injury.

THE STAGE OF ONSET 1 It may rapidly develop following a period of shock and concussion, indicating severe brain damage. The patient is usually deeply comatose.

2 It may gradually develop after a period of cerebral irritation.

3 There may be very slowly developing pressure, which may

PUPILLARY CHANGES IN CEREBRAL COMPRESSION

Stage	PUPIL ON SIDE OF COMPRESSION	PUPIL ON OPPOSITE SIDE
1	Slightly contracted ●	Normal ●
2	Moderately dilated. Reacts to light. ●	Normal ●
3	More dilated. Does not react to light. ●	Moderately dilated. Reacts to light. ●
4	Widely dilated and insensitive ●	Widely dilated does not react to light. ●

FIG 150

give rise to a period of excitement resembling acute alcoholism, followed by coma.

4 The stupor may come on after an interval following apparent complete recovery from concussion (the "lucid" interval), the syndrome of middle meningeal hæmorrhage.

COMPENSATED COMA SYMPTOMS The patient is deeply comatose, and may show no response to any stimuli. Generally there is some slight response to pain. In the early stages of shock the patient may be flaccid, but later localised rigidity may set in. As a localising phenomenon Jacksonian fits may occur. With hæmorrhage in various areas or spreading, various palsies may occur, hemiplegia, paraplegia, or the paralysis of a single limb, so that marked differences in the tendon reflexes may be noted.

Pupils As the sympathetic fibres to the pupils pass up the carotid canal in the carotid sheath they are very liable to damage when the bone in this area is injured. The fibres may either be paralysed or stimulated so varying pupillary reactions may be seen.

If the nerve is intact increasing pressure on the third nerve nucleus will cause the pupillary changes previously described, but it must be remembered that this area of the brain may be so damaged that it is out of action. In the stage of paralysis the larger pupil is on the side of greatest compression.

Eyegrounds Changes are usually noted only after a period of four to six hours. The retinal veins are pressed on first, and may be seen to be full. In twenty-four hours the disc may appear choked. Papilloedema is of slow development and not seen in the early days. In chronic conditions such as subdural hematoma, it is important. If there are any retinal hemorrhages present it is reasonable to suppose that there are hemorrhages elsewhere in the brain.

Pulse After recovery from shock the rapidity may persist, and is of grave significance, if accompanied by a rise of temperature. More usually it slows to forty to fifty beats. If no rise in B P accompanies this it is due to some damage to the cardiac centre. If, however, the B P together with the C S F pressure rises and the pulse slows it is due to cerebral compression. With this, in any developed form, the pulse is slow, full and increased in tension. When there is no rise in intracranial pressure the pulse is a slow normal, or weak pulse.

Blood pressure This rises with increasing intracranial pressure through the compensating mechanism to be described later. It is, of course, important to know if the patient has had a high B P before the accident, and when this information is not available, it is only change in pressure which can be relied on in elderly patients.

Respiration This becomes normal after recovery from shock, or, if there is gross damage to the respiratory centre itself it may never recover. Accompanying coma it may be normal or it may be irregular, but with rising intracranial pressure it becomes slower and deeper, till it is at last stertorous. Still later it becomes irregular or of the Cheyne Stokes type, while just before death it may be shallow.

Temperature With recovery from shock it is normal, and then may rise a little from the absorption of blood products. Rapid rise of temperature is unusual and associated with injuries to the corpus callosum, pons and thalamus and is of grave significance. A temperature of 106° to 107° is often a terminal phenomenon. The greater the cerebral damage the greater the temperature, and a steadily increasing temperature is a bad omen. It must be remembered that the temperature may be due to the onset of infection in the meninges, or to associated infections elsewhere. If a L P has not been already done it may become essential for the differential diagnosis of the

condition. Over dehydration may produce a late elevation of temperature, and still later secondary infection may cause it to rise.

Meningismus Signs of head retraction, neck rigidity, and Kernig's sign may appear early in the case and raise suspicions of meningitis. In such circumstances a lumbar puncture is necessary. In the very mild cases it is due to the irritation of the blood in the C.S.F., with the onset of infection the symptoms are very much more marked.

Pathology of Cerebral Compression

Cerebral damage is due to

1 Direct injury, from the blow, depressed bone, or a foreign body in the skull

2 Haemorrhage, primary, secondary or delayed

3 Oedema (Producing irritative rather than paralytic features)

An attempt to assay the amount of direct injury may be made from a consideration of the severity and type of injury, the presence of a foreign body, the amount of visible injury, and the X-ray.

Oedema can only be assumed as it has been shown to be present in cases dying after injury.

Haemorrhage can be analysed

1 EXTRADURAL Middle meningeal haemorrhage Diploic veins, and venous sinuses

2 SUBDURAL Due to filling of the space between the arachnoid and dura. Haemorrhage from venous sinuses or cerebral veins

3 SUBARACHNOID This is the most common form of severe bleeding and may arise from any of the sites of bleeding. It is widely distributed in the C.S.F.

4 CEREBRAL (a) Subpial Small contusions on the surface of the brain

(b) Intracerebral Resembling non-traumatic intracerebral haemorrhage, and often associated with vascular disease

(c) Intraventricular From the choroid plexus, or intracerebral damage. Invariably fatal

Haemorrhage from the diploic veins and the venous sinuses has usually insufficient pressure to strip up the dura, and unless the dura has been stripped by the injury does not form large collections. Only the arterial pressure working on the Bramah press principle can continue to strip up the dura progressively (see p. 219).

Subdural haemorrhage is comparatively common and, being venous in origin, is usually slight. It may be bilateral in the case of injury to the longitudinal sinus. The blood tends to trickle to the most dependent part of the space. Chronic subdural haematomata are rare. They are due to sudden increase in size of a small subdural

hæmatoma from an old injury and may light up at any time after the injury with symptoms vaguely resembling a tumour

Subarachnoid hæmorrhage may arise from

- (a) Large arteries of the circle of Willis
- (b) Cerebral veins
- (c) Venous sinuses

Hæmorrhage from a large artery produces rapidly increasing intracranial pressure and death in a few hours. Smaller arteries produce more localised hæmatomas, and may allow the detection of localising symptoms, as the onset of compression is slower, and




FIG 151 Diagrammatic representation of the various types of hæmorrhage met with in skull injury

time is given them to appear. In some cases it may cease after a time.

Hæmorrhage from a vein or sinus is slower still, and may be diffuse if passing into the C S F space, or localised. Hæmorrhage from a vein may cease with a rise of pressure of the C S F, but this is not so with that from an artery. Venous hæmorrhage tends to stop, and form a localised collection, which may later give rise to cysts from organisation of the clot.

Intracerebral hæmorrhage may produce localising signs, is accompanied by the features of non-traumatic cerebral hæmorrhage, and if continued gives rise to a general increase in intracranial pressure as before. Softening in a contused area may lead to a secondary hæmorrhage later, this condition being known to the Germans as "spät apoplexie".

Physiology of Cerebral Compression

The occurrence of cerebral hæmorrhage demands an adequate blood pressure to force the blood out of the vessel. In the presence of shock this may be low, and hæmorrhage only sets in with the recovery of the patient. In middle meningeal hæmorrhage this is seen in another way. Here the blood pressure must be sufficient to trip the dura mater from the skull. As this is more firmly attached below than above, the blood tends to be deflected upwards. Here also the phenomena of hydrostatics play a part, for a small amount of blood pumped into a larger space increases the pressure available and in a short time develops sufficient force to overcome any resistance. (The Bramah Press)

The development of compression may be divided into four stages

FIRST STAGE It has been shown experimentally that about 6 per cent of the C S F space may be encroached on without producing symptoms. Normally the C S F pressure equals the venous, so that veins would be equally affected. With the first small rise of pressure C S F is displaced and the patient may only complain of dullness, nausea and headache.

SECOND STAGE With the exhaustion of this space by increasing hæmorrhage pressure is produced on the veins, which with the exception of those supported by the dura (sinuses) collapse, thus increasing the space in the skull, but also the venous back pressure. This decreases the blood supply to the brain cells and so increases their CO_2 content. At first this change in pH seems to produce an added excitability of all brain tissues which is clinically shown as "cerebral irritation". Later on the pH imbalance may play a part in producing œdema of the cells.

THIRD STAGE The reduced blood supply to the vasomotor centre in the medulla results in an increase of the CO_2 content of the blood around the centre to which it is sensitive, and a reflex rise of B P is produced to restore the cerebral circulation. This increase of B P at the same time increases the rate of hæmorrhage, which was dropping off with the rise in intracranial pressure. In a short time this interferes with the blood supply to the centre again and a further rise of B P occurs. A vicious circle is set up which results in a huge rise of pressure to maintain the cerebral circulation, and a characteristic full slow pulse. This period of automatic raising of the B P by the anæmic vasomotor centre is known as the period of "medullary compensation".

FOURTH STAGE Finally the circulation in the medulla can no longer be maintained by a rise of pressure and the vasomotor centre fails, with a fall in B P and an increased pulse rate. Finally, failure extends to the respiratory centre and death ensues.

During the first three stages the hæmorrhage may cease, and a collection of blood may then produce localised pressure on the brain. On the other hand the slow development of pressure may give time for localising symptoms to appear before they are obscured by more serious ones. Endeavours to determine the side of the lesion are made by a study of the following facts

The site of the injury, the type of blow, and its direction

The presence of paralysis on one or other side

The state of the pupils Dilated on the side of compression

The presence of fits The important feature being the site of commencement of the fit (Jacksonian fits)

Ophthalmoscopic examination, which may show papilloedema on the side of the compression or venous engorgement

Later on features may make their appearance which suggest lesions of certain areas

CEREBRUM Frontal lobe, mental changes, loss of memory, changes in disposition

TEMPORAL LOBE Auditory aphasia in left sided lesions in right handed people, word or object blindness

PRECENTRAL CONVOLUTIONS History of convulsions, of Jacksonian type Paralysis and spasticity

POST CENTRAL CONVOLUTION Changes in cerebral discrimination of touch, pain and temperature sensation, *e.g.*, loss of tactile localisation, two-point discrimination, inability to tell rough from smooth Astereognosis

OCCIPITAL LOBE Visual field defects

CEREBELLUM Incoordination, nystagmus, vertigo, hypotonia, ataxia, past-pointing failure in finger to nose test, etc

GROUPING OF INJURIES AND COMMONLY ASSOCIATED BRAIN DAMAGE

1 Massive brain damage Severe fracture showing rapidly increasing intracranial pressure Death often in ten hours

2 Definite brain injury Moderately severe fracture

(a) If signs of increasing intracranial pressure death often in twenty-four hours

(b) No signs of increasing intracranial pressure

3 Depressed fractures of the skull Simple and compound Brain damage variable often small

4 Fissure fractures of the skull Usually with little evidence of brain damage

5 Middle meningeal hæmorrhage

These conditions are not separate entities, and overlap and pass



FIG 152 Massive fracture of the frontal bone The free bone fragment was depressed in the lateral film Death in eight hours

During the first three stages the hæmorrhage may cease, and a collection of blood may then produce localised pressure on the brain. On the other hand the slow development of pressure may give time for localising symptoms to appear before they are obscured by more serious ones. Endeavours to determine the side of the lesion are made by a study of the following facts

The site of the injury, the type of blow, and its direction

The presence of paralysis on one or other side

The state of the pupils Dilated on the side of compression

The presence of fits The important feature being the site of commencement of the fit (Jacksonian fits)

Ophthalmoscopic examination, which may show papilloedema on the side of the compression, or venous engorgement

Later on features may make their appearance which suggest lesions of certain areas

CEREBRUM Frontal lobe, mental changes, loss of memory, changes in disposition

TEMPORAL LOBE Auditory aphasia in left sided lesions in right handed people word or object blindness

PRECENTRAL CONVOLUTIONS History of convulsions, of Jacksonian type Paralysis and spasticity

POST-CENTRAL CONVOLUTION Changes in cerebral discrimination of touch, pain and temperature sensation, *e.g.*, loss of tactile localisation, two-point discrimination, inability to tell rough from smooth Astereognosis

OCCIPITAL LOBE Visual field defects

CEREBELLUM Incoordination, nystagmus, vertigo, hypotonia, ataxia, past pointing failure in finger to nose test, etc

GROUPING OF INJURIES AND COMMONLY ASSOCIATED BRAIN DAMAGE

1 Massive brain damage Severe fracture showing rapidly increasing intracranial pressure Death often in ten hours

2 Definite brain injury Moderately severe fracture

(a) If signs of increasing intracranial pressure death often in twenty four hours

(b) No signs of increasing intracranial pressure

3 Depressed fractures of the skull Simple and compound Brain damage variable often small

4 Fissure fractures of the skull Usually with little evidence of brain damage

5 Middle meningeal hæmorrhage

These conditions are not separate entities, an — and pass

into one another in variable ways, but they serve as a basis for discussion, particularly of treatment.

1 Massive brain damage The injury being severe there is usually a compound wound and other external evidence of brain damage, such as haemorrhage from the ears or the dripping of CSF from the nose. The patient is profoundly unconscious, the respirations stertorous, and later irregular, the pupils dilated and not reacting to light. The pulse is variable, either rapid and imperceptible, or slow and irregular. All reflexes are usually abolished. Death occurs early, often within ten hours.

TREATMENT Very little in the way of treatment is possible. The dressing of the wounds, and stopping of haemorrhage by the insertion of a few mattress sutures into the scalp is often all that can be done. Once the patient has recovered a little the compound wounds may be dealt with under local anaesthesia, but this is often in vain. Complete rest is all that can be assured in the hope that the anticipated damage is less than at first thought, and the patient may be classified into a more hopeful group.

2 Definite brain injury Group (b) No signs of increased intracranial pressure. Injury to the brain is deduced from the physical findings, and the patient's mental condition, with possibly localising signs. When first seen the patient may be semi-conscious and the CNS and general examination yield variable findings. The CSF is not increased in pressure though there may be some blood in it. Within twenty-four hours these patients usually develop the features of cerebral irritation, and it is therefore wise to anticipate events by commencing dehydration treatment from the start. A number of these cases will recover rapidly, while in others the state of cerebral irritation will drag on for days and weeks. The treatment under these circumstances has been described. If the patient develops signs of increase in intracranial pressure he passes into group (a).

Group (a) Cases with signs of increasing intracranial pressure. These cases are the ones which try the patience of the surgeon, for the treatment is difficult and often debatable, and the moment to interfere is a hard one to choose. The pathology in these cases is usually that of subdural haemorrhage, with lacerations of the temporal and possibly frontal or occipital lobes. These cases may be seen with the developed syndrome, or watched developing it. If the latter is the case the rate of development of compression is a valuable prognostic point. If the pressure rises rapidly the outlook is bad and interference usually useless. More slowly developing pressure offers the hope of it ceasing. In a certain group of cases the pressure will rise high and remain so, presumably due to the formation of a large haematoma which has upset the compensating mechanism as

subcutaneous hæmatoma can collect, and clotting at the edge give a sensation on palpation strongly suggestive of a depressed fracture. Subaponeurotic or subperiosteal hæmatomas may however arise under a skin laceration. If there is doubt, and an X-ray is available, this will clear it away, or a thick boro needle may be inserted and the hæmatoma aspirated. Palpation after this will clear the doubt up. If the swelling is due to fluid which communicates with the brain it will have an impulse on coughing, or can possibly be slowly emptied by pressure. All open wounds over the skull must be treated as wounds elsewhere, by debridement and excision, but they must also be adequately explored for fissure fractures or depressed fragments. A probe or finger nail passed over the bone will readily detect an irregularity.

As the force of the blow often depends itself on the damage to the bone, and there is not the accompanying deformation of the skull, brain damage is often quite negligible, in spite of moderately extensive skin lacerations. The patient is thus frequently conscious, or at the most has only a short period of amnesia. Where the area of brain damage corresponds to a known functional area, localising signs such as fits, aphasia or blindness may occur.

TREATMENT Closed depressed fractures unassociated with signs of brain damage are as a rule best left alone. Indications for interference would thus be signs of brain damage, suspicion of cerebral compression, cosmetic considerations, particularly in injuries in the frontal region, and cases in which it is obvious that the fragments have been driven in below the level of the dura. In these cases exploration of the wound is undertaken and the fragments elevated and left in position. Even if totally detached they will act as grafts and restore the continuity of the skull. If it is impossible to unlock the fragments trephining *en bloc* may be necessary. Once the fragments have been sorted out and pushed into position the whole amount of bone removed is replaced. Where the dura can be sutured together, it is lightly stitched after irrigation of the wound, the sucking out of loose brain tissue, and the removal of depressed fragments of bone.

Compound depressed fractures must be operated upon and the procedure is the same. The repair of the defect in view of the risk of infection must however be left, and no loose fragments of bone are replaced as grafts. The dura must not be widely excised if it has been torn, owing to the risk of disturbing adhesions already present. If the dura cannot be closed and a space is left which will fill with blood and CSF, it is best to pack it lightly with ribbon gauze, to avoid the risk of *bernia cerebri*, or CSF fistula, which may follow if infection occurs. The packing is removed in a few days after time

well as causing mechanical embarrassment. It is this group of patients which are likely to benefit from operation. To operate in cases with a rising CSF pressure other than when a meningeal hæmorrhage is suspected is to court death on the table, but if there is doubt as to whether the hæmorrhage is middle meningeal, subdural, and the general condition is fair, exploratory operation on the meningeal artery may be combined with a subtemporal decompression.

OPERATION. Local anæsthetic is used. The incision runs from above the ear sloping slightly downwards and forwards. The zygoma $\frac{1}{2}$ inch in front of the ear and $3\frac{1}{2}$ inches long. Forceps are placed on the galea to control the hæmorrhage. The temporal muscle and its aponeurosis are divided in the line of its fibres and separated from the skull by a periosteal elevator, and the skull entered with a trephine or a drill and perforating burr. The bone is then nibbled away around this opening according to what is found. If the hæmorrhage is extradural the clot is evacuated and the middle meningeal tied off above and below the site of rupture. Difficulty may be found when the hæmorrhage arises from the region of the foramen spinosum, when the bone is nibbled away in this direction and the foramen plugged with matchstick. If the artery lies on the dura it is easily under run, but when lying in a groove of bone it may be more difficult to plug with wax or wood. Further exploration depends on the findings, if the middle meningeal had not been bleeding and the dura was blank and tense, then incision and evacuation of the clots around the temporal lobe is the course to adopt. This necessarily demands some enlargement of the opening in the skull which later amounts to a decompression. If cortical vessels are bleeding they are clipped if of any size. Smaller vessels may be controlled by diathermy or where this is not available by small muscle grafts placed over the bleeding point. These may be conveniently obtained from the temporal muscle. All hæmorrhage must be stopped before suturing the wound. If the dura is not closed, the temporal muscle is accurately sutured to control the bulging brain.

Depressed fractures of the skull. Simple or compound. The injury is generally due to objects of great velocity and small mass, e.g., bullets, falls on to a spike, or a blow with a hammer. The injury is usually readily detected and confirmed with X-rays. It is to be noted that abrasions are generally a good sign as they indicate a glancing blow, while a laceration with crushed edges indicates that the blow has been direct. An external wound and hæmorrhage are more commonly associated with a depressed fracture than an intact scalp, and this is important, as it is only in the intact scalp that

involved. The method of use has already been discussed in the treatment of wounds (p. 76). It has been shown however that in brain tissue an undesirable gliosis is excited and this increased scarring might produce traumatic epilepsy at a later date. Sulphamidamide should also not be used in wounds in which nerves are exposed in the wound, for a similar reason. Systemic administration of the drug must replace local use under these conditions.

Injuries due to bullet wounds are in much the same category. Here the dura is torn, and exploration of a mild type is advisable.




FIG. 155. Trephining *en bloc* to remove a large number of depressed fragments combined with exploration.

The bullet should never be hunted for, but removed if readily obtained, the path of the bullet is sucked clean with a sucker or a catheter, and the dura approximated with a small drain into the track (Fig. 142).

3 Gutter fractures In these there is a linear fracture, in which one side is depressed below the other and caught there. They may be released by slow nibbling along the line of the fracture, to remove sufficient bone to allow of the lower edge flipping up, or by trephining over the base of the flap and inserting a lever and levering up. It must be ascertained that the lower edge of the flap is intact or it will merely rock and perhaps do more damage.

has been given for adhesions to close off the subarachnoid space. Should only a very small space be left it will probably be sufficient to close the scalp over it.

Damage below a fracture of this kind must be treated on its merits. If the dura is already torn there can be little increased risk of infection by exploration. If the dura is not torn the advantage of exploration must be weighed against the possibility of spread of infection later. These considerations naturally apply only to compound wounds. In the absence of strong evidence for interference, such as localised fits, increasing intracranial pressure, a tense blue and bulging dura, with little pulsation, it is best to leave the dura intact.

The wound can be treated in many ways. In some cases it may provide all the access desired when the edges are excised, and only require suture. In others it may be found convenient




FIG 153 One method of closing the skin of the scalp after loss of tissue




FIG 154 Method of closing a gap in the scalp tissues by using a U shaped incision. Either this or an S shaped incision is usually most satisfactory

to close the wound after excision and then make a set approach to the fracture through a horseshoe incision. This would be an ideal proceeding where the lacerations of the scalp did not connect with the fracture. In other cases S-shaped flaps have to be used so as to be certain of being able to close the wound (Fig 154), or, as it is important to have the skin closed over the bony defect, lateral incisions may be made in the scalp and thus drawn together, leaving healthy bone exposed. Drainage is necessary in all cases where hæmostasis is poor and is best done with a small rubber drain in a stab wound. The scalp wound is best sewn up firmly with mattress sutures with more accurate approximation between the deep sutures by a second layer of simple sutures (see Fig 42). The deep mattress sutures have the advantage of being hæmostatic as well as tension sutures, and by their use subcutaneous ligatures can be avoided, always a desirable aim in all skin wounds.

CHEMOTHERAPY There can be no objection to the use of sulphamamide in wounds of the head in which brain matter is not

X ray films. Confusion of an old with a recent injury must be avoided.

Middle meningeal hæmorrhage This is mentioned to complete the discussion. Occurring alone it may offer a clear picture, but it is frequently associated with other lesions which obscure it (Fig 151).

PATHOLOGY The artery entering the skull at the foramen spinosum divides after a short course into anterior and posterior branches, the anterior branch passing upwards in the line of the pre-rolandic gyri. It can be mapped by taking points 1, $1\frac{1}{2}$ and 2




FIG 157 A fissure fracture of the parietal running into the parieto occipital suture

inches from the upper border of the zygoma, and the external angular process of the frontal bone. The posterior ramus runs horizontally back parallel with Reid's base line, at the level of the upper border of the orbit. For trephining over this vessel the spot selected is 2 inches above and behind the external auditory meatus. For the anterior branch the spot is the uppermost one of those already mentioned. Rupture of the vessel can occur without fracture, but fracture in the region, commonly of the squamous temporal, should raise suspicions. Very rarely the hæmorrhage may be subaponeurotic as well as subdural, if the communicating crack

A similar method may be used in pond fractures in children, or through a small drill hole a hook can be inserted and the soft bone everted

Cases will naturally be seen which are a combination of the lesions just described, and combined methods of treatment may be used to advantage

Linear or fissure fractures of the skull In many of these cases there is no clinical sign of fracture, but the story makes one suspicious and X-ray may reveal it Often there is little damage to the brain, but the fact that any degree of damage can coexist with any extent




FIG 15b The elevation of depressed fragments by inserting a lever through a trephine hole on the edge of the fracture

of fracture must be remembered The most serious features of these cases are due to brain injury In compound wounds it must be remembered that while the skull is sprung open hair and other tissues may be caught in the opening, and be found deep to the subjacent bone on removing it If there is evidence of soiling of the edges of the bone, this must be removed all along the fracture for a few millimetres on either side with nibbling forceps

TREATMENT In simple fractures this is mainly of the brain complications In compound fractures it has already been outlined Adequate rest and observation are necessary, and are determined as outlined for concussion Note must be made that the healing of the bone is by fibrous tissue, and cracks have been seen ten years later in

Intra-Cranial Hæmorrhages in relation to Time

Site	Latent Period	Paralytic Signs
EXTRADURAL	Variable, usually a few hours	Face and arm Speech in L sided lesions Twitching going on to a spastic paralysis
SUBDURAL	Localised { Acute, 4 to 7 days { Chronic, 6 to 12 weeks	Legs involved Signs variable, like a cerebral tumour
SUBARACHNOID CEREBRAL	Diffuse Immediate Immediate Late, 7 to 10 days (Spasmodic apoplexy)	Spastic monoplegia Hemiplegia Spastic monoplegia

Indications for operation (in outline)

- IMMEDIATE**
- 1 Any type of compound fracture
 - 2 Depressed fractures, with intracranial complications

DELAYED

- | | |
|---------------------------------|---|
| <i>Inside twenty four hours</i> | Middle meningeal hæmorrhage |
| <i>Within a week</i> | Persistent raised intracranial pressure |
| | Early subdural hæmorrhage |
| | Delayed traumatic apoplexy |
| <i>After six weeks</i> | Late subdural hæmatoma |
| | Cerebral œdema syndrome |
| | Traumatic epilepsy |

Complications of Fractures of the Skull

At this point it seems correct to enumerate these to complete the survey, without going into them in detail as they are outside the scope of this volume

INFECTION The possible paths, i.e., infection from outside, or fractures into the sinuses or nose have already been mentioned. Where there is an open wound in the scalp treatment limits itself to the establishment of free drainage by removal of sutures, and expectant treatment with compresses. The seriousness of infection depends largely on whether the dura is intact or not and also on whether time has been given for adhesions to occur. When the

is large enough. The physiology of the condition has already been described.

SYMPTOMS The initial injury is in the overwhelming majority of cases of sufficient violence to cause a loss of consciousness, which may be of varying duration, and commonly very short. Various other features of fractures of the base or vault may be associated, such as orbital or aural hæmorrhage, or facial paralysis, but the chief difficulty arises in estimating other lesions present. Following the loss of consciousness the patient recovers to some extent. In some cases this may be complete, as where a footballer finishes a game, to lapse into coma later. In the more difficult cases the condition is associated with damage elsewhere, and there is perhaps only a lessening of the depth of unconsciousness. The essential features of the condition are the period of recovery, "the lucid interval," which is, as described, variable, and localising signs due to the hæmorrhage being concentrated over the lower portion of the pre-rolandic gyrus, so that increasing pressure produces

- 1 Irritation of the facial area, spreading to the arm, so that twitchings of face and arm occur.

- 2 Later paralysis of the face and arm on the opposite side, of a spastic type, and on the left side possibly motor aphasia.

The pupils may be an aid in showing the characteristic dilation on the side of the lesion. As a point of differential diagnostic significance it may be mentioned that the hæmorrhage from a torn cerebral vein, occurring near the falx, affects the leg area first, and its effects do not progress so rapidly as the hæmorrhage is venous.

TREATMENT This has already been discussed to some extent under the treatment of cerebral compression. After making the incision, the trephine is placed at the elective site, or if there is a fracture, at the point where artery and fracture cross, and the circle of bone removed. If a hæmatoma is present it is evacuated with a sucker and rubber tube, and the bleeding point sought for. If in the anterior branch it may be possible to under-run it with a fine needle and thread, but if the vessel is lying in a groove it must be plugged with wax or a match stick, after the bone has been carefully nibbled away to expose it, which may be difficult, as nibbling at the bone over the vessel often tears the vessel as well. If the anterior branch is found intact and the blood is coming from the posterior branch, two courses are open, either one enlarges the opening down till the whole vessel may be controlled at the foramen spinosum, or one starts afresh to trephine over the posterior branch. The former course is usually preferable if only as a time saving procedure.

serious cases, in which the mental symptoms have been marked, decompression has been tried

RHINORRHOEA AND OTORRHOEA The escape of CSF from the nose or ear does not as a rule persist very long. Either infection sets in or it clears up spontaneously. Delayed cerebrospinal rhinorrhoea demands operative repair.

CEPHALYDROCELE Due to a communication persisting between the subcutaneous tissues of the scalp and the CSF through a break in the skull. It is more common in children, and after persisting for some time usually subsides. Very rarely is operative interference to close the defect necessary.

DEAFNESS, complete or partial, tinnitus and vertigo are sequelae of injury to the middle and inner ear. They may be persistent and troublesome, requiring long periods of rest before they subside. While vertigo may improve, deafness if due to internal ear damage only improves to a certain extent. Haemorrhage into the middle ear causes serious deafness, which may improve considerably as the haematoma absorbs.

TRAUMATIC EPILEPSY This is a not uncommon sequela of serious or compound fractures. The fits are of the true Jacksonian type, and their commencing point is an important localising sign for exploration. The aetiology is variable, being due to pressure or irritation from depressed bone, old blood clot, or the presence of a foreign body. All genuine cases should be submitted to exploratory operation. To avoid this unpleasant complication all cases of severe fracture should be given luminal gr. 1 B.D. for a period of six to twelve months after the injury. Later this is reduced to $\frac{1}{2}$ gr. and then discontinued.

CHANGES IN INTELLIGENCE and in the character of the person may be found, and in some cases are very distressing. In the absence of localising phenomena the outlook is not good. Long periods of rest under suitable conditions and observation are necessary.

HEAD PAIN This is the most common symptom, and can be grouped into three types.

1 Generalised headache. Common in the early days, and subsides with rest. Recurrence suggests persistent oedema syndrome, subdural haematoma, or the like. It is characterised by its onset on awaking, its increase on coughing or straining, or in any posture in which the head is lowered.

2 Localised headache. This may be associated with other localising symptoms and signs. It may be very severe and sharply localised. It is frequently due to adhesions between skull and dura or subdural pathology and requires operative interference for cure.

infection is localised the outlook is fair, but once meningitis is established the prognosis is very depressing

Later infective complications may be

Extradural abscess

Cerebral abscess

Encephalitis

Thrombophlebitis of a cerebral sinus

Osteomyelitis of the skull Localised and spreading

HERNIA CEREBRI This complication is mentioned here as it has an important relation to infection. There is always infection associated with this condition, and when it subsides the hernia cerebri subsides. Treatment is therefore expectant, and consists of avoiding further damage to the hernia. The surface is syringed off daily with normal saline, the skin around the hernia cleaned and the whole covered with clean gutta-percha, which does not adhere to the granulating surface. When the shrinkage of the granulum has reached the level of the scalp it will epithelialise over, or may be grafted.

The hernia is hydrostatic in origin and contains a prolongation of a ventricle. Its size can be reduced by lumbar puncture and this should be carried out regularly.

LATE SUBDURAL HÆMATOMA Hæmorrhage occurs typically from a cerebral vein. Symptoms of increased intracranial pressure are, however, late in appearing, for reasons unknown. At operation the clot is found to have organised into a thin membranous sac containing degenerate blood. Symptoms are those of increased intracranial pressure in general with headache as the common onset symptom. Mental changes, motor interference, and later drowsiness deepening into coma may be seen. Treatment is removal of the cyst where possible, but with large cysts aspiration is often all that can be done, owing to the serious disturbance produced by any other proceedings.

CEREBRAL ŒDEMA SYNDROME This name has been applied to a group of cases in which after three months or so there is an onset of symptoms suggesting mild cerebral irritation. The patient complains of headache, giddiness, loss of concentration and sleeplessness, though he may be drowsy in the day, and occasionally mental changes. The condition is usually associated with a too early return to work. It has to be distinguished from malingering, and this can usually be done by noting the inexhaustibility of the malingerer while the genuine case tires of questioning easily. Treatment consists of adequate rest combined with some dehydration, magnesium sulphate enemas, and in a few cases lumbar puncture. In a few

CHAPTER XVI

FACIAL FRACTURES

(MR J N BARRON)

1 UPPER FACIAL FRACTURES

General Remarks The complicated bony architecture of the face is divided into three regions in descriptions of the common fractures of these bones. These regions are nasal, malar, and maxillary. Nasal fractures may involve the nasal bones, the frontal processes of the maxilla, the ethmoid and lachrymal bones, and the septal, alar and lateral cartilages. Malar fractures may involve the body of the malar, the zygomatic arch, the frontal process, the infra-orbital ridge and the adjacent maxilla, including the anterior antral wall with the infra orbital canal, and the orbital floor. Fractures of the maxilla may affect the body and the various processes. The maxillary antrum affords a space into which fragments can be displaced.

These injuries are the result of direct violence, and there is little tendency to spontaneous alteration in position of the fragments after the impact owing to the paucity of musculo attachments and the splinting effect of the soft tissues of the face.

Apart from cosmetic reasons, the indications for treatment are visual and sensory disturbances, nasal blockage and its sequelæ and dental mal occlusion. Inadequate reduction and splintage may have serious results because secondary correction is difficult and late restoration of the displaced bony fragments often impossible.

Cranial fractures are commonly associated with these injuries, and routine examination should include the cervical spine and peripheral nervous system for intracranial and cord damage. A fracture dislocation of the cervical spine should not be missed.

Nasal Fractures

Fractures of the nose are due to direct violence applied to the nasal bridge. The violence may be either from in front or from the side, and the resulting deformities are somewhat different. Most nasal fractures are comminuted and this has an important bearing upon the deformity and the treatment.

Blows from in front have a crushing effect, the fragments collapsing upon each other produce a "saddle" or depressed bridge. The whole bony structure may be involved, and in severe cases the ethmoid, with its cell complex, is splayed out into the orbital

3 Localised to the scar Due to adhesions between the bone and scalp, or the scalp and dura Often clears up in time

4 Shooting pains due to involvement of nerves in scars Requires operative section of the nerves

Errors in diagnosis of fracture of the skull and interpretation of symptom

Old fractures of the skull remain visible in the X ray up to ten years

Patients may have a bradycardia and hypertension before admission

A dilated pupil, or irregular pupil, may be an old lesion

A stroke may have preceded the fall which fractured the skull

A fracture line should not be confused with a suture line, which is much more irregular and less sharp in outline, in either the X ray or at the bottom of an open wound

The sulcus of the middle meningeal artery should not be confused with fracture line

A bleeding ear may be due to separation of the cartilage from the bone and may occur after blows on the jaw

A bleeding nose is commonly due to local injury

A black eye should not be confused with hæmorrhage into the orbit from fracture (See page 203)

Confusion should not occur between the syndrome arising from meningeal infection and that from compression

The difficulty of diagnosing a hæmatoma of the scalp from a depressed fracture is easily settled but much more commonly a fracture is suspected when it is not present than overlooked when it is present

REFERENCES

General

MOCK, MORROW and SHANNON "Fractures of the Skull" *International Surgical Digest*, June 1934, 17, 323

JEFFERSON GEOFFREY "The Physiological Pathology of Gunshot Wounds of the Head" *Brit J Surg*, 1919 7, 262

RAWLINGS, L B "Head Injuries" Oxford Medical Publications, 1934

TROTTER and TAYLOR "The Scalp Skull and Brain" Choyce's System of Surgery

RIDDOCH, JEFFERSON, RUSSELL and ROSS "Discussion on the Diagnosis and Treatment of Acute Head Injuries" *Proc Roy Soc Med*, 1931, 5, 735

ROWBOTHAM, G F "Acute Injuries of the Head" Their Diagnosis Treatment, Complications and Sequels Livingstone, Edinburgh 1942

Radiology

LYSHOLM E "Apparatus and Technique for the Roentgen Examination of the Skull" Stockholm 1931

for a few days before reduction is attempted. Reduction is most readily obtained by the use of Walsham's nasal forceps and Asches' septal forceps. Each nasal bone in turn is disimpacted with Walsham's forceps and elevated into its normal position. The septum is then held lightly between the blades of the Asches forceps and straightened out, the nasal bridge being elevated at the same time. Any tendency to splaying at the base of the nose is controlled by the fingers during this last manoeuvre. Long rubber covered forceps of any pattern can be used for this manipulation if the proper instruments are not available.

Where a crush fracture involves the ethmoids and there is



FIG 161 Plaster nasal splint to maintain mid line position of nose after reduction of fracture deviation



FIG 162 Silk mattress stitch passed through the nose and tied over dental rolls. This splint will maintain elevation of depressed fractures

lateral displacement into the orbits it is of the utmost importance that this should be corrected. With the septum held steady in the elevated position, the thumb and forefinger of the left hand are passed back into the orbits along the inner canthi. The lateral masses of the ethmoids are then squeezed back into their normal relationship in the nasal cavity.

Splintage In minor fractures no splintage is necessary. Care should be taken that no further trauma is inflicted during the first fortnight. Where there has been much comminution and displacement a plaster-of-paris pattern should be cut and moulded over the nose. It should have an extension on to the forehead and is fixed by tapes round the head. In some cases where there is a tendency for the whole bridge to collapse a stout silk mattress suture is passed

cavities The cribriform plate and dura may give way, in which case direct contact is established with the subdural space in the region of the gyrus rectus of the frontal lobe The septum is buckled



FIG 158 Saddle nose resulting from head on blow



FIG 159 Nasal deviation due to lateral injury

or fractured and the mucous membrane stripped from the underlying bone and cartilage so that a submucous hæmatoma may result

Lateral injuries involve the nasal bones and septum The main deformity is a deviation of the bridge, the fragmented bone on the




FIG 160 Rubber covered Walsham's forceps used in displacing nasal bones

Ascher's septal forceps for manipulation of septal deformities

side of impact being driven under the opposite side, which may itself be fractured The septum is deviated from the side of injury and is buckled or broken

Treatment Nasal fractures should be reduced at the earliest opportunity If there is early gross œdema it is justifiable to encourage its absorption by the use of alternate hot and cold packs

for a few days before reduction is attempted. Reduction is most readily obtained by the use of Walsham's nasal forceps and Asches' septal forceps. Each nasal bone in turn is disimpacted with Walsham's forceps and elevated into its normal position. The septum is then held tightly between the blades of the Asches forceps and straightened out, the nasal bridge being elevated at the same time. Any tendency to splavng at the base of the nose is controlled by the fingers during this last manuvre. Long rubber covered forceps of any pattern can be used for this manipulation if the proper instruments are not available.

Where a crush fracture involves the ethnoids and there is



FIG 161 Plaster nasal splint to maintain and line position of nose after reduction of fracture deviation



FIG 162 Silk mattress sitch passed through the nose and tied over dental rolls. This splint will maintain elevation of the pressed fractures

lateral displacement into the orbits it is of the ntmost importance that this should be corrected. With the septum held steady in the elevated position, the thumb and forefinger of the left hand are passed back into the orbits along the inner canthi. The lateral masses of the ethnoids are then squeezed back into their normal relationship in the nasal cavity.

Splintage. In minor fractures no splintage is necessary. Care should be taken that no further trauma is inflicted during the first fortnight. Where there has been much comminution and displacement a plaster-of-paris pattern should be cut and moulded over the nose. It should have an extension on to the forehead and is fixed by tapes round the head. In some cases where there is a tendency for the whole bridge to collapse a stout silk mattress suture is passed

cavities The cribriform plate and dura may give way, in which case direct contact is established with the subdural space in the region of the gyrus rectus of the frontal lobe The septum is buckled



FIG 158 Saddle nose resulting from head on blow



FIG 159 Nasal deviation due to lateral injury

or fractured and the mucous membrane stripped from the underlying bone and cartilage so that a submucous hematoma may result

Lateral injuries involve the nasal bones and septum The main deformity is a deviation of the bridge, the fragmented bone on the




FIG 160 Rubber covered Walsham's forceps used in disimpacting nasal bones
Asches septal forceps for manipulation of septal deformities

side of impact being driven under the opposite side, which may itself be fractured The septum is deviated from the side of injury and is buckled or broken

Treatment Nasal fractures should be reduced at the earliest opportunity If there is early gross oedema it is justifiable to encourage its absorption by the use of alternate hot and cold packs



FIG. 161 Separation of the zygoma without much displacement. Note the separation at the centre of the lower orbital margin and at the articulation with the frontal. The separation at the arch is not well shown in this film.

through the nose and tied over small wool rolls. This provides a satisfactory and stable splint.

Anæsthesia The nose should be packed half an hour before operation with 10 per cent cocaine and 0.1 per cent adrenaline. All but minor reductions should be done under endotracheal anæsthesia to obviate the risk of inhaled blood. Bleeding can be profuse in these operations.

Malar Fractures

(A) **Malar Zygomatic Fractures** The simplest fracture in this region is a depressed fracture of the zygomatic arch. Minor displacements may cause little or no functional or cosmetic disability,




FIG. 164. Diagram showing the sites of fracture of the maxilla and the method of levering out a depressed fracture of the zygoma. A Zygoma. B Fractures involving the antrum. C Line of separation of the alveolar margin. D Direction of leverage.

but in more extensive injuries the fragments impinge upon the underlying temporal muscle insertion and cause persistent trismus.

Force applied to the body of the malar may cause separation at the malar-maxillary, fronto-malar and zygomatic suture lines (see Fig. 165). The bone is depressed and rotated inwards, and flattening of the cheek results. Examination should be made from above and behind the patient so that contours can accurately be compared. Palpation reveals a step deformity in the infra-orbital ridge and separation at the fronto-malar suture. There may be a palpable separation in the zygomatic process but this is usually "sprung," the malar rotating inwards about this point. Swelling of the cheek and lids and subconjunctival ecchymosis are associated with this fracture, and œdema may be so great as to mask the underlying bony injury. An occipito-mental X-ray will reveal the displacement.



FIG. 163 Separation of the zygoma without much displacement. Note the separation at the centre of the lower orbital margin and at the articulation with the frontal. The separation at the arch is not well shown in this film.

Treatment Malar zygomatic fractures are best reduced by a temporal approach. A small incision is made inside the temporal hair line, and dissection carried through to the temporal fascia. The fascia is incised reaching the muscle fibres. A strong elevator is passed down between the muscle and fascia and is guided to the deep surface of the malar. Leverage is applied and the fracture reduces with a click. Re-displacement does not frequently occur. The temporal scalp wound is closed with a few sutures. Further trauma during the period of consolidation must be avoided.

(B) **Malar Maxillary Fractures** A severe lateral blow on the face may drive the malar bone into the antrum, comminuting the anterior wall and the floor of the orbit (see Fig. 165). The loss of orbital support results in depression of the eye and diplopia. There is marked flattening of the cheek, mottling over the distribution of the infraorbital nerve and the antrum fills with blood. There may be a related fracture of the alveolar process or the tuberosity of the maxilla. Early accurate reduction is necessary if serious functional disorders are to be avoided.

Treatment An incision is made in the upper buccal sulcus and the soft tissues reflected from the intral wall. A fracture line is usually apparent and through this the antrum is approached. Blood and clot are gently washed out and an elevator or the finger introduced to restore the main fragments. A wide bore rubber tube is placed with its upper end in the antero-lateral angle of the antrum and a length of ribbon gauze soaked in pirallin flavo or Whitehead's varnish is carefully picked in round the tube until the pupil level is slightly over corrected and the malar is restored to its normal position. Final adjustments to the malar can be done through the tube with a narrow elevator.

The tube and packing are left in for ten to fourteen days following removal, intral washouts are given duly until the wound closes. Strict attention to oral hygiene is necessary.

Maxillary Fractures

These are essentially central facial fractures and are produced by direct violence from in front. There are two main types: firstly, the horizontal supra-alveolar fractures, including Guerin's fracture, and secondly, the fractures of the body of the maxilla. In Guerin's fracture the upper alveolus and hard palate are separated from the superstructure, and either impacted backwards into the antra or remain loose ("floating maxilla"). Other alveolar fractures consist of separation of portions of the tooth-bearing ridge, and these may or may not be associated with malar maxillary displacements.

Fractures of the body of the maxilla are usually bilateral, and

the whole maxillary complex is driven down and back, impacting between the malar bones on either side. The posterior attachments to the pterygoid processes of the sphenoids are comminuted and impacted and the displaced bony mass is often firmly wedged in between the malar bones and the skull base. Nasal fractures frequently co exist -

Any combination of these injuries, together with malar zygomatic fractures, may be found, but in making the diagnosis consideration




FIG 165 Composite diagram of nasal and maxillary fracture lines. Any combination of these fractures may be found

of the three primary regions will afford material aid in sorting out the puzzle

Clinical Picture The degree of shock is variable but seldom severe. The possibility of skull vault and base fractures as well as cervical spine injuries should be remembered. There is very marked facial swelling and tense oedema of the eyelids. Irregularities in nasal and cheek contours are palpable if not visible, and there may be epistaxis and cerebro spinal rhinorrhoea. The nasal airway is impeded, and blockage may be complete. Loss of orbital support causes depression of the eye and diplopia. If the fracture lines pass

through the infra orbital foramina there will be an anesthesia over the area supplied by the infra orbital nerve. Dental occlusion is abnormal, the usual deformity being an "open bite" as the depressed upper molars impinge on their fellows in the lower jaw preventing closure of the anterior teeth.

Treatment In all fractures affecting alignment of teeth competent dental aid should be sought.

(A) Disimpaction of the maxilla is effected by inserting one blade of a Walsham forceps into the nose and the other into the mouth and gently rocking the whole mass forward. This manoeuvre



FIG 166 Typical appearance due to edema associated with maxillary fractures



FIG 167 Illustrating a convenient method of suspending a maxillary fracture to the skull. The wires fixed to the head cap by rubber bands to produce gradual elevation are attached to hooks soldered to the metal dental cap splints.

can also be made by grasping the alveolus in bone holding forceps. Splintage should make use of the most convenient fixed bony point which is the skull. Metal cap splints are made to fit the teeth and a stainless steel wire passed from a hook on each side of the splint, up through the buccal sulcus and soft tissues of the cheek, to emerge below the malar prominence. These wires are then attached to metal projections set into a plaster headcap. If metal cap splints are not available, dental arch wires should be wired to the teeth, and the jaws closed by wire or rubber band inter maxillary fixation. The cheek wires are fixed to the lugs on the lower arch wire in the pre molar region, and so fixation to the skull is obtained. The associated fractures of the nasal and malar regions should then be

reduced and splinted. The fixation of the maxilla provides a stable platform on which these secondary reductions can be based.

(B) Alveolar Fractures. The treatment of these fractures is primarily a dental problem. In cases where the fragment impacts into the antra, surgical reduction may be necessary, and this is done as described under fractures of the body of the maxilla.

Dental treatment will consist in wiring the jaws together with fine stainless steel wire, 0.35 mm, or brass wire, 0.5 mm. If laboratory methods are available, cast metal cup splints can be made to fit the teeth, and the two jaws are drawn into occlusion by fastening the splints together with rubber bands. When the correct bite is obtained, the splints are locked together by a metal key and the




FIG. 168. Dental arch wires wired to the teeth of either jaw provide a series of hooks which can be used for inter maxillary rubber band fixation or inter maxillary wiring.

rubber bands removed. If the fragment is very mobile the jaws should be fixed to a plaster skull cap as described above.

2 FRACTURES OF THE MANDIBLE

Anatomical Features. The mandible consists of a horizontal horse shoe shaped body and two vertical rami. At the junction of the body and the ramus is the angle. The ramus has two processes, the condylar which articulates with the temporal bone, and the coronoid, into which is inserted the powerful temporalis muscle.

The alveolar process of the body is the tooth bearing region and absorbs after extraction of the teeth. This fact accounts in the diminution in size and strength of the bone when it becomes edentulous. The mandibular canal passes through the substance of the bone, carrying the inferior dental vessels and nerve.

Fracture Sites in the Mandible. For the purposes of description,

fractures of the mandible can be divided into the following regions

- 1 Condylar process
- 2 Ramus
- 3 Angles
- 4 Body
- 5 Alveolus

Fractures of the Condylar Process

These are either transverse or oblique and may be bilateral. They are due to force transmitted through the bone from blows on



FIG. 169 Fracture of the condylar process of the mandible

the chin, and may or may not involve a dislocation of the temporomandibular joint. Diagnosis is made by palpation of the head of the condyle which fails to move as the jaw opens, and there is pain and tenderness in the preauricular region. Postero-anterior and 30° lateral X rays will demonstrate the fracture. In the oblique and bilateral fractures the "bite" is disturbed. In the former the jaw moves over to the injured side and may prop open on the molar teeth. In the latter shortening occurs in both ramus and results in a true "open bite"—a serious deformity.

Treatment Where there is no derangement of the bite no special

treatment is required except rest and a soft diet for a week or ten days. In cases where there is displacement of the jaw and an open bite the teeth should be wired or splinted together in normal occlusion for a fortnight, and a careful watch kept thereafter to ensure that displacement does not recur. External methods of fixation such as the chin sling or barrel bandage are without value in treatment except for first aid purposes.

Fractures of the Ramus

These are caused by direct blows on the cheek and often result in some comminution. There is little tendency to displacement owing to the splinting effect of the masseter and internal pterygoid



FIG 170 Fracture in the region of the angle of the mandible

muscles. Treatment is as for condylar fractures, and splintage is necessary only if there is displacement.

Fractures of the Angle

Caused usually by direct blows, they are sometimes secondary to violence applied to the chin or the opposite side of the mandible and are then associated with fractures elsewhere. In these fractures it is necessary to consider the displacement of both fragments in order that alignment of both can be restored. The common displacement of the posterior fragment is upwards and inwards. This is due to the pull of the temporalis and internal pterygoid muscles, the adducted position being due to greater power of the internal pterygoid as compared with the masseter.

Treatment Minor degrees of displacement of the posterior fragment can be ignored. If the anterior fragment is immobilised in correct occlusion, union will take place and result in satisfactory function.

More marked displacements of the posterior fragment demand reduction and splintage. In these cases both fragments should be accurately reduced and immobilised until union is sound.

The anterior fragment, which consists of the body and opposite ramus, is reduced into normal occlusion and maintained by metal cap splints designed to fit the teeth of each jaw. These splints are wired together or are locked by a metal key. Adequate splintage may be obtained by wiring a dental arch wire to the teeth in each jaw and subsequently wiring the arches together. Strong rubber bands can be used instead of wires for the intermaxillary fixation.

A small incision is made over the angle on the side of the fracture, and blunt dissection carried down to the bone. A metal guard is passed round the posterior border of the angle to its lingual aspect, and a hole drilled through on to this guard. A length of 0.35 mm soft stainless steel wire is passed through the hole in the bone and both ends brought out through the incision. The incision is closed round the wires.

A plaster headcap is fitted carrying a rigid metal bar which extends to a point one inch below and slightly behind the normal position of the angle on the side of the fracture. A hole is drilled through the free end of the bar.

The posterior fragment is reduced by depressing it with a finger inside the mouth, and the angle wire is threaded through the hole in the metal bar and twisted so that it is firmly anchored. This will hold the fragment in position. Care should be taken that over-reduction does not occur, as this favours non-union by creating a gap at the fracture site.

Fixation should be maintained for three to four weeks, at which time union is to be expected. A more elaborate method for splinting this fracture is by the use of modified Roger Anderson pins. These pins are drilled into the ramus and are connected by a locking device to a metal bar which is fixed to the cap splints on the anterior fragment. This method needs specialised technique and equipment.

Fractures of the Body of the Mandible

These are usually the result of direct violence, and may occur at any site. They may be bilateral or may be associated with condylar or angle fractures. Displacement will depend upon the amount of violence and upon the fracture site. Many of these fractures are

linear and do not tend to displace at all, splintage being provided by the adjacent soft tissues

Teeth in the Fracture Line Where there are sufficient teeth on both fragments for the purposes of fixation, teeth in the fracture line should be removed. Extraction may be delayed if the added trauma will complicate the fracture or result in further loss of bone. Teeth left in the line of fracture should be carefully watched and removed at the first sign of sepsis.

Treatment Reduction and splintage should be carried out as an immediate procedure. Splintage may be by metal cap splints, dental arch wire or eyelet wiring. In all cases dental co operation



FIG 171 Fracture of the body of the mandible with displacement

should be sought. Only in the undisplaced linear fractures is the barrel bandage or chin sling permissible.

Alveolar Fractures

Comminution of the alveolus is associated with fractures of the teeth. It results in a mass of crushed bone containing tooth roots with exposed pulps. Infection readily occurs, and the alveolar fragments and teeth should be removed as soon as possible.

The Edentulous Mandible

Fractures of the edentulous mandible present many problems in treatment. Minor degrees of displacements may not warrant fixation, as the deformity can be overcome by remodelling the denture. The simplest method of treatment is to wire the patient's

own denture on to the mandible by means of three steel wires passed round the body of the bone and twisted over the denture. If a denture is not available a metal or vulcanite trough should be made and filled with gutta percha. This lined trough is wired on in place of the denture. The modified Roger Anderson pin fixation method may be used in these cases.

Gunshot Wounds of the Face

The essential features of this type of injury are soft tissue disruption and bony loss or comminution. The key to the emergency surgery in these cases is conservatism. No tissue should be sacrificed unless its blood supply has been cut off. In the soft tissue lesion every effort should be made to accomplish complete wound toilette without doing a formal excision of the wound. Frayed edges and crushed or shredded tissue should be removed. This should be followed by accurate layer to layer suture and the provision of dependent drainage. In cases of tissue loss, complete epithelialisation should be obtained by the use of skin grafts or flaps, or by sewing skin to mucosa round the edges of full thickness cheek, lip or nose defects. This greatly facilitates subsequent plastic repair. In grossly comminuted fractures, as many bone fragments as possible should be saved. It is permissible to remove bone only if it is devoid of periosteal attachments. In all fractured mandibles compound to the exterior, dependent drainage should be provided. The problems of splintage in these cases demand considerable ingenuity, and accurate reduction of the main bony fragments should be the primary object of treatment.

REFERENCE

GILLIES, H. O., KILNER, F. P. and STONE, D. *Brit J Surg*, 1927, 14, 651

CHAPTER XVII

FRACTURES AND FRACTURE DISLOCATIONS OF THE SPINE

Surgical anatomy

Considered mechanically, the vertebral column must be regarded as consisting of two parts. First a supporting column of alternate layers of comparatively rigid material (the vertebral bodies) and more elastic layers (the intervertebral discs) thus combining strength and flexibility, which supports the second portion the protective part of the column, the neural arch. This functions as a sheath for the spinal cord and also carries the articular processes which cover the one weakness of the spinal column that of horizontal displacement, by interlocking with each other. Attached to the neural arch are the spinous processes which serve to limit extension by their bulk, and to limit flexion by the tension in the interspinous ligaments. Further strength is added by numerous short ligaments around the neural arches and the long anterior and posterior longitudinal ligaments attached to the vertebral bodies.

To add further elasticity to the column it possesses four curves

- | | | |
|------------------|-------------|--|
| 1 Dorsal curve | } Primary | Due to alteration in thickness of the vertebral bodies |
| 2 Sacral curve | | |
| 3 Cervical curve | } Secondary | Due to adaptation to the upright position |
| 4 Lumbar curve | | |

It is to be noted that it is the secondary adaptive curves which are most susceptible to injury and particularly at their junction with the primary curves.

Cervical spine The first and second vertebrae being of unusual structure, have fractures peculiar to themselves. The rest of the cervical spine is characterised by having curved cervical bodies which resist lateral force, and oblique articular facets which are not deep and so allow dislocation by overriding of one facet on another. The spinous processes are short and attached to the strong ligamentum nuchae.

Movements Flexion and extension of the head. At atlanto occipital junction.

Rotation of the head. At the atlanto axoid junction.

Both these movements are supplemented by small movements of the vertebrae on one another which summated allow considerable mobility. This is best seen in the movements of flexion and extension of the spine and of lateral bending.

Dorsal spine This portion of the column is much more fixed, chiefly by the attachment of the ribs but supplemented by the oblique nature of the articular facets which above look postero laterally and below antero medially. The oblique nature of the spinous processes also adds a bar to antero posterior displacement and generally increases the rigidity.

Lumbar spine Increased movement here, where the weight borne by the column is increasing, demands greater strength which is achieved by the increase in size of the vertebrae and greater ligamentous thickness. The thoraco dorsal junction is the region most commonly injured. The spinous

processes are short and strong, and the articular facets deep, and look radially, so that the facets of one vertebra clasp the facets of the vertebra above. These are increased in depth, which makes dislocation a rarity, as it requires great displacement.

The intervertebral discs consist of a fluid nucleus pulposus, surrounded by a fibrous ring (annulus fibrosus) which is attached by cartilage to the upper and lower surfaces of the vertebral body. This cartilage disc is not separated from the cancellous bone of the body by a layer of compact bone, but comes into intimate relationship with the circulation in the cancellous bone. By diffusion through the cartilage the avascular nucleus pulposus is nourished. The posterior longitudinal ligament is very rarely torn owing to its strength, and it depends mainly on this fact, together with the interlocking articular processes, that the spinal cord is rarely damaged, and reduction by hyperextension so safe and satisfactory.

The bony architecture of a vertebra shows it to consist of cancellous bone



FIG. 172. Lateral view of a lumbar vertebra showing the thinning of trabecular structure at the anterior margin of the vertebra.

covered by a layer of compact bone which is very thin. The compact bone is increased in strength posteriorly in the region of the pedicles and in the lamina. The cancellous bone of the body is weakest at the centre and the anterior margin of the body, which tends to allow easy compression of the body by the vertebra above, hinged on the articular facets behind.

Fractures of the spine lend themselves less to ordered treatment than fractures of the skull. It is impossible to discuss fractures and fracture dislocations separately, and so they will be handled together. Injury to the cord overshadows the bony injury, but the bony injury is nevertheless important, and much more so than in the skull. The discussion of the neurological phenomena in cases of fractured spine must be limited to a brief outline.

Ætiology

Direct injury. Owing to the protection of the spine by muscles, and its depth from the surface, little damage is usually done by direct injury to anything but the processes. A spinous or transverse

process may be broken off. Direct injury from projectiles can on the other hand produce the most severe injuries met with.

Indirect injury (1) **COMPRESSION** Produced by falls from a height on to the feet. It may be accompanied by calcaneal fracture. Diving into shallow water produces the same effect. Produces a wedging of the bodies rather than a fracture, and is commonly combined with flexion.

2 **FLEXION** May be produced in a variety of ways, *eg.*, a weight falling on to the bent back. It produces a compression of the vertebral body, which may result in a wedge-shaped deformity, or a fracture of the anterior upper lip of the body. If the force is continued there may be a dislocation, or gross comminution of a body.

3 **EXTENSION** Produced by the falling body landing with the small of the back across some raised object. This may produce extrusion of the nucleus pulposus anteriorly, or crushing injuries to the spines and laminae.

4 **LATERAL FLEXION** In the cervical region, if combined with some rotation, it may produce a dislocation. In the lumbar region it produces compression of one side of a vertebral body and scoliosis.

5 **ROTATION** This may be combined with lateral flexion or flexion and may be responsible for fractures of the articular processes, laminae and pedicles.

FIRST AID In fractures of the cervical spine hyper extension is to be aimed at as in other regions, and here the supine position with sandbags to check rotation is much better than the prone position, which is usually indiscriminately prescribed for fractured spines. In fractures elsewhere the prone position on the stretcher is best, not because it in itself is of much benefit to the patient, but in lifting the patient there is no danger of the acute spinal flexion which may occur in a supine case carelessly lifted by the feet and head. In gun shot wounds in which the vertebral bodies are destroyed, the patient should be carried supine. First aid classes need more instruction about the varieties of spinal injury.

FRACTURES AND DISLOCATIONS OF THE ATLAS AND AXIS

These rare lesions achieve an importance because of their danger to life from the risk of medullary compression by the dens. Cases which arise from trauma, and are suitable for treatment, are rare. Recently a series of cases from minor trauma, following inflammatory lesions in the vicinity of the tonsils and pharynx have been reported. In these it is supposed that from long standing vasodilation in the region from the chronic sepsis nearby, there is a decalcification of the atlas, which weakens the attachments of the transverse ligament, and

dislocation readily occurs from minor strains, such as moving the head roughly in the preparation for tonsillectomy. Such cases followed by serious results may be among the most distressing met with.



FIG. 173 The common fracture site in the atlas through the grooves for the vertebral artery



FIG. 174 The common fracture sites in the axis. A At the pedicle. B Through the lamina

Fractures ATLAS The two lateral masses are united by two comparatively weak arches. The junction of the posterior arch with these is still further weakened by the groove for the vertebral artery,



FIG. 175 The complete plaster applied for fracture of the upper cervical vertebrae. Absolute immobility is obtained by the grip on the chin the occiput and the frontal region

and fracture may occur here from hyper extension of the spine (Fig. 173)

AXIS In a similar way the axis may be fractured at the junction

of the pedicles and the body Fracture of the odontoid at its base allows the atlas to slip forward on the axis, producing medullary compression in the same way as rupture of the transverse ligament

DIAGNOSIS If the patient survives, the symptoms are similar to those of lesions of the cervical spine below this level Displacement of bony points and loss of movement should not be tested for owing to the attendant risks X-ray examination is made with all care, the lateral picture being taken in the ordinary manner, and the A P picture with the mouth open, and the central ray in line with the base of the occiput and upper incisors The patient will be found to hold the head in the hands, and be extremely reluctant to allow anyone else to do so Pain and stiffness are always present, and there may be symptoms of nerve pressure or paralysis of varying types

TREATMENT Immobilisation in plaster without anaesthesia, in the slightly hyper extended position, the plaster including the forehead and occiput and going down to the xiphisternum

Dislocations Rotary dislocation of the atlas on the axis is the most common lesion met with, but this is rare enough A subluxation of the atlanto epistrophic joint with spontaneous reposition may occur more frequently and pass undiagnosed The lesion illustrated (Fig 199) shows a lateral shift of the atlas on the axis, combined with some forward movement of the atlas, due to relaxation of the transverse ligament of the atlas following inflammation in the region

The more sudden dislocations usually produce sudden death

TREATMENT The maintenance of complete reduction in these cases is not always easy, though reduction by manipulation is simple Retention may be by light traction of 7 to 14 lbs depending on the weight of the patient, which can be conveniently applied by the Crile head tractor, a simple apparatus which obtains a firm but comfortable grip A plaster as described for fracture in this region is perhaps more satisfactory, as any possibility of gross redisplacement when moving is ruled out

FRACTURES, DISLOCATIONS, AND FRACTURE DISLOCATIONS OF THE CERVICAL SPINE

Fractures 1 Fractures of articular facets, and transverse processes

2 Fractures of the neural arch (Fig 174)

(a) At pedicle

(b) Behind articular facets

3 Compression fractures of vertebral body These are essentially similar to those in the lumbar spine and are not discussed separately (p 261)

4 Fracture of anterior margin of the body with fracture of the neural arch, articular facets or dislocation

5 Fissure fractures of the body, without compression

6 Fractures of the spinous processes (see p 259)

Dislocations 1 Unilateral Due to flexion plus some rotation, or violent lateral flexion. The articular process of the vertebra above slides over the facet below, and catches in the neural groove

2 Bilateral Due to severe flexion Both articular facets are displaced forwards into the neural grooves of the vertebra below

These are most common in the region of C 4, 5, and 6. The ligaments of the articulation and the intervertebral disc are always torn, and a chip fracture of the vertebral body below that dislocated is commonly associated with them (Fig 180)

Symptoms The minor fractures with no dislocation give a history




FIG 176 Unilateral dislocation of the cervical vertebra, viewed from behind. A Upper cervical vertebra rotating the head to the opposite side to the lesion. B Single upper articular facet visible from the posterior aspect



FIG 177 Lateral view of a bilateral fracture dislocation of the cervical spine




FIG 178 The same spine under traction as indicated by the arrows. A Ruptured intervertebral disc. B Torn inter spinous and interlaminar ligaments



FIG 179 The same case reduced. Compare with radiographs Fig 180

of injury associated with persistent stiff neck and the injury is only diagnosed by radiography

The more severe fractures gain their significance as a rule from the accompanying dislocation, which is responsible for the signs of pressure on the cord and which vary from complete paralysis to a transitory monoplegia. The cord is pressed between the neural arch of the vertebra above and the posterior aspect of the vertebral body below. A story of injury, followed by stiff neck, and possibly a wry

neck, is common to all cases, the more particular symptoms depending on whether the condition is unilateral or bilateral

UNILATERAL LESIONS The head is rotated away from the side of the lesion. If complete it is inclined to the side of the lesion, if incomplete, i.e., the articular facets are still riding on one another, the inclination is to the opposite side, but this is small, and in practice is obscured by the rotation. Pain is referred along a single



FIG 180 Fracture dislocation of the cervical vertebrae between C 5 and C 6. Note anterior margin of C 6 carried forward in evitable paraplegia and partial paralysis of the arms



FIG 181 Reduction under skeletal traction



FIG 182 Skeletal traction relaxed

nerve root. Displacement of spinous processes or transverse processes may be detected by palpation.

The chief problem in differential diagnosis is that of acute wry neck with which the patient may associate some minor injury. X rays will distinguish. In the radiograph a loss of the normal anterior convexity of the cervical spine must be sought for. This may even become concave.

BILATERAL LESIONS The head is pushed forward, and fixed in the midline, and there is a complete loss of rotation. Pain and paralysis from a spinal nerve lesion may be bilateral. The deformity of the depressed spinous process is more obvious, and cord symptoms are more likely.

FRACTURE DISLOCATIONS The fractures commonly associated

with dislocations are fractures of the spinous processes, fractures of the articular facets, and chip fractures of the type shown in Fig 183, and compression fractures of the vertebral body.

TREATMENT Reduction is soon as possible, either with no anaesthesia or local anaesthesia, or, as a last resort, with general anaesthesia. The necessity for anaesthesia depends to some extent on the method, and methods in which it is unnecessary are to be favoured, owing to the risk of manipulation in a touchless unconscious patient.

1 Manipulation by hand This is suitable for incomplete and complete unilateral lesions. With the head over the end of the table and held in the operator's hands, it is gently extended, then flexed to the opposite side to the lesion, and after further extension rotated to the side of the lesion, when the facets should ride over one another. This method is painful, and may require some local anaesthetic into the area of the dislocated facet (Fig 184).

2 Reduction by traction Slow reduction by traction over a period of hours or longer has been abandoned, but fairly rapid




FIG 183 Illustrating the mode of damage to the spinal cord in fracture dislocations of the cervical vertebrae. A Dens B Spinal cord C Chip fracture of the body of the sixth cervical vertebra with rupture of the nucleus pulposus D Cord ripped between the lamina of the vertebra above, and the body of the vertebra below E Torn ligamentum nuchae and interspinous ligaments (Compare Fig 180)



FIG 184 The manual method of reducing dislocation of the cervical vertebrae. Counter traction and steady force is applied by the hands on the shoulders.

reduction by traction has become the favoured method. It may be applied in a number of ways. In all cases a sloping bed is used and

the patient's weight used as counter-traction. Traction on the head may be made by a halter under the chin and occiput, or more



FIG 185 The technique of skeletal traction on the skull. The metal hooks penetrate the outer table of the skull only.

recently small trephine holes have been made in the outer table of the skull under local anaesthesia and an adjustable metal tractor caught under the outer table, and pull made from here. In either case the sling is attached to weights passing over a pulley, at the head of the bed. These are steadily increased, if necessary, up to about 40 lbs. The neck can be under radiological control, and it will be seen to slowly relax (Fig 180) till the facets disengage and slide over one another. This can be appreciated by the fingers if they are kept on the transverse processes of the vertebrae involved. Where the pulley and weights are not available the sling can be

attached to a belt around the waist of the surgeon, who holds the head in his hands and, by leaning back, produces an increasing amount of extension, and can, if necessary, manipulate the neck.




FIG 186 Illustrating the method of obtaining traction on the neck by a head halter attached to a belt around the surgeon's waist. Both hands are left free for manipulation and control.

(Fig 186) Another method of obtaining a graduated pull is by a pulley block and a spring balance. Reduction can be carried out under local anaesthesia as the time taken varies from two to fifteen minutes, rarely longer. If necessary gas with a little ether can be



FIG 187 Anteroposterior film showing unilateral dislocation on the left side of the articulation between the seventh and first cervical vertebrae



FIG 188 Forward dislocation of the seventh cervical vertebra on the first dorsal. Note the apparently excessively large foramen for the nerve due to the riding up of the articular process. The accompanying fracture of the spinous process of C 6 is not clearly shown



FIG 189 Compression fracture of a dorsal vertebra (D 7) showing the wedging of the vertebra



FIG 190 Film showing an accessory center for the anterior margin of the fifth lumbar vertebra. Sometimes mistaken for a fracture



given, or pentothal sodium used, but this increases the need for care and accurate radiological control

Retention After satisfactory control X rays, a plaster jacket




FIG 191 Diagrammatic representation of the method of applying a plaster in fractures of the cervical spine. The patient's head hangs over a thin wooden lath (A) attached to the table and is supported in the hands of a seated assistant

The head in hyper extension is applied, which extends from the sternum to the occiput and chin, which are held much on



FIG 192 Plaster jacket with cervical extension for fractures of the lower cervical region

the same plane. The method of application is shown in Fig 191. The patient is laid flat on an ordinary wooden table to which a thin wooden lath has been nailed, so that his head hangs extended over

the end of the lath and supported by an assistant. With his hands placed on the sides of the table a plaster jacket can be applied to the neck and upper part of the thorax. When this has set the patient may be slipped upwards off the lath, which being padded slides out readily, and the rest of the jacket completed.

Recurrence of displacement after reduction of a dislocation should raise, first, the question whether reduction was complete, and, second, the suspicion that an articular process may be fractured, thus allowing recurrence. Such cases should be treated by continuous skeletal traction, while lying on a modified plaster bed, including the thorax and neck.

FRACTURES OF THE DORSAL SPINE

This region is so protected and supported by the ribs that the only fracture commonly met with is a compression fracture of the vertebral body. This remark of course excepts the last two thoracic vertebrae which with the upper lumbar vertebrae are the vertebrae most commonly injured. It is perhaps owing to the support of the ribs that compression fractures of this region are often unrecognized on first appearance. A small kyphos may pass unnoticed and it takes a few days in the upright position before the vertebral body is further collapsed by the weight of the body. This difficulty is also noted in the lumbar region. It is highly probable that all cases of Kummel's disease are overlooked cases of compression fracture, and not due to any post-traumatic vascular pathology in an unfractured vertebra.

That the early symptoms may be very slight is vouched for by the statement of one authority that 70 per cent. of fractures of the spine are not diagnosed at the first examination.

The symptomatology, diagnosis and treatment will be discussed under fractures of the lumbar spine, which it closely resembles. It must be mentioned that the same features which render injury to the dorsal spine so uncommon also render its reduction difficult. It is impossible to get the leverage on the thoracic spine that one can get on the lumbar, and so it is difficult to reduce a compression fracture so satisfactorily. Complete reduction is, on the other hand, not so important. This is vouched for



FIG 193 Method of forcible reduction of compression fractures of the upper dorsal spine by hyper extension over the edge of the table

by the number of cases in which a sound functional result is seen in association with moderate wedging of several vertebrae, or marked wedging of one vertebral body. The difficulty in reduction combined with the wish to relieve the patient of a long stay in a plaster jacket, has encouraged the more casual treatment of these injuries, and this has not been followed by any rise in post traumatic disability. It is therefore better to treat moderately severe injuries of the thoracic spine by a period of bed rest, followed by bed exercises, and to allow the patient to get up when pain free. In fractures of the lower dorsal spine (T9-T12), the case is judged on its merits. A plaster jacket may be omitted in minor cases, but where there is much deformity, reduction and plaster are necessary.

If reduction is to be attempted, hyperextension of the spine over the edge of a table is much more likely to be effective than the sling recommended for lumbar fractures (Fig 193). If an anesthetic is needed to relieve pain, the application of the jacket is postponed till the patient has recovered, as the comatose patient is difficult to handle except by the longitudinal sling method, in which the patient is lying prone in a long towelling or canvas sling.

The most interesting complication of fractures of the dorsal spine is fracture of the body of the sternum, and the occurrence of such a fracture and, particularly, if it does not reduce itself spontaneously, should at once direct attention to the vertebral column (Fig 222).

FRACTURES OF THE LUMBAR SPINE

The first lumbar vertebra lies at the junction of the more rigid dorsal spine with the flexible lumbar spine, to the lower end of which is attached the long lever of pelvis and legs. It is for this reason the most frequently injured vertebra, and the incidence of injury to the other vertebrae falls off as one gets away from L1. Seventy per cent of fractures occur in the region T10 to L1. Fifty per cent of all fractures of the spine are compression fractures.

Mechanism See earlier discussion on page 248

Types of fracture 1 Fractures of the spinous processes and




Fig 194 Flexion fracture of the lumbar spine showing the fracture of the spinous process which may replace ligamentous rupture. (Compare Fig 193)

laminae (a) Alone, (b), in association with compression fractures of the body

2 Fractures of the transverse processes

3 Compression fractures of the vertebral bodies

(a) Fissure



FIG. 195 Fracture of the spine with rupture of the spinous processes; separation of a wedge from the vertebral body (Compare Fig 194)

(b) Compression In A P plane, kyphosis (Fig 202)
In lateral plane, scoliosis

(c) Comminuted fractures

4 Fracture dislocations of the vertebra

(a) Antero-posterior

(b) Lateral

5 Rupture and herniation of the nucleus pulposus

Fractures of the spinous processes and laminae For convenience fractures of the spinous processes of the lumbar and cervical spine will be discussed together They are uncommon and may be due to direct violence, *e.g.*, falling on the back across a beam, or more commonly due to the pull of attached ligaments In the cervical region the slender spines tend to fracture just below their terminal expansions, to which powerful muscles are attached In the lumbar region in flexion fractures of the spine the separation of



Fig. 195a Anteroposterior view of a flexion fracture of a spinous process and lamina and transverse process of a vertebral body Compare Fig. 197

the neural arches may not occur through a ligamentous area, but by splitting of a spinous process, the interspinous ligaments remaining attached to its upper and lower half (Fig. 194) Owing to the increased length of the process in the upper dorsal and cervical region it is most common here

The sixth cervical to the third thoracic spine are susceptible to fracture in workmen digging The history given is usually that the clod of earth being thrown off the shovel sticks to it, and the patient feels a sudden stab of pain in the back, accompanying the unexpected jar Its occupational associations has earned for this lesion the title of "shoveller's fracture"

SYMPTOMS Local pain, bruising, tenderness and muscle spasm in the region. Some depression of the spinous process may be palpated, or it may be discovered to be movable. Where the laminae are fractured and depressed there may be pressure on the cord, which will demand relief by open operation.




FIG 196 Schanz collar for the immobilisation of the cervical spine in cases of minor injury

TREATMENT Owing to the multitude of ligamentous attachments the displacement is usually small, the only necessity being the relief of pain, which may be obtained by confining the patient in bed, or more efficiently by infiltration of the area with novocaine. Three alternative lines of treatment present themselves in the cervical region.

(a) Massage exercises, and further infiltration with novocaine, with a Schanz collar for support.

(b) A light plaster jacket with cervical support.

(c) Excision of the tips of the fractured spinous processes.

In minor cases with one spinous process only involved the first procedure is satisfactory. Union is usually satisfactorily achieved in spite of the movement. Very rarely pain persists, and non union establishes itself, when the fractured tip of the process must be excised. If other lesions are associated with the condition, then the light plaster cast is needed. Where there are multiple fractures with two or more spinous processes involved, there is a tendency for non union to occur, probably due to the excessive mobility permitted, pain is apt to be troublesome and persistent. These cases, of which "clay shovellers" fracture is an example should have excision of the fractured fragments as soon as possible.

Fractures of the laminae tend to be bilateral, leaving the spinous process attached to the loose centre fragment. If depressed, which is uncommon and cord symptoms are present the need for operation is obvious. If not depressed they are often missed, till persistent pain, and the greater ease with which the fracture is seen in the radiograph after a short period has elapsed, enable a diagnosis to be made. In such cases the spinous process only should be excised.

Fracture of the transverse process The majority of these occur



FIG 198 Fracture of the transverse process of the first and second lumbar vertebrae



FIG 199A Anterior view of a dislocation of the axis from the atlas, due to relaxation of the transverse ligament of the atlas. The Δ ray of this case is shown in Fig 199



FIG 199B Posterior view of same case



FIG 199 Anteroposterior film of the first and second cervical vertebrae taken through the open mouth showing dislocation of the second cervical vertebra. (See also Fig 199A and B)

in the lumbar region due to direct violence, or more rarely to muscular violence from the pull of the psoas. The processes most frequently damaged are those of L2, 3, and 4, either singly or together.

SYMPTOMS Local pain, tenderness and limitation of movements of the spine due to muscle spasm are seen. The pain may be widely distributed or resemble lumbago of the localised type. Raising the leg from the bed on the affected side, or passive hyper extension may produce pain due to pull on the iliopsoas. A retroperitoneal hematoma or associated renal damage must be watched for in severe cases (Fig. 198).

DIAGNOSIS This depends on the X ray, but confusion with the features of recent fracture may arise from—
 1. An ununited centre for the transverse process. This is usually bilateral, is most common in L1, and shows a layer of cortical bone over the surfaces supposed to be the fracture line (Fig. 172).
 2. Similarly an atrophic rib attached to L1 may be mistaken.
 3. The line of the psoas shadow may be confusing.
 4. Rarely a calcified gland occupies a position opposite the end of a transverse process.



FIG. 197 Ununited accessory centre for the transverse process of the first lumbar vertebra resembling fracture

TREATMENT Owing to the fact that pain may persist for some time after this injury it is not to be treated lightly. Rest in bed to commence with is indicated, and, after improvement, judicious exercises and radiant heat are given.

PROGNOSIS This is good, but a few cases develop chronic back strain which shows up after the injury is apparently healed. In some cases this is psychotic in origin, and no man with fracture of a transverse process should be told he has a fractured spine.

Compression Fractures of the Lumbar Vertebrae

These may be divided into two groups of cases

Group 1 In which the interspinous ligaments and intervertebral ligaments are intact. This limits the displacement, and wedging of a vertebral body is usually all that occurs, sometimes there is a fissure, or a chip off the body below, or the wedging may extend over several vertebrae. The intervertebral discs remain intact. Cord symptoms and nerve root symptoms do not occur. This is the most common lesion (Fig. 200).




FIG 200 Compression fracture of a vertebral body without rupture of ligaments A Slightly wedged vertebra




FIG 201 Fracture of the upper anterior margin of a vertebra. Usually some wedging of one or other vertebra accompanies this lesion A Bony chip B Nucleus pulposus herniating through the fissure and lying below the anterior longitudinal ligament

Group 2 Where the interspinous and interlaminae ligaments are torn a much greater displacement can occur, and strain is thrown on the anterior and posterior longitudinal ligaments. The posterior ligament being very strong remains intact in all but shattering



FIG 202 Crush fracture of the twelfth dorsal and first lumbar vertebrae with marked kyphosis. No cord symptoms

lesions, and so helps to protect the cord. The tearing of one interspinous ligament usually allows the force to be expended on completely crushing the body of the vertebra below. Where there is definite fracture of the body the nucleus pulposus is ruptured and nuclear material is forced into the cancellous bone spaces. If the force carries the upper portion of the vertebral column still further forward there is danger of compression or even section of the cord which is caught between the lamina of the vertebra above and the posterior surface of the body below. It is only with injury of this type that dislocation may complicate the picture. The anterior longitudinal ligament being strong and at the centre of the angle of displacement is not torn and is a guarantee that in correction by hyperextension over displacement will not occur (fig 203).




FIG. 203. Fracture of the vertebral body with rupture of the interspinous ligaments showing the greater displacement allowed and the increased danger of cord damage. A. Herniating nucleus pulposus. B. Ruptured interspinous ligaments. C. Site for injection of local anesthetic.

SYMPTOMS. Pain in the back is the most prominent feature. Even in the absence of cord injury the patient may say he feels broken in two. A kyphosis may be obvious, but if the patient has been transported correctly it may not have occurred, or be partly reduced. In the severe displacements an irregularity in the level of the spinous processes may be palpated, or there may be a gap of unusual depth between them. The spine is fixed by muscle spasm. Nerve root pain of a unilateral type or "girdle" pain may be complained of, and all the degrees of cord injury to be discussed later may be associated with the lesion.

A history of suggestive injury plus local pain justifies an X ray. It is the lateral view which is most revealing. The antero-posterior film is often confusing, especially in the lower lumbar region where the vertebrae are on an angle.

Fracture dislocations. Most of the features of dislocation of both articular facets in the lumbar region have been discussed above, remains to mention a rare lateral fracture dislocation occurs with lateral flexion alone, or combined with a lateral the body when the pelvis is fixed. The upper articular side is broken which allows the vertebra above to slip this may be accompanied by a lateral compression the vertebra. This is best seen in the AP X ray,




FIG 200 Compression fracture of a vertebral body without rupture of ligaments A Slightly wedged vertebra




FIG 201 Fracture of the upper anterior margin of a vertebra. Usually some wedging of one or other vertebrae accompanies this lesion A Bony chip B Nucleus pulposus herniating through the fissure and lying below the anterior longitudinal ligament

Group 2 Where the interspinous and interlaminar ligament are torn a much greater displacement can occur, and strain is thrown on the anterior and posterior longitudinal ligaments. The posterior ligament being very strong remains intact in all but shattering



FIG 202 Crush fracture of the twelfth dorsal and first lumbar vertebrae with marked kyphosis. No cord symptoms

paralysis the treatment is as described later. If absent a plaster jacket can be applied.

Treatment of Compression Fractures

Fractures without displacement It is necessary to prevent compression by some form of spinal support, or in mild cases by a period of bed rest and graded activity (e.g., fractures of the dorsal spine). The most convenient is a plaster jacket applied by one of the various means described below. Poroplastic or other more expensive jackets may be used. They must be worn for a period of three to six months depending on the severity of the accident.

Fractures with displacement It is essential that the displacement be reduced for the satisfactory healing of the spine and the relief of pressure or tension on the cord if it is involved. The sooner the reduction is carried out the better, once the primary shock has




FIG. 200 One variety of hyper-extension frame as used to obtain gradual hyper-extension of the spine.

passed off. Local anæsthetic can be very useful, but it is amazing how many cases can be gently reduced under the influence of morphia and scopolamine, with no local anæsthesia at all. In at least 50 per cent. of cases any more anæsthesia than this is unnecessary. If any general anæsthesia is used pentothal followed by gas oxygen is satisfactory. Spinal anæsthesia has been used very successfully.

Reduction by all methods depends on the leverage exerted on the fracture site by hyper-extension of the spine. That hyper-extension can be carried out safely depends on the anterior longitudinal ligament being intact, and the interlocking of the articular processes. Where these are broken or dislocated there is much greater risk of displacement. Numerous methods for extending the spine have been developed and will be outlined.

1 *Slow reduction* on a hinged frame of the Bradford type. The kyphos is arranged to lie at the level of the hinge, and the extension increased daily. This is a slow method, which is not always satisfactory, and may be very uncomfortable. It keeps the patient on his back when other methods allow him about, and is very seldom




FIG 204 Dislocation of the lumbar vertebrae A Upper vertebra pushed forward B Lower facets riding on the laminae of the vertebra above C Upper facets of vertebra below visible at laminaectomy D Cord almost invariably damaged here

the upper surface of the lamina in front of them (Fig 204) It is obvious that to make them retrace their path the vertebrae must be separated for a distance equal to the depth of the articular facets, which in the lumbar region approximate to $\frac{1}{2}$ inch This is impossible to accomplish by traction and open operation must be resorted to Often the lesion is not recognised till control X rays are taken after attempted hyper-extension reduction These show a widening of the space between the vertebrae due to a hinging on the new articulation, together with a forward shift of the upper vertebra (Fig 205) The lesion is almost inevitably accompanied by cord damage of a serious type, and a compression fracture of the lower vertebra

OPERATIVE REDUCTION A curved incision is made over the kyphos, and the spines and laminae exposed The lesion is easily recognised by the uncovered glistening articular facets of the lower vertebra To allow reduction these must be cut away, and to approach them it is often necessary to remove the spinous process of the vertebra above Once cut away, reduction by elevation of the legs, as described later, is carried out In the presence of

and if there is little displacement may be overlooked in the lateral film A scoliosis together with many features mentioned above are found Treatment is very similar to the compression fractures, extension being combined with lateral pressure The risk of cord damage in reduction is nil, but there is a very grave risk at the time of the accident

Dislocation of both articular facets occurs in the lower dorsal and lumbar regions In these cases, following severe hyperflexion, the articular facets of the vertebra above ride up over the superior facets of the vertebra below, and come to rest on




FIG 205 Effect of extension on a lumbar dislocation A Upper vertebrae are still anterior to the vertebrae below B Increased intervertebral space larger than normal C Depression of the spinous processes still persists The dislocation is often not recognised till this picture is seen

in a downward direction, which is usually necessary to reduce fractures in this region, and the patient may require a gas anesthetic for this proceeding. As soon as the deformity is reduced to one's satisfaction the patient is slung in the manner described before except that the webbing is placed on a level with the lower thoracic vertebrae, and a plaster jacket applied (Fig. 193).

(c) The most satisfactory method of reducing the fracture and



FIG. 208. Hyperextension of the spine by a sling and pulley. This method is useful for reduction, but unless carefully used produces too great a dorsiflexion for the application of plaster.

of applying a jacket, is suspension with the patient in supine position. This is done by hanging the patient on a webbing strap stretched by a wide (28 inches) steel horse- can be elevated as desired by a block and tackle system off a hook in the ceiling. Alternatively, if a hydraulic operation available, fixed suspension, with the table fully elevated may and the table lowered to obtain hyperextension. The webbing is held by two hooks from which it can be readily detached on release. Between the patient and the webbing a pad of

used (Fig. 206) except in the presence of complications such as paralysis or abdominal distension.

2. *Rapid reduction by hyper-extension.* (a) By elevating the head and shoulders on one table while the body lies prone with the legs resting on a lower table which comes up to the level of the lower margin of the pubes and thus allows the lumbar spine to sag between them. After a little time has elapsed for muscular relaxation the deformity reduces itself and a plaster jacket is applied (Fig. 207).

(b) Leaving the legs strapped to the lower table a sling may be applied around the chest below the arms and this being attached by a pulley block to a hook high up in the wall tightening it still further hyper-extend the spine than method (a). After reduc-



FIG. 207. The two tables in bed of oblique corner and a traction of the lumbar spine and then allow the patient in a suitable position for the application of plaster. For a more complete reduction of the lumbar spine the pubes must be just free of the lower table and the patient must be given a pull on the legs.

tion it is wise to relax this a little as very full hyper-extension is painful for the patient and likely to produce pressure sores under the plaster or even paralysis (Fig. 208).

(c) By elevating the legs of a prone patient hyper-extension of the spine may be produced. This method is useful when accompanying operative procedures as the apparatus is out of the way. It produces only a moderate hyper-extension which is satisfactory for patients with a mild injury.

(d) By lying the patient supine and strapping the legs and feet firmly to the table so that the patient's upper thorax hangs over the end of the table some hyper-extension of the thoracic region may be produced. The edge of the table is placed at the level of the thoracic kyphosis. This position is very uncomfortable for the patient especially if it is accompanied by pressure on the shoulders.

tissue 15 inches by $4\frac{1}{2}$ inches is placed, and both are wrapped in cellophane. This is important as the cellophane prevents the



FIG 209 The padding in the suspensory method of applying a plaster jacket. Diagrammatic transverse section. A Skin B Layer of cellophane C Pad of gamgeo tissue $15 \times 4\frac{1}{2}$ inches D Webbing band E Plaster of jacket




FIG 210 Diagram of layers of material around spinal sling —

- A Layer of cellophane
- B Gauze pad
- C Sling

plaster from adhering to the webbing and so enables it to be pulled out from between the padding and the plaster once this has set (Fig 209)

The webbing and pad is arranged below the patient at a level



FIG 211 The method of application of a plaster jacket by the sling in the supine position. Note the pad between the sling and the patient and over the anterior superior iliac spine. The amount of extension is adjusted by blocks under the feet and the head

corresponding to that of the fractured vertebra. The patient is then gradually elevated by hoisting on the block and tackle. After a few minutes the muscles of the spine relax and the patient sinks over the webbing thus reducing the deformity and hyperextending the spine. The pain is controlled in all but severe fractures by morphine and scopolamine. In the more severe cases gas and oxygen is necessary, but where anesthesia is used the patient must not be raised so high from the table to avoid



Fig. 212 The plaster applied. The sling is left in position till the plaster sets and then can be easily withdrawn and the gaps plastered over.

over extension of the spine which is apt to occur if all muscle tone is lost.

A plaster jacket is applied in this position, as described in Chapter XIII, allowing the webbing to protrude through gaps in either side. When the plaster has set it is withdrawn through these, the gauze pad trimmed, and the gaps closed with a plaster bandage. The plaster is trimmed and a window made anteriorly over the stomach. Occasionally a window posteriorly over the spinous processes at the height of the lumbar curve may be needed to relieve pressure on the tips of the spinous processes of very thin or elderly

tissue 15 inches by $4\frac{1}{2}$ inches is placed, and both are wrapped in cellophane. This is important as the cellophane prevents the



FIG 209 The padding in the suspensory method of applying a plaster jacket. Diagrammatic transverse section. A. Skin B. Layer of cellophane C. Pad of gamgee tissue 15 x $4\frac{1}{2}$ inches D. Webbing band E. Plaster of jacket




FIG 210 Diagram of layers of material around spinal sling —

- A Layer of cellophane
- B Gauze pad
- C Sling

plaster from adhering to the webbing and so enables it to be pulled out from between the padding and the plaster once this has set (Fig 209)

The webbing and pad is arranged below the patient at a level



FIG 211 The method of application of a plaster jacket by the sling in the supine position. Note the pad between the sling and the patient and over the anterior superior iliac spine. The amount of extension is adjusted by blocks under the feet and the head

patients. The pad is left *in situ* under the posterior opening and prevents pressure on the edges of the plaster.

AFTER-TREATMENT After the application of such a jacket the patient is very uncomfortable till he adapts himself to the new position, and requires morphia for the first twenty-four hours. Vomiting during this period is not uncommon, and should occasion no alarm unless it continues. Paralytic ileus of a subacute type may follow a plaster applied too tightly and in too great hyperextension. This is rare, but is indicated by deterioration in the patient's condition, pain, distension and continuation of the vomiting. It necessitates removal of the plaster.

The patient should have the cast dried by being placed under a heat cradle for the first night. The back of the cast is dried first while the patient is awake and can be in the prone position. Careful

balancing of the cast is necessary for the first days, and an inexperienced nurse should be carefully instructed where pillows are to go, if the patient is to be protected from discomfort, and the plaster to remain undeformed. On the following day he is, as a rule, more comfortable sitting up or trying to walk, and when he commences this it will as a rule be found necessary to trim the plaster further as the patient settles into it. A control X-ray should be taken through the plaster to check the reduction. If unsatisfactory the patient is allowed to adapt himself to the amount of hyperextension obtained for a few days and is then replastered in greater hyperextension.

As soon as convenient exercises are commenced which are designed to use all the muscles of the body, and particularly the extensors of the spine. Those illustrated in Böhlke's book are rather heroic, but it is remarkable what a patient can do. These are continued throughout the period of immobilisation which varies according to the severity of the fracture from three to six months.

FIG. 211. The finished jacket.

A renewal of the plaster is usually necessary at the end of the second month and the opportunity is taken for a control X-ray without



(f) *Protrusion of a nucleus pulposus*—This may be either lateral, with features of nerve root irritation (e.g. sciatica, brachial neuritis), or central, with features of cord compression in the cervical region or bilateral nerve root involvement in the lumbar region.

4. **PARTIAL AND COMPLETE TRANSECTION OF THE CORD**—There is haemorrhage around the ends of the cord, which later become rounded off and attached to the dura. Small cystic cavities may develop containing degenerated blood.

Neurological features of cord injuries—It is only proposed here to give a brief outline of the main features of cord lesions.

INCOMPLETE TRANSECTION OF THE CORD—1. **Stage of spinal shock**—There is a flaccid paralysis with loss of all reflex activity,



FIG. 214. Patient with fracture of the lumbar spine and cord symptoms treated on a double Braun's splint with skeletal traction through both iliac tubercles.

except perhaps a flexor plantar response, and loss of all sensation. This stage is not so complete as in total section of the cord, and tends to pass off rather usually four to five days' sensibility recovering first.

2. **Stage of returning reflex activity**—(a) Tone returns to smooth muscle first, with improved bladder function and improved vasomotor condition of the skin.

(b) Tone returns to voluntary muscle, but the extensor muscles have the maximum tone, producing 'paralysis in extension'. This is due to the dominance of the extra-pyramidal tracts, especially the vestibulo-spinal.

(c) Involuntary movements are infrequent.

(d) Reflex movements—Extensor thrust reflex may be elicited,

vomiting There may be passage of flatus, and audible borborygmi, but in severe cases there is absolute paralysis for a short period. With the treatment of the shock and rest the patient's condition generally improves, and intestinal function is restored again.

6 **Damage to nerve roots** This may occur by direct involvement in bony fragments (rare), or more commonly by the disc prolapse described above.

INJURIES TO THE SPINAL CORD ASSOCIATED WITH THE FRACTURES OF THE SPINE

It is in the fracture dislocations that sufficient movement of one vertebra on another is allowed to produce severe injury to the cord. Thus in the cases of fracture dislocation of the lumbar vertebrae, when the articular facets sit on the laminae of the vertebra below, the cord is inevitably damaged and frequently severely. Usually the cord is nipped between the laminae of the vertebra above and the posterior aspect of the body below. Cord injury may be produced in other ways as outlined below.

Types of cord injury 1 **STRETCHING** Severe extension or flexion may produce a very short-lived quadriplegia with rapid recovery, if it occurs in the neck. A paraplegia of similar type seldom occurs from injury in the lumbar region as the range of movement is more limited. Later there may be some paraesthesia or muscular weakness. The X ray will be negative in a few cases.

2 **SPINAL SHOCK OR CONCUSSION** This may follow bullet wounds in the region of the cord. The paraplegia lasts three days to three weeks and goes on to complete recovery. The symptoms of the above types of injury tend to be less complete than the succeeding two types.

3 **COMPRESSION** This may be due to a variety of causes.

(a) *Edema* Possibly the most frequent cause in cases which recover completely.

(b) *Pressure of a foreign body*

(c) *Depressed fragments of bone* Usually the spine and laminae. Demands relief by operation.

(d) *Hæmorrhage* The symptoms are masked at first by spinal shock.

1 *Extra medullary* Produces mild symptoms as a rule (Risk of ascending paralysis as the spinal theca fills with blood).

2 *Intramedullary (Hæmatomyelia)* Shows features of dissociated anaesthesia with some lower motor neurone paralysis over the affected segments.

(e) *Inflammation and later fibrosis, or pressure of an abscess*

(f) *Prolapse of a nucleus pulposus* This may be either lateral, with features of nerve root irritation, e.g. sciatica, brachial neuritis, or central, with features of cord compression in the cervical region, or bilateral nerve root involvement in the lumbar region

4. **PARTIAL AND COMPLETE TRANSECTION OF THE CORD** There is hemorrhage around the ends of the cord, which later become rounded off and attached to the dura. Small cystic cavities may develop containing degenerated blood.

Neurological features of cord injuries It is only proposed here to give a brief outline of the main features of cord lesions.

INCOMPLETE TRANSECTION OF THE CORD 1. Stage of spinal shock. There is a flaccid paralysis with loss of all reflex activity,



FIG. 214. Patient with fracture of the lumbar spine and cord symptoms treated on a double Braun's splint with skeletal traction through both tibial tuberosities.

except perhaps a flexor plantar response, and loss of all sensation. This stage is not so complete as in total section of the cord, and tends to pass off earlier, usually four to five days, sensibility recovering first.

2. Stage of returning reflex activity. (a) Tone returns to smooth muscle first, with improved bladder function and improved vasomotor condition of the skin.

(b) Tone returns to voluntary muscle, but the extensor muscles have the maximum tone, producing 'paralysis in extension'. This is due to the dominance of the extra-pyramidal tracts, especially the vestibulo-spinal.

(c) Involuntary movements are infrequent.

(d) Reflex movements. Extensor thrust reflex may be elicited,

or the crossed extensor reflex. The deep reflexes become easier to elicit, and the knee jerk shows a prolonged relaxation from increased extensor tone.

COMPLETE TRANSECTION OF THE CORD 1 Stage of spinal shock. Severe and lasts two to three weeks. The persistence of this stage over one week indicates that recovery is unlikely.

2 Stage of reflex activity (a) Tone returns first, as above, to smooth muscle.

(b) Tone returns to voluntary muscle, but the flexor muscles have the maximum tone, producing "paralysis in flexion." All muscles are much more hypotonic than in incomplete lesions.

(c) Involuntary movements and reflex activities are frequent.

(d) Reflex movements. The flexor reflex, which is a fractionated withdrawal reflex from nociceptive stimuli, returns, and with it various amounts of withdrawal. The mass reflex may be elicited by stimuli, and the coitus reflex. The deep reflexes return some weeks after the flexor reflexes.

3 Stage of failure of reflex activity. The threshold of stimuli required to produce reflex action is raised, retention sets in again, vasomotor control is lost, bed sores develop, and muscles waste grossly.

The development of a true Brown Sequard syndrome is a very rare occurrence with fractures, though it may occur atypically.

The care of cases with paralysis. Difficulties arise from (1) The maintenance of correction of the deformity (2) Retention of urine, and urinary infection (3) The presence of constipation or incontinence (4) The development of bed sores (5) The development of deformities from muscle imbalance.

The deformity is as easily corrected as in cases without paralysis, but the method of retention is difficult as any fixation is likely to produce bed sores. For this reason patients have been nursed on water beds, in plaster beds, and even in warmed oil. The most satisfactory method is a plaster shell, in which the pressure on the sacrum is relieved by having both legs supported on Braun's splints with traction on pins through the tibial tubercles (Fig. 214).

Retention of urine occurs most markedly with partial lesions, and it is important to avoid over distension in the first twenty four hours. Cases with a complete lesion have relaxed sphincters and dribble urine at intervals. It takes a little time for the automatic bladder to be developed, and during this time the patient must be regularly catheterised, or, better, have a catheter tied in and attached to a machine which automatically empties and washes the bladder at the same time (tidal drainage).

Others are in favour of an early suprapubic cystotomy with a

tight fitting tube. This can be attached to the tidal drainage machine and avoids metritis. If infection of any severity occurs, suprapubic cystotomy is necessary and in a complete lesion is most satisfactory done as early as possible. Medical methods of controlling urinary infection should of course be invoked.

Incontinence is more trouble than constipation as it tends to produce bed sores. Constipation is treated by a daily enema, and this is not always simple as the patient tends to retain it.

Bed sores are avoided by relieving the known pressure points by a well shaped plaster bed, skeletal traction on the legs and frequent turning of the patient. The skin is carefully hardened with spirit, and powdered. Hot water bottles are taboo. When developed the necrotic tissue may be removed by fomentations of 10 per cent aluminum acetate. The sore is then protected by elastoplast, which is only changed when dirty. If pressure is kept from the skin it usually heals under such treatment. When the patient is better, ultra-violet light, fresh air and sun, may be used to stimulate healing.

Deformities can only be prevented by adequate splinting. A patient nursed on Braun's splints with the feet held in the neutral position is having his flexion contractures of the hips and knees controlled, and the equinus deformity of the feet can be easily corrected. Should deformities develop in spite of this tenotomies are usually necessary for their correction, or neurectomies of the stronger muscle groups.

Lesions of the cauda equina. As the spinal cord ends at the level of the second L vertebra, injuries to the spine below this involve the cauda equina. Such lesions take the form of a peripheral nerve injury, with a root distribution. Thus there will be flaccid paralysis, with complete loss of reflexes, patchy loss of sensation, and sensory paralysis with incontinence of the rectum and bladder. Slow recovery of function is observed, as in peripheral nerve lesions elsewhere, but the patient is liable to the complications of a long standing partial lesion of the cord, and must be nursed as such. In a few cases where there is evidence of pressure of bone laminectomy and nerve suture has been carried out.

Compound injuries of the spine. The treatment of these lesions may be worked out from a consideration of the treatment of compound fractures in general, and of those of the head in particular. All damaged tissue is removed. The theca is preserved intact if possible. If it is impossible to close the wound owing to loss of tissue, it is packed with gauze as in other cases of gross tissue loss, and the patient nursed in a plaster bed. Occasionally it is possible to treat clean rifle bullet wounds expectantly, but generally speaking

the track should be opened up, cleaned and the edges excised. Drainage must be inserted if the hæmostasis is doubtful.

Operative treatment of cases with paralysis The symptoms of compression are the same as those of complete or partial transection of the cord. First the stage of spinal shock must be allowed to pass off, unless there is definite evidence of bone or a foreign body pressing on the cord which are the only indications for immediate laminectomy. Nor should operation be carried out in the stage of primary shock or in the presence of infection. Operation is rarely indicated and can serve only one purpose, the relief of pressure on the cord. In the absence of X-ray evidence of this the distinction between a lesion of the cord due to partial or complete section and one due to pressure is very difficult. A test of paramount importance to determine the presence of pressure on the cord is the Queckenstedt test. This consists of performing lumbar puncture below the level of the lesion, and measuring the pressure with a manometer. The jugular veins are now pressed upon, thus causing a rise in intracranial pressure. If there is no block in the spinal canal this will be fairly rapidly transmitted to the manometer. If there is a block, no change in pressure will occur, and the fluid withdrawn will be tinged yellow, and show a great rise in protein content (Froms syndrome). If the block is partial the rise in pressure will be gradual, and it will subside slowly. By this means a suspicion of pressure on the cord can be confirmed, and it is only in the presence of a positive Queckenstedt that operation is to be recommended. Factors in the clinical progress of the case which may suggest pressure are the development of paralysis after a stage of improvement in an incomplete case. If paralysis occurs later in a case it may be due to fibrosis, or to cystic change in hæmorrhage round the cord. These conditions offer some hope of relief. Operation is useless in complete cases and in incomplete cases which continue to improve.

We may sum up the indications for laminectomy as follows

- 1 Immediate Compound, wounds, foreign bodies and bone pressing on cord Dislocations
- 2 In incomplete cases only if improvement suddenly ceases
- 3 If paralysis occurs later in the case
- 4 For the relief of severe root pain
- 5 For suture of the anterior nerve roots in cruda equina lesions

PROGNOSIS In all cases of complete lesion it is very bad, as, if the patient does not die of the immediate lesion, he dies later from renal infection or pressure sores. In incomplete lesions which do not make a good recovery it is a little better, but it usually means that the onset of fatal complications is only delayed. In all cases

it must be borne in mind that a final prognosis can only be given after watching the patient for at least a month to allow the effects of spinal shock to wear off completely

REFERENCES

General

- DAVIS, A. G. 'Tensile Strength of the Anterior Longitudinal Ligament in the Relation to Treatment of 132 Crush Fractures of the Spine' *J Bone and Joint Surg*, 1938, 28, 429
- WATSON JONES 'The Results of Postural Reduction of Fractures of the Spine' *J Bone and Joint Surg*, 1938, 20, 567
- ROGERS W. A. 'Cord Injury during Reduction of Thoracic and Lumbar Vertebral Body Fracture and Dislocation' *J Bone and Joint Surg*, 1938, 20, 691
- JEFFERSON, G. 'Discussion on Spinal Injuries' *Proc Roy Soc Med*, 1927-28, 21, 625
- JORDEN, R. 'The Intervertebral Disc' *Surg Gynaec and Obstet*, 1935, 61, 591

Cervical Spine

- CRITCHFIELD 'The Treatment of Injuries of the Cervical Spine' *J Bone and Joint Surg*, 1938, 20, 705
- McKELLAR HALL. 'Clay Shoveller's Fracture' *J Bone and Joint Surg*, 1940, 22, 63
- JEFFERSON, G. 'Fracture of the Atlas Vertebra' *Brit J Surg*, 1920, 7, 407
- ROBERTS, S. M. 'Fracture and Dislocation of the Cervical Spine' *J Bone and Joint Surg*, 1937, 19, 199
- LANGWORTHY, M. 'Dislocations of the Cervical Vertebra' *J A M A*, 1930, 94, 86
- BARTON, L. G. 'The Reduction of Fracture Dislocations of the Cervical Spine by Skeletal Traction' *Surg Gynaec and Obstet*, 1938, 67, 94

Kummell's Disease

- KUMMELL. "Die Posttraumatische Wirbelerkrankung" *Arch f Klin Chir*, 1921, 118, 876 (Review of disease with full references)
- HOSFORD, J. P. "Kummell's Disease," *Lancet* 1930, 230, 249 (Short summary of modern views and further references)

Neurological Aspects

- PIDDOCH 'Injuries to the Spinal Cord' *Proc Roy Soc Med*, 1927, 28, 625
- NAFFZIGER H. C. "The Neurological Aspects of Injuries to the Spine" *J Bone and Joint Surg*, 1938, 20, 444
- DENNY BROWN and GRAEME ROBERTSON. 'The State of the Bladder and its Sphincters in Complete Transverse Lesions of the Spinal Cord and Cauda Equina,' *Brain*, 1933, 56, 149 and 397
- WATKINS K. "Bladder Function in Spinal Injury" *Brit J Surg*, 1935-36, 23, 734
- BARRINGTON, J. F. et al. 'The Treatment of the Paralyzed Bladder' Discussion, *Proc Roy Soc Med*, 1943, 36, 197
- BARNES, R. "Paraplegia in Cervical Spine Injuries" *Bone and Joint Surg*, 1948, 30b, 234-244

the track should be opened up, cleaned and the edges excised. Drainage must be inserted if the hæmostasis is doubtful.

Operative treatment of cases with paralysis The symptoms of compression are the same as those of complete or partial transection of the cord. First the stage of spinal shock must be allowed to pass off, unless there is definite evidence of bone or a foreign body pressing on the cord which are the only indications for immediate laminectomy. Nor should operation be carried out in the stage of primary shock or in the presence of infection. Operation is rarely indicated and can serve only one purpose, the relief of pressure on the cord. In the absence of X-ray evidence of this the distinction between a lesion of the cord due to partial or complete section and one due to pressure is very difficult. A test of paramount importance to determine the presence of pressure on the cord is the Queckenstedt test. This consists of performing lumbar puncture below the level of the lesion, and measuring the pressure with a manometer. The jugular veins are now pressed upon, thus causing a rise in intracranial pressure. If there is no block in the spinal canal this will be fairly rapidly transmitted to the manometer. If there is a block, no change in pressure will occur, and the fluid withdrawn will be tinged yellow, and show a great rise in protein content (Froms syndrome). If the block is partial the rise in pressure will be gradual, and it will subside slowly. By this means a suspicion of pressure on the cord can be confirmed, and it is only in the presence of a positive Queckenstedt that operation is to be recommended. Factors in the clinical progress of the case which may suggest pressure are the development of paralysis after a stage of improvement in an incomplete case. If paralysis occurs later in a case it may be due to fibrosis, or to cystic change in hæmorrhage round the cord. These conditions offer some hope of relief. Operation is useless in complete cases and in incomplete cases which continue to improve.

We may sum up the indications for laminectomy as follows

- 1 Immediate. Compound wounds, foreign bodies and bone pressing on cord. Dislocations
- 2 In incomplete cases only if improvement suddenly ceases
- 3 If paralysis occurs later in the case
- 4 For the relief of severe root pain
- 5 For suture of the anterior nerve roots in cauda equina lesions

PROGNOSIS In all cases of complete lesion it is very bad, as, if the patient does not die of the immediate lesion, he dies later from renal infection or pressure sores. In incomplete lesions which do not make a good recovery it is a little better, but it usually means that the onset of fatal complications is only delayed. In all cases




FIG. 217 When the ribs are fractured by direct violence if the force continues a fracture by indirect violence at the angle of the ribs may follow (see Fig. 221). Note that the unsupported chest wall between the fractures may show paradoxical movements.

injuries, such as occur in a stampeded crowd of people trying to get out by a narrow exit. The elasticity of the rib is overcome, and it fractures at a point near the angle as a rule, though in a few cases it may break just lateral to the tubercle. The fragments tend to bow outwards, so the pleura usually escapes damage. When one rib is fractured in two places the fracture near the angle is due to indirect



FIG. 218 Compressing the thorax antero posteriorly to test for fracture of the ribs (springing the thorax).

violence, transmitted from the region of the direct violence which has caused the other fracture.

MUSCULAR VIOLENCE from sneezing or coughing is a rare cause.

The fractures may be oblique or transverse, or comminuted. Displacement is as a rule slight. Compound fractures, except those from gunshot wounds, are rare.

Symptoms After a typical injury, such as falling and striking the side on the kerb, the patient complains of pain, which is usually well localised, over one or more ribs. The pain is increased by move-

CHAPTER XVIII

FRACTURES OF THE RIBS AND STERNUM

Surgical anatomy

The thoracic cage, which serves as a protection to vital organs and at the same time as support for the bellows action of the respiratory muscles is extremely elastic particularly in the earlier years of life, and so resistant to injury. Later on, as the costal cartilages calcify, the ribs also become more brittle, and the frequency of fracture increases. The upper ribs which do not move much with the respiratory excursion, are protected by the shoulder girdle. The lower ribs have a protection from their increased mobility, particularly the last two, aptly named "floating ribs." Injuries occur most frequently to the fifth to ninth ribs, which have the greater respiratory excursion and so are more difficult to keep at rest.

Fractures of the Ribs

Mechanism of fracture of the ribs **DIRECT VIOLENCE** This is the most common cause, fracture occurring at the point of impact of the blow, and the number of ribs fractured depending directly on the area of chest struck and the force of the blow. The fragments tend to be driven inwards, and so injuries to the pleura and the lung are more common than in fractures from indirect violence.

INDIRECT VIOLENCE This usually takes the form of crushing




FIG. 215 Fracture of the ribs due to direct violence. The fractured surfaces may be driven into the lung.




FIG. 216 Fracture of the ribs due to indirect violence. The ribs yield at the angle and the lung is unlikely to be lacerated.

ment, coughing, straining, and similar actions, and the patient may press his hands on the chest to prevent movement. Bruising, local crepitus, and deformity may be found. In thin people running the fingers along the ribs will give exact information. In the obese an X-ray may be necessary to be certain a fracture is present. Auscultation may enable slight crepitus to be heard. Compression of the thorax from spine to sternum (springing the ribs) will produce pain, localised to the site of fracture. To these features may be added the features of complications, due to injury to other structures in the chest or abdomen.

DIAGNOSIS This is usually simple. Certain cases of spontaneous fracture from cough have been diagnosed as pleurisy or intercostal myositis. An X-ray is usually conclusive, but in frac-




FIG. 219 Strapping the chest completely. The vertical layers applied in inspiration




FIG. 220 The horizontal layers, applied in expiration

tures in the mid axillary line it is necessary to have an oblique or lateral view, as they may not show in an A.P. film.

Treatment This is often difficult to carry out satisfactorily though it is comparatively simple. In fractures of the upper ribs the parts can be little further immobilised. Rest in bed is all that can be done to supplement the natural rest of muscular spasm. Below the level of the fourth rib strapping can be used. To control the ribs satisfactorily it must be remembered that the ribs have a hinged upward movement on the vertebral column, which at the same time increases the diameter of the chest. Maximum rest can only be obtained by preventing downward movement of the ribs, which is very difficult, by strapping passed over the shoulder from the twelfth rib behind to the costal margin in front, applied in inspiration. Over this is applied a circular plaster which completely surrounds the chest, and is applied in overlapping layers from below upwards in expiration. Fixation as firm as this can only be tolerated

by healthy patients in whom it will give much relief. In patients with cardiac or respiratory difficulty it cannot and should not be applied. A compromise which aims at as much fixation as the patient can bear must be arrived at. Sometimes a single 1 inch wide piece of strapping passed completely around the chest at the site of fracture may be suitable, in others only one half of the chest can be strapped as previously described. The use of single stretch strapping makes the patient much more comfortable than ordinary strapping. In fat women the breast makes strapping awkward, and a tight binder may have to be substituted.

The most troublesome feature of fractured ribs is often the pain and the inability to cough. In old people this may be extremely serious, limiting the respiratory excursion and interfering with rest. It is best treated by the infiltration of the fracture hematoma with novocaine, which is a very comforting procedure, and well worth keeping in mind in any case in which pain is to the fore.

In more complicated injuries, where several ribs are crushed, the patient is more comfortable in the sitting or half sitting position in bed. Strapping is contra-indicated particularly if there is any depression of the ribs. Compound fractures are treated as compound fractures elsewhere. It is particularly important to control a "sucking" wound by excision and suture as it interferes with the air entry into the lung. Similarly, in "stove in" chests, the free portions of the chest wall undergo paradoxical movements with respiration, and this reduces the air entry. It is important that this free mass of ribs and muscle should be fixed without constricting the chest. This can be done by applying elastoplast over the side of the thorax and then covering this with a layer of plaster. When the plaster sets the mobile portion remains attached by the elastoplast to the plaster. Foreign bodies should not be removed immediately from the lung or deeper structures in the absence of complications, but only if superficial in the chest wall.

PROGNOSIS Rapid and satisfactory union occurs even in the untreated case in three to five weeks. In a small percentage of cases, particularly in the old, there is a troublesome persistence of pain at the fracture site. Its origin is difficult to determine, and it can only be combated by novocaine injections and physiotherapy. After some months it subsides.

In more severe chest injuries the prognosis is that of the complications present (*q v*).

INJURIES TO THE COSTAL CARTILAGES These may consist of fracture, separation at the costo-chondral junction, or at the chondro-sternal junction. The history and symptoms are similar to that of fractured ribs, but the injury is localised over a cartilage. The



FIG 221 Lateral view of a fracture of the sternum due to direct violence



FIG 222 Fracture of the sternum accompanying fracture of the second thoracic vertebra



FIG 223 Fracture of the ribs. A healing fracture of the four upper ribs with early callus has been followed by a recent fracture of three of the same ribs more anteriorly

shows itself at the neck. It is of serious import, and can only be given supporting and expectant treatment.

3 HÆMOTHORAX. This is only of importance when of some amount, indicating that an artery, either in the lung, or the internal mammary, or an intercostal vessel, is ruptured. Blood in the pleural cavity does not clot, and can be easily aspirated. After the hæmorrhage has stopped this should be done if there is any amount present in the chest in order to hurry resolution. Difficulty arises in the cases in which the hæmorrhage continues, or there are symptoms of lung compression. These should first be relieved by aspiration, and this followed by blood transfusion if the patient is exsanguinated. Should the hæmorrhage still continue operation must be carried out. Aspiration must be tried first to be certain that the hæmorrhage has not ceased as open operation is a risk not lightly to be undertaken.

4 PNEUMOTHORAX. May be due to a penetrating wound of the pleura or to a wound of the lung. In the open variety, the free communication of the pleural cavity with the air allows the lung to collapse, and air is sucked in and out the wound, often frothing up the escaping blood in the wound. Such a wound needs to be closed at once with a wet dressing preparatory to its excision and suture to assure air entry into the lungs.

The closed variety of pneumothorax is unimportant provided the wound is not of a valvular type, which allows the entry of air but prevents its expiration (tension pneumothorax). Such a condition is most commonly due to a wound of the lung, and results in a steady rise in intra pleural pressure with marked mediastinal displacement, and much increased respiratory difficulty. The discovery of such a condition demands immediate relief by needling the pleural cavity and allowing the air under pressure to escape. The needle may be left in some time if necessary to continue the decompression.

5 TRAUMATIC CYANOSIS (asphyxia). This produces a dramatic coloration of the skin of the face and shoulders above the level of the second rib, together with extensive subconjunctival hæmorrhages. It is due to, (1) A wave of back pressure in the veins of the chest, head and upper extremities, which are devoid of veins. This occurs instantaneously following a blow which may be of short duration, and is responsible for the petechial hæmorrhages in the skin and the subconjunctival hæmorrhages. (2) These hæmorrhages may occur on top of a cyanosed condition of the skin, or alone. Where cyanosis is present it is due to a paralysis of the skin venules, due to long-continued venous back pressure, and demands that the thorax be compressed for some minutes. Slow compression of the thorax may produce this condition without petechiæ. The normal tone is

X ray will not show the lesion except in cases in which the cartilage is calcified. Where there is an obvious costo-chondral dislocation it may be reduced by arching the patient's back over a pillow or the knee and getting him to take a deep inspiration. Strapping is seldom required for these lesions.

Rarely union between the rib cartilages at the lower costal margin does not occur or they are separated by trauma, and a condition of slipping cartilage develops, in which during muscular movements the lower cartilage slips over the upper one, producing an unpleasant sensation and persistent local tenderness. Excision of the cartilage under local anaesthesia is a satisfactory cure.

Fractures of the Sternum

These are due either to direct violence or to hyperflexion of the spine. The fracture is usually transverse, and there is little displacement. The sites most commonly involved are the centre of the bone, or the synchondrosis between the manubrium and body. Rarely the xiphisternum is fractured from the body. Displacement if present is due to flexion injury and should raise suspicion of a fracture of the spine. The lower fragment is usually displaced forwards (Figs 221, 222).

DIAGNOSIS This is usually straightforward, and is confirmed by a lateral X ray. A P X-rays will not show the lesion. Where there is displacement the patient tends to walk in a stooping position.

TREATMENT In cases without displacement rest in bed till the acute pain has gone, followed by strapping, is all that is required. Where there is displacement it can be reduced by hyper extension of the thoracic spine. Local anaesthesia may be used to relieve the pain while this is being done.

Complications of thoracic injury 1 **HÆMOPTYSIS** This indicates damage to the lung, and the degree of hæmoptysis indicates to some extent the site and size of the lung injury. Thus a small amount of pink frothy sputum coughed up some hours after the injury indicates a small degree of peripheral lung damage, while a continued hæmoptysis of dark blood occurring rapidly after the injury indicates rupture of a large vessel near the root of the lung. It is to be remembered however that a serious injury to the lung may be present without hæmoptysis owing to the cessation of hæmorrhage with the collapse of the lung and the inhibition of the cough reflex by the patient on account of pain.

2 **SURGICAL EMPHYSEMA** Indicates perforation of the lung. It settles down rapidly even if moderately extensive. Rarely a bronchus may be ruptured with mediastinal emphysema, which first

shows itself at the neck. It is of serious import, and can only be given supporting and expectant treatment.

3 HÆMOTHORAX. This is only of importance when of some amount, indicating that an artery, either in the lung, or the internal mammary, or an intercostal vessel, is ruptured. Blood in the pleural cavity does not clot, and can be easily aspirated. After the hæmorrhage has stopped this should be done if there is any amount present in the chest in order to hurry resolution. Difficulty arises in the cases in which the hæmorrhage continues, or there are symptoms of lung compression. These should first be relieved by aspiration, and this followed by blood transfusion if the patient is exsanguinated. Should the hæmorrhage still continue operation must be carried out. Aspiration must be tried first to be certain that the hæmorrhage has not ceased as open operation is a risk not lightly to be undertaken.

4 PNEUMOTHORAX. May be due to a penetrating wound of the pleura or to a wound of the lung. In the open variety, the free communication of the pleural cavity with the air allows the lung to collapse, and air is sucked in and out the wound, often frothing up the escaping blood in the wound. Such a wound needs to be closed at once with a wet dressing preparatory to its excision and suture to assure air entry into the lungs.

The closed variety of pneumothorax is unimportant provided the wound is not of a valvular type, which allows the entry of air but prevents its expiration (tension pneumothorax). Such a condition is most commonly due to a wound of the lung, and results in a steady rise in intra pleural pressure with marked mediastinal displacement, and much increased respiratory difficulty. The discovery of such a condition demands immediate relief by needling the pleural cavity and allowing the air under pressure to escape. The needle may be left in some time if necessary to continue the decompression.

5 TRAUMATIC CYANOSIS (asphyxia). This produces a dramatic coloration of the skin of the face and shoulders above the level of the second rib, together with extensive subconjunctival hæmorrhages. It is due to—(1) A wave of back pressure in the veins of the chest, head and upper extremities, which are devoid of veins. This occurs instantaneously following a blow which may be of short duration, and is responsible for the petechial hæmorrhages in the skin and the subconjunctival hæmorrhages. (2) These hæmorrhages may occur on top of a cyanosed condition of the skin, or alone. Where cyanosis is present it is due to a paralysis of the skin venules, due to long-continued venous back pressure, and demands that the thorax be compressed for some minutes. Slow compression of the thorax may produce this condition without petechiæ. The normal tone is

restored to the skin capillaries and venules in three to five days, the "blue" discoloration fading without intermediate pigmentary change. This leaves the petechiæ more distinct, when present, and these fade with the usual colour changes of a hæmatoma in ten to twelve days.

TREATMENT The cyanosis being entirely peripheral no treatment to the chest is of avail in clearing it up. Oxygen may, however, be required for the damage to the lung associated with such a lesion, which may be a contusion or mild pulmonary œdema.

A most important feature of the condition is the occurrence of retinal hæmorrhages and optic atrophy, which not infrequently follow.

6 CONTUSION OF THE HEART Bruising of this and other mediastinal structures is first shown by severe shock and precordial pain. More severe injury may rupture the heart or great vessels.

7 MASSIVE COLLAPSE OF THE LUNG This may follow other injuries, and the pathology is not clear. The lung is collapsed but there is a negative pressure in the thorax and the mediastinum is deviated to the side of the lesion. It can best be diagnosed in the X-ray as the clinical signs are often confusing. Cyanosis may occur, and for this CO_2 and oxygen may be given in an endeavour to expand the lung. The condition settles down of its own accord in one to three weeks.

8 RUPTURE OF THE LIVER AND SPLEEN These injuries may occur without fractures of the ribs, but fractures of the lower ribs should put one on guard, so that an intra abdominal hæmorrhage is not overlooked.

REFERENCES

General

- SAUERBRUCH and O SHAUGHNESSY "Thoracic Surgery," London, 1938
TUDOR EDWARDS, A "Treatment of Injuries of the Chest," *Brit M J*, 1938, 2, 1096

Associated Injuries

- HAMILTON BAILEY "Injuries to Kidney and Ureter," *Brit J Surg*, 1923, 11, 609
BUTLER E "Injuries of the Chest and Abdomen," *Surg Gynec and Obsts*, 1938, 66, 448
BIZARD, J D "Slipping Ribs. Report of a Case," *J A M A*, 1931, 97, 23
BONNEN, J G "Traumatic Asphyxia," *Lancet*, 1941 ii, 333

Sternum

- STUCK, W G "Fractures of the Sternum," *Am J Surg* 1933 22 266, 1937, 38, 560

CHAPTER XIX

THE CLAVICLE

Anatomy Development First bone to appear Laid down in main brane bone, ossification commencing in the centre of this at two centres in the sixth week. The two ends are laid down later in cartilage (probably indicating the fusion of two morphologically distinct bones) but ossification spreads to them from the primary centre. One secondary centre for the disc of bone on the sternal articular surface appears at 20 and unites at 25 years of age. It is completely intracapsular.

The bone is S shaped, with two broader and stronger ends, and a weakness at the junction of the outer third and middle third, due to

- 1 Groove for the subclavius
- 2 Alteration in the internal architecture of the bone
- 3 Junction of two curves
- 4 Foramen for the nutrient artery

An elastic rod broken by compression tends to break near its centre, and in




FIG. 224 The sternal end of the clavicle. A Manubrium sterni B Intra articular fibro cartilage C Rhomboid ligament D First rib E Sternal end of the clavicle



FIG. 225 The acromial end of the clavicle. A Section of the clavicle B Coroid ligament C Trapezoid ligament D Coracoid process E Sloping surfaces of the acromio clavicular joint. F Section of the acromion

the case of the clavicle, the weak points above determine the site. The double curve of the clavicle is important as it increases the elasticity of the bone, which is the only bony bridge connecting the superior extremity with the trunk.

Attachments Ligaments are more important than muscles, which are the deltoid, sternomastoid, subclavius, pectoralis major, and trapezius.

Ligaments Sternal end

Intra articular fibrocartilage, bound to the upper surface of the clavicle, and lower aspect of the sternal joint

Capsule, reinforced by fibres of the sterno mastoid

Interclavicular ligament

Rhomboid ligament Very strong, attaching the clavicle to the first rib

Ligaments Acromial end

Coracoid ligament } Attaching clavicle to the coracoid process

Trapezoid ligament }

These form the main strength of the coraco acromial joint pulling down the oblique articulating surface of the clavicle which would otherwise tend to ride up

Joint capsule, reinforced a little above

Relations Arches over the important structures passing from the thorax and neck to the axilla, which in spite of their position between two bones are seldom injured

Injuries to the Clavicle

- 1 Fracture at the junction of the outer and middle third
- 2 Fracture of the acromial tip lateral to the trapezoid ligament
- 3 Fracture of the acromial end in the region of the conoid and trapezoid ligaments (Rare)
- 4 Fracture of the sternal end (Uncommon)
- 5 Separation of the epiphysis (Very rare)



FIG 226 The fracture sites in the clavicle (The numbers correspond to those in the text)

Type of injury DIRECT VIOLENCE From bars falling on the shoulder and the like Produces any of the above fractures, and

is the only type of injury which may produce comminution and damage to vessels and nerves




FIG 227 Fracture at the junction of the outer and middle third of the clavicle showing well the usual downward and medial displacement of the outer fragment and the shoulder

INDIRECT VIOLENCE Force is transmitted through the extended arm or from the elbow, or perhaps more frequently from a fall on the shoulder. Fracture occurs at the weakest point, the type varying with the age of the patient.

Greenstick, in children up to the age of ten.

Compression, or infraction fracture. In children. Rare.

Complete, in adults, at classical site.

Fracture is most common in children. In spite of the subcutaneous nature of the bone the fracture is nearly always simple. Damage to nearby structures is rare. The brachial plexus is seldom injured. Paralysis, if it occurs, is always temporary, and little good is to be done by interference, so such injuries are left alone. The subclavian artery is rarely injured, the subclavian vein more frequently.

Fracture of the shaft 1 **COMPRESSION** Occurs in the young under six years. There is complaint of local pain, and a swelling may be palpable. X-ray shows the bone intact, but a slight swelling near the weak point, and an alteration in trabecular lines. The child can use the arm, but is reluctant to do so.

Treatment (See below) Sling

Two smglet method

2 **GREENSTICK** Features similar to compression fractures, from which it is distinguished by the presence of angulation, and a little more pain and disability. Local bruising is often absent. Local pain, and reluctance to use the arm, and local tenderness are found. If in doubt the X-ray confirms the diagnosis.

Treatment Figure-of-eight bandage and sling, or sling alone.

3 **COMPLETE** Break tends to be oblique or spiral, with finely jagged ends if due to indirect violence, the line of the fracture running forwards and medially. In direct violence it tends to be more transverse.

Displacement Outer fragment. The weight of the shoulder pulls it down. Pectoral muscles pull shoulder medially and forwards.

Inner fragment. Fixed by the pull of the rhomboid ligament and the sternomastoid, which may tilt it a little upwards.

As a result of this the medial fragment overrides the lateral, which lies a little below and medially displaced. (Fig. 227)

Symptoms and signs Arm on the affected side is rendered powerless.

Patient supports the elbow with the opposite hand (as he will for other fractures of the arm and shoulder).

Head is inclined to the affected side to relax the sternomastoid, and the trapezius.

Local pain, tenderness, bruising and deformity.

Crepitus is usually felt

Shoulder may be higher or lower than on the uninjured side, depending on the amount of muscle spasm in the trapezius

Fracture of both clavicles Rare Due to crushing injuries Both arms are powerless, and their weight on the thoracic cage may, together with the loss of the accessory muscles of respiration, cause acute respiratory embarrassment in elderly people



FIG 228 Figure of eight method of drawing the shoulders back, using two triangular bandages knotted behind The cross bandage in front is necessary to prevent slipping over the shoulders




FIG 229 Back view of the figure eight bandages

is unsightly Non union is almost unknown (Fig 56A), and when fibrous union occurs, the functional result is quite satisfactory

All methods of treatment depend on increasing the distance between the two ends of the clavicle, by

- 1 Drawing the shoulder backwards
- 2 Drawing the shoulder outwards
- 3 Elevating the shoulder

or combinations of these methods

This can be treated with bilateral abduction splints, preferably light and made of such a material as Cramer wire (Fig 101) This frees the thorax and the patient can be sat up Two arm Thomas splints have been used if the patient must be nursed recumbent

Treatment of complete fractures of the clavicle The multiplicity of methods invented indicates that none are universally used, or completely satisfactory The results are good as far as function is concerned, whichever method is employed, but there may be a marked overlap, and a mass of subcutaneous callus, which

The most suitable treatment depends largely on the age

BETWEEN ONE TO FOUR YEARS A child does not require more than a sling, but wriggles out of this. A suitable method of retention, if the mother is helpful, is to get her to put two singlets on the child, one under the arm and the other over it, and sew the two together around the arm and hand, while the hand rests on the opposite shoulder. This has the advantage of remaining in place however much the child wriggles, which very few other methods have at this age.

BETWEEN FOUR TO TEN YEARS The figure eight application of the three handkerchief method will be found most satisfactory. Two triangular bandages are folded over some lint to make some extra padding till they form two bandages about 2 inches or more wide. These are put around each axilla, and then tied crosswise at the back, thus pulling the shoulders back. In small children this is all that is necessary, but in larger children and in adults it is necessary to pull the two axillary rings nearer to the mid line, by a bandage pinned across the front. This prevents the rings slipping over the acromial process, but draws the point of pressure nearer to the fracture site.




FIG. 230 Reduction of a fractured clavicle over the fist in the axilla

ADULT METHODS *Reduction*

This may be made after the injection of a local anæsthetic, or without it in many cases, by putting the fist in the axilla and lowering the arm to the side over it. It can also be made by placing a knee against the back and pulling both shoulders back over it. Slow reduction may be obtained by retentive apparatus, which is duly tightened. This is probably the best method, as, after reduction, most fractured clavicles tend to slip back to their original position.

Retention 1 Bed, with a pillow between the shoulders. Unnecessarily tedious. Where the minimum of callus and deformity is required this can be obtained by an abduction splint.

2 Abduction splint. Applied as for fractures in the region of the neck of the humerus, with extension on the upper arm. All displacements can be corrected by this method, but it requires constant supervision and is clumsy.

3 Sayre's method. Pad in axilla. Strapping is passed around

the arm, with the adhesive side out, and fastened to the back, so drawing the whole arm backwards. An oblique strip split over the olecranon is now passed from behind forwards, over the elbow, and up along the forearm to the opposite shoulder. By this means the elbow is carried forward and the shoulder levered up and back. It is a useful temporary measure, but it tends to slip, is uncomfortable, and makes the skin sore after a time (Figs 231, 232).

4 Wharton Hood's method. Direct pressure on the fracture with strapping passed from below the scapular of the opposite side




FIG 231 Sayre's method. The first layer. The strapping applied sticky side out to the arm may be brought completely around the chest and over this again.



FIG 232 Sayre's method. Second layer. A pad placed between the hand and the chest makes the patient more comfortable. Note also the pad over the olecranon.

over the shoulder, to below the nipple of the opposite side. Provides no fixation, but some support.

5 H. O. Thomas' strapping, as used for dislocation of the acromio-clavicular joint (see p. 604). This steadies the clavicle and supports the weight of the arm and is simple and effective as any other strapping method.

6 Bohler's clavicle splint. Consists of a thick wooden wedge in the axilla, combined with local pressure from a strip over the fracture, and an attached piece to which the forearm may be tied if necessary. It is excellent in mechanical principle, but the wedge even if padded produces unpleasant pressure effects, and the whole apparatus is clumsy. It is valuable in allowing free shoulder movements in the aged, which is necessary to avoid a stiff shoulder.

7 Artificial clavicle. In this method two malleable aluminium



FIG. 233 Bohler's clavicle splint, showing the wooden wedge for the axilla and forearm bar



FIG. 234 Bohler's clavicle splint applied. Note axillary padding

plates lined with felt are fitted over the anterior aspect of the point of each shoulder. These are joined anteriorly by an adjustable bar, and held in position posteriorly by flat straps crossed at the mid-line, and a wider strap joining both lower ends behind. By adjusting the length of the bar in front, and the tension in the straps posteriorly, the clavicle can be manipulated into good position and retained there. The absence of apparatus behind enables the patient to sleep on the back, and there is freedom from pressure on the fracture site, anteriorly, while the shoulder can move freely (Fig. 235)





FIG. 235 Artificial clavicle. Front view showing the adjustable bar, and the curved metal shoulder caps which do not press on the broken bone. Back view showing the absence of apparatus thus enabling the patient to sleep in comfort

Fractures of either end of the clavicle **THE ACROMIAL TYPE**
 This is nearly always due to direct violence. If the conoid and trapezoid ligaments are intact there is little displacement and the main complaint is local pain, which can be relieved by sling, or, more certainly, by Robert Jones' strapping, which takes the weight of the limb off the injured part. Immobilisation is only necessary till pain on abduction of the arm is absent. When this lesion is combined with rupture of the conoid and trapezoid ligaments, longer rest is required (see page 605).

FRACTURE BETWEEN THE CONOID AND TRAPEZOID LIGAMENTS
 The clavicle is broken by depression of the shoulder and bending of



FIG. 236 Fracture of the outer end of the clavicle

the bone over the coracoid process. The conoid and trapezoid ligaments maintain the fragments in position, and it is only necessary to support the weight of the arm by a sling or Robert Jones method.

FRACTURE AT THE STERNAL END Due to indirect violence. It is rare that the rhomboid ligament is torn, and when this occurs there is usually other severe damage as well. Unless this ligament is torn the displacement is slight, and a sling is sufficient to take the weight of the arm till healing has occurred. An interesting complication is surgical emphysema which may occur from injury to the lung. It settles down readily.

H. O. Thomas' method (often called Robert Jones' method)
Application The strapping is applied firmly from below the inferior

angle of the scapula of the opposite side, over a pad of felt, placed as near the root of the neck as possible (to avoid pressure on the acromion) down the anterior aspect of the arm, firmly around a pad placed over the subcutaneous border of the ulna, and then up behind, and across the upper pad, ending under the nipple of the uninjured side. It is important that the strapping be crossed as far medially on the neck as possible so that the weight falls on the



FIG 237 Robert Jones strapping correctly applied on the left shoulder incorrectly on the right

medial end of the clavicle. This method is particularly useful for acromio clavicular dislocations, and the pad must leave the joint just clear at its outer edge to be sure no pressure is applied to the acromion. In fractures of the outer end of the clavicle this is not so important, as the fragments are usually in good position and only require support. The illustration exaggerates the common faults in applying this method.

- 1 Too thin strapping
- 2 No felt pads
- 3 Strapping crossed too laterally over the acromion

The strapping works loose every four days or so and it must be

tightened up, which is done with least discomfort to the patient by passing a new strip over the old one

LENGTH OF IMMOBILISATION In compression and greenstick fractures in the young it need only be continued till they are free from pain. Recovery is often only a matter of days. In young people up to twenty, three weeks' rest is sufficient, and over this age, depending on the amount of pain when free movement is attempted, four to five weeks. It is not suggested that in the old complete immobilisation is continued for this time. Their greatest danger is stiffness of the shoulder, and as soon as possible active and passive movements of the joint should be commenced. They will probably need some support for the arm such as a sling for this period. Bony union always occurs in the young. In adults firm fibrous union is satisfactory.

COMPLICATIONS 1 Excessive callus. Due to inadequate fixation, comminution, or poor reduction. Can be removed later by open operation if unsightly, but care must be taken to avoid adhesion of the scar to the bone.

2 Pain over the distribution of a supraclavicular nerve. Very rare, and due to involvement of the nerve in scar tissue. It may require section of the nerve in the supraclavicular triangle.

3 Cervical rib syndrome. Some features of pressure on the inner cord of the plexus may be caused by a dropped shoulder with gross mal-union. Reconstruction of the fracture, and resetting, or excision of part of the first rib may be necessary to relieve it.

4 Stiffness of the shoulder. This is perhaps the most common and serious complication, due to neglect to exercise the shoulder joint, which is frequently bruised in the accident. If movements of the shoulder are neglected, particularly in the old, great disability may follow. All cases should therefore be encouraged to move the supported arm daily, and as soon as pain has subsided to exercise the shoulder carefully. Retentive apparatus allowing the greatest freedom of movement should be used, the most suitable being the artificial clavicle.

REFERENCES

- BOHLER, L. 'The Treatment of Fractures,' Bristol, 4th Edition, 1930 p. 168.
 KIRK. 'Fractures of the Clavicle' *Am J Surg* 1937, 38, 485.
 GREENWOOD. 'Fracture of the Clavicle' *Brit M J* 1928 1 1021.
 YOUNG, C. S. 'The Mechanics of Ambulatory Treatment of Fractures of the Clavicle,' *J Bone and Joint Surg* 1921 13 299.





FIG. 240 Fracture of the body of the scapula. The fissure fracture runs from the glenoid to the vertebral border above the inferior angle.

CHAPTER XX

FRACTURES OF THE SCAPULA

Surgical anatomy The scapula is so well protected by muscles, and so well supported by the thorax, from which it is cushioned by the serratus magnus and the subscapularis, that fracture is uncommon considering the size of the bone. The close attachment of muscles serves to limit displacement and minimise hemorrhage. No important structures being closely related, complications are uncommon.

The only developmental fact of importance is the occasional failure of union of the acromial centres with the spine, which may be thought to be a fracture, but may be excluded by an X ray of the opposite side, as may most developmental anomalies of bones which are almost universally bilateral.

Modes of injury Injuries fall into two broad groups, those to the processes of the bone, and those to the body. Direct violence is likely to




FIG 238 The sites of fracture in the scapula (The numbers correspond to those in the text)



FIG 239 The sites of fracture in the scapula around the glenoid (The numbers correspond to those in the text)

fracture any process, or the body. Indirect violence transmitted along the arm tends to fracture the region of the glenoid, but may fracture the body by buckling it.

Sites of Scapular Fracture

- 1 The body, including the upper and lower angles
- 2 The spine of the scapula
- 3 The acromion (a) Medial to the acromio clavicular joint
(b) Lateral to the acromio clavicular joint
- 4 The neck of the scapula (Anatomical)
- 5 The glenoid and coracoid (Surgical neck)
- 6 The coracoid
- 7 The glenoid margin

Fractures of the body Fracture is more frequent in the lower half of the body, and may be fissured, stellate or irregular. Owing to the fixation by subscapularis and infra-spinatus displacement is small. There is a tense even swelling below the infra spinatus fascia. Clinically there is a story of local injury (rarely indirect) and pain. There is difficulty in raising the arm, which is very variable. Tenderness and crepitus may be elicited by grasping the lower angle of the scapula and moving the arm. In thin subjects the axillary border and vertebral border may be palpated. In fatter subjects the humerus may be brought nearer the hand by elevating the shoulder and pushing backwards with the fingers in the axilla.

When the fracture is due to severe direct trauma, such as a blow or a bullet, fractured ribs and chest complications may be seen, otherwise they are rare.

TREATMENT This depends largely on the amount of pain, which is related to the severity of the lesion. Fixation being good, movement is to be encouraged as soon as it can be borne. In mild cases a sling for a week is sufficient. In more severe cases this must be supplemented by some form of strapping of the chest, including the infra spinous portion of the scapula, and possibly the bandaging of the arm to the side over this. The time of retention varies from one to three weeks, and then a sling is substituted, which is worn for a corresponding shorter period. Movements of the shoulder are to be encouraged as early as possible. Very rarely there is overlap of the fragments, and this must be corrected by forced abduction of the arm, with the fingers on the axillary border to manipulate the body.

Fracture of the spine of the scapula This can sometimes be detected by its mobility in thin patients. It is often associated with fracture of the body, and the treatment is similar.

Fracture of the acromion Due commonly to falls on the shoulder.

(a) Medial to the acromio clavicular joint. Fracture at junction of the body and spine.

(b) Lateral to the acromio clavicular joint. Fracture across the broad acromial process.

In this latter case there is little displacement, and merely local tenderness, an X-ray usually being necessary to identify the fracture. The treatment is to carry the arm in a sling till pain has subsided. Shoulder movements are commenced early to avoid stiffness.

In the first and more serious condition we have a lesion which is comparable with acromio-clavicular subluxation. Usually the coraco-clavicular ligaments are intact and there is little displacement. Two to three weeks rest in a sling will usually be sufficient treat-

ment Should the coraco-clavicular ligaments be torn the scapula will sink down, the condition then being comparable to acromioclavicular dislocation, and as the ligaments are slow in healing more prolonged and firmer support by Robert Jones' strapping will be necessary In many people the damage to the ligaments may be shown by calcification occurring in them as they heal

Fractures of the anatomical neck of the scapula These occur just behind the glenoid They are almost unknown, and the treatment that of fracture of the surgical neck

Fractures of the surgical neck of the scapula These occur in a line running from the supra scapular notch to the infra glenoid tubercle The two fractures are similar in origin and effect, except that in the latter the arm is also deprived of the support of the coraco-brachialis, which is attached to the coracoid There are two varieties of the lesions, depending on the severity of the accident



FIG. 211 Fracture of the coracoid process

In the minor type, in which muscles and ligaments are not torn, there is little displacement and the lesion may be difficult to recognise Some pain on movement of the shoulder and pain on pressure high in the axilla may be all that is found Such cases require support for the arm for two to three weeks by a sling Shoulder movements are actively encouraged, and at the end of six weeks there should be little disability

In the more severe group of cases tearing of ligaments and crushing of bone allows the arm to be displaced medially, and to drop downward The lesion may thus resemble a dislocation of the shoulder, with loss of movements, prominence of the acromion, and flattening of the deltoid, but there is no fixation of the arm Crepitus is usually easily elicited and this emphasises the necessity for an X ray Other suggestive findings are the ease with which the parts are replaced and the immediate recurrence on removal of support In this the condition resembles dislocation of the shoulder with complete separation of the musculo tendinous cuff

TREATMENT In the absence of comminution of the glenoid cavity this fracture may be treated with the arm at the side if elevation of the humerus restores the parts to position. It is slung by Robert Jones' strapping over which a circular layer is applied to keep the arm at the side. Careful watch must be kept for redisplacement.

Where comminution of the glenoid is present, or upward pressure on the humerus fails to restore the parts to normal position, it is necessary to treat the arm in the abducted position. A simple extension frame attached to the side of the bed is more satisfactory than a Thomas arm, which is uncomfortable and tends to displace the parts. Traction, as shown in Fig 114, with 6 to 10 lbs weight is applied. This is maintained for two to four weeks while physiotherapy is also carried out. In severe cases some limitation of the shoulder movements must be expected, and the likelihood of this increases rapidly with age.

The coracoid Rarely fractured. Injury is due either to direct violence from which it is well protected, or muscular violence, which is usually forced abduction, which overstrains the pectoralis minor, or coraco-brachialis. Displacement is small, and Robert Jones' strapping applied over a pad of adhesive felt placed over the coracoid for a week is all that is necessary. (Fig 241)

Fracture of the glenoid Simple chip fractures, due to indirect violence, or the pull of the long head of the triceps (Fig 242), are usually not displaced, and can be treated by a pad in the axilla and slung with a circular bandage over it for seven to twelve days and then slowly increasing the movements allowed, first with the arm in the sling and then without.

Comminuted fractures usually accompanied by other fractures must be treated by traction as described above to avoid adhesions to the glenoid surface. This is maintained for three to five weeks, and then active exercises slowly commenced. During this period massage, friction and muscle-tensing exercises are kept up to prevent wasting and aid in avoiding stiffness of the joint.

REFERENCES

- FINDLAY, R. F. "Fractures of the Scapula and Ribs" *Am J Surg*, 1937, 38, 489
 FINDLAY, P. I. "Fractures of the Scapula" *Am J Surg*, 1931, 93, 1001

- HITZROT and BOLLING "Fractures of the Neck of the Scapula," *Ann Surg*, 1919, 63, 215 (Full article with further references)
- COTTON and BRICKLEY "Treatment of Fracture of the Neck of the Scapula," *Boston Med and Surg J*, 1921, 185, 326
- PFAB, B "Die Fraktur des Proc Coracoides" *Zentralbl f Chir*, 1930, 57 718

CHAPTER XXI

FRACTURES OF THE HUMERUS

Surgical anatomy

Development The primary centre for the shaft appears at the end of the seventh week. Secondary centres for the head appear as follows

Head	First year	} Unite about sixth year, and fuse with the shaft at twenty to twenty five years
Greater tuberosity	Third year	
Lesser tuberosity	Fifth year	
Secondary centres for the lower end appear as follows		
Lateral condyle	Twelfth year	} Unite about puberty, and fuse with the shaft about seventeen years
Capitellum	Third year	
Trochlea	Tenth year	
Separated by a process of the diaphysis from the,		
Medial epicondyle	Sixth year	Fuses with shaft about eighteen years

Upper end From the point of view of fractures the internal architecture of the bone is a more important guide to the site of fracture than either the anatomical or surgical neck.




FIG 143 Diagram illustrating the fracture sites at the upper end of the humerus. The arrows indicate the surgical and anatomical necks. The dotted line indicates the junction of the compact bone of the shaft and the cancellous bone of the head while the straight lines indicate the more common directions of fracture.

It is now realised that fractures cannot be classified into fractures of one or other neck. Reference to the illustration showing the bony structure of the upper end of the humerus will make this clear. The weak line in the bone, i.e., the line through cancellous bone, joining the upper ends of the compact bone of the shaft lies midway between the anatomical neck and the surgical neck. A fracture through the anatomical neck is a fracture through cancellous bone and tends to be of the crushing or impacted type. A fracture through the compact bone of the surgical neck is difficult to produce, tends to be transverse, and resembles a fracture of the shaft. It is due to direct violence. In practice any injury is likely to be one of compression combined with leverage and the tendency is for the cancellous tissue of

the head to be levered over and pushed down on the stronger tissue of the shaft

The attachment of the capsule of the shoulder joint follows the anatomical neck, except posteriorly where it passes a little lower down following the insertion of the *tubercle minor*, and so comes to overlap the epiphyseal line, making a small portion of the *diaphysis intracapsular*. In the specimen shown in the photograph the almost obliterated epiphyseal line may be seen, and it shows how the conical head sits on the pyramidal end of the humeral shaft, thus rendering epiphyseal separation unlikely. It will be noted that the epiphyseal line lies slightly cranial to the line of weakness in the bone.

Shaft The shaft of the humerus is of the typical cylindrical build of the long bones, showing some thickening for the insertion of the deltoid on its outer aspect, running up from its mid point. It becomes triangular below, where the medial and lateral supracondylar ridges develop, which increases its resistance to transverse strain but weakens it to blows from in front and behind. The relationship of the radial nerve which winds around the bone, lying in contact with it for a short course above the mid point, must be noted, and the close attachment of the brachialis anticus to the anterior aspect of the bone remembered.

Lower end The irregular structure of the lower end provides a number of lines of weakness in the bone which is reflected in the variety of fractures met with. The prominence of the medial epicondyle grooved by the path of the ulnar nerve must be compared with the stronger lateral condyle on which the epicondyle is much less prominent.

FRACTURES OF THE UPPER END OF THE HUMERUS

General It has already been shown that the fractures of the upper end of the humerus cannot be classified on an anatomical basis, but must be considered on the basis of internal architecture. Fractures most commonly occur at the weak line previously mentioned, but they may run obliquely so that on one side the fracture is through compact bone and on the other through cancellous bone. Because adduction is limited by the body abduction is much more commonly the position in which strain is transmitted to the shoulder from falls on the hand or elbow. From the structure of the bones it will be obvious that this results in a compression strain on the inner aspect of the bone, and a bending strain on the outer aspect of the shaft. This results in a fracture of the outer compact layer, and then a folding of the head over the sharp end of the compact bone. Owing to the curved nature of the compact layer on the inner aspect the strain is more evenly spread here, and the head tends to fold over on this as on a hinge. The opposite mechanism in the adducted position is much rarer, but accounts for a small percentage of fractures. Fractures of the upper end of the humerus tend on the whole to show little displacement owing to this tendency to impact, and owing to the numerous tendinous insertions prolonged down the neck of the bone. Frequently neither abduction nor

adduction can be recognised, and a film in the abducted position will show angulation open anteriorly or posteriorly (Figs 251, 252).

Fractures at the level of the surgical neck are through compact bone and do not show that tendency to be impacted which is characteristic of fractures above. Displacement here may be classified into adduction or abduction of the head on the A.P. film, but this does not as a rule fully describe the position. The short scapular muscles tend to abduct the upper fragment, while the pectoralis major, latissimus dorsi, and teres major tend to adduct the lower fragment. The deltoid and arm muscles tend to produce shortening.

TYPE OF VIOLENCE This is most commonly indirect from falls on the hand or elbow. Direct violence tends to produce an unimpacted fracture. Occasionally muscular pull may be responsible for fractures of the tuberosities.

Classification It will be seen that there is no satisfactory way of grouping all fractures of the upper end of the humerus, so for purposes of discussion and record a clinical classification is recommended.

1 Complete fractures of the upper end of the humerus. Tend to occur below the weak line, through compact bone, or be comminuted.

2 Impacted fractures of the upper end of the humerus. Occur through or in the region of the weak line.

3 Fracture dislocations of the humerus.

4 Separation of the upper epiphysis of the humerus.

5 Fractures of the greater tuberosity.

6 Ligament traction fractures (fractures of the lesser tuberosity).

It is to be noted that compound fractures in this region are rare.

Complete Fractures of the Upper End of the Humerus

SITE. The common site has been described already, together with the characteristic displacement. The fracture may be complicated by gross comminution or dislocation.

SYMPTOMS AND SIGNS. There is a complete inability to use the arm, which is usually held by the opposite hand to prevent displacement. Pain is severe. A hematoma rapidly collects below the deltoid, and manifests itself by staining of the skin appearing at the lower border of the deltoid in a short time. Later the hematoma tracks down the arm to the elbow. The shoulder appears more rounded and swollen. If there is displacement, the deltoid may appear flattened in its lower part, but there is not the emptiness below the acromion characteristic of a dislocation. The whole arm can be displaced medially (false motion) and crepitus readily elicited. The anterior axillary fold may be deepened. Shortening is present,

as measured from the acromion to the external condyle. Telescopic movement confirms what is usually a simple diagnosis. The axillary and radial nerves are sometimes injured and the examination should include tests for this.

The differential diagnosis is from the other fractures in the region,



FIG. 244 Complete fracture of the upper end of the humerus X-rayed in abduction

including the fractures of the glenoid and neck of the scapula, and dislocation (*q.v.*), and is usually simple.

X-RAY In all cases of fracture in the shoulder region, the usual




FIG. 245 The various positions of the humerus in relation to the scapula which may be useful in difficult fractures —

- A Abduction and external rotation (Polkeman stop position)
- B Abduction and neutral rotation
- C Adduction and neutral rotation (hand pointing forwards)
- D Adduction and internal rotation (In the thoraco brachial box, a position midway between C and D is used—with the arm at a tangent to the chest)
- E Adduction forward flexion and neutral rotation (Zeno's position Fig 248)

antero posterior film should be supplemented by a film in the lateral plane taken from the axilla with the arm abducted. Abduction, if painful, should be obtained after the injection of local anaesthetic or under the influence of a general anaesthetic. This is very important as a case in which there is little displacement in the A.P. picture may show gross displacement in the lateral view. (Figs 251, 252)

Treatment In many cases there is no displacement, or very little, and these cases can be retained in position by any of the following methods preferred. Where there is displacement it must be reduced by manipulation. Whatever the displacement, the most important manoeuvre is that of traction in abduction, which may be applied by traction on the forearm. (In uncomplicated fractures pin in the olecranon is unnecessary.) This is accompanied by manipulation of the fragments by the fingers in the axilla, and varying degrees of rotation till the position is felt to be satisfactory. It is conveniently done under a screen if X rays are available. A few fractures in which the upper fragment is adducted may require firm pressure in the axilla, such as from a foot, and strong adduction of the extended arm over this, but generally long and steady traction till the muscles relax produces reduction. Local or a general anæsthesia can be used as preferred.

Once reduced, there is considerable discussion as to the method of retention. The choice lies between

1 Treatment in adduction (a) Without extension (b) With extension (Robert Jones' bent arm splint)

2 Treatment in abduction (a) Without extension (b) With extension

The debate as to whether abduction or adduction gives the best result is carried on with undiminished vigour. All shoulder injuries are liable to be followed by limitation of movement out of proportion to the damage, and it was in an endeavour to minimise these bad results that treatment in abduction was devised. Whatever method is adopted it must be remembered that freedom of movement is the object, and so early assisted active and passive movement should be begun to avoid adhesions. It is abduction, together with internal and external rotation, which is most limited in all cases. Treatment in abduction does not increase the amount of abduction possible at the shoulder, for both methods if thoroughly carried out should result in the same degree of shoulder stiffness, but it increases the amount of abduction possible by utilising the uninjured rotation of the scapula to its fullest extent. To bring the arm to the side the stiff shoulder, treated in abduction, swings the scapula nearer the mid-line, and this degree of rotation is added on to the normal rotation of the scapula in full abduction. The disability is not less, but to some extent hidden and overcome. It is also a fact that a stiff abducted arm much more readily regains adduction than a stiff adducted arm. Abduction, owing to the assistance of gravity. For these reasons treatment in abduction is favoured, so long as it is realised that an arm put in the abducted position is only half treated and exercises are as thoroughly carried out as when other methods

are used. It must be remembered that the abducted position in an ambulatory patient is uncomfortable, the splint is difficult to maintain in position, and if allowed to slip may actually displace the fracture. Where, for other reasons, the patient must be in bed the position is not difficult to maintain.

Treatment in abduction is advisable in the following cases, to simplify dressing or avoid swelling:

1 Cases with severe soft tissue injury, compound fractures, or after operative reduction, or with damage to the glenoid.

2 Cases in which the fragments cannot be retained in position in adduction.

3 All cases requiring efficient extension.

4 Cases with deltoid pouches.

METHODS OF OBTAINING ABDUCTION. *The abduction splint.* This may consist of the well padded Cincinnati splint (see Fig. 101) or the manufactured splint which is fully adjustable. In the simpler splint the elasticity of the splint provides a rather weak extension.

In the manufactured splint of the Bohler pattern a measured tension may be applied by a spring balance. Traction may, of course, be made by strapping or skeletal traction. The application of the splint has been described earlier (See Chapter XII).

Abduction in the recumbent position. This has usually been obtained by a Thomas arm splint which is very uncomfortable around the shoulder, due to

pressure when lying on the ring. The full extension of the elbow joint is also very uncomfortable. For these reasons it has been abandoned for traction with the bent elbow by a simple apparatus such as that illustrated in Chapter XII. A weight of 6 to 10 lbs. is usually sufficient. In certain cases, and where the apparatus described is not available, it may be advantageous to use Zeno's position. In this position the arm is held above the head with the elbow flexed, the arm fully flexed at the shoulder and midway



FIG. 246 Bohler's splint for treatment of the arm in abduction. Front view.

between internal and external rotation. Strong traction can be obtained by a wire in the olecranon, with the patient's weight as counter-extension. The position is useful where the upper frag-



FIG. 247. View from above showing the hand in front of the face and the arm brought forward from the frontal plane to relax the pull of the pectorals.



FIG. 248. Zeno's position. In place of the Kirschner wire in the olecranon a long strip of elastoplast may be placed along the arm and bandaged on. This serves well where the position is being used for other reasons than the treatment of a fracture.

ment is flexed and adducted, and where other injuries make easy access to the shoulder essential.

The length of time in the abducted position is governed by the progress of the case. After a fortnight or three weeks the tendency to redisplacement has usually passed, and the extension may be

Indirect compound fracture The small distal fragment tends to be displaced upward and forward, which does not interfere with flexion

INCIDENCE Confusing figures are given owing to a failure to separate adult from children's figures. Extension fractures are most common in children (supra condylar) and less common in adults, where the extension strain produces a posterior dislocation of the elbow. Flexion fractures are more common in adults and less common in children, and in adults the lower fragment is commonly comminuted, producing the T-shaped fracture

DIAGNOSIS The patient has lost the use of the forearm, and holds it with the hand of the opposite side. The deformity tends to resemble that of a dislocation of the elbow, the forearm appearing lengthened. The three bony points of the elbow are in their normal relationship, and occasionally the spicula of the humerus may be felt as a fourth. False motion of the forearm forwards is free, but backwards is limited

Treatment **REDUCTION** is readily accomplished as follows. A general or local anæsthetic is used. Manipulations are easier with the patient sitting which is an advantage favouring local anæsthesia. The arm is fixed by an assistant. Grasping the forearm firmly with both hands and with the thumbs in the cubital fossa and the fingers on the epicondyles and fracture site, the elbow is flexed to a right angle and then strong pressure made in the line of the humerus, to restore the length of the bone. When this has been done the forearm and the lower fragment are pushed directly backwards, where they should engage firmly

RETENTION in this type of fracture is not as a rule as easy as in extension fractures, but slight deformity is not so important as it is in the latter. A plaster gutter splint with the arm at right angles and the slab applied to the anterior aspect of the arm will be satisfactory in most cases, but in a few this will fail. The alternatives, then, are extension with a pin in the olecranon, which is maintained till early union has occurred, or a plaster gutter splint with an extended elbow, which is very satisfactory in children. The reluctance to use this position is unnecessary. Children, and to a less extent adults, regain flexion as easily as extension. There is no risk of swelling causing pressure, and in this position radiography gives one a more accurate idea of the position of the parts

Union occurs rapidly, in children in three to four weeks, and in adults in four to five weeks. While exercises to uninvolved joints are to be encouraged, it is important to keep the elbow at rest so long as resolution is occurring. There is a tendency for ossific deposits to occur round the elbow in the muscles and in any




FIG 203 T shaped fracture into the elbow joint Antero posterior view



FIG 204 Lateral view of same case



FIG 265 Same case as previous figure under olecranon skeletal traction with a bent elbow Lateral view



FIG 266 Same case as previous figure showing the final result in the antero posterior X ray

hematoma present, and this is encouraged by any further trauma to the region from early movement. After adequate immobilisation as outlined, the arm is carried in a sling, and gentle active movements which do not produce pain encouraged. When these are free the sling is abandoned. At no period are passive stretching exercises or strong active exercises, to be used. These inevitably increase the stiffness of the joint. To measure the amount of improvement in movement of the joint some form of angle measuring instrument (or goniometer) is important, and a convenient type is illustrated in Fig. 107.

In children, even with remarkable displacements, the return of function is good, but in adults there is liable to be permanent limitation. Where limitation occurs in children one of the complications outlined later has usually occurred.

T-shaped fractures. The fragments are frequently grossly misplaced, and appear to lie in a pool of blood in which manipulation becomes uncertain and retention impossible. Full return of function of the elbow demands accurate reconstruction of the lower end of the humerus. Even at open operation this may be difficult. Treatment by traction with a pin through the olecranon and the elbow held at a right angle will generally get the fragments into good position and maintain them there. If the position is unsatisfactory at first the fragments are manipulated under anaesthesia. A very convenient apparatus for maintaining traction with the elbow flexed is that described in Chapter XII. It is comfortable for the patient, adaptable to many positions and comparatively simple and cheap. Treatment should be commenced at the earliest possible moment and this is particularly so in children, in whom callus rapidly forms. Failure to obtain satisfactory position at the end of a week by this method demands open operation through a posterior approach. The use of metal retentive apparatus is advised in adults but in children suture with strong catgut after drilling the bones is best.




FIG. 26~ Extension fracture of the lower end of the humerus showing the manner in which the brachial artery may be pressed upon.

Extension Fractures, Supracondylar Fractures, and Complete Epiphyseal Separations

IN EXTENSION FRACTURES the line of fracture runs from behind, downwards and forwards, leaving a sharp spicule of bone anteriorly, which is liable to be pushed into the cubital fossa. It is less inclined to produce indirect

compound fracture thru the spicula in flexion fractures. In children the obliquity tends to be less marked, and the separation less complete. Many supra condylar fractures are really transverse, and of the greenstick variety. The short distal fragment is commonly displaced backwards (74 per cent), and if detached this displacement is increased by the pull of the triceps. Displacement may be marked, indicating severe periosteal damage, with the formation of a large hæmatoma. This is important, as it may lead to ossific deposits outside the usual limits. The capsule is attached above the epiphyseal line



FIG 268 Extension fracture of the lower end of the humerus united with posterior displacement



FIG 269 Supra condylar fracture of the lower end of the humerus

and so the joint is inevitably involved in epiphyseal separations, and almost inevitably so in supra condylar fractures.

EPIPHYSEAL SEPARATIONS The separation of the conjoined epiphyses as a unit can only occur before the trochlear portion of the diaphysis has grown down between the epiphyses for the medial and lateral condyles. It therefore does not occur after the fifth year. The mechanism and displacement is essentially the same as a supra-condylar fracture, the separation occurring on the metaphyseal side of the cartilage.

DIAGNOSIS The ease of diagnosis depends on the separation of the fragments. At one end of the scale we have the child in whom no deformity is visible, very little bruising, and slight tenderness in a line above the condyles combined with a reluctance to use the limb. At the other end of the scale is the adult in whom the condition resembles a posterior dislocation of the elbow, with gross

deformity, apparent shortening of the forearm, and prominence of the olecranon behind. False movement at the fracture site is generally easily elicited, though swelling may be so great as to obscure the usual bony landmarks. Supra-condylar fractures being so common in children it is the age of the patient which gives the clue to the diagnosis in most cases.

Treatment Cases in which there is no displacement (22 per cent) and little swelling may be treated by a cuff and collar for two weeks, a sling for a week, and then active movements. As there is no periosteal tearing there is no fear of excessive ossification in the surrounding tissues from comparatively early use.



FIG. 270 Reduction of an extension fracture of the lower end of the humerus

When there is displacement it should be reduced. It only takes a moment with firm pressure of the thumbs over the lower end of the humerus to restore the part to normal if there is no tension in the soft parts and it can usually be felt to grate as it returns to position, and when in position full flexion of the elbow can, and must, be obtained. In children there is little tendency to recurrence. Acute flexion, the natural splint position, has been recommended for this fracture as the ideal method of retention. In most cases the fragment stays in position easily, and the right angle position is more comfortable and less worrying. A posterior plaster gutter splint and a sling for three weeks, followed by a sling only for a week or two, is usually quite satisfactory.

It is in the older children or in adults that trouble arises from

difficulty in reduction, due to a tense hematoma around the fragments and incomplete reduction is followed by difficulty in retaining the fracture in position. Retention may be found easy when the arm is put into acute flexion and the triceps made to act as a splint, but such a position must be most carefully watched owing to the risk of vascular obstruction. In the majority of patients the position with the arm in a posterior gutter splint and held at right angles is satisfactory. When neither of these methods suffice in adults one must use skeletal traction with a pin in the olecranon and the elbow at right angles. At the end of four weeks the plaster or other support can be discarded, and the arm is then carried in a sling for two weeks. Flexion is encouraged in the sling, but active extension is not allowed till the sling is removed in the sixth week. In children it is better to fix the limb temporarily and wait till swelling has subsided, when reduction can usually be achieved. Too much time must not be allowed to elapse between attempts, as union is rapid. Failure to obtain perfect position (Fig. 268), is not followed by any untoward result, the humerus remodelling itself to allow full flexion.

Very rarely operative reduction is necessary. This is done through a lateral incision. Fixation by olecranon traction and plaster or plaster alone follows, and as in all cases in which it is desired to get rid of swelling around the elbow early use of an abduction splint or Zeno's position is made. In Zeno's method the forearm is hung over the chest in a sling, while traction is exerted in the line of the humerus by the wire in the olecranon (Fig. 247). If the arm has been plastered without the use of a Kirschner wire stripping is attached to the arm portion of the plaster.

In both extension and flexion fractures there has been considerable discussion as to the influence of pronation and supination on the lower fragment. The only possible movement of the lower fragment on a fixed forearm is flexion and extension. The pull of the pronators and supinators can only perform this movement. Certainly the adduction and abduction of the lower fragment can be controlled by the pronation and supination of the forearm, but this is due to rotation developed around the central line of the forearm, and not due to relaxation of muscles. The best position of the forearm is that of mid-pronation.

Incomplete Fractures of the Lower End of the Humerus

Fractures of the lateral epicondyle. This is an uncommon lesion owing to the lack of prominence of the lateral compared with the medial epicondyle. In either fracture the mechanism is similar.

(a) Due to direct violence

(b) Due to adduction (or abduction) strains of the extended elbow, when the tensed extensor (or flexor) group of muscles pulls off the epicondyle

(c) In association with a dislocation of the elbow

CLINICAL FEATURES In fractures of either epicondyle there is usually little displacement. The chief features are local pain and bruising. The bruising may extend down the group of muscles attached to the epicondyle, and result in pain and paresis of the group. There is a variable amount of effusion into the elbow, and limitation of movement. In cases with no displacement the X-ray distinguishes the condition from a severe bruise.

DIFFERENTIAL DIAGNOSIS Old fractures may fail to unite, and be regarded as a recent lesion, but the layer of compact bone on the supposed fractured surface in old lesions shows the condition to be of some standing. In fractures of the medial epicondyle the epiphyseal line which is usually much more even than the fissure of a

fracture, may cause confusion. An X-ray of the opposite side may aid in distinguishing the condition, but in the absence of displacement an X-ray later which may show the presence of callus is the only proof available that there was a lesion through the epiphyseal line. If the case is clinically a separated epiphysis it is best treated as such in spite of negative X-ray evidence.

Another cause of difficulty are plates of ossified tissue which may occur in the fibrous intermuscular septa of the flexor and extensor




FIG. 271. Ossification in the intermuscular septa attached to the medial epicondyle of the humerus. See also Fig. 244.

muscle groups. These are usually multiple and bilateral. They show a well organized periphery (Figs 271, 285).

Bony deposits in the tissues of osteoarthritic elbows, or

ossifications in hematomas after old injuries, may occasionally be confusing

Treatment In cases without displacement a sling is sufficient till the pain has gone. In cases with displacement, longer rest is necessary as there is associated damage to the joint, but there is very rarely the necessity to peg the fragment back into position, seen with the medial epicondyle. After four weeks, gentle exercises in the sling are commenced and this is abandoned in a week. Full function is restored in five to six weeks, there being, as a rule, no disability.

Fracture of the lateral condyle (and capitellum) In children from the age of six to fourteen an essentially similar lesion is a fracture separation of the lateral epiphysis. Separation is on the meta-



FIG. 272. Fracture of the lateral condyle of the humerus with posterior dislocation of the head of the radius, to which it has remained attached.

physical side, and usually takes a flake of bone with it. The diagnosis and treatment is similar to the adult condition.

TYPE OF INJURY The fracture is most commonly due to falls on the extended or partly flexed arm, in which the force is transmitted along the radius, and so may be associated with fracture of the head of the radius. Direct injury, such as may occur in falls, in which a sharp edge is struck by the condyle, may cause the condition, and fractures from severe adduction strain may involve the condyle rather than the epicondyle. The fracture runs from the lateral epicondylar ridge to the medial aspect of the capitellum. Displacement of the fragment with the extended and abducted arm tends to be out and up, and with the adducted arm down and inwards. It is important to remember that in cases associated with disloca-

tion of the head of the radius the capitellum remains attached to the head of the radius and moves with it

DIAGNOSIS The symptoms are those of severe injury to the epicondyle, together with increased lateral movement at the elbow joint, which is distended with blood. The lower end of the humerus is broadened, and the lateral condyle can be moved separately in an A P plane with the production of crepitus. It is important to note that dislocation of the head of the radius from the upper radio-ulnar joint and lateral dislocation of both bones of the forearm are common accompaniments of the lesion, and must be excluded by careful lateral and A P X-rays

TREATMENT Cases may be grouped into those with, and without, displacement. In cases without displacement the ligamentous attachments of the condyle are holding it in place, and relaxation by a high sling or collar and cuff for two to three weeks will be sufficient. Where the displacement is slight and accompanied by swelling, a dorsal plaster gutter splint with the arm at right angles will be better. Exercises are begun at the end of three to four weeks.

Displacement varies. It may be (1) Posterior, accompanying the head of the radius, (2) Rotation, so that the fractured surface

looks laterally. (3) Varying displacements to a lesser degree. Reduction must be attempted under local or general anaesthesia. In the first group reduction of the radio-ulnar dislocation reduces the fracture as well. The second group may be difficult, and usually require operative replacement, but they may be replaced by manipulation of the fragment, especially if the case is seen early before gross swelling has occurred. After replacement retention is often more satisfactory with the arm extended. Similar principles apply to the third group in which replacement by manipulation is usually not difficult. Retention is by a plaster gutter splint, with the elbow at right



FIG. 273 Fracture of the lateral condyle of the humerus with rotation so that the fracture surface looks outwards

angles, where possible, for three to four weeks, followed by a sling for a fortnight, after which gentle movements are begun.

OPERATION The approach is best made through a posterior incision, and the triceps retracted till the fractured surface is seen. When the clot is cleared away the twisted condyle may be readily untwisted and restored to position. It is drilled with a fine hand awl, and corresponding drill holes made in the shaft of the humerus. These are then threaded with catgut which is firmly tied. After operation the arm is put on a posterior plaster slab with the elbow at right angles, and the joint is moved at the same time as the cases treated non-operatively.

Fractures of the capitellum In this not uncommon condition, a flake of bone may be knocked off the round surface of the capitellum by the impact of the head of the radius and may be associated with fracture of the head of the radius. It may vary in size, and, unless large, is usually overlooked, even in the X-ray, owing to it being largely cartilaginous. Later locking and arthritic symptoms develop as it forms a loose body in the joint, or attaches itself in a situation limiting movement (osteochondritis dessicans of the elbow). The immediate symptoms of the lesion are effusion into the elbow, with variable pain, limitation of movement, and some pain on pronation and supination. These may be very slight. It is usually diagnosed on the X-ray findings.

Treatment Large fragments frequently remain in good position and should be left, the elbow being rested in a plaster. Smaller fragments, if noticeable on the radiograph, are usually displaced and lying loose in the joint. They should be removed. Occasionally the anterior half of the capitellum is sheared off and displaced upwards (Fig 274). It should be reduced by open operation and can usually be retained in position by flexion of the elbow. Satisfactory union follows.

Separation of the capitellar epiphysis This occurs in children up to the age of ten, before the capitellar epiphysis fuses with the other epiphyses to form the lateral epiphysis whose separation is similar. In separation of the epiphysis of the capitellum alone the cartilaginous structure of the lateral condyle and the trochlear are involved, but they are not shown in the X-ray film.



FIG. 274. Fracture of the capitellum resulting in upward displacement of a hemispherical fragment of bone.

The injury may occur in the same way as that to the lateral condyle. Displacement may occur backwards, forwards, or laterally, or these displacements may be combined, which is usually the case.



FIG. 275 Cohn's lines showing the normal relation of the capitellar epiphysis to a line along the anterior surface of the humerus and one parallel to this through the centre of the shaft.

SYMPTOMS These resemble supra condylar fracture. Suspicion may be aroused by noting that there is a slight lateral dislocation



FIG. 276 Slight posterior displacement of the capitellar epiphysis.



FIG. 277 Lateral displacement of the capitellar epiphysis. Lateral view showing the slight associated posterior displacement.

of the forearm, in cases seen before swelling has occurred. In most cases the differential diagnosis from supra condylar fracture depends



Fig. 278 Antero posterior view showing the lateral displacement of the epiphysis



Fig. 279 Antero posterior view of the normal elbow for comparison



Fig. 280 Antero posterior view of the elbow after reduction

on the X-ray. In spite of good X-rays careful examination of films is necessary to distinguish the lesion and this demands a knowledge of the normal relations of the epiphysis to the diaphysis. In the antero-posterior film the capitellar centre appears as a triangular shadow, with a sloping upper surface lying against the diaphysis. The outer edge is slightly curved and lies distinctly medial to a line joining the lateral epicondyle and the head of the radius in a true A P film (Fig 279). The upper end of the ulna when the arm is extended overlaps the medial end of the capitellar shadow. According to the direction of the chief displacement so the lateral or the A P X-ray gives the most information. In the lateral film of the normal arm the epiphysis is seen as a rounded shadow lying below the shaft of the humerus and in front of it. This can be best shown by prolonging two lines through the epiphysis. The first runs down the anterior surface of the humerus. The second is a line parallel to the first through the centre of the shaft. Up to the age of nine the epiphysis lies behind the anterior line. After the ninth year two thirds of the epiphysis is in front of it, while the whole epiphysis is

in front of the posterior line (Fig 275).

In lateral displacement there are two points to look for

- 1 The outer edge of the epiphysis is now nearer the line joining the lateral condyle and the head of the radius

- 2 The ulna shadow, unless the bone is dislocated, lies free of the shadow of the capitellar centre, or just over its edge (Fig 278)

In anterior displacements the epiphysis may lie in front of the anterior line but most often

it is only moved a small distance in front of the posterior line, which runs down the centre of the shaft.

For these comparisons accurate films in the A P plane and the




FIG 281 Anterior displacement of the capitellar epiphysis

lateral plane are required, with the elbow completely extended in the A P film and flexed in the lateral view. Comparative pictures of the opposite side are useful. Flexion of the elbow alters the



FIG 282 The reduction of lateral displacements of the capitellar epiphysis

relation of the ulnar shadow to the capitellar centre, but does not alter the relation of the capitellar centre to the humerus, and if extension cannot be obtained the humerus must be kept parallel



FIG 283 Fracture of the medial condyle of the humerus into the olecranon



FIG 284 A fracture of the medial humeral condyle of the type shown in Fig 283 accurately plated by Lane

with the plate that this observation at least is accurate. Films for comparison must be made with the sound elbow at the same angle as the injured one.

Treatment Reduction is by manipulation. In posterior displacements full firm flexion of the elbow is made, while gentle forced

hyper-extension of the elbow reduces anterior displacements. In lateral displacements lateral pressure is required, and can be easily applied by a narrow padded board, which is firmly pressed into the flexed elbow as it lies on its inner side, between the lateral condyle and the head of the radius (Fig 282). There is no tendency for the epiphysis to redisplace, and a cuff and collar is sufficient for retention. In two to three weeks a sling is used and movements allowed inside this, and it is discarded a week later. In a correctly reduced case there is no disability. In cases which are neglected there is loss of extension.

Fractures of the medial condyle. The mechanism is essentially similar to that of fractures of the lateral condyle. The associated dislocations of the elbow are posterior and medial. The line of the fracture runs up from the just lateral to the trochlea almost vertically to the medial supra condylar ridge. From the mechanics of the injury it can be seen that the ulna will frequently be displaced medially with the fragment. Dislocation of the head of the radius may be associated. Symptoms are comparable to those of lesions of the lateral condyle. Displacement tends to be greater owing to the disturbance of the ulna, and there may be symptoms of ulnar nerve pressure. If the head of the radius is dislocated in addition to the dislocation of the ulna the elbow is quite unstable after reduction and requires both extension and lateral pressure to control it. If the ulna alone is dislocated the displaced condyle can usually be restored to a stable position. Treatment will be along the following lines.

1 No displacement. Posterior gutter splint, three to four weeks.
Sling, two weeks.

2 Slight displacement. Reduction by manipulation and posterior gutter splint.

3 Gross displacement. Reduction by manipulation, and retention by

(a) Pin through the olecranon and traction with pressure on the epicondyles.

(b) If this fails, open operation and fixation (Fig 284).

Accurate reduction is essential if the elbow is to function normally, and time should not be wasted between efforts to reduce the bone as callus is thrown out very early, particularly in children. The method of operative fixation in children is the same as adopted for fractures of the lateral condyle, but in adults a bone peg or screw may have to be employed.

Fractures of the medial epicondyle, and epiphyseal separation. The medial epicondyle being more prominent is more easily damaged than the lateral, but the mechanism is much the same. Abduction

strum plays the part of adduction strum, and up to the age of sixteen the lesion may take the form of an epiphyseal separation. The most important mechanism, however, is that associated with a lateral dislocation of the elbow. When the elbow is seen dislocated the lesion is usually recognised, but in many cases there is a spontaneous reduction of the elbow after the accident and the small fragment of the medial epicondyle is caught between the sigmoid notch of the ulna and the trochlea, where it may be easily overlooked with grave consequences later (see p 612 and Fig 286)



FIG 285 Heterotopic ossification in the region of both epicondyles. One fragment on the medial side is an old displaced medial epicondyle. The lateral fragment is an ossification in the radial collateral ligament.



FIG 286 Dislocation of the elbow with accompanying fracture of the medial epicondyle showing it displaced in front of the trochlea (see p 612)

DIAGNOSIS The symptoms are comparable to those of the lateral epicondylar lesion. The flexor group of muscles may be weakened with inability to fully flex the fingers. Characteristic bruising extending down the flexor pronator group of muscles may be seen. The ulnar nerve is damaged to a variable degree in most cases, and in the cases where the fragment has been displaced into the joint there is always a temporary complete lesion. In these cases haemorrhage may obscure the fact that the epicondyle is missing from its usual situation. Where it still remains in position abnormal mobility can be detected. With the fragment displaced into the joint there is a gross effusion of blood into the joint and

restriction of movement, though the latter may not be as great as might be expected. The X ray in such a case shows a fragment with a well defined rounded border lying in the sigmoid notch, and usually best seen in the lateral film. Though the absent epicondyle is obvious it has been frequently overlooked and the A P film regarded as normal. This is a serious error.

Treatment If there is no displacement, the flexor group is relaxed by a low cuff and collar. This is maintained for two to three



FIG 287 Fracture of the medial epicondyle with displacement of the epicondyle into the joint. Lateral view



FIG 248 Fracture of the medial condyle with displacement into the joint. Antero posterior view, showing the epicondyle lying between the trochlea surface of the humerus and the sigmoid notch of the ulna. (Same case as Fig 287)

weeks, and then a sling is substituted for it, and movements inside the sling commenced. At the end of a further week the sling is discarded.

When there is moderate displacement but the fragment is not in the joint, it can usually be neglected. Any grosser displacement is uncommon and requires pegging or suture.

If the condyle is in the joint operation is essential. A vertical incision is made over the condyle and the common flexor origin will be found to lead down to the fragment which lies in the joint. It is removed and the flexors and fragment stitched back in position.

Most surgeons take the opportunity to transplant the damaged ulnar nerve anteriorly at the same time. The after treatment is similar, except that immobilisation is maintained for three to four weeks before movements are allowed. In young people satisfactory union with no disability follows. In older patients there is likely to be some difficulty in regaining full extension.

In cases with little or moderate displacement the prognosis is always good.

Complicated or compound injuries to the elbow. These are treated on the same general lines as compound fractures elsewhere. To reduce swelling rapidly no position is so good as Zeno's position. For complete immobilisation in a compound fracture a cast is applied from the axilla to the heads of the metacarpals (Fig 120). This may be put in Zeno's position by a strapping extension to the arm portion of the plaster, and a sling under the forearm. If a Kirschner wire has been used in the reduction its retention in the olecranon makes suspension so much the easier. If the swelling does not warrant elevation of the arm, it is wise to keep the patient in bed for a few days to reduce the swelling and œdema around the joint.




FIG 289 Diagrammatic section of the lower end of the humerus showing the correct site for insertion of a Kirschner wire into the ulna and its relation to the elbow. A Posterior capsule of the elbow. B Section of the trochlea. C The joint space. D Section of the sigmoid notch of the ulna. E Area of the ulna through which the Kirschner wire is best inserted.

Complications of fractures in the elbow region. IMMEDIATE (See Chapters V and VI for complications in general.)

1 *Dislocation of the elbow.* The relationship of this to various fractures of the elbow has been discussed, and it indicates more serious damage to the joint, longer immobilisation, and a worse prognosis (see also p 612).

2 *Dislocation of the head of the radius* from the radio-humeral and radio-ulnar joint. (Mentioned so that it will not be overlooked.)

3 *Injuries to the main blood vessels.* If ruptured the vessel requires urgent treatment, as do all ruptured vessels. It is particularly important that the development of a tense hæmatoma in the cubital fossa be avoided. (See Volkmann's contracture and p 48.)

4 *Injuries to the nerves.* Radial, ulnar, and median. This must be examined for and treated as outlined previously.

DELAYED 1 *Myositis fibrosa* (Volkmann's ischæmic contracture) See earlier chapters for pathology and treatment

2 *Myositis ossificans* Occurs in the brachialis as a rule It is increased by early passive and active movements (See earlier chapters)

3 *Excessive callus formation* This may occur in all fractures in this region, with the exception of epiphyseal lesions It is stimulated by early movements and is another reason why these should be avoided Immobilisation results in its reduction in size in the early stages

4 *Ossifying hæmatoma* Related to excessive callus formation (See earlier chapters)

LATE 1 *Mal-union* Due to neglect, or to unavoidable causes The most common disabilities met with are (1) Posterior displacement of the lower fragment of the humerus in supra-condylar fractures with a consequent loss of flexion This is cured by the growth of the bone in children In adults an oblique osteotomy, with traction, may improve the position, but it is seldom necessary and is not a reliable cure (2) Upward displacement of either condyle This may lead to an adduction or abduction deformity at the elbow In early cases it may be improved by osteotomy and fixing the arm in a corrected position (3) Irregularity of epiphyseal growth This leads to the deformity outlined above Operative interference in these cases is inadvisable

2 *Late ulnar neuritis* This arises years later from the continued friction of the ulnar nerve in the ulnar nerve groove It may be due to stretching of the nerve in an abduction deformity in which the carrying angle is increased, or due to pinching in an adduction deformity, in which the olecranon approaches the medial condyle, or due to excessive callus around the medial epicondyle Anterior transplantation of the nerve effects a cure It is most commonly associated with mal-union of fractures of the lateral condyle

3 *Traumatic arthritis* This is essentially similar to the same condition in joints elsewhere While the absence of weight bearing relieves the joint of some strain, its peculiar construction and combined activities render any small alteration of alignment of bony surfaces a continued source of strain Degeneration occurs with resultant pain, limitation of movement, presence of loose bodies, and occasional locking, while weakness of the grip and pain in the forearm is commonly complained of The general aspects of treatment have been discussed before

REFERENCES

Upper End of the Humerus

WATSON JONES "Fractures in the Region of the Shoulder Joint," *Proc. Roy Soc Med*, 1936, 29, 1058

- CORDON "Fractures of the Upper End of the Humerus," *Im J Surg*, 1937, 38, 495
- FUNSTEN, R. V. "Fractures and Dislocations around the Shoulder," *J Bone and Joint Surg*, 1930, 18, 191
- FRANKAU, C. "Reduction of Fractures of the Surgical Neck of the Humerus," *Lancet* 1933, 2, 755
- FAIRBANK, F. J. "Fracture Subluxations of the Shoulder," *J Bone and Joint Surg*, 1948, 30b, 454-460

Lower End of the Humerus

- ARTHUR, A. "Intra articular Displacement of the Internal Epicondyle following Dislocation," *J Bone and Joint Surg*, 1938, 20, 161
- FAIRBANK and BUNTON "The Displacement of the Internal Epicondyle into the Elbow Joint" *Lancet* 1934, 2, 218
- BUNTON "Ossification in the Ligaments of the Elbow Joint," *J Bone and Joint Surg*, 1938, 20, 709
- CORN, I. "Observations based on the Study of Injuries to the Elbow," *Arch Surg*, 1921, 3, 357
- SCRIS, I. E. "Supracondylar Fracture of the Humerus" Analysis of 330 cases *Surg Gynec Obst*, 1939, 68, 201 (Analyses the displacement None, 22 per cent, backward, 74 per cent, forward, 4 per cent)
- JONES ROBERT "Remarks on Injuries about the Elbow in Children," *Brit M J*, 1932, 1, 739 (Good summary and general criticism)
- WEST, L. F. "Fractures in the Region of the Elbow," *Med J Australia*, 1937, 1, 773 (With further references)
- ROBERTS "Displacement of the Internal Epicondyle into the Elbow Joint Four Cases Treated by Manipulation" *Lancet*, 1934, 2, 78
- EASTWOOD "The T shaped Fracture of the Lower End of the Humerus" *J Bone and Joint Surg*, 1937, 19, 3 and 64
- WILSON "Fracture of the Lateral Condyle of the Humerus in Childhood," *J Bone and Joint Surg*, 1930, 18, 312 (With full bibliography)

CHAPTER XXII

FRACTURES OF THE RADIUS

Surgical anatomy The head of the radius lies comparatively superficially below the lateral epicondyle, and above and behind the outstanding belly of the brachio radialis where it can be readily palpated and rotational movements imparted to it by twisting the wrist can be appreciated. The head of the radius plays a part in two joints, the radio ulnar, and the radio humeral. One fifth of its circumference only is in contact with the lesser notch of the ulna, but a segment of 160° comes in contact with it on pronation and supination. It is plain that fractures involving this 160° segment will affect movements more than fractures in that part only in contact with the annular ligament.




FIG 290 The correct method of examining the head of the radius for loss of rotation, or eccentric movement




FIG 291 Diagrammatic transverse section of the upper end of the ulna at the level of the head of the radius to show the 60 degrees of circumference of head normally in contact with the lesser sigmoid notch and the range of movement of pronation and supination on either side of it

The shaft The muscle balance is situated around the pronator teres insertion, which is into the highest part of the curve of the bone. Displacement in fractures of the shaft varies in relationship to this point.

1 Above P teres Upper fragment Flexed and supinated by biceps, and supinated by supinator brevis

Lower fragment Pronated by pronator teres and quadratus and adducted by pronator quadratus.

2 Below P teres Upper fragment Flexed by biceps. Drawn medially but remains midway between pronation and supination.

Lower fragment Drawn medially by pronator quadratus and insertion of brachio radialis and pronated.

The close relation of the abductor pollicis longus and the extensor pollicis brevis to the bone here is to be noted but they are at too great a mechanical disadvantage to produce displacement though they may be caught between the bone ends.

Lower end The bony architecture of the bone here is important for it is at the junction of the thick layer of compact bone of the shaft with the thinner lamella clothing the cancellous bone of the distal end that the bone




FIG 292 Diagrammatic view of the left forearm to show the influence of the various muscles in displacing fractures of the shaft of the radius
 A Biceps B Pronator teres C Pronator quadratus D Fracture below the insertion of P. teres E Fracture above the origin of P. teres
 H Humerus




FIG 293 Antero-posterior view of the lower end of the radius to show the angle of approximately 30 degrees made by the articular surface with the transverse




FIG 294 Lateral view of the lower end of the radius to show the manner in which the articular surface looks downward and forward, at an angle of 10 to 15 degrees with the vertical




FIG 295 Comparison of the relative levels of the radial and ulnar styloid processes of both wrists

gives in many fractures. The transition is very rapid, and the area is at a consequent mechanical disadvantage. The upper margin of the articular surface overhangs the lower, so that the joint surface looks forwards and down at an angle of 10° to 15°, with the A P plane. The articular surface also makes an angle of 25° to 35°, with the transverse at the lower end of the bone and these angles are important in the transmission of force along the bone

and so determine the lines of fracture The styloid process lies $\frac{1}{2}$ inch distal to the styloid process of the ulna

Ossification Radius and ulna

Primary centres for the shafts appear at seventh week

Secondary centres (Rarely additional centres for the tip of the olecranon and radial styloid process)

Distal	R	Appears second year	Unite with shaft eighteen to twenty one
	U	Appears fourth year	Ulna joining first
Proximal	R	Appears fifth year	Unite with shaft seventeen to twenty
	U	Appears tenth year	Ulna joining first

FRACTURES OF THE HEAD OF THE RADIUS

These may be due to

Direct violence Comminuted fractures Fractures of neck

Indirect violence Fissure fractures, impacted and infraction fractures

Other injuries commonly associated with fracture of the head of the radius may be

1 Dislocations of the elbow

2 Fractures of the shaft of the ulna

3 Dislocations of the head of the radius alone

4 Fracture of the lateral condyle

5 Chip off anterior surface of the capitellum (This will not show in the X ray if it is entirely cartilaginous)

6 Rupture of ulnar collateral ligament of the elbow

Types of fracture 1 *Chip* This is due to two radial fissures meeting and leaving a small fragment free



FIG 296 Chip fracture of the head of the radius Compare Fig 300



FIG 297 Fissure fracture of the head of the radius Compare Fig 304

2 *Fissure* This may be complete, which virtually produces a large chip fracture or an incomplete split

It is the commonest lesion of the head of the radius, and due to either heavy impaction against the capitellum, or forced abduction of the forearm at the elbow



FIG 298 Fracture of the neck of the radius with displacement of the head




FIG 299 Varieties of infraction fracture of the head of the radius

Injuries to the medial side of the joint should therefore be sought for in association with the fracture The stretching is rarely sufficient to produce

an ulnar nerve paralysis but if it ruptures the ulnar collateral ligament may do so

3 *Impacted fractures* Usually just at the junction of the head and neck, where the compact bone is thin. May be difficult to detect, or there may be gross displacement of the head.

4 *Comminuted fractures* with gross damage and distortion.

5 *Epiphyseal separations*

DIAGNOSIS Usually a characteristic story of a fall on the extended arm is given, followed by pain in the elbow and loss of the movements of pronation and supination. The joint is usually filled by an effusion which limits flexion and extension if it is not already limited by other damage, but it is interesting to note that in the absence of damage to any other part than the head of the radius, pronation and supination may be complete, and full extension impossible, and this may be the only sign present.

Examination may show local bruising. Pain is usually well localised. It is tested for with the thumb at the same time as rotational movements of the head are tested for. This test may elicit crepitus. Rarely in fractures of the neck the head may not rotate, or more commonly an eccentric movement of the head is felt below the thumb (Fig 290).

Accurate diagnosis demands an X-ray, as the following conditions may be associated with, or mistaken for, fracture.

- 1 Fracture of the lateral condyle or epicondyle
- 2 Rupture of some fibres of the extensor group of muscles
- 3 Haemorrhage into the joint
- 4 Dislocation of the head of the radius, especially if spontaneously reduced



FIG 301
Comminuted fracture of the head of the radius. Compare Fig 300



FIG 302 Displacement of the epiphysis of the head of the radius. Compare Fig 300



FIG 300 Chip fracture of the head of the radius

5 Pulled elbow, in which the synovial reflection around the head is pinched.

6 Osteo-arthritis of the joint.

The following are some helpful points in the consideration of such cases

and so determine the lines of fracture The styloid process lies $\frac{1}{2}$ inch distal to the styloid process of the ulna

Ossification Radius and ulna

Primary centres for the shafts appear at seventh week

Secondary centres (Rarely additional centres for the tip of the olecranon and radial styloid process)

Distal	R	Appears second year	Unite with shaft eighteen to twenty one
	U	Appears fourth year	Ulna joining first
Proximal	R	Appears fifth year	Unite with shaft seventeen to twenty
	U	Appears tenth year	Ulna joining first

FRACTURES OF THE HEAD OF THE RADIUS

These may be due to

Direct violence Comminuted fractures Fractures of neck

Indirect violence Fissure fractures, impacted and infraction fractures

Other injuries commonly associated with fracture of the head of the radius may be

- 1 Dislocations of the elbow
- 2 Fractures of the shaft of the ulna
- 3 Dislocations of the head of the radius alone
- 4 Fracture of the lateral condyle
- 5 Chip off anterior surface of the capitellum (This will not show in the X-ray if it is entirely cartilaginous)
- 6 Rupture of ulnar collateral ligament of the elbow

Types of fracture 1 *Chip* This is due to two radial fissures meeting and leaving a small fragment free



FIG 296 Chip fracture of the head of the radius Compare Fig 300



FIG 297 Fissure fracture of the head of the radius Compare Fig 304

2 *Fissure* This may be complete, which virtually produces a large chip fracture or an incomplete split

It is the commonest lesion of the head of the radius, and due to either heavy impaction against the capitellum, or forced abduction of the forearm at the elbow.

Injuries to the medial side of the joint should therefore be sought for in association with the fracture The stretching is rarely sufficient to produce



FIG 298 Fracture of the neck of the radius with displacement of the head




FIG 299 Varieties of infraction fracture of the head of the radius

an ulnar nerve paralysis but if it ruptures the ulnar collateral ligament may do so

the wrist strongly. The annular ligament being intact then pulls the fragment up into position, and if the arm is put up in extension maintains it there. Extension being an awkward position for the patient, the arm is flexed as soon as the fragment has become attached, i.e., in ten to fourteen days. The arm is then carried in a sling for a further fourteen days, movements being attempted during the last week. After this full movement of the arm is permitted.

3 Impaction fractures If the head is in good position leave it, if poor, operate. In the young, replace, in the old, remove.



FIG 303 Same case as Fig 304 after treatment showing the restoration of the position of the fragment by treating the elbow in extension



FIG 306 Comminuted fracture of the head of the radius. X ray showing forward dislocation of the head of the radius and how the acute flexion of the elbow has produced the deformity. Treatment of the elbow in flexion would tend to maintain this

4 Comminuted fractures These can only be treated satisfactorily by removal of the whole head.

5 Separated epiphysis Replace by manipulation or open operation. Never remove owing to the probability of interference with growth.

It is not justifiable to temporise and see how the joint progresses. If it becomes stiff permanent damage is done which cannot be undone by late excision of the head of the radius.

OPERATION Carried out as a rule after the acute bruising has subsided, i.e., in three to ten days. A tourniquet is used. The incision is two inches long in the line of the bone over the head of the radius. The brachio-radialis is separated from the extensor carpi radialis, and the joint capsule exposed. By cutting vertically

Effusion of blood into the joint may be almost the only sign of fracture of the head of the radius

The patient may neglect the original injury and come up because of loss of extension of the elbow

In muscular rupture the strain is an extension strain and not compression. The hæmorrhago in this case tends to pass down the muscle group, and gives rise to characteristic bruising later

Treatment This demands careful consideration because of the two joint surfaces involved, and the fact that excision to attain its greatest success must be done early before the mal position of the head has produced a traumatic arthritis, *i e*, within two or three weeks

1 *Chip fractures* If in good position, immobilise with a cuff and collar for three weeks, and then commence active movements. If the chip is displaced and free it must be removed

2 *Fissure fractures* These can frequently be treated with



FIG 303 Comfortable cuff and collar sling made with a padded triangular bandage tied over felt at the wrist



FIG 304 Fissure fracture of the head of the radius with distal displacement of the fragment

a cuff and collar, as the fragment is in good position. With such fractures damage to the capitellum must be looked for which may result in more stiffness than may be expected. It is in fissure fractures, particularly the fissure most commonly met with, which separates almost the lateral half of the head, that the fragment is displaced downwards to some extent. This displacement can be corrected by placing the arm in full extension and adducting

the wrist strongly. The annular ligament being intact then pulls the fragment up into position, and if the arm is put up in extension maintains it there. Extension being an awkward position for the patient, the arm is flexed as soon as the fragment has become attached, i.e., in ten to fourteen days. The arm is then carried in a sling for a further fourteen days, movements being attempted during the last week. After this full movement of the arm is permitted.

3 *Impaction fractures* If the head is in good position leave it, if poor, operate. In the young, replace, in the old, remove.



FIG 305 Same case as Fig 304 after treatment showing the restoration of the position of the fragment by treating the elbow in extension.



FIG 306 Comminuted fracture of the head of the radius. X ray showing forward dislocation of the head of the radius and how the acute flexion of the elbow has produced the deformity. Treatment of the elbow in flexion would tend to maintain this.

4 *Comminuted fractures* These can only be treated satisfactorily by removal of the whole head.

5 *Separated epiphysis* Replace by manipulation or open operation. Never remove owing to the probability of interference with growth.

It is not justifiable to temporise and see how the joint progresses. If it becomes stiff permanent damage is done which cannot be undone by late excision of the head of the radius.

OPERATION Carried out as a rule after the acute bruising has subsided, i.e., in three to ten days. A tourniquet is used. The incision is two inches long in the line of the bone over the head of the radius. The brachio-radialis is separated from the extensor carpi radialis, and the joint capsule exposed. By cutting vertically

through the radial collateral and annular ligaments the bone is exposed. The head is treated as necessary, and if removed



FIG. 307. Section of the head of the radius after a comminuted fracture—satisfactory rounding of cut end of radius and absence of new bone formation. Note ossification in the radial collateral ligament indicating that this was damaged at the same time as the fracture of the radius by abduction violence.

entirely the neck is nibbled away to a rounded stump. No periosteum is separated and no tags left if possible. The wound is closed with one or two sutures in the capsule and in the skin, and no



FIG. 308. Lateral view of the same case.

drainage. A firm pressure bandage is applied. After this the Esmarch bandage or tourniquet is released. The elbow is then immobilised in a dorsal gutter splint at right angles for two weeks and then active movements are begun.

PROGNOSIS. This is good in all the minor fractures, and fairly good if the above lines of treatment are carried out. Where there is limitation of movement after an old fracture the result of operation is a little uncertain, but in a bad case an improvement is likely. If there is a bad traumatic arthritis present the results are bad, and much pain may demand an arthrodesis. The chief permanent disability likely to follow the



FIG. 309 Separation of the epiphysis of the head of the radius



FIG. 310 Same case as Fig. 309 after operative restoration of the position of the epiphysis. Lateral view

injury is not loss of pronation and supination, but loss of complete extension. Major injuries may result in much permanent stiffness and this is only avoided by early operation. The results of complete excision of the head of the radius are, however, not so satisfactory that it should be done without suitable indications.

Complications 1 *Arthritis* Usually traumatic and secondary to an associated dislocation. Avoided by early reduction, removal of grossly displaced fragments and the avoidance of force later in dealing with limited mobility. Active movements by the patient only should be used to restore mobility. Once established, the possibility of improvement by excision of the head must be considered. The usual physiotherapeutic treatment may make the life of the patient more comfortable and prevent the condition getting worse.

2 *Loss of pronation and supination* Do not forget to examine the lower radio ulnar joint as well. Usually due to leaving displaced fragments *in situ* or excessive callus. Excision of the head must be considered.

3 *Loss of flexion and extension at the elbow* Often a small

amount of extension is lost, but as the patient never uses the elbow fully extended it is of little moment

4 *Paralysis of the posterior interosseous nerve* May be due to injury at the time of the accident or to a later developing traumatic neuritis from the friction of a deformed radial head. The features are those of a radial palsy, without the loss of skin sensation. Immediate lesions of the nerve are very rare, and the associated injury would inevitably demand operation. In late lesions the head is excised.

5 *Osteochondritis dessicans* Damage to the capitellar surface of the humerus, with or without fracture of the head of the radius, may result in the later separation of a flake of bone, with all the features of a loose body in the elbow. The sclerosis below the site of separation suggests its similarity to the lesion occurring in the knee.

FRACTURES OF THE SHAFT OF THE RADIUS

Fracture of the shaft of the radius alone is rare, as

1 The shaft is dense compact bone, and the cancellous bone at either end gives first

2 A mobile joint at either end tends to dissipate force

3 In direct injuries, such as warding off a blow, the ulna is more superficial and thus more frequently injured

Fractures in adults, when they do occur, are most commonly due to direct violence, and so tend to be transverse. They are more common in children and then are frequently greenstick, and are often associated with fractures of the ulna. In the lower end there is a particular tendency to infraction fractures, which occur a little above the site for Colles's fractures.

DIAGNOSIS The upper third of the radius is buried in muscle and so less likely to be injured, but correspondingly more difficult to examine. Deformity in the lower subcutaneous portion is often obvious. There is a loss of active supination in all fractures. Rotation of the head of the radius transmitted from the wrist is not evidence against fracture, as it may be impacted or greenstick, but non rotation of the head is proof of fracture. An X ray is often necessary in children, whose only complaint may be a refusal to use the arm, and a little local swelling.

TREATMENT (see *Displacement*, p. 342)

Fractures above pronator teres	} {	With no displacement
Fractures below pronator teres		With displacement

1 Fractures above the pronator with no displacement. Immobilise with the arm in full supination and the elbow at 90° for four weeks.

2 With displacement. This can only be angulation or shortening, and these must be corrected by manipulation. Traction to correct the shortening must be firm and with the wrist in ulnar

deviation, to overcome the splinting of the ulna, and finger pressure is made to correct the angulation. The arm is then immobilised in the supinated position with the elbow at about 60° by a posterior gutter splint. Union is slow, and may take four to six weeks.

3 Fractures below the pronator teres, with no displacement. The arm is put in a plaster from the mid-humerus to the metacarpal heads to prevent rotation, care being taken that the bones are not pushed together, and with the elbow at 90° , and the forearm in the mid prone position.

4 With displacement. Reduction by manipulation, followed by a plaster, as before. Union occurs in four to six weeks in an adult, three weeks in the child.

If reduction by manipulation does not produce a good reduction, perfect reduction should be achieved by open operation. The ends may interlock sufficiently well not to need any fixation, but it is safer to insert a single screw. As less desirable alternatives, the methods discussed under fractures of both bones of the forearm (p 384) may be used. Perfect reduction of the radius is important, but not quite so important as perfect reduction of the ulna.

Greenstick fractures should have any angulation corrected by manipulation, a proceeding which often turns them into complete fractures. They are then immobilised in a short forearm plaster, for two or three weeks. In children with complete fractures in the distal fourth of the bone it is unnecessary to immobilise the elbow, the forearm being carried in a sling for the first two weeks and then exercised as in a Colles's fracture. Intrafracture fractures require a supporting plaster up to the elbow for two to three weeks, and can use their hands freely.

Fractures of the lower fourth of the shaft of the radius. These fractures fall into two groups.

1 Those in which the lower radio ulna joint is intact,

2 Those in which there is a dislocation of the lower radio-ulna joint (Fig 311).

They occur from backfire injuries or from direct violence applied to the radius. The dislocation of the ulna is forwards in nearly all cases. This displacement is readily overlooked if the radiographs are not true lateral views of the wrist, and as failure to reduce the dislocation produces considerable disability its importance needs to be emphasised. The persistence of some pain at the lower radio ulnar joint and some loss of supination is not uncommon after this injury. Accurate reduction of the radius is important in all cases and must be obtained by one of the following methods. Once reduced there is often a tendency to redisplace, particularly in those cases associated with dislocation. This may be due to the pull of

amount of extension is lost, but as the patient never uses the elbow fully extended it is of little moment

4 *Paralysis of the posterior interosseous nerve* May be due to injury at the time of the accident or to a later developing traumatic neuritis from the friction of a deformed radial head. The features are those of a radial palsy, without the loss of skin sensation. Immediate lesions of the nerve are very rare, and the associated injury would inevitably demand operation. In late lesions the head is excised.

5 *Osteochondritis dessicans* Damage to the capitellar surface of the humerus, with or without fracture of the head of the radius, may result in the later separation of a flake of bone, with all the features of a loose body in the elbow. The sclerosis below the site of separation suggests its similarity to the lesion occurring in the knee.

FRACTURES OF THE SHAFT OF THE RADIUS

Fracture of the shaft of the radius alone is rare, as

1 The shaft is dense compact bone, and the cancellous bone at either end gives first

2 A mobile joint at either end tends to dissipate force

3 In direct injuries, such as warding off a blow, the ulna is more superficial and thus more frequently injured

Fractures in adults, when they do occur, are most commonly due to direct violence, and so tend to be transverse. They are more common in children and then are frequently greenstick, and are often associated with fractures of the ulna. In the lower end there is a particular tendency to infraction fractures, which occur a little above the site for Colles's fractures.

DIAGNOSIS The upper third of the radius is buried in muscle and so less likely to be injured, but correspondingly more difficult to examine. Deformity in the lower subcutaneous portion is often obvious. There is a loss of active supination in all fractures. Rotation of the head of the radius transmitted from the wrist is not evidence against fracture, as it may be impacted or greenstick, but non rotation of the head is proof of fracture. An X ray is often necessary in children, whose only complaint may be a refusal to use the arm, and a little local swelling.

TREATMENT (see *Displacement*, p. 342)

Fractures above pronator teres	} {With no displacement With displacement
Fractures below pronator teres	

1 Fractures above the pronator with no displacement. Immobilise with the arm in full supination and the elbow at 90° for four weeks.

2 With displacement. This can only be angulation or shortening, and these must be corrected by manipulation. Traction to correct the shortening must be firm and with the wrist in ulnar

with a Kirschner wire. This wire may run transversely across the radius and ulna, or it may be more easily and equally satisfactorily



FIG 312 Oblique fracture of the lower end of the radius accompanied by dislocation of the lower radio-ulnar joint

introduced from front to back. The wire is incorporated in the plaster.

3 Open operative reduction and fixation. This is most satis-



FIG 313 Fixation of the fracture by a single screw

factorily carried out by a small plate. Less convenient are a single oblique screw or a graft.

It is essential to fix the elbow as well as the wrist in immobilising these fractures. Union is satisfactory in four to six weeks. If there is any doubt a short forearm plaster is applied for a further fortnight. This unstable lesion is the homologue of the Monteggia fracture

the pronator quadratus, but is more commonly due to imperfect reduction, a rotational deformity being apt to remain unrecognised. Methods of reduction and retention available are



FIG 311 Fracture of the lower end of the radius, with dislocation of the lower radio ulnar joint



FIG 311b Fracture of the lower end of the radius together with complete dislocation of the lower radio ulnar joint

- 1 Manipulation and plaster Suitable in cases which interlock readily and in greenstick fractures of the type shown in Fig 311
- 2 Manipulative reduction and transfixion of the lower fragment

the upper end of the humerus occurs. Indeed they may occur together, and cases have been seen in which the concentration of attention on the wrist lesion has caused the humeral fracture to be overlooked.

The name Colles's is applied to a transverse fracture of the lower



FIG 314 Characteristic Dinner Fork deformity of a Colles's fracture

end of the radius which occurs just distal to the point where the compact bone of the shaft thins to become the covering of the cancellous bone of the lower end. It is thus a fracture through cancellous bone. With this is frequently associated a fracture of the ulnar styloid process which may be broken transversely at its base, or merely have a chip pulled out from the tip. In a severe




FIG 315 Colles's fracture with moderate displacement. Lateral view

Colles's fracture where the ulna styloid is not fractured the ulnar collateral ligament is torn, but this is very uncommon as fracture usually occurs first.

Clinically, Colles's fractures can be divided into mild and severe. In the mild cases the diagnosis rests between a Colles's and any other of the seven fractures named. In the severe case with marked displacement it rests between a Colles's, a separated epiphysis, and

dislocation in the upper third of the forearm. Both may reduce easily, but are subject to later displacement of the fracture, usually angulation, with impaired function. Open operative fixation with the control provided by a plate is therefore recommended in all cases (see p. 382).

Traction on the thumb has been recommended for controlling these cases. It is to be avoided as it produces serious stiffness in the thumb.

FRACTURES OF THE LOWER END OF THE RADIUS

Types 1 Colles's fracture, and reversed Colles's or Smith's fracture

2 Marginal fractures Dorsal

3 " " Volar

4 " " Styloid

5 Longitudinal fissure fractures

6 Separation of the lower epiphysis

7 Infracarpal fractures (Greenstick, with little displacement)

Colles's fractures **MECHANISM** 1 Direct violence Starting handle injuries. There are two varieties of starting handle injuries.

(a) Backfire on the downward compression. This drives the handle into the palm and produces a Colles's fracture or fracture of the navicular.

(b) The backfire on the upward compression, in which the handle is torn out of the hand and swings around striking the back of the wrist. This usually produces a transverse fracture of the lower end of the radius above the level of the Colles's fracture and which may be associated with dislocation of the lower radio-ulnar joint (p. 351).

2 Indirect violence. Falls in which the hand is used to save the body. In falls with the hand palm down, the force on the thenar and hypothenar is transmitted up the bones of the forearm, and may be accompanied by acute dorsiflexion and a rotational strain, on the lower end of the radius the fingers acting as part of a short lever. Falls with the hand doubled under in which the hand is hyperflexed should produce the characteristic Smith's fracture, but rarely do so, and they more commonly produce a Colles's fracture.

INCIDENCE The fracture is particularly common in middle aged women, when some general decalcification of bones, accompanied by an increased deposit of fat seems to occur after the menopause (See table in Chapter I). In such cases if the wrist does not give, and the force is sufficiently strong, an impacted fracture of

broadened, and the fingers are flexed to relax the tendons over the volar aspect of the fracture. Crepitus is often absent due to impaction, and must be distinguished from the soft crepitus of epiphyseal injuries. There is a loss of pronation and supination.

Associated injuries which must be watched for

1 Dislocation at the lower radio-ulnar joint

2 Injury to the sensory branch of the radial nerve, with pain around the base of the thumb, often considered due to the plaster

3 Fracture of the navicular. Rare

4 Injury to elbow, humerus or clavicle



FIG 318 Comminuted Colles' fracture with marked displacement. Lateral view

Comminution of the lower fragment is not uncommon in severe injuries, usually in the old, the crack running into the joint, and it



FIG 319 Same case as in previous figure. Antero-posterior view

a large hematoma appears at the elbow, around the medial epicondyle

is important as it makes retention less easy, producing an effusion into the joint and an irregular joint surface with consequent increased disability later. It is particularly in these comminuted fractures that a watch for a recurrence of the deformity in the plaster must be kept, and a control X-ray taken about the tenth day. If it shows a recurrence the fracture is reduced in exactly the same manner as before. In old people with a Colles' fracture of any degree of severity

a fracture of both bones a little above the wrist The clinical features will be obvious from the description of the deformity which follows

The distal fragment is displaced

- 1 As a whole dorsally
- 2 As a whole upwards, *i e*, towards the elbow
- 3 It is rotated on a transverse axis so that the upper margin



FIG 316 Same case as previous figure Antero posterior view

of the bone is turned dorsally, and the lower articular surface tends to look dorsally

- 4 It is rotated on an AP axis so that the radial styloid is pushed upwards to the level of the ulnar styloid, and the articular surface of the radius is more at right angles to the shaft

This produces the characteristic dinner fork deformity The fourth displacement allows the hand as a whole to move radially, and the ulnar styloid or its fractured base becomes prominent The




FIG 317 Lateral and A P views of the radius showing the characteristic displacement of a Colles's fracture (Compare Figs 318 319)

diagnosis is usually obvious, but in the less displaced fractures only an X ray will distinguish it from the fractures previously mentioned The displacements described above can be verified by palpation before swelling has occurred The whole wrist from above appears

this the fracture line can be readily felt and the hæmatoma entered. Fifteen cubic centimetres of 2 per cent novocaine are injected here. In order to be certain that this is diffusing into the hæmatoma, after the



FIG. 322 The stages in the reduction of a Colles's fracture. The introduction of the local anæsthetic.

first few cubic centimetres are injected the syringe is detached and blood stained fluid should regurgitate back along the needle. If there is little displacement of the fragments it will be found necessary to pass the needle in front of the bone and inject some novocaine there, as otherwise it will not percolate through the impacted bone to this region.

REDUCTION The patient is placed on a table, and the thumb and index, middle, and ring fingers are painted with mastisol, and a few turns of bandage placed around the three fingers and the thumb separately, leaving the little finger free. A pad is then placed over the arm in front of the biceps, and a broad webbing loop



FIG. 323 The syringe is removed allowing blood stained anæsthetic solution to trickle back along the needle, thus showing that the hæmatoma has been entered.

slipped over the arm, which can be attached to a hook in the wall. The patient or the fracture site is then anæsthetised. Disimpaction and reduction is then brought about by firmly grasping the wrist and the hand, and strongly palmar flexing it at the wrist.

Treatment For perfect function perfect reduction is essential. All Colles's fractures should be reduced if there is the slightest displacement, even if impacted. The essentials of a good reduction, only seen in the X ray, are



FIG 320 Colles's fracture in Fig 318 after reduction. The curve of the under surface of the radius is restored. The joint surface looks down and forward. It has been impossible to elevate a small depressed fragment which spoils the alignment of the dorsal surface but this is of no moment.



FIG 321 Antero posterior view of the previous case showing the reduction of the ulnar styloid and the ulnar deviation of the hand.

1 The line of the dorsal surface of the radius is smooth and not stepped or angled (Fig 320)

2 That the articular surface in a lateral view looks down and forwards at an angle of 10° to 15° (Fig 320)

3 That the line of the articular surface in the AP view is at least at an angle of 25° with the transverse (Fig 321)

4 That the ulnar styloid is in position, and the hand deviated ulnarwards (Fig 321)

5 That the lower radio-ulnar joint surfaces are in normal relationship

ANÆSTHESIA Local anæsthetic is very suitable in recent cases. Any general anæsthetic may be used.

Technique of local anæsthesia Using the apparatus and method set out previously, two skin blebs are first raised with fine hypodermic needles, one over the base of the ulnar styloid (unnecessary if the ulnar styloid is intact) and one over the lateral surface of the radius just below the line of fracture. A larger needle is now taken and $2\frac{1}{2}$ cc of 2 per cent novocaine is injected at the base of

the fractured ulnar styloid. A fresh needle is taken and entered obliquely against the upper surface of the bone. By sliding it over

and this is the ideal position for plastering. Very rarely is it necessary to palmar-flex the wrist to maintain the fragments in



FIG 326 Testing for complete disimpaction by hyper extension with the fingers on the fracture site

place, and if this is done it should only be left so for ten days and then replastered in the more usual position

RETENTION A plaster slab about six layers deep is now placed



FIG 327 Traction applied to the forearm. There is a counter traction band around the arm attached to a hook in the wall. The nurse pulls with straight arms using the body weight which is much less tiring

on the dorsum of the forearm and trimmed so that it extends from the heads of the metacarpals to just distal to the elbow crease, and so allows full flexion of the elbow. It must be sufficiently wide to

With much the same grip and only shifting the two thumbs over the fracture site, disimpaction can be readily tested by dorsiflexing the wrist. Reposition of the loose fragment is now brought about by traction on the fingers, the strap in the crook of the elbow providing counter-traction. The fingers are held in one hand and the thumb in the other and traction is applied mainly to the thumb which produces ulnar deviation and so corrects the radial displacement. Grasping only three fingers does not contract the metacarpal arch, as does grasping the whole four. Traction is applied with the arms straight, and the body leaning back, as with flexed elbows the traction is uneven and tiring to maintain. By traction the shortening is overcome, and the dorsal rotation, which was undone by the disimpaction, is also corrected. The shifting of the whole fragment dorsally is usually also undone, but it may be made certain by pressure with the thenars on either side of the fracture, with the fingers interlocked, when great force can be exerted. This manoeuvre is very useful in comminuted fractures with much displacement, and by maintaining the traction, and combining a rocking movement with



FIG 324 The correct way to bandage the fingers for applying traction in the reduction of a Colles' fracture. The fingers are first painted with mastisol.

useful in comminuted fractures with much displacement, and by maintaining the traction, and combining a rocking movement with



FIG 325 Disimpaction of the fracture by firm flexion of the wrist.

the pressure, the fragments can all be worked back into position. The arm is now held in flexion at the elbow, and midway between pronation and supination. The wrist is in the neutral position,

date of plastering, and approximate date of removal, together with a diagram of the fracture, are written on the plaster with an indelible



FIG 330 With the arm still under traction which is not relaxed till the plaster has set the short forearm plaster is applied. In the figure the corner which is cut off to allow full flexion of the elbow is being removed.

pencil. This is only to facilitate treatment in a large clinic. If a gauze bandage has been used, provided everything is satisfactory on the following day, it is then covered with a starch bandage, on which the same details can be written.

The important points about a plaster for a Colles's fracture are

- 1 It extends from the elbow to the heads of the metacarpals, but allows full flexion of the elbow.

- 2 It is sufficiently wide to surround the metacarpals on either side, for it is only the resistance offered by moulding it around the cone of the metacarpals which prevents the occurrence of shortening.

- 3 The metacarpal arch of the fingers must be flat to allow full finger movements.

- 4 The band crossing the palm which maintains the metacarpals against the dorsal slab, and which can be of wire, or of sticking plaster, must not extend further than the level of the distal crease of the palm on the



FIG 331 The complete plaster. From in front.

ulnar side and the middle crease on the radial side, so that full flexion of the fingers is possible. This point is frequently overlooked in the region of the index finger which comes out of the plaster much stiffer at the metacarpal joint than the other fingers.

wrap around the metacarpals on either side, a firm grip around the base of the first metacarpal being particularly important. A small cut is made beside the second metacarpal to allow the plaster to be



FIG 328 While the wrist is under traction manipulation of comminuted fragments into position may be done by pressure of the palms with the fingers locked accompanied by a rocking motion of the forearms

folded back to the level of the head of the thumb metacarpal and give an edge for the binding across the palm. This dorsal slab is now carefully smoothed on to the skin. The further wrapping to maintain this in place depends on whether swelling of the fracture




FIG 329 Trimming the plaster slab used in the retention of a Colles's fracture. C The corner cut off to allow full flexion of the elbow. D Line of fold around base of thumb. E Line on which flap B is folded back. F Line of scissor cut down to level of E for cutting flap A. [In applying a plaster for a fractured navicular in which the thumb is not fixed this portion of plaster is also removed.]

site is to be anticipated. If the fracture is fresh and no swelling has taken place, a gauze bandage is wrapped around the plaster slab. If swelling has occurred a plaster bandage may be used, care being taken in both cases that the portion crossing the palm is not too tight. The plaster is carefully moulded as it sets, so that there is a hollow under the lower surface of the radius, and a smooth fit around the base of the first metacarpal. This not only helps to turn the lower

end of the radius in the correct direction, i.e., looking downwards, but very definitely helps in the retention, while the moulding around the metacarpals is the only way in which the resistance to shortening can be maintained. Traction is only relaxed when the plaster is set. If a plaster encircling bandage has been used the date of fracture,

In this classification the fractures are arranged in the order of their seriousness. The last group of severely comminuted fractures involving the wrist joint may also involve the lower radio ulnar joint with further disability.

The length of immobilisation increases with the severity of the lesion. In young people the uncomminuted and undisplaced fracture may be given a minimum period of two weeks in plaster. For each further degree of severity another week of immobility is insisted on, so that in the grossly comminuted fracture involving the joint five weeks rest may be needed. In older patients these times are each increased by a further week. To obtain the total disability period, an equivalent period for rest and exercises must be added to that already spent in plaster.

Given uniform treatment the final result will be a reflection of the increasing severity of the lesion. The two important factors which will govern the prognosis more than any others are, accurate reduction and the presence of a fracture line running into the joint. Accurate reduction is essential for good function. The fracture entering the joint is bound to disturb the smoothness of the articulation, and such patients are much slower in gaining a wrist free from pain with reasonably full movements. In such cases complete restoration of movement seldom occurs, but the amount lost should not amount to a disability. More of a problem is the persistence of pain, and the development of a traumatic arthritis in older patients. In severe comminuted fractures this is always to be feared.

Re-education. This is one of the most important parts of treatment, if not the most important part, and must be combined with the supervision of the plaster. The maintenance of adequate joint and muscle function is only possible by free exercises of the unfixed joints, and it is the ability to leave so many joints free, and yet maintain adequate fixation, that makes plaster the only satisfactory means of retention in this fracture. The patient is seen on the second day, and if the plaster is satisfactory, is instructed to do without the sling and use the fingers as much as possible in the ordinary way. To make certain that the arm is adequately exercised he is sent to the massage department for exercises, as follow

- 1 Extension of the fingers, deliberate and strong
- 2 Spreading of the fingers
- 3 Flexion of the fingers
- 4 Extension and flexion of the thumb
- 5 Extension and flexion of the elbow
- 6 Hand behind head and behind back
- 7 Pronation and supination of the hand with the elbow steadied on the thigh if patient is seated, or held in against side if standing, and in the elbow grasp position if possible

5 The plaster must extend to the end of the first metacarpal or pressure sores on the thumb will occur

In comminuted or badly displaced fractures, and particularly in incompletely reduced fractures, a tendency for the deformity to recur in the plaster will be found. It seems to occur about the seventh to tenth day and should be checked by a routine X ray on the tenth day. It is possibly due to a subsidence of the swelling allowing redisplacement in the cast. If it occurs the wrist is set again as if the fracture were a recent one.

COMPLAINTS WITH REGARD TO THE PLASTER 1 Pain over the thumb. May be due to injury to the sensory branch of the radial nerve, and not due to pressure. Usually the plaster has to be removed and reapplied.

2 Swelling of the fingers. Is not uncommon for the first forty-eight hours, but goes away with exercise of the fingers. The precautions with regard to fresh fractures should be noticed. If swelling occurs the plaster must be split and the arm raised above the head and exercises encouraged. Recently we have developed the habit of cutting down the gauze bandage from the base of the fingers to two thirds of the way down the forearm, half an hour after the plaster has set, and then lightly rebandaging. By this means the firm bandage necessary to hold the plaster in position can be applied, and all possibility of later constriction is removed by splitting the bandage, while the freeing of the venous return at the wrist improves the colour of the fingers.

3 Inability to move the fingers is commonly complained of even in normal plasters, and is due to pain, nervousness, and pressure. Some relief of pressure, *e.g.*, by a partial split down the forearm, and encouragement cures the condition. This is also a symptom of more serious pressure (see Chapter II), and this must not be overlooked.

Prognosis Fractures can be classified as follows, and this serves as a guide to the prognosis, and also to the time of immobilisation necessary in each case. The fracture of the ulnar styloid can be neglected, except in so far as it indicates a more severe lesion.

Uncomminuted fractures 1 With little displacement (Mild Colles's) (Plaster 2—3 weeks)

2 With displacement and fracture of the ulnar styloid (Severe Colles's) (Plaster 3—4 weeks)

Comminuted fractures These almost always show gross displacement

1 With the comminution not involving the joint surface (Plaster 4—5 weeks)

2 With the line of the comminuted fragments entering the joint (Plaster 5—6 weeks)

In this classification the fractures are arranged in the order of their seriousness. The last group of severely comminuted fractures involving the wrist joint may also involve the lower radio ulnar joint with further disability.

The length of immobilisation increases with the severity of the lesion. In young people the uncommuted and undisplaced fracture may be given a minimum period of two weeks in plaster. For each further degree of severity another week of immobility is insisted on, so that in the grossly comminuted fracture involving the joint five weeks rest may be needed. In older patients these times are each increased by a further week. To obtain the total disability period, an equivalent period for rest and exercises must be added to that already spent in plaster.

Given uniform treatment the final result will be a reflection of the increasing severity of the lesion. The two important factors which will govern the prognosis more than any others are, accurate reduction and the presence of a fracture line running into the joint. Accurate reduction is essential for good function. The fracture entering the joint is bound to disturb the smoothness of the articulation, and such patients are much slower in gaining a wrist free from pain with reasonably full movements. In such cases complete restoration of movement seldom occurs, but the amount lost should not amount to a disability. More of a problem is the persistence of pain, and the development of a traumatic arthritis in older patients. In severe comminuted fractures this is always to be feared.

Re-education. This is one of the most important parts of treatment, if not the most important part, and must be combined with the supervision of the plaster. The maintenance of adequate joint and muscle function is only possible by free exercises of the unfixed joints, and it is the ability to leave so many joints free, and yet maintain adequate fixation, that makes plaster the only satisfactory means of retention in this fracture. The patient is seen on the second day, and if the plaster is satisfactory, is instructed to do without the sling and use the fingers as much as possible in the ordinary way. To make certain that the arm is adequately exercised he is sent to the massage department for exercises, as follow

- 1 Extension of the fingers, deliberate and strong
- 2 Spreading of the fingers
- 3 Flexion of the fingers
- 4 Extension and flexion of the thumb
- 5 Extension and flexion of the elbow
- 6 Hand behind head and behind back
- 7 Pronation and supination of the hand with the elbow steadied on the thigh if patient is seated, or held in against side if standing, and in the elbow grasp position if possible.

5 The plaster must extend to the end of the first metacarpal or pressure sores on the thumb will occur

In comminuted or badly displaced fractures, and particularly in incompletely reduced fractures, a tendency for the deformity to recur in the plaster will be found. It seems to occur about the seventh to tenth day and should be checked by a routine X ray on the tenth day. It is possibly due to a subsidence of the swelling allowing redisplacement in the cast. If it occurs the wrist is set again as if the fracture were a recent one.

COMPLAINTS WITH REGARD TO THE PLASTER 1 Pain over the thumb. May be due to injury to the sensory branch of the radial nerve, and not due to pressure. Usually the plaster has to be removed and reapplied.

2 Swelling of the fingers. Is not uncommon for the first forty-eight hours, but goes away with exercise of the fingers. The precautions with regard to fresh fractures should be noticed. If swelling occurs the plaster must be split and the arm raised above the head and exercises encouraged. Recently we have developed the habit of cutting down the gauze bandage from the base of the fingers to two thirds of the way down the forearm, half an hour after the plaster has set, and then lightly rebandaging. By this means the firm bandage necessary to hold the plaster in position can be applied, and all possibility of later constriction is removed by splitting the bandage, while the freeing of the venous return at the wrist improves the colour of the fingers.

3 Inability to move the fingers is commonly complained of even in normal plasters, and is due to pain, nervousness, and pressure. Some relief of pressure, e.g., by a partial split down the forearm, and encouragement cures the condition. This is also a symptom of more serious pressure (see Chapter II), and this must not be overlooked.

Prognosis Fractures can be classified as follows, and this serves as a guide to the prognosis and also to the time of immobilisation necessary in each case. The fracture of the ulnar styloid can be neglected, except in so far as it indicates a more severe lesion.

Uncomminuted fractures 1 With little displacement (Mild Colles's) (Plaster 2—3 weeks)

2 With displacement and fracture of the ulnar styloid (Severe Colles's) (Plaster 3—4 weeks)

Comminuted fractures These almost always show gross displacement

1 With the comminution not involving the joint surface (Plaster 4—5 weeks)

2 With the line of the comminuted fragments entering the joint (Plaster 5—6 weeks)

DEFORMITY Not characteristic, and may be confused with volar dislocations of the wrist. The signs and symptoms are much the same as for a Colles's fracture, only the displacement is volar-wards as a whole, and the rotation in the transverse axis increases.




FIG. 332. Lateral and A.P. views of a reversed Colles's fracture. (See Fig. 333.)

the angle of the joint. The other displacements are as in Colles's fracture. The radial styloid is elevated, and the general deformity has been called the "spade handle deformity."



FIG. 333. Smith's fracture or the reversed Colles's fracture.



FIG. 334. The deformity in a reversed Colles's fracture. The same case as in Fig. 333.

TREATMENT Follows similar principles to a Colles's fracture, the movements of reduction being reversed, and the wrist is put up in the same neutral position.

THE MARGINAL FRACTURES

- 1 Dorsal
- 2 Volar
- 3 Styloid

Complications 1 REDISPLACEMENT Occurs (a) About seventh to tenth day, re reduce and plaster

(b) If plaster is removed too soon in old people, and in badly comminuted fractures Depending on how serious this is and on the time since the fracture, one must decide between leaving it or re reducing it

2 PAIN OVER THE ULNAR STYLOID Common complaint due to non-union of the styloid or the torn ulnar collateral ligament Demands more careful ulnar adduction in the plaster to avoid it If it occurs after the plaster is removed it will pass off in time in most cases, but in a very few the detached fragment has to be removed Novocaine infiltration should be tried

3 PAIN OVER THE SENSORY BRANCH OF THE RADIAL NERVE Usually settles in time

4 LOSS OF PRONATION AND SUPINATION TO SOME DEGREE Due to arthritis of the lower radio ulnar joint, and usually improves with time It occurs in badly reduced and grossly comminuted fractures In patients in the twenties and thirties, if very severe may require excision of the lower end of the ulna

5 LATE RUPTURE OF THE EXTENSOR POLLICIS LONGUS TENDON Very rare, but an interesting complication, and difficult to treat, as the fragment of bone causing the fraying must be removed and the frayed tendon may be in no condition for suture A free tendon graft may be employed, or the distal end implanted into the abductor pollicis longus

6 PERSISTENT PAIN IN THE WRIST (a) Too early removal of the plaster Immobilise for a further two weeks

(b) Rheumatic flare up in the injured joint General physio-therapeutic treatment

(c) Early traumatic arthritis Usually associated with comminution or a bad reduction These cases seen up to three months after the accident can be refractured and reset, but this is only advisable in the younger patient

7 DEFORMITY This usually takes the form of radial deviation, with a prominent ulnar styloid, and is the most common complaint in inadequately reduced or immobilised fractures, and can only be avoided by careful observation of the principles outlined If very marked it may be corrected in the young by osteotomy of the radius and resetting In the old it is best left alone

Reversed Colles's or Smith's Fracture

Due most commonly to direct violence knocking the hand volar-wards, but may be due to indirect violence in falls on the dorsum of the hand with the hand strongly flexed

SIGNS Similar to those for a Colles's fracture, without much deformity and from which it can only be distinguished by X rays. The differential diagnosis rests between injury to the carpal bones, a severe sprain, separation of the epiphysis, and a mild



FIG. 339 Showing the reduction of the displacement by splinting the hand in the neutral (mid) position

Colles's fracture The dislocation of the wrist as a whole must not be overlooked as it demands a much longer period of immobilisation than the fracture alone (i.e., six to eight weeks)

Reduction In each case the detached fragment is attached



FIG. 340 Marginal fracture of the radial styloid. The fracture line enters the joint just medial to the ridge between the navicular and lunate articular areas



FIG. 341 Longitudinal fissure fracture of the radius. Compare fig. 342

to the carpus by its appropriate ligament, and it is through carpal manipulation that its position is influenced. In the radial styloid fracture, which usually runs straight out from immediately lateral

The mechanism is much the same in dorsal and volar marginal fractures, and resembles that of a Colles's fracture, the force varying, in direction, in the amount of leverage from the hand combined




FIG 335 Dorsal and volar marginal fractures of the lower end of the radius



FIG 336 Styloid marginal fracture Compare Fig 340

with the compression and in degree. The deeper overhanging posterior articular margin tends to receive more force. The injury is often regarded as minor, but is important owing to joint involve-



FIG 337 Volar marginal fracture of the radius with anterior subluxation of the wrist



FIG 338 Showing the effect of dorsiflexion in increasing the subluxation and may be associated with a dislocation of the wrist in a palmar or dorsal direction

SIGNS Similar to those for a Colles's fracture, without much deformity, and from which it can only be distinguished by X rays. The differential diagnosis rests between injury to the carpal bones, a severe sprain, separation of the epiphysis, and a mild



FIG. 339 Showing the reduction of the displacement by splinting, the hand in the neutral (mid) position

Colles's fracture The dislocation of the wrist is a whole must not be overlooked as it demands a much longer period of immobilisation than the fracture alone (i.e., six to eight weeks)

REDUCTION In each case the detached fragment is attached



FIG. 340 Marginal fracture of the radial styloid. The fracture line enters the joint just medial to the ridge between the navicular and lunate articular areas



FIG. 341 Long ulnar fissure fracture of the radius. Compare FIG. 342

to the carpus by its appropriate ligament, and it is through carpal manipulation that its position is influenced. In the radial styloid fracture, which usually runs straight out from immediately lateral

carries a chip of the dorsal margin of the metaphysis with it (Fig. 345). Separation of the ulnar epiphysis or fracture of the ulnar styloid (see Fig. 344) may be associated with the condition.

Reduction. This is usually easy, and the crenellated surface



FIG. 344. Posterior displacement of the radial epiphysis with separation of the ulnar styloid process. Antero-posterior view of case shown in Fig. 343.

FIG. 345. Lateral view of the previous case.

of the epiphysis, once back in position, tends to stay there. A dorsal plaster, as for a Colles's fracture, is applied. Union is satisfactory in three weeks in all cases. If the epiphysis is replaced interference with growth never occurs.

It is very difficult to connect Madelung's deformity with malunited fractures of this type, but it may develop after crushing injuries of the epiphysis which cause premature fusion (see Fig. 575).

Infraction fractures. These occur in the young and are really greenstick fractures with little displacement. As a result deformity is frequently hardly visible and barely palpable, and swelling and pain often the only symptoms complained of.

The X-ray is characteristic, showing a slight bulging of the compact bone between 1 and 2 inches behind the joint in the A.P. view, and some crumpling of the compact bone with deformity in the lateral view. All grades of this may be found, passing into the



FIG. 346. Posterior displacement of the lower epiphysis of the radius showing the small fragment of the metaphysis carried away with the epiphysis (see Fig. 561).

complete fracture of the lower fourth of the bone, described under fractures of the shaft

TREATMENT Where the displacement is small a supporting



FIG 347 Greenstick (bamboo) fracture of the lower end of the radius
Antero posterior view

plaster for two weeks is sufficient, but where displacement has occurred it must be corrected by manipulation and a forearm



FIG 348 Lateral view of the same case showing crumpling of the posterior compact bone More often the anterior side of the radius crumples

plaster applied for three weeks In children exercises are unnecessary

REFERENCES

Colles's Fracture

- BOWYER J. "The Treatment of Fractures." Bristol, 1936, p. 227.
 GURD J. B. "The Colles-Pouteau Fracture of the Lower End of the Radius," *Im J Surg*, 1937, 38, 520.
 PRATT H. "Colles's Fracture of the Radius." *Brit M J*, 1932, 2, 288.
 (With some historical details, and references.)
 MOORE. "Spontaneous Rupture of the Extensor Pollicis Longus Tendon associated with Colles's Fracture." *Brit J Surg*, 1936, 23, 729. (With further references.)
 McMASTERS P. L. "Late Ruptures of the Extensor Pollicis Longus and Flexor Pollicis Longus Tendons following Colles's Fracture," *J Bone and Joint Surg*, 1932, 14, 93.

Head of the Radius

- ELMUND, C. W. "Fractures of the Head of the Radius," *Proc Roy Soc Med*, 1931, 25, 1011.
 MICH. "Unusual Fractures of the Capitulum Humeri and the Capitulum Radii," *J Bone and Joint Surg*, 1911, 13, 882.
 PATTERSON. "Treatment of Displaced Transverse Fractures of the Head of the Radius in Children," *J Bone and Joint Surg*, 1934, 16, 695.
 MURRAY, R. C. "Fractures of the Head and Neck of the Radius," *Brit J Surg*, 1940, 28, 100.

Radial Epiphysis

- THURSTON HOLLAND. "Radiographic Note on the Injuries to the Distal Epiphyses of the Radius and Ulna," *Proc Roy Soc Med*, 1929, 22, 695.
 ATKIN, A. P. "The End Results of Fractured Distal Radial Epiphysis," *J Bone and Joint Surg*, 1935, 17, 302.

CHAPTER XXIII

FRACTURES OF THE ULNA, AND BOTH BONES OF THE FOREARM

THE ULNA

Surgical anatomy The ulna occupies a peculiar position in the forearm providing the pivot around which the radius turns, but not taking any compression strain, which is borne by the radius. Its readily palpable subcutaneous border is uppermost when the arm is used to shield the face, and so the bone is frequently the recipient of direct violence, and fractures are commonly compound.

CONSIDERABLE discussion has surrounded the decision as to which bone it is most important to reduce accurately. For sound function of the forearm it is important to reduce both perfectly, but if comminution or compound injuries limit consideration to one bone, then the ulna is the most important to align. The axis of rotation of the radius is thus restored and the ends of the radius will be pulled into moderately good position by the ligaments attaching them to the ulna. A fair degree of pronation and supination is thus likely to be restored. Minor degrees of mal alignment of the radius or ulna will be repaid by traumatic arthritis at one or other radio ulna joint a few years later.

Classification of fractures of the ulna 1 Fractures of the small processes of the ulna

- (a) Coronoid
- (b) Olecranon (Tip)
- (c) Styloid

2 Fractures of the olecranon through the sigmoid notch

3 Fractures of the shaft of the ulna

- (a) Alone
- (b) Associated with a dislocation of the head of the radius
- (c) Associated with fractures of the radius (Both bones)

Fractures of the Small Processes

FRACTURES OF THE CORONOID PROCESS OF THE ULNA arise from tendon strain in over extension of the elbow, or from injury by the lower end of the humerus in posterior dislocations of the elbow. The displacement of the fragment is variable, but it can best be returned to position by acute flexion of the arm. Following dislocation this may be a dangerous procedure, and it may have to be done gradually as the swelling subsides. The position is maintained for three weeks and then movements gradually commenced.

FRACTURES OF THE TIP OF THE OLECRANON may arise from direct violence. They are rare. More commonly a small bony spur, or osteophyte, is knocked off. In children after the age of ten the centre for the tip of the olecranon may be knocked off, an essentially similar lesion. A sling for a fortnight is usually sufficient treatment.

FRACTURES OF THE STYLOID PROCESS are most commonly associated with a Colles's fracture of the radius. They may, however, arise from ligament strain in severe wrist sprains, and from direct violence.

Where due to direct violence stripping is sufficient, but those associated with severe sprains require more serious attention. It is advisable to immobilise the wrist in plaster for a fortnight as non union of the fragment and persistent pain are common (see p. 359).

Fractures of the Olecranon through the Sigmoid Notch

TYPE OF VIOLENCE. These fractures most commonly arise through direct violence from falls on the point of the elbow. In this



FIG. 349 Upward dislocation of the elbow with fracture of the olecranon

case the fracture is usually transverse, lies at the centre of the sigmoid notch, and frequently shows no displacement. Should muscular contraction of the triceps have succeeded the fracture, or should the fracture be due to the pull of the triceps snapping the ulna over the lower end of the humerus, the ligament may be widely displaced and the fibrous expansions on either side of the insertion of the muscle widely torn. The position is thus analagous to that occurring in fractures of the patella. Fractures may however occur from the weight of the body being transmitted to the sigmoid notch when the forearm, but not the elbow, is supported (Fig. 349). Under these circumstances either an oblique fracture such as is shown in Fig. 352 occurs or a transverse fracture near the coronoid occurs (Fig. 356).

with anterior subluxation of the elbow. In the latter case the antero posterior stability of the elbow joint is seriously compromised.



FIG 350 Transverse fracture of the olecranon tip



FIG 351 This fracture is best treated by excision of the fragment and attachment of the triceps to the fracture surface

With any of these injuries comminution may occur, or one form of violence may succeed another.

Fractures of the olecranon can thus be divided up into four groups:

1 Fractures involving the attachment of the triceps and the posterior third of the sigmoid notch which do not imperil the



FIG 352 Oblique fracture of the base of the olecranon often accompanied by forward dislocation of both bones of the forearm



FIG 353 Correct and simple method of fixation by a single screw

stability of the elbow and can be treated by excision of the fragment (Figs 350, 351).

2 Fractures of the middle of the notch without displacement which can be treated expectantly (Figs 358).



FIG 354 Comminuted fracture of olecranon



FIG 355 Comminuted fracture of olecranon treated by bone graft

3 Fractures, usually oblique, which involve the middle third of the notch and upset the stability of the joint, and which do not lend themselves to excision. These are best treated by single screw fixation (Figs 352, 353).

4. Fractures which may be comminuted, involving the anterior third of the sigmoid notch, and gravely imperil the stability of the



FIGS 34 and 35. Transverse fracture of the olecranon at a more distal site. This fracture may be treated by a single screw as shown.

joint. These must be treated by restoration of the fragments to their normal position if possible (Figs 354, 355).

DIAGNOSIS. The lesion produces local pain with an inability to straighten the arm, and usually a characteristic swelling over the olecranon due to effusion of blood into the olecranon bursa and surrounding tissues. It is occasionally difficult to exclude this



FIG. 358. Fracture of the olecranon without displacement due to direct violence.

fracture in the presence of a typical history when there is blood clot or loose bodies in the olecranon bursa. The simulation of a fracture line may be very confusing and require an X ray to differentiate it. Owing to the subcutaneous position of the bone, fractures are occasionally compound.

TREATMENT. Cases with no displacement are immobilised in plaster with the elbow 45° to 60° short of full extension, which is

with anterior subluxation of the elbow. In the latter case the antero posterior stability of the elbow joint is seriously compromised.



FIG 350 Transverse fracture of the olecranon tip



FIG 351 This fracture is best treated by excision of the fragment and attachment of the triceps to the fracture surface

With any of these injuries comminution may occur, or one form of violence may succeed another.

Fractures of the olecranon can thus be divided up into four groups.

1 Fractures involving the attachment of the triceps and the posterior third of the sigmoid notch which do not imperil the



FIG 352 Oblique fracture of the base of the olecranon often accompanied by forward dislocation of both bones of the forearm



FIG 353 Correct and simple method of fixation by a single screw

stability of the elbow and can be treated by excision of the fragment (Figs 350, 351).

2 Fractures of the middle of the notch without displacement which can be treated expectantly (Figs 358).



FIG 354 Comminuted fracture of olecranon




FIG 355 Comminuted fracture of olecranon treated by bone graft

3 Fractures, usually oblique, which involve the middle third of the notch and upset the stability of the joint, and which do not lend themselves to excision. These are best treated by single screw

4. Fractures which may be comminuted, involving the anterior end of the sigmoid notch, and gravely impair the stability of the



Figs. 36 and 37. Transverse fracture of the olecranon at a more distal site. This fracture may be treated by a single screw as shown.

joint. These must be treated by restoration of the fragments to their normal position if possible (Figs. 354, 355).

DIAGNOSIS. The lesion produces local pain with an inability to straighten the arm, and usually a characteristic swelling over the olecranon due to effusion of blood into the olecranon bursa and surrounding tissues. It is occasionally difficult to exclude this



Fig. 38. Fracture of the olecranon without displacement due to direct violence.

fracture in the presence of a typical history when there is blood clot or loose bodies in the olecranon bursa. The simulation of a fracture line may be very confusing and require an X ray to differentiate it. Owing to the subcutaneous position of the bone, fractures are occasionally compound.

TREATMENT. Cases with no displacement are immobilised in plaster with the elbow 45° to 60° short of full extension, which is

more comfortable than the completely extended position. This position is maintained for three weeks, when a sling is substituted and movements within it allowed. This is discarded in two more weeks. The result is usually very satisfactory, though a few cases take time to recover full extension.

Fractures with displacement These must be operated on to restore the structure of the joint accurately and unite the torn aponeurosis. Occasionally in comminuted fractures it is necessary to operate in the absence of wide separation of the fragments because a small fragment is tilted into the joint.

Operative treatment The approach is from behind through a curved incision. This may be curved transversely, or longitudinally,



FIG. 369 A transverse fracture of the olecranon with displacement

and is so arranged that the fracture line and the incision do not cross one another. A tourniquet may be used if desired. The fragments and torn fascia are exposed and cleared of debris. When their accurate configuration is appreciated, a decision as to the best method of fixation may be arrived at. In transverse fractures a long screw inserted from the posterior surface of the olecranon will usually impact the fragments well and maintain good alignment. In fractures of the anterior third, this is essential to avoid recurrent anterior subluxation. If the fragments are badly comminuted this may be difficult and compromises such as that shown in Fig. 363 may have to be used. In oblique fractures, there are usually a few small fragments which have to be removed before the proximal fragment can be fitted into place. It is then best fixed with a single oblique screw inserted from the subcutaneous surface of the olecranon. Wire

may be used, but screws are more satisfactory because of their steady effect, and the impaction they produce. If desired, a thin



FIG. 360 An oblique fracture of the olecranon

bone peg may be substituted. The screws may be uncomfortable later because of their subcutaneous position and because they inter-



FIG. 361 The previous case after wiring

fered with the olecranon bursa. They may always be removed easily. After accurate suture of the skin the elbow is covered with a pressure bandage and the whole enclosed in a light plaster case from axilla

more comfortable than the completely extended position. This position is maintained for three weeks, when a sling is substituted and movements within it allowed. This is discarded in two more weeks. The result is usually very satisfactory, though a few cases take time to recover full extension.

Fractures with displacement These must be operated on to restore the structure of the joint accurately and unite the torn aponeurosis. Occasionally in comminuted fractures it is necessary to operate in the absence of wide separation of the fragments because a small fragment is tilted into the joint.

Operative treatment The approach is from behind through a curved incision. This may be curved transversely, or longitudinally,



FIG. 359 A transverse fracture of the olecranon with displacement

and is so arranged that the fracture line and the incision do not cross one another. A tourniquet may be used if desired. The fragments and torn fascia are exposed and cleared of debris. When their accurate configuration is appreciated, a decision as to the best method of fixation may be arrived at. In transverse fractures a long screw inserted from the posterior surface of the olecranon will usually impact the fragments well and maintain good alignment. In fractures of the anterior third, this is essential to avoid recurrent anterior subluxation. If the fragments are badly comminuted this may be difficult and compromises such as that shown in Fig. 363 may have to be used. In oblique fractures, there are usually a few small fragments which have to be removed before the proximal fragment can be fitted into place. It is then best fixed with a single oblique screw inserted from the subcutaneous surface of the olecranon. Wire

firmly pulled down and united by catgut to the fascia around the ulna. The arm is treated post-operatively in the same manner as after screwing or pegging the fragment. This treatment is suitable for comminuted fractures and in the old, particularly, if there is any osteo arthritis.

PROGNOSIS. Union is usually rapid and satisfactory. The amount of movement which returns varies largely with the age of the individual. In the young it is usually complete, in older people there may be a permanent loss of 10° to 15° of movement. In a few cases, particularly comminuted fractures, there is a later development of traumatic arthritis. The principal advantage urged for removal of the fractured fragment is freedom from this latter complication. Excision of the proximal fragment is however only suitable for a limited number of cases.

Fractures of the Shaft of the Ulna

Fractures of the shaft alone are most commonly due to direct violence, and occur in the weak lower third of the bone. The fracture may be transverse, comminuted, or oblique. Displacement is, as a rule, small, owing to the bracing action of the radius and tends to be a bowing of the ulna towards the radius, due to muscle pull.

Owing to the ease with which the bone may be palpated, diagnosis is simple. Difficulty may arise in children in whom the break is greenstick, when false motion cannot be detected. Pronation and supination are painful or lost. In children blows on the inner side of the forearm are liable to produce a greenstick fracture of the ulna with lateral bowing of the bone associated with a lateral subluxation of the elbow and occasionally a fracture of the lateral condyle, or more commonly a separation of the lateral epiphysis (fig 365).

TREATMENT. When displacement is present the following manoeuvres may be tried. Firstly, simple extension, as applied to reduce a Colles's fracture, may be tried with the hand held, however, in radial deviation to exert as much traction on the ulna as possible. This is aided by manipulation with the fingers, which try to bow the ulna posteriorly, a move which usually springs the ends apart. Secondly, if a screwing room is available, a small Steinmann's pin may be inserted under a local anæsthetic and engaged in the bone ends, and used to lever them back into position. Failing this open operation is the last hope. (This is more commonly required to retain position than to reduce the deformity.) Fixation is by an arm plaster, including the elbow held at a right angle, and the forearm in the mid-prone position, the plaster being continued down to the meta-

to metacarpal heads. The elbow is placed at an angle of 90 to 115 degrees, depending on the amount of relaxation of the triceps




Fig. 362 A comminuted fracture of the olecranon treated by the removal of the proximal fragment

required. The plaster is removed at the end of a fortnight and the stitches removed. Subsequent treatment depends on the rigidity

of fixation achieved. In oblique cases with a single screw fixation, gentle movements may be commenced at this stage and the forearm merely supported in a sling. In other cases further immobilisation in plaster for a fortnight may be required.

TRANSPLANTATION OF THE TRICEPS INSERTION. Recently removal of the fractured fragment of the olecranon has been practised with considerable success. It appears to be more satisfactory than the corresponding removal of the patella for fractures of the patella. In either case the important feature of the operation is the union of the



Fig. 363 The previous case after operative removal of the proximal fragment. There is some formation of new bone in the tendon of the triceps but the functional result is excellent.

expansions of the muscle, in this case the triceps. The operation is planned as for suture, the proximal fragment of bone is removed and any spicules around the distal end trimmed up. The triceps is then



FIG 361 Green tick fracture of the upper end of the ulna with a lateral subluxation of the elbow and the upper radio ulnar joint



FIG 367 Separation of the lower radial epiphysis showing the small chip of metaphysis usually displaced with it



FIG 368 Lateral view of a wrist showing posterior dislocation of the thumb from the trapezium (metacarpal major) and anterior dislocation of the trapezoid (metacarpal minor) accompanied by a dislocation of the second metacarpal at its articulation with the carpus (See FIG 411)



FIG 368 Fracture of a sesamoid bone of the thumb. There is also a sesamoid bone at the insertion of flexor pollicis longus into the base of the distal phalanx. This is commonly present and may be mistaken for a fracture

carpals, to prevent rotation, and to use radial deviation of the hand if necessary, as a method of control. In a few cases there is associated dislocation of the lower radio-ulnar joint which must be reduced, and makes retention of the fragments more difficult. The circular plaster bandage must not be tight as that may bend the ulna toward the radius, and methods to prevent this as in fractures of both bones of the forearm may have to be adopted. (See Figs 376, 377)

The ulna unites slowly and requires immobilisation for four to six weeks in the young, and six to eight weeks in the old. Even then




FIG 364 Fracture of the shaft of the ulna with forward dislocation of the head of the radius. The so called Monteggia fracture. The same case as shown in Fig 35.

it may not be firm. If it is, a sling is worn for a further fortnight. If it is weak a plaster splint is applied to the forearm only. In cases of delayed union the whole arm plaster is repeated for four weeks and the case reviewed again.

Fracture of the Ulna associated with Dislocation of the Head of the Radius

This fracture was first described by Monteggia in 1814 and bears his name. It consists of a fracture of the ulna in the upper half accompanied by a dislocation of the head of the radius and is usually due to direct violence applied to the ulna. If the fracture of the ulna



FIG. 364 Green stick fracture of the upper end of the ulna with a lateral subluxation of the elbow and the upper radio-ulnar joint



FIG. 367 Separation of the lower radial epiphysis showing the small chip of metaphysis usually dis-



FIG. 368 Lateral view of a wrist showing posterior dislocation of the thumb from the trapezium (multangulum majus) and anterior dislocation of the trapezoid (multangulum minus) accompanied by a dislocation of the second metacarpal at its articulation with the carpus (See FIG. 411)



FIG. 369 Fracture of a sesamoid bone of the thumb. There is also a sesamoid bone at the insertion of flexor pollicis longus into the base of the distal phalanx. This is commonly present and may be mistaken for a fracture



occurs below the centre there is a tendency for the radius to fracture rather than dislocate, hence the common association with fractures of the upper third of the ulna. The dislocation of the radius may be anterior (Fig. 364), posterior (Fig. 372), or lateral. Fracture of the head of the radius is not uncommonly associated. The inevitable rupture of the orbicular ligament is not important, unless it obstructs, or renders reduction of the dislocation impossible. The lesion is important for two reasons, firstly, because the dislocation of the head of the radius is often overlooked, and, secondly, because there is a great tendency of the ulna to unite with bowing towards the radius if the condition is not correctly treated. The accident is most common in children between the ages of five to nine and in them non-operative reduction is usually satisfactory, and a good position can be maintained with a plaster. In adults this is not the case and the need for perfect reduction of the ulna demands frequent open operative interference. Fracture of the head of the radius demands operation in most cases, due to the displacement of the fragment.

REDUCTION. This is accomplished by traction combined with manipulation of the head of the radius. In anterior dislocations, which are more common, the forearm is flexed and the head of the radius pushed down into position (Fig. 370). In posterior dislocations the head of the radius is pushed up. Immobilisation in plaster from the metacarpals from the axilla is necessary, and cases of anterior dislocation should be put up in slight flexion, while cases of posterior dislocation should be in incomplete extension (135 degrees). Cheek radiographs are taken to ensure the head of the radius is reduced and the ulna in good position.

OPERATIVE TREATMENT. Open operation is to be recommended to the following cases:

(a) Those in which the head of the radius cannot be reduced or retained in position. Exposure of the head and division of the orbicular ligament is usually all that is required.

(b) Cases in which the ulna remains bowed toward the radius, or otherwise displaced.

(c) All adult cases with any displacement, owing to the necessity for perfect reduction and the early use of the forearm.

(d) Cases in which there is a fracture of the head of the radius with displacement of the fragment. Best treated by excision of the head of the radius.

The alternative open operative methods for fixation of the ulna are described in fractures of both bones of the forearm, and rest between, single screw fixation in oblique fractures, plating or the use of a bone graft, and the use of intramedullary Kirschner wires.

The use of the bone graft is to be preferred as it gives sound fixation and the situation is a technically easy one for its use Early move




FIG 369 Fracture of the ulna with anterior dislocation of the head of the radius (Monteggia fracture) showing the usual directions of traction in reducing a forearm fracture

ments of the forearm can be encouraged and the definite risk of non-union with this fracture in adults is avoided

In children open operation is to be discouraged, the head of the




FIG 370 Showing the reduction of the fracture and dislocation by traction on the hand combined with anterior pressure over the head of the radius

radius must not be excised, and anything more than the embedding of a single screw in the ulna is to be avoided if possible




FIG 371 The same case after the application of plaster

Fractures of Both Bones of the Forearm

These are due to direct and indirect violence in almost equal proportion They are more common in the lower third of the



FIG. 372 Fracture of both bones of the forearm with posterior dislocation of the head of the radius



FIG. 373 The same case after reduction. There was also a chip fracture of the head of the radius which required open operation and removal of the fragment

The use of the bone graft is to be preferred as it gives sound fixation and the situation is a technically easy one for its use Early move




FIG 369 Fracture of the ulna with anterior dislocation of the head of the radius (Monteggia fracture), showing the usual directions of traction in reducing a forearm fracture

ments of the forearm can be encouraged and the definite risk of non-union with this fracture in adults is avoided

In children open operation is to be discouraged, the head of the




FIG 370 Showing the reduction of the fracture and dislocation by traction on the hand combined with anterior pressure over the head of the radius

radius must not be excised, and anything more than the embedding of a single screw in the ulna is to be avoided if possible




FIG 371 The same case after the application of plaster

Fractures of Both Bones of the Forearm

These are due to direct and indirect violence in almost equal proportion They are more common in the lower third of the



FIG. 372. Fracture of both bones of the forearm with posterior dislocation of the head of the radius.



FIG. 373. The same case after reduction. There was also a chip fracture of the head of the radius which required open operation and removal of the fragment.

The use of the bone graft is to be preferred as it gives sound fixation and the situation is a technically easy one for its use. Early move




FIG 369 Fracture of the ulna with anterior dislocation of the head of the radius (Monteggia fracture), showing the usual directions of traction in reducing a forearm fracture

ments of the forearm can be encouraged and the definite risk of non union with this fracture in adults is avoided

In children open operation is to be discouraged, the head of the




FIG 370 Showing the reduction of the fracture and dislocation by traction on the hand combined with anterior pressure over the head of the radius

radius must not be excised, and anything more than the embedding of a single screw in the ulna is to be avoided if possible




FIG 371 The same case after the application of plaster

Fractures of Both Bones of the Forearm

These are due to direct and indirect violence in almost equal proportion. They are more common in the lower third of the



FIG. 372 Fracture of both bones of the forearm with posterior dislocation of the head of the radius



FIG. 373 The same case after reduction. There was also a chip fracture of the head of the radius which required open operation and removal of the fragment

The use of the bone graft is to be preferred as it gives sound fixation and the situation is a technically easy one for its use. Early move




FIG 369 Fracture of the ulna with anterior dislocation of the head of the radius (Monteggia fracture) showing the usual directions of traction in reducing a forearm fracture

ments of the forearm can be encouraged and the definite risk of non union with this fracture in adults is avoided

In children open operation is to be discouraged, the head of the




FIG 370 Showing the reduction of the fracture and dislocation by traction on the hand combined with anterior pressure over the head of the radius

radius must not be excised, and anything more than the embedding of a single screw in the ulna is to be avoided if possible




FIG 371 The same case after the application of plaster

Fractures of Both Bones of the Forearm

These are due to direct and indirect violence in almost equal proportion. They are more common in the lower third of the



FIG. 372. Fracture of both bones of the forearm with posterior dislocation of the head of the radius.



FIG. 373. The same case after reduction. There was also a chip fracture of the head of the radius which required open operation and removal of the fragment.

forearm, and in children in whom the lesion is commonly greenstick. When both bones are completely broken and there is considerable



FIG 374 Greenstick fracture of both bones of the forearm

overlap, or there is comminution, it becomes a difficult fracture to treat. Displacement is usually due to the direction of the force, combined with the action of gravity and the manipulations of the patient. Muscle spasm produces shortening and overlap of the fractured ends. The displacement of the radius which may occur is similar to that in fractures of this bone alone, and the ulna tends to bow in towards it. Dislocation of either upper or lower radio ulnar joint may also occur (Fig 372)



FIG 375 Diagram to show the approximation of the forearm bones produced by a circular plaster



FIG 376 One method of overcoming the difficulty. Two wooden rods ($\frac{1}{2}$ inch \times $2\frac{1}{2}$ inches) are pressed into the plaster slabs on either side of the arm and the whole covered by the circular plaster




FIG 377 A second method for avoiding the approximation of the bones at the site of fracture. A narrow board C which is wider than the forearm is placed on the inner aspect of the forearm and held there by the circular bandage B which also covers the usual plaster slab A

Owing to the peculiar relationship of the upper and lower radio-ulnar joints which permit the complicated movement of pronation and supination alteration of bony alignment is particularly liable to be followed by limitation of movement the imposition of strain on the two joints, subsequent traumatic arthritis. It follows that perfect reduction of the fractures of both bones is necessary if function is to be satisfactory. In children growth will compensate for minor imperfections but not so in adults who require the most careful attention if satisfactory results are to be obtained. The

difficulties are due to the tendency of the two bones to bow into one another due to muscle pull, and the pressure of a circular plaster, the tendency to cross union in fractures at the same level, the difficulty in reducing both fractures equally well, and the frequent failure to correct rotational deformities. Rotational deformity is particularly difficult to correct and most important. It is impossible to check its reduction radiologically, and it can be said with truth that the only way to be certain that it is corrected is to see the interlocking of the bony spicules of the fractured surfaces at open operation.

DIAGNOSIS. This is usually straightforward. In children there may be very little deformity, but when there is, on account of the incomplete nature of the fracture, it is fixed, and false motion is not detectable.

TREATMENT. Perfect reduction must be kept the goal of all methods. Numerous methods have been devised to achieve this and are adaptable to each case. Each case is a separate problem, in which the deformity present, the type of fracture, the levels of the two fractures, and the degree of soft tissue injury must be carefully considered and the appropriate decision reached. The available methods will be outlined, the combinations of these methods possible can only be briefly discussed, but will, I hope, be sufficient to stimulate interest in each case as a separate problem.

CASES WITHOUT DISPLACEMENT. It is necessary here to avoid deformity from the pull of muscles, the action of gravity, and the pressure of the splint. The forearm is splended by gentle traction as for a Colles's fracture and a plaster applied from the metacarpals to the elbow. It is subsequently continued above the elbow when the traction is released. Two methods may be adopted to avoid the pressure of the circular bandages narrowing the interosseous space, and these are shown in Figs. 176 and 177. The forearm is most satisfactorily treated in the mid pronated position, which relaxes as many muscles as possible. Full supination has the advantage of maintaining the interosseous space at its widest, but this is not necessary in cases in which there is no danger of cross union. In all other cases, however, supination is a safer position than pronation, not only for the reason given, but because pronation can be compensated for by the shoulder, while supination cannot. The plaster having been completed is carried in a sling. It is replaced as soon as it becomes loose, careful watch being kept for angulation by clock radiographs. Its occurrence demands replaster or the adoption of a method in which retention is better controlled.

CASES WITH DISPLACEMENT. Reduction may be carried out under anaesthesia in a similar manner, or by the use of skeletal

forearm, and in children in whom the lesion is commonly greenstick. When both bones are completely broken and there is considerable



FIG 374 Greenstick fracture of both bones of the forearm

overlap, or there is comminution, it becomes a difficult fracture to treat. Displacement is usually due to the direction of the force, combined with the action of gravity and the manipulations of the patient. Muscle spasm produces shortening and overlap of the fractured ends. The displacement of the radius which may occur is similar to that in fractures of this bone alone, and the ulna tends to bow in towards it. Dislocation of either upper or lower radio ulnar joint may also occur (Fig 372)



FIG 375 Diagram to show the approximation of the forearm bones produced by a circular plaster



FIG 376 One method of overcoming the difficulty. Two wooden rods ($\frac{1}{2}$ inch \times 2 $\frac{1}{2}$ inches) are pressed into the plaster slabs on either side of the arm and the whole covered by the circular plaster




FIG 377 A second method for avoiding the approximation of the bones at the site of fracture. A narrow board C which is wider than the forearm is placed on the inner aspect of the forearm and held there by the circular bandage B which also covers the usual plaster slab A

Owing to the peculiar relationship of the upper and lower radio ulnar joints which permit the complicated movement of pronation and supination alteration of bony alignment is particularly liable to be followed by limitation of movement the imposition of strain on the two joints, subsequent traumatic arthritis. It follows that perfect reduction of the fractures of both bones is necessary if function is to be satisfactory. In children growth will compensate for minor imperfections, but not so in adults who require the most careful attention if satisfactory results are to be obtained. The

in the radius might be satisfactorily held if the ulna was fixed at the same time. Varying combinations of fractures are met with both transverse at the same level, transverse at different levels, one



FIG. 380. Reduction and fixation of previous case by an intramedullary Kirschner wire in the ulna and single screw in the radius. AP view.



FIG. 381. Lateral view of same case.



FIG. 382. Use of intramedullary Kirschner wire alone in fractures of both bones of the forearm. Displacement of radius insufficient to warrant open operation and owing to comminution fixation would be difficult.

transverse the other oblique, one oblique the other comminuted, and so on. It is possible to fix one bone, usually the ulna, and if there is little displacement in the radius leave it alone. Commonly combinations of methods adapted to the type of fracture are employed.

METHODS. 1. *Single screw fixation.* Adaptable to oblique

traction (Fig 384) The wires are inserted in the olecranon and through the metacarpal heads, or through the lower end of the radius and the ulna By traction and manipulation under radiological control a fairly good position of the bones can usually be achieved, though rotation is still likely to remain uncorrected The chief disadvantage is the liability to recurrence of the displacement as soon as the traction is released while inside the plaster In order to maintain control of the bones the wires may be incorporated in the plaster, thus making use of fixed distraction This is undesirable anywhere, and particularly in the forearm where it is likely to lead



FIG 378 Fracture of both bones of the forearm with dislocation of the lower radio ulnar joint A P view



FIG 379 Lateral view of the same case

to non union of the ulna Control of the fragments by pins which screw into the bones and enable the angle of the fracture to be controlled and which can be incorporated in the plaster is more satisfactory, but seldom produces perfect reduction

Open operative methods Three principles must be borne in mind, early and perfect reduction minimum soft tissue disturbance, and the imparting of sufficient rigidity to the bones by the fixation used to render the need for plaster except as a protection unnecessary The ulna tends to bow more readily than the radius and requires stronger fixation to maintain its rigidity A transverse fracture in the ulna is not satisfactorily fixed by a single screw but

2 *Plates or bone grafts* These have the advantage of restoring the rigidity of the bone and this is particularly valuable here. They are most conveniently applied to the ulna which fortunately is the most important bone to fix but may be applied to both bones. The radius is cut level to facilitate the application of the graft.

3 *Intramedullary Kirschner wires* This is a particularly useful method for the ulna, where the wire can be brought out through the olecranon but is less satisfactory in the radius where it must be brought out in the vicinity of the styloid process. The bones are exposed as for open operation but through a much smaller incision, a long sterile Kirschner wire is introduced down the proximal fragment and made to protrude through the olecranon. It is withdrawn till the end just disappears from view at the fracture line. The two bones are then accurately reduced and the wire pushed across the fracture line to lock the bones in position. The forearm is then put in plaster leaving the wire protruding. When union is firm enough to prevent rotation and deformity the wire is removed, usually between the fourth and sixth week.

In Figs. 380, 382 different combinations of the methods described which produced satisfactory results are shown.

Union is slow, taking four to eight weeks in children and six to twelve weeks in adults. The nearer the fracture to either end of the bone the more rapid the union. Delayed union is common, and is treated by repeated plasters by Beck's drilling. An unusual and serious complication is the occurrence of cross union between the bones, due to the hematoma around both bones being continuous. Ossification occurs in this, and the bones become connected by a firm bar which prevents pronation and supination. After time has elapsed for this bone to become well organised its operative removal is the only hope of cure.

Separation of the epiphyses of both bones This may occur up to the age of sixteen years. The treatment is similar to that of separation of the radial epiphysis alone. The ulnar epiphysis being firmly attached to it, they are easily reduced together and the position maintained by a short forearm plaster, with the hand in slight palmor flexion.

REFERENCES

Fractures of the Olecranon

- NAUGHTON DUNN "Operation for Fracture of the Olecranon," *Brit. M. J.* 1939, 1, 214
DALAND J. M. "Fractures of the Olecranon," *J. Bone and Joint Surg.*, (Recommending fascia lata suture.)

fractures and to half oblique, half transverse fractures, and spiral fractures, of either bone. Single screws may be used in transverse




FIG 383 Fixation of the forearm in difficult fractures with two thin Steinmann's pins incorporated in the plaster. The dotted line indicates the site for the wooden rods described in Fig 376



FIG 384 The use of the Bobler leg frame for traction in cases of fracture of the forearm. The patient is under brachial plexus anesthesia. One wire runs through the metacarpal heads, the other through the olecranon




FIG 385 The same case with the plaster applied over the wires which are removed when it has set

fractures to control position when angulation is controlled by fixation of the other bone

CHAPTER XXV

FRACTURES AND DISLOCATIONS OF THE CARPUS

Surgical anatomy—The complex articulations of the carpal bones allow an injury the chance of many joint paths and this, combined with the fractures of the bones which may be associated, allows a multiplicity of lesions to be developed. As a guide to these the following points must be noted. The proximal bones of the wrist, navicular, lunate and triquetrum, each have a large doubly-curved articular area for articulation with the lower end of the radius, and the triangular fibrocartilage. This area is more extensive on the dorsum, and it allows flexion and extension, and abduction and adduction at the wrist. The large area of articulating bone, consequently, renders dislocation at this level more frequent than at the intercarpal or carpo-metacarpal level.

The capitate fits into a socket formed by the navicular, lunate and hamate and terminal flexion and extension of the wrist occurs at this joint. It is strongly resistant to lateral strain, but anterior or posterior dislocation may occur at this level. The navicular lies as a lynch pin across the two carpal rows, strongly articulated with each row, and forming a bony link between them. It follows that in strains on the intercarpal joint it is subjected to heavy shearing forces, and not infrequently breaks at the wrist, such a fracture being accompanied by displacement. In the more common lesion of the navicular, it is merely squeezed violently between the carpal bones and the lower end of the radius. This results in a fissure of the cancellous bone, the deformity produced being insufficient to rupture the cartilaginous capsule of the bone, and displacement is negligible. These are the fractures which it is difficult to see radiologically. The articulation of the carpo-metacarpal joints is an irregular line, which will similarly resist lateral strain, but is susceptible to dislocation in the A/P plane. The first metacarpal has a separate saddle-shaped joint, where it articulates with the multangulum major.

As it is impossible in a book of this size to go into the numerous lesions which occur in the carpus they will be briefly listed, and then the more common and important lesions described. The figures given, taken from Schuck, indicate the frequency of the lesions.

Fractures

Navicular	Old and new	234
Lunate	Body and posterior process	82 (100 high—1 fracture of posterior tubercle of triquetrum were included)
Triquetrum		18 (Too low)
Pisiform		13
Multangulum major		13
Hamate		10
Capitate		6
Multangulum minor		1

General

- HEIN "Fractures of the Forearm," *J Bone and Joint Surg*, 1935, 17, 272
- SOWLES "End Results of Fractures of both Bones of the Forearm," *J Bone and Joint Surg*, 1934, 16, 193
- CUNNINGHAM "Fractures of the Ulna and Dislocation of the Head of the Radius," *J Bone and Joint Surg* 1934, 16, 351
- NAYLOR, A "Monteggia Fracture," *Brit J Surg*, 1942 30, 323
- SMITH, F M "Monteggia Fractures" *Surg Gynec and Obstets*, 1947, 85, 630-640

be seen. These cases form 80 per cent. of the cases met with and do extremely well if immobilised in plaster. It is obvious from the fact that the cartilaginous envelope is nearly always partly intact that it is unnecessary to fix the thumb in the plaster cast to obtain adequate rest for union to occur.

2. **FRACTURES OF THE WAIST WITH DISPLACEMENT.** These are due to fracture of the bone associated with a subluxation or spasm of the mid carpal joint, the navicular being snapped as the connecting link between the two rows. (Compare with perilunar dislocation of the wrist.) The displacement is obvious or appears immediately or after a short interval as an elliptical clear space between the bones. In the past this has often been considered to be a sign of bone erosion at the fracture line, but is due to the shadows produced by the overlying margins of the fractured bone as the central ray passes obliquely through the fracture site. It is an indication of displacement and there is consequently greater risk of non union. These cases demand reduction and a longer period of immobilisation to secure union. To be safe it is necessary to immobilise the thumb to exclude all possibility of movement at the wrist. It is in this group of cases (5 per cent.) that early operation can produce more rapid and more certain union, though the final results except in skilled and practised hands are not much improved.

Avascular necrosis. Failure of the blood supply to the proximal fragment results in a delay in union and may result in avascular necrosis of the proximal pole. This is a serious complication as it prevents union and usually results in a rapid breakdown of the radio carpal joint. The blood supply to the navicular enters the dorsal surface along a groove which crosses the waist of the bone obliquely and leaves the proximal pole to obtain what nourishment it can through the navicular lunate ligament. It is owing to the fact that this pole is largely covered in cartilage that a blood supply cannot develop through the formation of adhesions. The cartilaginous portion of the bone survives in the tissue fluids, thus making an effective barrier to revascularisation from that area. Revascularisation can thus come only through the fracture line, or the navicular lunate ligament. Not all fractures through the proximal pole, and only a few through the waist, show avascular necrosis and its onset is determined by other factors than the fracture itself. Avascular necrosis manifests itself by the series of changes previously



FIG. 386. Fracture sites in the navicular.

- A. Fracture of the neck to its
- B. Fracture at the waist cutting the line of the nutrient foramina.
- C. Fracture proximal to the line of blood supply.

Dislocations

Lunate Old and new 25

Lunate and navicular dislocated 10

Dislocation of the lunate and fracture of the navicular 7

Pisiform 6

Triquetrum 1

Capitate 1

Dislocations of the wrist, anterior and posterior, at the carpo metacarpa carpo carpal, and radio carpal joints occurred only once each

In discussing these lesions the general principles will be first outlined, and then the individual, more important bones mentioned.

In the case of fractures there is generally little displacement and the treatment consists in immobilising the wrist in moderate dorsiflexion until clinical and X-ray evidence shows that the bone has united. This will be elaborated in the description of fracture of the navicular. In fracture dislocations the dislocation is reduced. This is usually accomplished by steady traction, under local or general anaesthesia, accompanied by manipulation and pressure with the fingers. At the same time any displacement of an associated fracture is reduced, and the case is then treated on the merits of the fracture. In dislocations alone the reduction is accomplished as outlined, and the wrist then immobilised in plaster for three to five weeks, while exercises as for a Colles's fracture are carried out.

Fracture of the Navicular (Scaphoid)

This is the most commonly injured bone in the wrist, the bone being broken in the transmission of force from the hand to the radius. Fractures of the navicular consist of fractures of the tuberosity and of the proximal pole of the bone, forming 12 per cent of all cases, the remaining large majority (88 per cent) being fractures of the waist of the bone. These are the most important and interesting group and are subdivided into two great classes.

1. FRACTURES OF THE WAIST WITHOUT DISPLACEMENT. These are due to falls on the hand in which the weight is transmitted through the navicular to the radius. The bone is squeezed between the carpus and the radius, but cannot be deformed or displaced being well supported on all sides. As a result a crack in the cancellous bone occurs, which in a great many cases does not involve the cartilaginous envelope of the bone. As a result the fragments are held in exceedingly close apposition and difficulty may be found in discovering the fracture in the first radiograph. The importance of the central ray lying in the plane of the fracture is obvious and three or more views are necessary to ensure this. These facts have often been proved at operation where in spite of radiologic evidence of fracture no external evidence of fracture can

basis of the first metacarpal. Rarely the navicular is fractured in association with other lesions, which may be dislocations of the lunate, or of the wrist, fractures of the lower end of the radius or of the styloid process of the ulna, or the bone may be involved with others in complex crushing injuries.

X-RAY INVESTIGATION The films must be of good definition, and of sufficient detail to show the bony trabeculae. Owing to the fact that the fracture line is sometimes oblique it may not show up in certain positions, so that it is necessary to radiograph the wrist in an oblique position as well as the lateral and AP positions. The fracture may be obvious or require a careful search with a lens. In searching, the thin layer of compact bone must be accurately followed. When, in spite of a negative X-ray, signs and symptoms remain, the wrist should be rested in plaster for three weeks and then re-X-rayed. If a fracture has been present there will be sufficient




FIG. 185. Plaster for fracture of the navicular

decalcification along the line of fracture to make it obvious in the second radiograph (Fig. 193).

Later films may show varying degrees of sclerosis and rarefaction in the bone which may be interpreted as the sequelae of vascular changes around the fracture line. This has been mentioned especially in connection with the small fragment near the lunate. Both rarefaction and patchy sclerosis on either side of the fracture line will disappear with adequate immobilisation, and healing can only be said to be complete when trabeculae can be seen to cross the line of fracture. Sclerosis of a uniform and continuous type on either side of the fracture line is a sign of complete non-union and an indication that unless some treatment is given bony union will never occur, and is going to be very difficult to achieve if treatment is instituted.

The significance of the elliptical shadow appearing at the fracture line has already been mentioned. Gauging union is not always easy, and a decision to allow use of the wrist is often based more on the

outlined (p 17), and finally by a hypercalcification of the fragment. In this event the removal of the fragment may be indicated, though some remove the whole bone. If gross traumatic arthritis of the wrist is present it is probable that the case will go on to an arthrodesis of the wrist.

The fracture has gained a bad reputation from the fact that a great many cases have been unrecognised, and consequently inadequately treated, and many cases have been treated over an insufficient length of time to obtain union. Ununited fractures of the navicular are painful, and result in a feeling of weakness in the wrist, while in cases in which the proximal fragment undergoes necrosis a seriously disabling arthritis of the wrist is set up, which will be sufficient to totally incapacitate a working man. Recently it has been shown that prolonged immobilisation will cure the most obstinate cases unless sclerosis of the fracture line is present, or there is degeneration of portion of the bone.



FIG 357 Testing for fracture of the navicular. Weight bearing on the thenar placed on the corner of the table produces pain.

DIAGNOSIS Following a story suggestive of Colles's fracture the patient will be found to complain of pain which will be maximum over the "anatomical snuff box," i.e., directly over the navicular, this being the most important clinical sign. In most cases the fact that the lower end of the radius is free from tenderness can be found by careful pressure. The swelling is confined mainly to the radial side of the wrist, and the obliteration of the anatomical snuff box is easily seen by comparison with the opposite wrist. All movements of the wrist are painful, but abduction particularly so. There is pain on grip-

ping and weakness of the grip, and there is always pain if the patient is asked to press firmly on the thenar eminence. Once seen the syndrome will be readily recognised, but a few atypical cases occur, and any lesion of the wrist displaying one or more of the features mentioned justifies an X ray examination of the wrist.

DIFFERENTIAL DIAGNOSIS Lesions producing a similar picture may be a severe sprain, fracture of the tuberosity of the navicular, fracture of the tip of the radial styloid process, and fractures of the

the patient's work necessitates putting the hand in water, "Castex," a compound of cellulose in acetone, may be used. It is slow in drying, but impervious to water.

During the period of immobilisation in plaster it is necessary, particularly in the old, to give exercises to the fingers and other joints of the arm as in cases of Colles's fracture. Immobilisation is carried out on these lines for seven weeks, the plaster is then removed which gives opportunity to inspect the skin and estimate the clinical improvement. The wrist is X-rayed and if there is evidence of obliteration of the fracture line, and particularly if trabeculae can be seen to cross the fracture line, union can be said to be sound. The changes in the bone outlined previously must be watched for and if found demand further immobilisation, till they have cleared up or become permanent when other methods must be used. Union at the end of seven weeks is often sound; if not the wrist is immobilised as before for a further four weeks. At the end of this period the examination is repeated and, if satisfactory, the patient is given a clinical trial of the unsupported wrist; if unsatisfactory, the plaster is repeated. This is continued up to a period of eight months, when the most obstinate fractures will usually have united. If not, then other methods must be adopted to obtain union. If the patient on clinical trial gets increasing pain in the wrist with use it is a sign that the union is incomplete and the X-rays are carefully re-examined and the wrist further immobilised for four weeks.

Delay in union may be due to

- (1) Late institution of treatment
- (2) Inadequate immobilisation
- (3) Avascular degeneration in portions of the bone
- (4) General bony degeneration in arthritic wrists

In the first two groups continued and more satisfactory immobilisation can be tried if there is no evidence of established non-union, i.e., sclerosis of the fracture surfaces with smoothing off of their outlines and even the formation of a thin layer of compact bone. If these are present further immobilisation is useless and the functional capacity of the wrist should be given a clinical trial. In many cases in which no heavy



FIG. 191. Bed a bone drilling for ununited fracture of the navicular under the skin.

absence of signs of delayed union in a case adequately treated than on definite appearances of union

Treatment Cases without displacement Firm fixation in a plaster, which extends from just below the elbow to the heads of the metacarpals, with the hand in moderate dorsiflexion, and the wrist slightly ulna adducted, will, if maintained long enough, result in union in all but very old cases There is considerable discussion as to the necessity for immobilising the thumb In unskilled hands it is possibly safer to include the thumb metacarpal in the plaster, but



FIG. 389 Palmar view of the same plaster. Note that the thumb is left free




FIG. 390 Lateral view of the same plaster

we have had no difficulty in obtaining bony union in the usual time in cases in which the thumb has been left entirely free In such cases more than usual care was taken that the plaster fitted accurately around the outer side of the fifth metacarpal and the thumb side of the second metacarpal, so that abduction and adduction at the wrist were completely prevented and the firm bar across the palm of the hand was carefully watched and renewed as soon as a tendency was shown for the hand to come away from the plaster This usually necessitated a renewal of the plaster at the end of the first week when the swelling had subsided and again as often as was necessary In a man doing heavy work this was often every ten days or so If

the patient's work necessitates putting the hand in water. Castex's compound of cellulose in acetone may be used. It is slow in drying, but impervious to water.

During the period of immobilisation in plaster it is necessary, particularly in the old, to give exercises to the fingers and other joints of the arm as in cases of Colles's fracture. Immobilisation is carried out on these lines for seven weeks; the plaster is then removed, which gives opportunity to inspect the skin and estimate the clinical improvement. The wrist is X-rayed and if there is evidence of obliteration of the fracture line, and particularly if trabeculae can be seen to cross the fracture line, union can be said to be sound. The changes in the bone outlined previously must be watched for, and if found demand further immobilisation, till they have cleared up or become permanent, when other methods must be used. Union at the end of seven weeks is often sound; if not the wrist is immobilised as before for a further four weeks. At the end of this period the examination is repeated, and if satisfactory the patient is given a clinical trial of the unsupported wrist; if unsatisfactory the plaster is repeated. This is continued up to a period of eight months, when the most obstinate fractures will usually have united. If not, then other methods must be adopted to obtain union. If the patient on clinical trial gets increasing pain in the wrist with use it is a sign that the union is incomplete and the X-rays are carefully re-examined and the wrist further immobilised for four weeks.

Delay in union may be due to

- (1) Late instigation of treatment
- (2) Inadequate immobilisation
- (3) Avascular degeneration in portions of the bone
- (4) General bony degeneration in arthritic wrists.

In the first two groups continued and more satisfactory immobilisation can be tried if there is no evidence of established non-union, i.e. sclerosis of the fracture surfaces with smoothing off of their outlines, and even the formation of a thin layer of compact bone. If these are present further immobilisation is useless and the functional capacity of the wrist should be given a clinical trial. In many cases in which no heavy



FIG. 391. Beck's bone drilling for ununited fracture of the navicular under the screen.

absence of signs of delayed union in a case adequately treated than on definite appearances of union

Treatment Cases without displacement Firm fixation in a plaster, which extends from just below the elbow to the heads of the metacarpals, with the hand in moderate dorsiflexion, and the wrist slightly ulna adducted, will, if maintained long enough, result in union in all but very old cases There is considerable discussion as to the necessity for immobilising the thumb In unskilled hands it is possibly safer to include the thumb metacarpal in the plaster, but




FIG 389 Palmar view of the same plaster Note that the thumb is left free



FIG 390 Lateral view of the same plaster

we have had no difficulty in obtaining bony union in the usual time in cases in which the thumb has been left entirely free In such cases more than usual care was taken that the plaster fitted accurately around the outer side of the fifth metacarpal and the thumb side of the second metacarpal, so that abduction and adduction at the wrist were completely prevented and the firm bar across the palm of the hand was carefully watched and renewed as soon as a tendency was shown for the hand to come away from the plaster This usually necessitated a renewal of the plaster at the end of the first week when the swelling had subsided and again as often as was necessary In a man doing heavy work this was often every ten days or so If



FIG. 312. Fracture fracture of the navicular wrist



FIG. 313. X-ray film of a fracture of the navicular three weeks after the accident. The fine fissure fracture in the films at the time of the accident was overlooked. Now rarefaction around the fracture line shows up clearly.



FIG. 394. Ligament traction fracture of the dorsal tubercle of the triquetrum. Old case in which the fragment appears like a sesamoid.



FIG. 395. Fissure fracture of the lunate showing some early sclerosis in the distal fragment.

demands are placed on the wrist the result will be moderately satisfactory. If it is unsatisfactory, excision of the proximal pole or of the whole navicular may be carried out, though this is not likely to produce a strong wrist, it may relieve pain. After eight months' immobilisation there is little value in keeping the wrist further immobilised, and a clinical trial should be given as in the case of established non-unions.

Where avascular necrosis has been the cause of the non union, excision of the proximal pole should be carried out. The earlier this is done, i.e., the less the degree of established arthritis the better the result. These cases are best treated by immediate excision of the proximal pole as soon as avascular necrosis is diagnosed, that is in the first four to six weeks. Where there is a general arthritic condition



FIG 396 Fracture of the navicular with displacement



FIG 397 The same case after reduction. This must be checked in the lateral and oblique views as well as the A.P.

in the wrist, ankylosis is the only alternative to palliative measures such as the wearing of a moulded wrist support or wrist strap.

Fractures with displacement. Satisfactory reduction is not easy to accomplish, in any case with displacement in two planes. If the displacement is in one plane the position can often be made satisfactory by putting the hand in ulna deviation. It is the displacement present in the lateral view which is difficult to control, because it depends on a disturbance of the mid carpal joint. It is for this reason that early operative interference is advised, as under radiographic control perfect reduction can be achieved by manipulation of the proximal fragment by means of the pin inserted into it. It can then be locked in position and the graft inserted. In the open method the reduction is visual and a graft from the styloid process of the radius is used. In the closed method special apparatus is necessary and considerable skill in its use is required before a good graft

can be inserted. Unfortunately though the immediate results of grafting appeared fair, the long term results are bad, due to the development of a radio carpal arthritis and the method has been almost entirely given up.

Displaced fractures of the navicular have a much worse prognosis than the undisplaced due to the frequency of non union and increased risk of ischaemic necrosis. Where necrosis of the proximal pole develops early excision is recommended as in undisplaced fractures. A longer period of immobilisation is necessary if union is



FIG 398 Fracture of the tuberosity of the navicular



FIG 399 Perilunar dislocation of the wrist (Fig. 400) accompanied by fracture of the navicular and followed rapidly by the appearance of Kienbock's disease of the scaphoid

to occur and this may take as long as fifteen months. Again positive evidence of non union makes persistence in immobilisation useless and the wrist should be given a trial as it may function moderately well with fibrous union. Late grafting will produce even more unsatisfactory results than early grafting. Treated as outlined only a very small percentage will show such a degree of arthritis that the patient is seriously crippled, and demands further treatment. This may consist of excision of the proximal carpal row, or arthrodesis of the wrist. Recently excision of the radial styloid has been tried to relieve cases with a localised arthritis but it is too early to speak of the results.

Fractures of the tuberosity of the navicular are rarer than fractures of the body. The symptoms resemble a mild fracture of the body and the lesion is detected on the antero posterior X ray film. Immobilisation for three weeks in the position used for fractures of the body produces union with no disability.

to the tuberosity of the bone being involved. The successful recognition of the lesion depends on good radiography, with at least one additional oblique view of the wrist.

Diagnosis. The condition rarely occurs alone and its signs are usually masked by the associated lesion. The most common isolated lesion is the fracture of the dorsal tubercle, which produces swelling and pain localised to the ulnar side of the wrist. There is moderate pain on all movements, but radial deviation and palmar flexion are most painful. Undiagnosed cases may be seen with complaints of chronic sprain and the fragment of the posterior tubercle may be mistaken for a sesamoid in the lateral film (fig. 394). Injury to the triquetrum should be looked for in association with any fracture of the radius, fractures of the other carpal bones, and in carpal dislocations.

Treatment. Isolated fractures of the bone should be treated in a similar manner to fractures of the navicular of which they are the ulnar counterpart. Fractures of the tubercle and the tuberosity correspond to fracture of the tubercle of the navicular and should be put in plaster with the wrist in the neutral position for three weeks. Clinical non-union of the dorsal tubercle is common, but usually symptomless.

Vascular necrosis, or changes similar to Kienbock's disease, are unknown in this bone.

Fractures of the Lunate (Semilunar)

This bone is the least commonly fractured bone of the proximal carpal row, and its lesions are equally divided between fractures of the posterior pole, often confused with fractures of the dorsal tubercle of the triquetrum and those fractures of the body. Fractures of the posterior pole of the bone may occur alone, but usually indicate that there has been marked displacement of the lunate. It may or may not have restored itself to its normal position, so that the fracture may be seen in association with unidirectional volar dislocations of the lunate (fig. 409).

Posterior pole (fig. 402). This is a ligament traction fracture and treated in a similar manner to the fractures of the tubercles of the other two proximal carpal bones.

Compression fractures of the body. These may show displacement and narrowing of the bone which is impossible to reduce and which presages an almost inevitable necrosis of the bone and radio carpal arthritis. The addition of the damage of degeneration to that of trauma may be avoided by early eversion of the bone, which, while not producing a perfect result, is a great improvement on the usual end result.

Fractures of the Triquetrum (Cuneiform)

This is a comparatively common lesion and forms $3\frac{1}{2}$ per cent of all cases of wrist injury. In the past it has been confused with



FIG. 400 Fracture of the posterior tubercle of the triquetrum



FIG. 401 Fracture of the posterior tubercle of the triquetrum associated with a perilunar dislocation of the wrist

fracture of the posterior pole of the lunate, and as a consequence its frequency has been underestimated. Injuries to the bone occur by compression the bone being caught in ulna deviation of the hand,



FIG. 402 Fracture of the posterior tubercle of the triquetrum and of the posterior pole of the lunate

between the other carpal bones and the radius and ulna or by ligament traction injuries. The attachments of the dorsal carpal ligaments to the dorsal tubercle, or of the ulnar collateral ligament

is put up in plaster is for a Colles's fracture for four to five weeks.

The difficulty of dislocation associated with anterior and posterior marginal fractures of the radius has been discussed in the chapter on the radius.

Dislocation of the wrist is most commonly associated with



FIG. 400. Posterior dislocation of the carpus without fracture.

fracture of the navicular and dislocation of the lunate. The lunate may remain attached to the lower end of the radius by its volar and dorsal ligaments. The line of separation may cross the body of the navicular which is fractured, the small medial fragment of the navicular then remaining in position with the lunate. The wrist is thus dorsally dislocated leaving the lunate and fragment of the navicular in contact with the radius.



FIG. 401. Posterior dislocation of the carpus the lunate remaining attached to the radius a condition identical with that shown in Fig. 399.

DIAGNOSIS. The symptoms resemble those of a severe Colles's fracture. The irregularity of the wrist lies distal to the

styloid processes, and palmar flexion is grossly limited. There may be inability to extend the fingers, from pressure on the extensor tendons, or to flex the fingers from the pressure of the dislocated lunate. Both this and median nerve pressure symptoms are much greater in cases in which the lunate alone is dislocated forwards than in the more common case in which the lunate is dislocated with the radius, i.e. the wrist is dislocated dorsally over the lunate.

Most cases of fracture of the lunate resemble fractures of the navicular in that the fracture occurs within the cartilaginous envelope of the bone and consequently shows little displacement. It may thus be recognised in films taken three weeks later after an



FIG 403 Sclerosis of the lunate following injury indistinguishable from Kienbock's disease

apparently normal first radiograph. More commonly the condition is overlooked till avascular necrosis of the bone is apparent. This condition is indistinguishable from Kienbock's disease, which probably is the same thing (Fig 403). At operation a living but broken cartilaginous envelope is found surrounding a dense whitish core of separated cancellous bone. This lies loose like a pea in a pod, and this detachment is in all probability the reason why a fresh vascular supply fails to develop. In some cases it will be seen that the necrosis only involves part of the bone. At operation these cases will show an intact cartilaginous sheath to the living portion. Excision of the bone produces only moderately satisfactory results as the arthritis in the radiocarpal joint tends to spread.

Dislocations of the Radio-carpal Joint



FIG 404 Dislocation at the radio-carpal joint. The continuous line indicates the pure dislocation, the dotted line the more commonly associated fractures.

These may occur

- 1 Alone (Fig 404)
- 2 Associated with fractures or dislocations of the carpal bones
- 3 Associated with fractures of the lower end of the radius and ulna

Occurring alone, the lesion is very rare. It is readily reduced by traction combined with antero-posterior pressure, and the

is put up in plaster as for a Colles's fracture for four to five weeks.

The difficulty of dislocation associated with anterior and posterior marginal fractures of the radius has been discussed in the chapter on the radius.

Dislocation of the wrist is most commonly associated with



FIG. 99. Anterior dislocation of the carpus without fracture.

fracture of the navicular and dislocation of the lunate. The lunate may remain attached to the lower end of the radius by its volar and dorsal ligaments. The line of separation may cross the body of the navicular which is fractured. The small medial fragment of the navicular then remaining in position with the lunate. The wrist is thus dorsally dislocated, leaving the lunate and fragment of the navicular in contact with the radius.



FIG. 100. Posterior dislocation of the carpus, the lunate remaining attached to the radius, a condition identical with that shown in Fig. 99.

Diagnosis. The symptoms resemble those of a severe Colles's fracture. The irregularity of the wrist lies distal to the styloid processes, and palmar flexion is grossly limited. There may be inability to extend the fingers from pressure on the extensor tendons, or to flex the fingers from the pressure of the dislocated lunate. Both this and median nerve pressure symptoms are much greater in cases in which the lunate alone is dislocated forwards than in the more common case in which the lunate is dislocated with the radius, i.e., the wrist is dislocated dorsally over the lunate.

Most cases of fracture of the lunate resemble fractures of the navicular in that the fracture occurs within the cartilaginous envelope of the bone and consequently shows little displacement. It may thus be recognised in films taken three weeks later after an



FIG 403 Sclerosis of the lunate following injury, indistinguishable from Kienbock's disease

apparently normal first radiograph. More commonly the condition is overlooked till vascular necrosis of the bone is apparent. This condition is indistinguishable from Kienbock's disease, which probably is the same thing (Fig 403). At operation, a living but broken cartilaginous envelope is found surrounding a dense whitish core of separated cancellous bone. This lies loose like a pea in a pod, and this detachment is in all probability the reason why a fresh vascular supply fails to develop. In some cases it will be seen that the necrosis only involves part of the bone. At operation these cases will show an intact cartilaginous sheath to the living portion. Excision of the bone produces only moderately satisfactory results as the arthritis in the radio-carpal joint tends to spread.

Dislocations of the Radio-carpal Joint



FIG 404 Dislocation at the radio-carpal joint. The continuous line indicates the pure dislocation, the dotted line the more commonly associated fractures.

These may occur

- 1 Alone (Fig 404)
- 2 Associated with fractures or dislocations of the carpal bones
- 3 Associated with fractures of the lower end of the radius and ulna

Occurring alone, the lesion is very rare. It is readily reduced by traction combined with antero-posterior pressure, and the wrist

moment of restoration. The lunate is left hanging by the attachment of the anterior ligament alone and may be turned in almost any direction as it lies in the carpal canal.

SYMPTOMS. Those of a severe sprain of the wrist accompanied




FIG. 410. Anterior dislocation of the lunate. Note that the posterior ligament of the lunate is torn and the lunate hinges forward on the intact volar ligament through which its blood supply is maintained.

by local features due to the displacement of the lunate. Thus a depression may be felt where the lunate should be, on palpation of the dorsum of the wrist. Anteriorly there is a bulge which may be masked by swelling. Pressure on the median nerve with pain and paresthesia, and inability to flex the fingers from pressure on tendons in the carpal tunnel may be present. Recession of the knuckle of the middle finger is occasionally seen.



FIG. 411. Anterior dislocation of the lunate with less marked displacement than that in Fig. 410.

TREATMENT. Reduction varies very greatly in its ease of accomplishment. It is best attempted under skeletal traction with a wire through the metacarpals, just below their heads and a wire through the olecranon for counter traction. (If this is not available traction as for a Colles's fracture may be used.) X-rays taken during the manipulation will show the increase in the space available for reduction under this method. The return of the bone to its normal position may be accomplished by the pressure of the stretched

Reduction in this latter case is relatively easy. Strong traction made by a relay of assistants, combined with manipulation, usually results in the wrist being shipped forwards easily. Traction will




FIG 407 Dislocation of the lunate combined with posterior dislocation of the wrist. The continuous line indicates the pure dislocation and the dotted line the alternate paths, above the navicular or through a fracture at the waist of the bone. In the lateral view, note that the posterior ligament of the lunate attaching it to the radius is intact.



FIG 408 Anteroposterior view of the same case showing the slight difference from the normal radiographic appearance of the wrist shown in this view.

obviously be required for a longer time under a local anaesthetic than under a general. A plaster is applied as for a fractured navicular, and similar after treatment is instituted. If the navicular is not fractured the result is satisfactory in four to six weeks, but if the bone is broken the period of immobilisation is determined by

the rate of union of that bone. The onset of degenerative changes in the lunate is denied by Bohler, and this is probably true, the onset of Kienbock's disease being due to separation of the cartilaginous envelope.

Dislocations of the lunate. This may occur alone, but it is more commonly due to a spontaneous rectification of a



FIG 409 Anterior dislocation of the lunate with marked forward rotation.

posterior dislocation of the wrist described above. For the lunate to turn forwards it is, however, necessary that the posterior ligament be torn, and this may be done at the time of the dislocation or in the

moment of restoration. The lunate is left hanging by the attachment of the anterior ligament alone and may be turned in almost any direction as it lies in the carpal canal.

SYMPTOMS. Those of a severe sprain of the wrist accompanied




FIG. 410. Anterior dislocation of the lunate. Note that the posterior ligament of the lunate is torn, and the lunate bulges forward on the intact volar ligament, through which its blood supply is maintained.

by local features due to the displacement of the lunate. Thus a depression may be felt where the lunate should lie, on palpation of the dorsum of the wrist. Anteriorly there is a bulge which may be masked by swelling. Pressure on the median nerve with pain and paresthesia, and inability to flex the fingers from pressure on tendons in the carpal tunnel may be present. Recession of the knuckle of the middle finger is occasionally seen.



FIG. 411. Anterior dislocation of the lunate, with less marked displacement than that in Fig. 409.

TREATMENT. Reduction varies very greatly in its ease of accomplishment. It is best attempted under skeletal traction with a wire through the metacarpals, just below their heads, and a wire through the olecranon for counter traction. (If this is not available traction as for a Colles's fracture may be used.) X-rays taken during the manipulation will show the increase in the space available for reduction under this method. The return of the bone to its normal position may be accomplished by the pressure of the stretched




FIG 412 Dislocation of the lunate under skeletal traction showing the wide space it is possible to obtain for reduction of the bone



FIG 413 The final result in a wrist which was seen too late after the dislocation for operative reduction to succeed and in which the lunate was removed. Functionally the wrist though limited in range of movement is strong and painless

tendons, but has usually to be aided by pressure of the fingers. The type of rotation has much to do with the difficulty of reduction, and the ease of reduction cannot be forecast. If manipulative reduction fails, open reduction must be proceeded with through an incision on the ulnar side of the wrist between the ulnar and the tendon of the flexor carpi ulnaris. This is best done while the limb is still under skeletal traction.

After reduction the wrist is immobilised in the neutral position for three to four weeks. The possibility of late degenerative changes in the lunate appear to be increased if the bone is fractured at the same time, but they are remote in correctly treated cases. The rare case in which the bone cannot be replaced even under open operation, demands excision of the bone, but with modern skeletal traction reduction can be obtained in all recent cases.

Complicated Injuries to the carpus. These are frequently due to crushing injuries and are consequently often compound. They can only be treated in accordance with the general principles outlined and the wrist immobilised in plaster. Extension splints may be necessary to individual fingers. To

reduce swelling the abduction splint or Zeno's position may be useful, and all severe cases should be put to bed for the first few



FIG. 411. Complicated carpal injury. Fracture of the distal radius accompanied by anterior dislocation of the multangular minor and dislocation of the second carpo metacarpal joint. Ant. to posterior view of the case in Fig. 304.



FIG. 415. Dislocation at the intercarpal joint.



FIG. 416. Dislocation at the carpo metacarpal joint.

days, to avoid oedema of the dependant hand, and to facilitate complete rest.

Dislocation at the intercarpal and carpo metacarpal joints is extremely rare. The path of separation and possible associated fractures is shown in Figures 415, 416

REFERENCES

Navicular

- OBLETZ and HALBSTEIN "Non union of Fractures of the Carpal Navicular," *J Bone and Joint Surg*, 1938, 20, 424
 BOHLER L "The Treatment of Fractures" Eng Trans Bristol, 1936, p 236
 MURRAY G "Bone Graft for Non union of the Carpal Scaphoid," *Brit J Surg*, 1934, 22, 63
 SOTO, HALL and HALSEMAN 'Treatment of Fractures of the Carpal Scaphoid,' *J Bone and Joint Surg*, 1934, 16, 822

Triquetrum

- BONVIN J G, and GREENING W P "Fractures of the Triquetrum," *Brit J Surg*, 1944 31, 278

Lunate

- ADAMS "Displacement of the Carpal Semilunar Bone," *J Bone and Joint Surg* 1925, 7, 665 (Review of 12 cases with further references)
 FARR C L Dislocation of the Carpal Semilunar, 'Ann Surg', 1926, 54, 112
 WATSON JONES 'Carpal Semilunar Dislocations with Nerve Lesions,' *Proc Roy Soc Med* 1929, 22 1071
 MONT, WILKIE and HARDING 'Isolated Fractures of the Carpal Semilunar, and Kienbock's Disease,' *Brit J Surg*, 1931 19, 577

Hamate

- MILCH 'Fractures of the Hamate' *J Bone and Joint Surg*, 1934 16, 495
 GEIST "Dislocation of the Hamate." *J Bone and Joint Surg*, 1939, 21, 215

General

- SCHNEK "Die Verletzungen der Hand wurzel," *Ergebn d Chir u Orthop*, 1930 23, 1 (The fullest German review of the subject with copious references)
 SHORBE H S Carpo metacarpal Dislocations' *J Bone and Joint Surg*, 1938 20, 454 (One case and literature)

CHAPTER XXV

FRACTURES OF THE METACARPALS AND PHALANXES

Surgical anatomy The metacarpals and phalanges are small "long" bones, and so are liable to the same varieties of fracture. Of the metacarpals only the first has a freely movable joint at both ends, and so is peculiarly liable to fracture-dislocations. The hinge-shaped interphalangeal articulations with their double curve facilitate chip fractures of the base due to ligament strain.

Ossification Centre for shaft appears in ninth week. Epiphyses for the heads appear at two years and unite at fifteen to twenty years. The first metacarpal is an exception, its epiphyses being proximal and appearing at three years.

Function The goal of all treatment is function, and as a secondary condition stability. In the hand in particular the functional use of the fingers must be kept in mind. The multiple small joints lend themselves particularly to stiffness developing from unresolved blood and tissue exudates. Two points must be continually borne in mind in the treatment of the hand. First the function of the hand, if not upset seriously by the fracture, should not be disturbed by splinting. In other words splinting of metacarpal and phalangeal injuries should be avoided if possible and active use of the fingers encouraged. It is surprising how often a fracture is stable, or after reduction remains sufficiently stable to dispense with splinting. Secondly, if the hand must be splinted, this must be the minimum possible and allow free use of the uninvolved fingers. Oedema of the fingers should be avoided partly because of the probable increase in periarticular adhesions when it is present, but also because of the restriction of movement.



FIG. 417. Fractures sites in the first metacarpal.
A Oblique fracture of the shaft
B Transverse fracture at the base
C Stave fracture of the base



FIG. 418. Greenstick fracture of the base of the first metacarpal.

Operative Fixation The apparently absurd description of the phalanges as short "long bones" has been used for years, yet it is only recently that the same methods of treatment have been applied to both fingers and long bones. It is particularly in the fingers and thumb where comparatively small adhesions cause considerable disability that the advantages of operative fixation and early movements are likely to be of benefit, and striking improvement in results can be achieved by open operation in selected cases. Broadly speaking, injuries to the hands fall into two categories, whether bone is involved or not, those in which there is localised soft tissue trauma, best exemplified by a knife cut, and those in which there is crushing of soft tissue over a wide area, *e.g.*, in a compound fracture of a phalanx from a hammer blow. The result of the injury will depend on the degree of soft tissue damage, and the presence or absence of infection. By adequate surgery, skin grafting and chemotherapy the latter disaster should be avoided. No surgery can repair the damage of severe crushing, in which for example tendon and tendon sheath may be pulped together, but it can do much to minimise after effects. This is not the place to enlarge on the benefits of tendon suture with stainless steel wire, by the Bunnell pull out technique, but the same material is a very useful agent for fixing small fractures, where screws are unavailable or unsuitable. Fractures in which metallic fixation is often desirable are —

1 Fractures involving the interphalangeal joints, in which the fracture contributes to the instability of the joint, *e.g.*, the fracture of the posterior margin of the terminal phalanx with subluxation (mallet finger) (Fig 446)

2 Comminuted phalangeal fractures (Fig 444a), particularly involving a joint

3 Unstable oblique or spiral fractures of the phalanges

4 Markedly unstable or displaced fractures of the metacarpals

The opportunity for early fixation by the primary excision of compound wounds should not be neglected, as it is particularly in this type of case that gross displacement allows the inclusion of soft tissue in the fracture line, and is accompanied by soft tissue damage.

Post-operative care is extremely important, and movements of the affected finger should be encouraged as soon as possible when the tendons are intact. The limitation of movement of uninjured fingers should be minimal and these should be freely exercised. It is in the treatment of injuries to the hand that occupational therapy plays its most important role, while later on the sheltered workshop can be of great assistance in encouraging the patient to make the most of stiffened fingers.

Fractures of the Metacarpals

The first metacarpal Types of fracture 1 Transverse above the base A Impacted B Unimpacted

2 Spiral or oblique of the shaft

3 Oblique, involving the base (True Bennett's fracture)

4 Comminuted fractures

In the first and second groups the proximal joint is not involved, and reduction and retention comparatively easy

SYMPTOMS In all cases these are similar, consisting of gross swelling of the thumb, bruising and pain. Crepitus can usually be



FIG. 419 Fracture of the shaft of the first metacarpal



FIG. 420 Same case showing the satisfactory result of treatment with a finger wire lying on the extensor aspect of the thumb

easily detected, and false movement, particularly in Bennett's fractures, is obvious

TRANSVERSE FRACTURES above the base of the metacarpal are commonly impacted. If this is so and there is little displacement the fracture is better left and the patient's attention concentrated upon active use. If there is marked displacement, or the fracture is loose, it must be held in position after reduction on a finger wire splint of a similar type to that used for Bennett's fracture. The wire

Operative Fixation The apparently absurd description of the phalanges as short "long bones" has been used for years, yet it is only recently that the same methods of treatment have been applied to both fingers and long bones. It is particularly in the fingers and thumb where comparatively small adhesions cause considerable disability that the advantages of operative fixation and early movements are likely to be of benefit, and striking improvement in results can be achieved by open operation in selected cases. Broadly speaking, injuries to the hands fall into two categories, whether bone is involved or not, those in which there is localised soft tissue trauma, best exemplified by a knife cut, and those in which there is crushing of soft tissue over a wide area, *e.g.*, in a compound fracture of a phalanx from a hammer blow. The result of the injury will depend on the degree of soft tissue damage, and the presence or absence of infection. By adequate surgery, skin grafting and chemotherapy the latter disaster should be avoided. No surgery can repair the damage of severe crushing, in which for example tendon and tendon sheath may be pulped together, but it can do much to minimise after effects. This is not the place to enlarge on the benefits of tendon suture with stainless steel wire, by the Bunnell pull out technique, but the same material is a very useful agent for fixing small fractures, where screws are unavailable or unsuitable. Fractures in which metallic fixation is often desirable are —

- 1 Fractures involving the interphalangeal joints, in which the fracture contributes to the instability of the joint, *e.g.*, the fracture of the posterior margin of the terminal phalanx with subluxation (mallet finger) (Fig 446)

- 2 Comminuted phalangeal fractures (Fig 444a), particularly involving a joint

- 3 Unstable oblique or spiral fractures of the phalanges

- 4 Markedly unstable or displaced fractures of the metacarpals

The opportunity for early fixation by the primary excision of compound wounds should not be neglected, as it is particularly in this type of case that gross displacement allows the inclusion of soft tissue in the fracture line, and is accompanied by soft tissue damage.

Post operative care is extremely important, and movements of the affected finger should be encouraged as soon as possible when the tendons are intact. The limitation of movement of uninjured fingers should be minimal and these should be freely exercised. It is in the treatment of injuries to the hand that occupational therapy plays its most important role, while later on the sheltered workshop can be of great assistance in encouraging the patient to make the most of stiffened fingers.

Fractures of the Metacarpals

The first metacarpal. Types of fracture: 1. Transverse above the base. A. Impacted. B. Unimpacted.

2. Spiral or oblique of the shaft.

3. Oblique involving the base (True Bennett's fracture).

4. Comminuted fractures.

In the first and second groups the proximal joint is not involved, and reduction and retention comparatively easy.

SYMPTOMS. In all cases these are similar, consisting of gross swelling of the thumb, bruising and pain. Crepitus can usually be



FIG. 419. Fracture of the shaft of the first metacarpal.



FIG. 420. Same case showing the satisfactory result of treatment with a finger wire lying on the extensor aspect of the thumb.

easily detected, and false movement, particularly in Bennett's fractures, is obvious.

TRANSVERSE FRACTURES above the base of the metacarpal are commonly impacted. If this is so and there is little displacement the fracture is better left and the patient's attention concentrated upon active use. If there is marked displacement, or the fracture is loose, it must be held in position after reduction on a finger wire splint of a similar type to that used for Bennett's fracture. The wire

is run along the dorsum of the thumb, attached to the thumb by strapping, and then thumb and wire bent to the desired position. Immobilisation is maintained for two to three weeks, and removed as soon as active movements of the thumb can be carried out.

SPIRAL AND OBLIQUE FRACTURES of the shaft require some extension for their reduction. This is accomplished as in fractures of the other metacarpals by a wire finger splint incorporated in a forearm plaster. According to whether the angulation is volar or dorsal (Figs 420, 428) the wire is placed on the flexor or extensor aspect of the thumb, which is attached to it by strapping. The position of the fragments is then controlled by bending the wire with the finger attached. Union is firm in three to four weeks.

BENNETT'S STAVE FRACTURE In this case the fracture runs vertically from the joint surface to the medial border of the bone. It is due to violence applied in the line of the metacarpal, commonly from blows with the clenched fist, the base of the metacarpal being sheared off against the multangulum major (trapezium). The metacarpal in consequence slides up past the lateral aspect of the joint if the capsule is torn, and retention is difficult, particularly as the line of fracture is in the direction of pull of the muscles.




FIG 421 Bennett's stave fracture of the thumb showing the combination of fracture with dislocation and the direction of the forces necessary to maintain reduction.

Clinically two types of stave fracture are met with.

1 In which there is a small triangular chip fractured from the medial edge of the metacarpal, but there is no dislocation of the joint (see Fig 422).

2 In which the fracture involves more of the base of the metacarpal, and dislocation consequently occurs (see Fig 423).

In the first case there is no difficulty with retention, and reduction is equally easily accomplished by putting the thumb into full abduction.

In the second group of cases reduction is usually easy by traction and abduction of the thumb, for which a local anaesthetic is suitable though often it can be done without. Retention is not easy and demands two factors, first, lateral pressure on the base of the metacarpal, and secondly, extension of the thumb. In certain cases lateral pressure alone, combined with full abduction

of the thumb suffers to mount on the fracture, which is accomplished as described below by strapping. Where this fails a more elaborate



FIG. 4.2 Chip fracture of the base of the first metacarpal without displacement



FIG. 4.3 Chip fracture of the base of the first metacarpal with displacement of the carpometacarpal joint from its stable position



FIG. 4.24 Method of strapping the thumb for injury at the metacarpal base. Site of application of the rubber pad



FIG. 4.25 Circular strapping, compressing the pad against the base of the thumb of non-stretch strapping



FIG. 4.26 Figure of eight strapping, abducting the thumb over the fulcrum provided by the compressed pad of single stretch elastoplast

fixation is necessary, though in our experience the necessity for extension with a wire in the pulp of the finger never occurs

attached a wire finger splint passing along the outer border of the thumb. This wire is covered by a layer of strapping, and at the base of the wire which corresponds to the base of the metacarpal a small square of rubber sponge 1 inch square and $\frac{1}{2}$ inch thick is inserted between the wire and the metacarpal. The thumb is then abducted over this and attached to the splint by a few turns of strapping. Holding thumb and splint, both are bent so that the thumb is fully abducted over the small rubber pad. By this manoeuvre both extension and lateral pressure on the thumb are obtained, and this usually suffices to retain the most difficult fractures. The strapping and rebending of the wire are repeated as often as necessary. Fixation must last three to four weeks, and at the end of this time the strapping method of treatment is applied for one to two weeks. This allows some movement, which is encouraged, and after the removal of the strapping movements are usually rapidly restored in all but elderly people, in whom there is a tendency to arthritis. Care must be taken that the pressure of the sponge rubber does not produce a pressure sore.

Fractures of the other Metacarpals

May be

- | | | | |
|--------------------------|-----|---|-----------------------------------|
| 1 Fractures of the shaft | } { | Due to either direct or indirect violence | } Transverse
Oblique or spiral |
| 2 Fractures of the neck | | | |
| 3 Fractures of the base | | | |

The fifth metacarpal is most commonly involved in direct violence. Punch fractures most commonly affect the third metacarpal with the prominent knuckle while multiple fractures are usually due to crushing injuries and are frequently compound.

DIAGNOSIS In addition to the usual features recession of one or other knuckle may be seen if there is shortening. In fractures without displacement pressure on the finger of the affected metacarpal or tapping the knuckle will produce pain. In oblique fractures telescoping may be noticed. Difficulties in diagnosis may arise in fine transverse fractures with no displacement which require careful scrutiny of the X ray films to detect them. When this is being done care must be taken not to confuse the line of a nutrient artery with a fracture as they are frequently very clear and suggestive.

Treatment This depends on the degree of displacement and the freedom of mobility of the fingers. Restriction of movement will usually be found to be due to pain and this can be relieved by an injection of local anæsthetic. Minor degrees of shortening of the finger can be neglected, recession of the knuckle not being very

important. In many cases the injection of novocaine suffices and the fixation of the finger should be avoided if possible. In other cases with pain and much bruising and possibly fracture of other metacarpals it is best to immobilise the metacarpals in a plaster extending on the dorsum to the heads and well up to the distal palmar crease on the palm. This immobilisation of wrist and metacarpus results in a return in power to the affected fingers which by gripping firmly over the end of the plaster exert a little traction on themselves. The active use of the fingers in such a plaster (Fig. 388) results in a rapid subsidence of the usual puffy swelling over the



FIG. 431. An oblique fracture of the fifth metacarpal.



FIG. 432. A transverse fracture of the fourth and fifth metacarpal shafts.

dorsum of the hand and the plaster can usually be removed in ten days to a fortnight.

In cases with displacement, or compound injuries, it is necessary to immobilise the finger after reduction. In open cases this is usually easy, but reduction may not be so easy to accomplish in closed cases by mere manipulation. The use of leverage by means of a thin Stemmann's pin inserted through the skin of the dorsum of the hand is not to be forgotten.

METHOD OF FIXATION BY FINGER WIRES. A volar plaster slab is applied to the forearm, extending from the metacarpal heads to just below the elbow and so cut out in the palm that it affects

attached a wire finger splint passing along the outer border of the thumb. This wire is covered by a layer of strapping, and at the base of the wire which corresponds to the base of the metacarpal a small square of rubber sponge 1 inch square and $\frac{1}{2}$ inch thick is inserted between the wire and the metacarpal. The thumb is then abducted over this and attached to the splint by a few turns of strapping. Holding thumb and splint, both are bent so that the thumb is fully abducted over the small rubber pad. By this manoeuvre both extension and lateral pressure on the thumb are obtained, and this usually suffices to retain the most difficult fractures. The strapping and rebending of the wire are repeated as often as necessary. Fixation must last three to four weeks, and at the end of this time the strapping method of treatment is applied for one to two weeks. This allows some movement, which is encouraged, and after the removal of the strapping movements are usually rapidly restored in all but elderly people, in whom there is a tendency to arthritis. Care must be taken that the pressure of the sponge rubber does not produce a pressure sore.

Fractures of the other Metacarpals

May be

- | | | |
|--------------------------|---|-------------------|
| 1 Fractures of the shaft | } { Due to either direct or indirect violence | Transverse |
| | | Oblique or spiral |
| 2 Fractures of the neck | | |
| 3 Fractures of the base | | |

The fifth metacarpal is most commonly involved in direct violence. Punch fractures most commonly affect the third metacarpal with the prominent knuckle, while multiple fractures are usually due to crushing injuries and are frequently compound.

DIAGNOSIS In addition to the usual features recession of one or other knuckle may be seen if there is shortening. In fractures without displacement pressure on the finger of the affected metacarpal or tapping the knuckle will produce pain. In oblique fractures telescoping may be noticed. Difficulties in diagnosis may arise in fine transverse fractures with no displacement which require careful scrutiny of the X ray films to detect them. When this is being done care must be taken not to confuse the line of a nutrient artery with a fracture, as they are frequently very clear and suggestive.

Treatment This depends on the degree of displacement and the freedom of mobility of the fingers. Restriction of movement will usually be found to be due to pain and this can be relieved by an injection of local anæsthetic. Minor degrees of shortening of the finger can be neglected, recession of the knuckle not being very

ing from the elbow to the wrist if a single metacarpal is affected, but over the dorsum of the wrist if two or more are broken. The finger wire is then covered with stripping to make a flat surface along which the finger is laid. The pressure tends to be a maximum under the head of the metacarpal, so a small square of felt is placed here between the wire and the bone. The finger is then strapped to the wire splint over this with narrow strapping. Extension is produced by bending the finger and splint together, the finger thus being compelled to follow a curve of larger diameter, and so pulling on the metacarpal head. About every four days the stripping must be renewed and the splint rebent. X ray control of the fracture is simple. Immobilisation is maintained for three weeks, the other fingers being carefully exercised. After removal of the splint return of function is usually rapid. It is important that the finger should be held in flexion as the lateral ligaments of the interphalangeal joints are then held stretched and unable to shorten, a potent cause of stiff fingers (Fig 435).

FRACTURES OF THE METACARPAL BASES. There is is a rule no displacement, and to relieve pain all that is necessary is a plaster to the level of the metacarpal heads. This is maintained for a fortnight to three weeks, and early finger movements commenced as in all other cases.

FRACTURES OF THE NECK OF THE METACARPAL. These may give rise to a little difficulty as there is a tendency for the head to bow forwards, especially if the fracture is treated with a tennis ball or bandage clasped in the palm. The prominent head then receives all the pressure in gripping, and in time becomes very painful. For this reason the correction of the deformity is important. It can only be satisfactorily achieved by using the proximal phalanx as a bar to push the flexed head back. Once reduced the cases fall into two classes, those which will remain reduced with no further immobilisation, and those which



FIG 436 Forearm plaster carrying a finger wire for extension of a fracture of the proximal phalanx of the middle finger. Note felt pad under the head of the metacarpal. Wire is shown extending unnecessarily far beyond the end of the finger. Usually it need only be the length of the finger which is strapped to it and both wire and finger flexed together.



FIG 433 The same case under treatment with two wire finger splints incorporated in a light forearm plaster




FIG 434 Retention of a phalangeal fracture with a finger wire incorporated in a forearm plaster. The same principles are employed for metacarpal fractures.

A Plaster B Finger wire C Resultant direction of pull if finger and wire are strongly bent in the direction D




FIG 435 Illustrating the effect of extension and flexion on the lateral ligaments of the interphalangeal joints. If the finger is held flexed the ligament is stretched and so cannot shorten and produce a stiff finger joint.

flexion of the involved fingers only. On this is laid a wire finger splint, which is adjusted to be in line with and extend just beyond the pulp of the involved fingers. This is incorporated in the plaster by passing a few circular turns of plaster over it, these turns extend

ing from the elbow to the wrist if a single metacarpal is affected, but over the dorsum of the wrist if two or more are broken. The finger wire is then covered with strapping to make a flat surface along which the finger is held. The pressure tends to be a maximum under the head of the metacarpal, so a small square of felt is placed here between the wire and the bone. The finger is then strapped to the wire splint over this with narrow strapping. Extension is produced by bending the finger and splint together, the finger thus being compelled to follow a curve of larger diameter, and so pulling on the metacarpal head. About every four days the strapping must be renewed and the splint rebent. X-ray control of the fracture is simple. Immobilisation is maintained for three weeks, the other fingers being carefully exercised. After removal of the splint return of function is usually rapid. It is important that the finger should be held in flexion as the lateral ligaments of the interphalangeal joints are then held stretched and unable to shorten, a potent cause of stiff fingers (Fig. 435).

FRACTURES OF THE METACARPAL BASES. There is as a rule no displacement, and to relieve pain all that is necessary is a plaster to the level of the metacarpal heads. This is maintained for a fortnight to three weeks, and early finger movements commenced as in all other cases.

FRACTURES OF THE NECK OF THE METACARPAL. These may give rise to a little difficulty as there is a tendency for the head to bow forwards, especially if the fracture is treated with a tennis ball or bandage clasped in the palm. The prominent head then receives all the pressure in gripping, and in time becomes very painful. For this reason the correction of the deformity is important. It can only be satisfactorily achieved by using the proximal phalanx as a bar to push the flexed head back. Once reduced the cases fall into two classes, those which will remain reduced with no further immobilisation, and those which



FIG. 435. Forearm plaster carrying a finger wire for extension of a fracture of the proximal phalanx of the middle finger. Note felt pad under the head of the metacarpal. Wire is shown extending unnecessarily far beyond the end of the finger. Usually it need only be the length of the finger, which is strapped to it and both wire and finger flexed together.

require some retention. Retention may be of a temporary nature, consisting of strapping passed over the knuckle from the dorsum of




FIG 437 Reduction and retention of fractures of the neck of the fifth metacarpal. The typical displacement is shown above. Below the method of retention with a dorsal finger wire bent around the finger, and pressing on the head of the proximal phalanx. The finger wire is steadied in a forearm plaster.



FIG 438 Fracture of the necks of the fourth and fifth metacarpals.

the hand and continued over the finger which is flexed into the palm with the distal interphalangeal joint straight, and then over the



FIG 439 Retraction of the fourth knuckle of the left hand after fracture of the metacarpal.

wrist. A circular layer around the palm maintains the flexion at the proximal joint. This method is most satisfactory in the case of the fifth metacarpal, which is the most commonly injured. A

more durable method of fixation is provided by running a finger wire down the back of the finger after incorporating it in plaster, as shown in Fig. 437. It is a more certain method of preventing a recurrence of deformity, but is apt to produce stiffness of the finger and should be removed at the earliest opportunity, about the tenth day.

Fractures of the Phalanges

Surgical Anatomy

Like the metacarpals the proximal and middle phalanges are short "long" bones, and suffer similar fractures. The terminal phalanx, however,



Fig 440 An oblique fracture of the proximal phalanx of the thumb involving the joint




Fig 441 Fracture sites in the phalanges
A At the neck
B Anterior marginal fracture of the base
C Posterior marginal fracture of the base
D Lateral marginal fractures
E Sites of ligament traction fractures



Fig 442 A transverse fracture of the proximal phalanx of the thumb

differs in construction having a splayed out head of cancellous bone. It is the most liable to crushing injuries.

Ossification A secondary centre for the proximal ends of the bones appears at the end of the second year and unites about eighteen to twenty years.

Types of Fracture

Shaft Oblique, transverse and comminuted. Epiphysis rarely separated.

Ends 1. Anterior, posterior, and lateral marginal fractures involving the joint.

2 Ligament traction fractures due to forced abduction or adduction of the finger



FIG 443 A fracture separation of the epiphysis at the base of the proximal phalanx of the fourth finger



FIG 444 A lateral marginal fracture of the base of the proximal phalanx of the thumb

Any of these fractures may be associated with a dislocation of the interphalangeal joint and many may be best treated by fixation with a small screw or stitch of stainless steel wire



FIG 444a AP view of a compound comminuted fracture of the base of the proximal phalanx of the thumb

FIG 444b Lateral view of the same case

FIGs 444c and 444d Corresponding views of same case after open operative reduction and fixation of the fracture with stainless steel wire

Fractures of the shaft These are easily reduced under general or local anesthesia and are best fixed on a finger wire splint similar to that used for fracture of the metacarpals. Being only a skeleton splint it is very adaptable and equally useful in the presence of lacerations, which it is desired to leave open to the air. The finger should be kept flexed to avoid subsequent stiffness. Union occurs in three to four weeks, when the splint is

removed and exercises encouraged (Fig 434)

It must be remembered that quite a large number of phalangeal

fractures are stable, often in spite of being comminuted and not appearing so in the radiograph. Other phalangeal fractures remain stable after reduction, and in all these cases the finger should be merely protected for the first two days by a padded finger splint of the type shown in Fig. 441 and early movements encouraged.




FIG. 443 Mallet finger.
Above due to fracture of the insertion of the extensor expansion (posterior marginal fracture). Below due to rupture or division of the extensor expansion.



FIG. 440 A posterior marginal fracture of the base of the terminal phalanx.



FIG. 447 The position of the finger in a mallet finger plaster.



FIG. 448 The patient maintaining the position as the plaster sets.

Shortening is important to avoid, but is easy to control by the above method. Angulation is similarly easy to control but rotation is apt to be overlooked. If the finger has united with a rotation deformity it may appear quite straight when extended, but on flexion the terminal phalanx or middle phalanx will slew to one or

other side, which may be a very severe disability in a skilled worker

Fractures of the phalangeal ends Abduction and adduction strains may result in a ligament traction fracture, the collateral ligaments of the joint pulling a small portion of bone of the base away with their attachment, or occasionally fracturing the base into the joint. Blows on the flexed finger may result in anterior or posterior marginal fractures, which may be associated with dislocations, the anterior fracture tending to allow posterior dislocation and *vice versa*. In most cases the displacement is small, and all that is needed is adequate rest for three weeks with the finger flexed, which is secured by a wire finger splint set in plaster as outlined. Where there is displacement traction is applied by bending the wire with the finger attached, and this reduces and fixes the fracture. Owing to the involvement of the joint stiffness is liable to be more marked than in fractures not involving it. Crush fractures with considerable joint destruction can be very crippling owing partly to joint damage and partly to fibrosis and adhesions around the tendons, and in many of these cases early complete and accurate operative reduction is necessary (Fig 444a)

Fractures of the terminal phalanx May be

- | | |
|------------------|--|
| 1 Longitudinal | } Due to crushing injuries |
| 2 Transverse | |
| 3 Chip fractures | Anterior Rare, due to hyperflexion |
| | Posterior Due to a blow Mallet finger |
| | Lateral Due to abduction and adduction |

All these fractures may be associated with lacerated and bruised pulps, and are frequently compound. Such fractures are carefully cleaned up under block finger anaesthesia and sutured. If the nail is damaged it is better removed, as it relieves pressure below it, an important cause of pain, and it allows the wound to dry up. Further, in any case with displacement of the nail the fracture is frequently compound into the nail bed and its removal provides opportunity for suture of a potentially infected area. No harm has ever been done by removing a nail carefully—much has been caused by leaving it in place. All such fractures must be immobilised on a finger splint at once, and maintained at rest until healing has commenced.)

In cases in which there is no great damage to soft parts a collodion splint made of several turns of gauze soaked in collodion, or a splint of several turns of strapping may provide sufficient protection and rest. They are renewed till the finger is free from pain.

Mallet finger more commonly occurs from rupture of the extensor tendon than from fracture at its insertion. Three clinical varieties can be distinguished

- 1 Due to rupture of the extensor tendon Best treated in young

people by tendon suture by the Bunnell technique, with the strain relieving suture running through the pulp of the finger, and tied over a button on the end, maintaining hyper extension. Alternatively a mallet finger plaster (fig 448) may be applied for four weeks. Full extension is scarcely ever obtained by this method, but the resultant drop is little disability.

2. Due to fracture of the posterior margin involving the insertion of the extensor tendon. (a) Without subluxation. (b) With volar subluxation of the terminal phalanx. The prognosis in these cases for a good functional result in spite of the fracture into the joint is better than for tendon ruptures provided complete reduction can be obtained. This should be attempted by a mallet finger plaster in the first instance. If the displacement of the subluxation persists, the fragments should be perfectly reduced by open operation through a lateral incision, and the fragment retained in position by a suture of stainless steel wire passed around or through the bone.

Anterior chip fractures of the base require rest in a slightly flexed plaster finger splint. One important point in diagnosis is that there is frequently a small sesamoid in the tendon of the flexor profundus at its insertion and it must not be mistaken for a fracture. It is regular in outline, often rounded, and may be seen in other fingers or the same finger of the opposite hand. When there is an accompanying posterior subluxation this must be carefully reduced employing open operation and suture when necessary.

Lateral marginal fractures of the base can be treated in a plaster finger splint in slight flexion for two to three weeks, after which movement is encouraged. Great care must be taken in these cases to make certain that the commonly associated interphalangeal subluxation is fully reduced.

REFERENCES

Metacarpals

- JAHSS S A "Fractures of the Metacarpals" *J Bone and Joint Surg*, 1938, 20, 178
 RIDER, D L "Fractures of the Metacarpals, Metatarsals and Phalanges" *Am J Surg* 1937, 38, 549
 ROBERTS N "Fractures of the Phalanges of the Hand, and of the Metacarpals" *Proc Roy Soc Med* 1938, 31, 793 (Sound review including statistics)
 MCNEALY and LICHTENSTEIN "Bennett's Fracture and other Fractures of the First Metacarpal" *Surg Gynec and Obstets*, 1933, 56, 197

Phalanges

- SMITH, F L and RIDER, L "A Study of the Healing of 100 Consecutive Phalangeal Fractures" *J Bone and Joint Surg*, 1935, 17, 91
 SMILLIE "Mallet Finger" *Brit J Surg*, 1936 24, 439

CHAPTER XXVI

FRACTURES OF THE PELVIS, SACRUM AND COCCYX

Development The three bones of the os innominatum commence ossification from primary centres appearing in the ilium in the second month, the ischium in the third and the pubis in the fourth month. Ossification continues slowly, and at the tenth year a variable number of centres for the acetabulum appear. These occasionally fuse to form the os acetabuli. At sixteen to eighteen years they fuse with the other centres, completely ossifying the acetabulum. In the cartilaginous border of the bone a variable number of secondary centres appear at puberty as follows:

- 1 For the anterior superior iliac spine and anterior part of the iliac crest
- 2 For the posterior superior iliac spine and the posterior half of the iliac crest
- 3 For the anterior inferior iliac spine
- 4 For the ischial spine
- 5 For the surface of the ischial tuberosity
- 6 For the angle of the symphysis
- 7 An inconstant centre for the pubic spine

These fuse with the main centres about twenty-one years.

Surgical anatomy The bone consists of two parts, meeting roughly at right angles: the ilium above forming the wing of the false pelvis and the ischium and pubis below forming the lateral wall of the true pelvis. The transition from one plane to another is sudden externally, but gradual internally, where the angle is strengthened by the iliopectineal bar. The pelvis is inclined so that the pelvic brim forms an angle of 60° with the horizontal. The sacrum is thus lying above the pubis and suspended between the two halves of the pelvis by the sacro iliac ligaments. The weight transmitted through the femoral heads lies outside the line of the sacro iliac joints and so tends to open the two halves of the pelvis and to put traction on the pubic symphysis. In sitting down the weight is transmitted by the ischial tuberosities, which lie medial to the line of the sacro iliac joint and so the tendency is to compress the pubis. The curves of the pelvis adapt it as an elastic base for transmitting the weight of the spine to the legs or the ischial tuberosities while the sacrum is slung between the two halves of the pelvis as the centre piece of a cantilever.

Of the soft tissues in contact with the bony pelvis, the rectum, urethra, and, in the female, the vagina are the most important as all may be damaged indirectly by the entry of bony spicules or more commonly directly by the injury with consequent risk of sepsis. In the female the urethra is well protected, but in the male on account of the close relationship of the urethra to the pubic arch, and its comparative laxity it is liable to injury particularly in falls astride. The rectum is in relationship to the anterior surface of the last two and a half pieces of the sacrum and the coccyx. It is rarely injured except by perforating injuries and gunshot wounds. The iliac vessels and the sciatic nerve though closely related to the bone are rarely injured though the sciatic nerve may be involved in lesions in the sacro iliac region.

The mechanical construction of the pelvis presents a series of weak spots through which fracture is most likely to occur either alone or more commonly

in combination with a second fracture through another weak spot. The weak spots are —

- | | | |
|-------------|---|------------------------------------|
| Anteriorly | The pubic symphysis | |
| | The ischio pubic ram | |
| Centrally | The acetabular floor | |
| Posteriorly | The sacrotuber joint | } or a mixed lesion involving both |
| | The ala of the ilium | |
| | The lateral mass of the sacrum where weakened by the foramina | |

FRACTURES OF THE PELVIS

These may be classified as follows

- 1 Single FRACTURES OF THE PELVIC RING, most commonly
 - 1 Separation at the pubic symphysis with or without fracture
 - 2 Separation at the sacrotuber joint with or without fracture
 - 3 Fractures of the ischio pubic ram
- 2 Double FRACTURES OF THE PELVIC RING
 - 1 The double vertical fracture of Malgaigne (Fig 411)
 - 2 Severe multiple fractures of the pelvis
- 3 FRACTURES OF THE ACETABULUM
 - 1 Of the rim Associated with dislocations
 - 2 Of the floor Associated with central dislocation
- 4 FRACTURES OF INDIVIDUAL BONES
 - 1 The ala of the ilium
 - 2 Fractures of a single ramus
 - 3 Fractures of the anterior superior iliac spine
 - 4 Fractures of the tuberosity of the ischium
 - 5 Fractures of the sacrum and coccyx

Fractures of the pelvis become serious from the shock associated with an injury severe enough to fracture so strong a bone, and the damage to intrapelvic organs which may occur. Apart from these complications there is little to be feared. The displacement is, as a rule, small, owing to the fixation of the bone by muscular and ligamentous attachments, and the chief concern is to make the patient comfortable while union is occurring.

MODE OF INJURY The various fractures of individual bones are produced by direct injury. Acetabular fractures may be produced by falls on the lateral aspect of the great trochanter, or falls in which one leg in the extended position receives the full weight of the body. If the head is not driven centrally one half of the pelvis may be dislocated, but more commonly the double vertical fracture of Malgaigne (Fig 450) results. This particular lesion may be produced by lateral crushing. The arch is first broken anteriorly, and the continuation of the force breaks the arch posteriorly, or

separates the sacro iliac joint. Perhaps more common than separation is a subluxation of the sacro iliac joint, and associated with this are small fractures of the anterior surface of the ilium at the joint margin. These cannot be seen on X-ray films, but are consistently found at post mortems on patients with severe pelvic injuries. Crushes in which the force is applied in an antero-posterior direction tend to fracture the rami on both sides and depress the pubic symphysis (Fig 453).

The most common cause of pelvic injuries is, however, the leverage applied to one half of the pelvis through the leg. Hyperabduction, or more commonly hyperextension, tends to twist off the affected side of the pelvis. The line of separation has many paths to choose from. Anteriorly it may pass through the pubic symphysis, the weak area in the two rami, or through the area just anterior to the acetabulum. Posteriorly the choice is even more varied. Separation may occur at the sacroiliac joint, or partly through this joint and partly through the ala of the ilium, the ilium may be fractured, or the attachments of the os innominatum to the sacrum, may be strong enough to separate the lateral mass of the sacrum from the body of the bone.

The degree of displacement present will vary with the type of fracture, and whether or not the force has continued to act after the fracture has occurred.



FIG 449 Testing for pain in doubtful fracture of the pelvis by pressure on both anterior superior iliac spines

Examination and diagnosis of pelvic fractures. In severe pelvic fractures the satisfactory examination of the case may be prevented by shock or associated injuries. If the patient is conscious he will complain of local pain, and of pain on moving the leg on the affected side. Where the ring is completely broken he may complain of a sensation of falling apart. Haematomas should be searched for, particularly the tell tale one in the perineum which indicates a probable rupture of the urethra. Palpation of the pubic and ischial rami is easy

and should not be neglected. Irregularity in the line of the crest of the ilium may be appreciated with the fingers without turning the patient. In cases where there is suspicion of fracture the

pelvis may be sprung by pressing firmly down and out on the anterior superior iliac spines (Fig 449). The patient will complain of pain over the fracture site if the pelvic ring is broken. Separation or an alteration in the levels at the pubic symphysis may be felt. Finally, the examination is not complete without a search for damage to the urethra or bladder, especially in the presence of any of the four classical signs, hemorrhage from the urethra, retention of urine, perineal bruising, and extravasation of urine, and in some cases a rectal examination. A neurologic examination should be made in all cases in which the sacrum is fractured.

Single Fractures of the Pelvic Ring

It is to be remembered that though a single fracture may be seen on the film, there is commonly an associated subluxation with minor fractures around the sacro iliac joint, which cannot be seen. The most common single fracture is through the two weak points on the pelvic ring, where the obturator notch grooves the upper ramus of the pubis, and where the lower rami of ischium and pubis meet. The displacement is variable and usually small. The ends of the bones are finely spiculated and interlock. As a rule there are no complications and the treatment consists of rest in bed for four to eight weeks with a pelvic sling in the earlier weeks to facilitate moving the patient. During this period the patient is given exercises to all four limbs, breathing exercises, and is encouraged to sit up and exercise the spine. If such exercises are carried out thoroughly the patient will be walking well a few days after he gets out of bed.

Less commonly the fracture occurs just lateral to the pubic symphysis, leaving the circle of bone around the obturator foramen complete, or the pubic symphysis may be dislocated with a subluxation of one or other sacro iliac joint associated. The displacement is as a rule small, and rest in bed, as previously described, is the correct treatment.

Gross sacro iliac separation is very rare unless associated with fractures elsewhere. The minor degrees of sacro iliac separation associated with marginal chip fractures, which may be overlooked in the X ray, may be the cause of persistent pain if the patient is not adequately rested for six to eight weeks after the accident.

Double Fractures of the Pelvic Ring

The classical fracture of Malgaigne is a very severe injury which brings a very seriously shocked patient into hospital. In this lesion the fracture is through the weak areas of the rami anteriorly, and through the sacro iliac joint or just immediately lateral to it posteriorly on the same side. The displacing force, together with



FIG 450 Fracture of the left ala of the ilium involving the sacro iliac joint together with dislocation of the pubic symphysis and upward displacement of the left half of the pelvis (Compare with Fig 451)




FIG 451 Same case under treatment showing the reduction of the displacement by traction first skeletal and then skin traction




FIG. 452 The double vertical fracture of Malgaigne showing how the displacement is produced by the contraction of the psoas femoral and vertebro femoral muscles



FIG. 453 Fracture of both ischio pubic rami together with an impacted fracture to the left of the pubic symphysis and a crush fracture of the right side of the sacrum involving the sacro iliac joint

the pull of the pelvi-femoral and vertebro femoral muscles results in an upward displacement of the whole half of the pelvis, often associated with grave internal injuries. In some cases the fracture passes through the sacro iliac region of the opposite side, in which case there is no displacement. Injury without displacement is due to lateral crushing injuries, while that with displacement is due to falls on the extended leg or on one half of the buttocks, and there



FIG. 454. Fracture of the pelvis associated with fracture of the sacrum. The pelvis and ischium are fractured anteriorly. The lateral mass of the sacrum is fractured and compressed with loss of the sacral pattern and the whole innominate bone is displaced upwards. There is a fracture of the transverse process of the fifth lumbar vertebra. Note the defect in the lateral margin of the sacrum below the pelvic brim. Features of root damage to S. 1 and 2 accompanied this lesion.

may, in addition to the signs outlined above, be shortening of one leg.

In the rarer type of double fracture due to antero posterior compression the pubic rami of both sides fracture at their weak spots, and the symphysis is depressed. This fracture is important as under the usual treatment with a tight binder or a sling the two halves of the pelvis may be approximated, and the pelvic inlet and outlet considerably narrowed, which in the female may lead to difficult labour. Such cases should be nursed flat on a divided mattress (Fig. 453) and often without a pelvic sling.

Complicated multiple fractures must be treated on their merits according to the fractures present. There are usually more important injuries present, such as rupture of the bladder which demand urgent treatment. For the patient's comfort treatment as for double fractures of the pelvis should be carried out if possible.

Treatment of fractures of the pelvis (Uncomplicated) Treatment is directed to making the necessary movements of the patient as comfortable as possible and by adequate support, allowing as much exercise to the rest of the body as is compatible with the patient's condition. In cases with displacement of the fractured



FIG. 455 The reduction of a displaced half of a fractured pelvis by manipulation. Traction is applied through the upper leg to the displaced ilium while the pressure on the lower foot produces counter traction. Under anæsthesia it is necessary to have the sound leg held rigid by bandaging it to a straight splint. A plaster including the whole pelvis and both thighs may then be applied while the reduction is maintained in this position.

pelvis this must be combined with traction to maintain reduction.

Reduction of the displacement This may be accomplished rapidly under spinal or general anæsthesia by lying the patient on the sound side with the sound leg held firm by being bandaged to a straight splint, and combining a certain degree of abduction with traction on the affected limb. (Attempts have been made to apply a plaster spica to maintain reduction after this has been done (Watson-Jones), but in our experience this is neither satisfactory nor comfortable for the patient.) In practice the slow reduction of the displacement by traction on a Kirschner wire or Steinmann's pin in the lower end of the femur is more readily combined with the treatment of shock and after treatment of the patient, and is recommended.

1 A fracture bed is prepared with two overhead bars lying parallel to the sides of the body. Two Braun's splints are bandaged in the usual way and placed on the bed, and a pelvic sling, consisting of a canvas sheet 30×10 inches attached to wooden rods at each end, is laid at the upper end of the Braun's splints. The patient is now lifted on to the bed the pelvis lying on the sling and the legs being placed on the splints. The cords of the sling are now run over single pulleys attached to the beams above, and weights equivalent to one fourth of the body weight are evenly divided and attached to




FIG 406. Patient with a fractured pelvis arranged with a crossed sling counterpoised with weights and both legs resting on Braun's splints. Patient raising himself for the use of the bed pan.

the two sides. If there is a tendency for the pubic symphysis to gape the cords are crossed and pass to the pulleys of the opposite side. After passing a wire or pin through the lower end of femur on the affected side, skin extension is applied to both legs, and 10 lbs extension attached to each. The pin or wire is placed in the lower end of the femur, as the force necessary for reduction may amount to 40 lbs, and it is unwise for such a force to act through the knee. A pull of 20 lbs is used to commence with. This necessitates elevation of the foot of the bed, and if the weight has to be increased to 40 lbs, blocks of 18 to 20 inches must be used to get

adequate counter extension from the body weight. With such a weight on one leg it is necessary to increase the weight on the other to prevent twisting of the pelvis and this may necessitate a wire in the tibial tuberosity of the sound leg. If the weights have been built up to 40 to 50 lbs. and the extension has acted for three days without producing reduction, then manipulation under a general anæsthetic, as previously described, will result in reduction and the patient can be put back to bed with extension to maintain it. Foot drop is prevented by one of the methods shown in Figs 501, 550. A patient so arranged will soon learn to raise himself for the use of the bed pan. The traction on the legs combined with the sling prevents the development of bedsores. Exercises can soon be carried out to a fairly active degree.

Union cannot be expected to be sound for eight to twelve weeks, but at the end of the fifth week Uina's paste extension to the leg and thigh can be substituted for the pin. If the pin is giving trouble at the end of the third week, it is better removed and a wire put in the tibial tuberosity through which lighter extension can be continued for another fortnight. Any serious inflammation around the pin will, of course, justify doing this earlier. Sound union of such fractures can always be expected with little disability, except in the old, where the enforced rest may result in some stiffness, but if exercises are carried out in bed thoroughly this can be avoided.

Fractures with no displacement
Where there is no displacement the arrangement of the patient is the same, but the extension through the femur is omitted. That on the legs is used to steady the patient, and relieve the pressure on the sacrum. Exercises in such cases can be begun earlier, and be more active.

The period of immobilisation likewise can be reduced, according to the progress seen in radiographs. Usually at the end of four weeks the patient can be nursed without




FIG. 457. Diagram illustrating the correct site for the introduction of a Kirschner wire (or Steinmann's pin) into the lower end of the femur. The site lies $\frac{1}{2}$ inch anterior to and $\frac{1}{2}$ inch above the adductor tubercle. A Quadriceps tendon. B Suprapatella bursa. C The synovial sac of the knee. D The patella. E The meniscus. F Infrapatella bursa. G Tibial tuberosity. H The ideal area for insertion of the wire. I Semi-membranosus bursa. J Tendon of popliteus. K The bursa around the popliteus tendon. L The fibula collateral ligament of the knee.

apparatus in a bed with a divided mattress, and at the end of a further four to six weeks can begin to walk. Little disability results from these cases in the absence of complications.

Fractures of the Acetabulum

These may be (1) Fractures of the rim, associated with anterior and posterior dislocations, and (2) fractures of the acetabular floor associated with central dislocations (Fig 457a). The latter are usually due to falls on the lateral aspect of the great trochanter. More commonly an abduction fracture of the neck of the femur results, but where this does not occur the head may be driven into the floor of the acetabulum sufficiently hard to produce a fracture. In the majority of cases the head is not driven completely through into the pelvis. Less commonly the lesion results from a fall on the extended leg.



FIG 457a Central dislocation of the head of the femur with fracture of the acetabular floor

1. Fractures of the acetabular rim are reduced when the dislocation commonly associated with them is reduced, but occasionally the fragment may get into the hip joint preventing full reduction. Such rare cases require open operation.




FIG 458 Separation of the pubic symphysis with wide opening of the sacroiliac joints



FIG 459 Reduction of separation by a simple pelvic sling with crossed traction

The two common varieties are dependent on the size of the fragment.

1. Small. At least partly reduced when the dislocation is reduced. These are left as they are not likely to cause trouble.

2 *Large*—The damage to the posterior rim is sufficient to make the hip joint unstable and the fragment remains partly displaced after reduction associated with a partial subluxation of the hip. These cases demand open operation on the hip through a posterior approach and the nailing or screwing of the fragment into position. Confusion with the occasionally present os marginale is to be avoided by careful examination of the X ray (Fig. 535).

2 *Fractures of the acetabular floor*—In the less severe cases the signs and symptoms resemble those of median fracture of the neck




FIG. 460 Fracture of right and left ischio pubic rami anteriorly—with fracture of the left ilium running into the sacro iliac joint posteriorly. There is sacralization of the fifth lumbar vertebra. (Compare Fig. 452)

of the femur. Where there is a central dislocation the depression of the trochanter can be noted and the head of the femur is palpable per rectum.

The treatment is similar to that of a complete fracture of the pelvis with displacement. The amount of extension necessary varies with the amount of displacement of the head of the femur and may have to be raised to 40 to 50 lbs. to obtain reduction. It is helpful in many cases to supplement this with a direct lateral pull from a Kirschner wire passed vertically through the great trochanter and to which is attached a 10 lb. pull over a pulley on the side of the bed. If this fails manipulation must be tried. When reduced the

extension can be reduced to 10 to 14 lbs. The displaced fragments of the floor follow the head to a variable degree. Such traction is maintained for six weeks and then reduced to 10 lbs. on skin traction, and the patient encouraged to exercise. At the end of twelve weeks the patient is allowed about on a walking calliper. This is abandoned in a further three to six months. In spite of the seriousness of the lesion the results are better than might be expected. A hip with good function can be expected, but the later onset of arthritis is to be feared.



Fractures of the Individual Bones

1. Fracture of the ala of the ilium. This is due to direct violence or lateral crushing injuries. The displacement is as a rule spontaneously corrected by the pull of the large muscle masses attached to the fragments. The amount of bone involved may vary from a small wedge to almost the whole of the wing of the bone. The features of the fracture are local pain and bruising, together with pain on moving the leg on the affected side. Abnormal movement of the anterior superior iliac spine may be

FIG. 461 Fracture of the anterior superior iliac spine

detected if it is attached to the fragment or, in a few cases, it may be displaced above its normal level. Rarely the hematoma may press on the lateral cutaneous nerve of the thigh and cause pain. If so the hematoma should be aspirated.

TREATMENT is directed to making the patient more comfortable. Many patients are best nursed for a fortnight as for the fracture of the pelvic ring without displacement. A firm binder around the

pelvis below the spines may give some relief, but in others it may increase the discomfort when it should be removed. It is best applied by passing two circular turns of 1 inch elasto-plast around the pelvis just below the level of the anterior spines. Free movements in bed are encouraged and the patient is allowed about as soon as he is free from pain on movement, usually about the end of the third week.

2 **Fractures of a single ramus** These are rare and due to direct violence. Usually the upper ramus of the pubis is fractured. There is local bruising and pain, but as the ring is not broken there is a freedom of movement and absence of pain on springing the pelvis which is not found in the complete fractures. The only treatment necessary is rest till the patient can get about comfortably, usually ten days to a fortnight, after which walking can be encouraged.

3 **Fractures of the anterior superior iliac spine** may arise due to direct injury, but may also arise from the sudden spasm of the sartorius and tensor fasciae latae pulling off their bony origin. There is local pain, bruising and tenderness, occasionally referred pain down the lateral cutaneous nerve of the thigh, and pain on attempts to abduct the thigh. The treatment is rest in bed with the knees flexed and abducted over a pillow. The fragment frequently unites at a lower level than before, but no disability arises. The patient is allowed to sit out of bed as soon as he is free from pain, and walking is commenced at the end of three to four weeks.



FIG 401a. An old ununited avulsion fracture of the ischial tuberosity in adolescence as a result of hurdling.

4 **Fractures of the ischial tuberosity** This is a rare lesion due to falls in the sitting position. There is local pain and bruising, pain on sitting, and marked pain on stretching the hamstrings. Displacement is small, and the treatment is rest in bed for three to four weeks. The patient may be nursed on the side, or an air cushion may be found to afford relief.

5 **Fractures of the coccyx** are interesting, if at times annoying, on account of the frequent late development of pain in the region with little evidence as to the cause. It is possibly due to an arthritis at the sacro coccygeal joint, or to involvement of the coccygeal nerves in the scar tissue. A neurotic element is frequently associated with the condition. The diagnosis depends on features similar to fracture of the sacrum. Radiologically the fracture may not be easy to demonstrate because of the irregularities in the normal architecture of

the bone Coccydynia can, however, arise in the absence of fracture, associated with strain of the sacro coccygeal joint only

TREATMENT The displaced fracture must be reduced by a finger in the rectum, and the patient given two to three weeks rest, not necessarily all the time in bed. If any feature of coccydynia arise hot baths and postural exercises are commenced at once. If it persists the patient is carried on by palliative methods, diathermy,



FIG 462 Obstetric view of pelvis to show the displacement in a fracture of the sacrum. Note the interruption in the outline of the pelvic brim. Double fracture anteriorly.

radiant heat and the injection of proctocaine around the bone as long as possible. Only if these methods fail is it justifiable to excise the coccyx. In many cases this will not cure the condition, the pain persisting as before, and the operation is to be avoided.

Fractures of the Sacrum

Fractures of the sacrum occur in 45 per cent of cases of double fracture of sacrum, and the failure to recognise them is due to the difficulty in getting satisfactory views of the sacrum. The sacrum is a strong bone very resistant to compression, but having a weak

area due to the perforations of the anterior and posterior sacral foramina between the lateral mass of the sacrum and the body of the bone. Fracture therefore most commonly involves this area running through the first, second and third sacral foramina to its exit just below the sacro iliac joint. It may take the form of a fissure, a fissure with displacement, or compression. An interesting fracture is sometimes associated with these lesions, a fracture of the lower lateral margin of the bone corresponding to the attachment of the sacrotuberous ligament. This is a ligament traction fracture due to the deformity of the pelvis at the time of injury.

RADIOGRAPHY. Clear views of the sacrum are necessary to recognise fine fissures, and the small fractures which occur around the margin of the sacro iliac joint must often be missed in spite of good radiography. Comparison of the architecture of the bone around the sacral foramina on both sides is necessary. The pattern should be unbroken on both sides if the bone is normal. Narrowing of the bone on one side may be obvious (Fig 454). A most important view in doubtful cases, and in cases in which full details of the displacement are wanted, is the obstetric view of the pelvis. Irregularity in level of the brim of the pelvis is common in fractures in this region (Fig 462).

NEUROLOGICAL FEATURES. The treatment of the bone injury is practically impossible, but neurological features are often associated with such cases and these demand treatment. The lesion commonly present is due to pressure on the first and second roots of the sacral plexus. This produces an incomplete lesion and this, combined with the vagueness of root syndromes generally, may make the syndrome difficult to recognise. It is obviously similar to that of a prolapsed disc but involves the second sacral root which is not usually pressed on by a disc. The characteristic features of pressure on S 1 and S 2 roots are —

- 1 Paræsthesiæ, and varying degrees of loss of sensation of light touch and pin prick over the outer side of the leg (S 1, S 2 area)
- 2 Loss of muscle power and wasting in the calf, the hamstrings and the buttocks, in that order of severity. Biceps femoris is sometimes almost completely wasted
- 3 Loss or diminution of the ankle jerk

There is, of course, no interference with bowel or bladder function. The treatment is confined to trying to maintain the tone and development of the affected muscles, by exercise, electrical stimulation and massage. It is characteristic of the lesion that, owing to the retention of some voluntary power in all muscles, the condition is not recognised till disproportionate wasting in the muscles described, on the injured side calls for explanation. The prognosis is good in the

the bone. Coccydynia can, however, arise in the absence of fracture, associated with strain of the sacro-coccygeal joint only.

TREATMENT The displaced fracture must be reduced by a finger in the rectum, and the patient given two to three weeks rest, not necessarily all the time in bed. If any feature of coccydynia arise hot baths and postural exercises are commenced at once. If it persists the patient is carried on by palliative methods, diathermy,



FIG 402 Obstetric view of pelvis to show the displacement in a fracture of the sacrum. Note the interruption in the outline of the pelvic brim. Double fracture anteriorly.

radiant heat and the injection of proctocaine around the bone as long as possible. Only if these methods fail is it justifiable to excise the coccyx. In many cases this will not cure the condition, the pain persisting as before, and the operation is to be avoided.

Fractures of the Sacrum

Fractures of the sacrum occur in 45 per cent of cases of double fracture of sacrum, and the failure to recognise them is due to the difficulty in getting satisfactory views of the sacrum. The sacrum is a strong bone very resistant to compression, but having a weak

Injury to the urethra The triad of symptoms indicating this are perineal bruising, the escape of blood from the urethra, and retention of urine, to which a fourth may be added, extravasation of urine, a complication to be avoided at all costs. In a suspicious case, who cannot hold urine any longer or in whom the bladder is distended and giving pain, it is justifiable to puncture the bladder suprapubically as often as is necessary till he can be given the correct treatment to avoid extravasation.

EXTRAPELVIC RUPTURE OF THE URETHRA 1 May be in the bulb below the compressor urethræ. Spasm of this muscle then gives rise to retention.




FIG 46. The treatment of extrapelvic rupture of the urethra. Catheters are inserted through both portions of the urethra and brought out the perineal wound.

2 May be in the bulb above the compressor urethræ, when early extravasation will occur.

INTRAPELVIC RUPTURE OF THE URETHRA Separation occurs at the apex of the prostate where the prostatic urethra is torn away from the membranous portion. It is clinically impossible in the presence of extravasation of urine to distinguish this from extraperitoneal rupture of the bladder.

EXTRAPERITONEAL RUPTURE OF THE BLADDER Extravasation occurs into the cava of Retzius, and the tissues between the peritoneum and the anterior abdominal wall. The lesion lies in the anterior bladder wall and may be caused by a wide separation of the pubis or perforation with a spicule of bone.

INTRAPERITONEAL RUPTURE OF THE BLADDER Due to the bladder being full at the time of injury. The rupture is posterior.

average case, satisfactory recovery taking place. As in neurological lesions elsewhere, the more complete the lesion at first the worse the ultimate recovery.

Transverse fracture of the sacrum just below the sacro iliac joints, i.e., of that part which lies in the true pelvis, may occur from falls or kicks. The displacement is usually small and the condition should be treated by early exercises, particularly exercises involving the pelvic diaphragm.

COMPLICATIONS OF FRACTURE OF THE PELVIS

Death in fractures of the pelvis is commonly due to the associated severe injuries. In 10 per cent of fractures of the pelvis alone




FIG 463 Intrapelvic rupture of the prostatic urethra showing the course of the extravasation




FIG 464 Extraperitoneal rupture of the bladder showing the course of the extravasation

there are associated visceral injuries which may cause serious trouble. The urethra is commonly injured and if the bladder is full it may be ruptured. Injuries to the vagina, rectum, or small intestine are much less common. Still more rarely the pelvic blood vessels are torn, or the sciatic nerve injured. If the nerve is paralysed this is usually temporary and demands no other treatment than the prevention of foot drop and electrical stimulation of the muscles.

In any pelvic fracture of any severity there is likely to be some lower abdominal rigidity whether there is injury to a viscus or not. It is possibly due to retroperitoneal hæmorrhage causing peritoneal irritation. It can be sufficiently marked to confuse the issue when there is suspicion of a ruptured viscus. In the case of the bladder more exact information can be obtained, but in the case of suspected injury to bowel careful observation or laparotomy may be needed.

In extraperitoneal rupture of the bladder, or intrapelvic rupture of the urethra, the signs of peritoneal shock are not so marked, and there is a palpable swelling in many cases, which is either an extravasation in the lower abdominal wall or the distended bladder. The catheter passes and some bloodstained urine is withdrawn and this has lulled many people into a sense of false security. It is due to the escape of a little urine free in the tissues along the catheter. To carry the diagnosis further, the injection of some boric lotion will result in only a very small portion being returned, and a palpable increase in the suprapubic swelling. The injection of sodium iodide and an X ray will show the scattered urine in the pelvic tissues, but the solution is irritating to them.

At operation the bladder must be repaired through a suprapubic incision without, if possible, opening the peritoneum. The tissues involved in the extravasation are adequately drained and a catheter tied in the urethra. In intrapelvic rupture of the urethra the treatment is the same, the catheter serving in this case to retain the dislocated apex of the prostate against the membranous urethra. The objection to a tied in catheter does not hold here as there is not the same tendency to stricture formation. A suprapubic catheter may be left in as a safeguard, and it facilitates later changing of the catheter by the railroad method. The chief points of after-treatment are the frequent irrigation of the bladder with boric lotion and the avoidance of stricture by careful control with sounds, and, if possible, the urethroscope.

In intraperitoneal rupture of the bladder the catheter can be passed, but only a few drops of blood-stained urine are obtained. The features of peritoneal irritation are marked, and the shock is greater. If there is still a doubt some boric solution can be injected along the catheter. Only a small part can be recovered. Laparotomy with suture of the tear, peritoneal drainage, and urethral drainage of the bladder is necessary.

REFERENCES

- PEABODY "Disruption of the Pelvis with Luxation of the Innominate Bone," *Arch Surg*, 1930, 21, 970
 COHEN "Avulsion Fracture of the Ischial Tuberosity," *J Bone and Joint Surg*, 1937, 19, 1138
 CONWAY "Fractures of the Pelvis," *Am J Surg* 1935, 30, 69 (Recommends the rather doubtful procedure of abdominal puncture for intra abdominal injury. Laparotomy is safer. Further references.)
 WATSON JONES "Dislocation and Fracture Dislocation of the Pelvis," *Brit J Surg*, 1938, 25, 773-781
 WAKELEY "Fracture of the Pelvis," *Brit J Surg*, 1929, 17, 22 (Gives the figure of 11 per cent for visceral complications.)
 BONNIN J. G. "Sacral Fractures and Injuries to the Cauda Equina," *J Bone and Joint Surg* 1945, 27, 113
 LAYTON, R. G. "Pelvic Dislocations," *Brit J Surg* 1942, 30, 126-132

In the presence of any of the signs mentioned steps must be taken to clear up the diagnosis and institute treatment as soon as possible. This can only be satisfactorily done in the operating theatre. After cleaning up the anterior urethra, a size 8 gum elastic catheter of the coude type is passed. If it passes easily and clear urine is withdrawn then serious injury to the urinary tract is excluded. If difficulty is met with accompanied by pain and hæmorrhage, but the catheter can be passed, then partial rupture of the urethra has occurred. One must then decide between leaving the catheter tied in, with risk of sepsis, and later stricture, or treating the case as a complete rupture, with perineal drainage in the hope of avoiding




FIG 446 The treatment of intrapubic rupture of the urethra. A catheter is inserted supra pubically and below this the cave of Retzius is drained. Another catheter is passed through the urethra and tied in

later scarring. Personally we have treated one such case by supra-pubic insertion of a catheter, and continuous suction for a fortnight. The result was very satisfactory, but one case is not conclusive. Failure to pass the catheter indicates complete rupture. An attempt is then made to find the divided ends of the urethra in the perineum by passing a sound as far as possible along the penile urethra and cutting down on the end of this. The difficulty of finding the proximal end is notorious, and if perineal search fails a supra-pubic incision must be made and retrograde catheterisation carried out. The two catheters are brought out through the perineum and the tissues sutured around them with drainage. If extravasation has occurred adequate incisions and drainage is provided in the affected tissues.

Fractures of the head These fractures are rare and almost impossible to diagnose except at open operation. They may be suspected after severe injury to the hip, such as dislocation, in which the joint movements do not return as quickly as expected. Most fractures of the head take the form of chip fractures in association with dislocation of the hip and it may sometimes be difficult to say whether the fragment in the joint comes from the posterior lip of the acetabulum or the head. Undisplaced fragments are left, and the hip is fixed from pressure by high traction (10 to 15 lbs.) for a few weeks and then active non-weight-bearing exercises commenced. Displaced fragments should be removed by open operation, if preventing reduction. If not they should be left as the results are much better than might be expected.

Fractures of the Neck of the Femur

The fact that the lesion is most common in elderly people, associated with senile decalcification of bones, has lent to the treatment of the fracture peculiar difficulties which are still only partly resolved. The lesion is slightly more common in women, showing, like Colles's fracture, a tendency to be associated with obesity, indicating that the decalcification may be partly an endocrine disturbance. To this factor are added two others, the neck of the bone is inclined more nearly at a right angle in women and thus increases the leverage possible, and the bones are thinner.




FIG. 467. Fracture sites in the upper end of the femur. Subcapital fractures occur most frequently between the two upper lines. Pertrochanteric fractures occur between the two lower lines. In between these areas is a strip of bone in which the so-called lateral fracture of the neck of the femur occurs. More important than the site of fracture is the obliquity of the fracture, i.e. its relation to the axis of the neck of the femur.

The situation of the fracture, lying across a curve in a bone which shares with another the weight of the body and is subject to the full

CHAPTER XXVII

FRACTURES OF THE FEMUR

Surgical anatomy **Development** The primary centre for the shaft appears at the seventh week Secondary centres appear as follows

Head	First year	}	Fuse with the shaft about eighteen years
Greater tuberosity	Third year		
Lesser tuberosity	Thirteenth year		
Lower epiphysis	Shortly before birth		Unites twenty three to twenty four years

The femoral neck in the adult makes an obtuse angle with the shaft, which varies from individual to individual, and is less in the female but average; about 120°. The neck is also inclined forward at an angle of 10° to 15° from the frontal plane. It is to be regarded as a continuation of the shaft of the bone which is modified by growth so that it lies at the angle described. To it is attached the greater tuberosity and the lesser tuberosity. In accordance with the laws of ossifying bones a greater density of bone is laid down on the inside of the curve of the neck forming the *calcar femorale*. The outer side of the curve which becomes the upper part of the neck is modified to cancellous bone and incorporated in the trochanter the internal trabecular formation corresponding to the lines of stress through the bone. The strength of the *calcar femorale* is the determining factor in the position of fractures of the upper end of the femur, and a spike of it impacted into the cancellous bone of the head may be the cause of failure to reduce a subcapital fracture.

The blood supply of the head of the bone is derived from arteries in the shaft of the bone vessels running along the capsule of the joint and passing back along the *retinaculæ*, and the artery of the *ligamentum teres*. This extensive anastomosis consequently requires considerable displacement of bone before the blood supply of the head is interfered with.

The epiphyseal line for the head is entirely intracapsular that for the great trochanter partly so. At the lower end the epiphysis is intracapsular anteriorly. It is also to be noted that the adductor tubercle is on the metaphysis and not on the epiphysis.

Fractures of the Upper End of the Femur

Fractures of the head of the femur		0.5 per cent
Fractures of the neck of the femur		33
Medial or subcapital	{ Abduction 12	
	{ Adduction 58	
Lateral	Adduction	"
Pertrochanteric fractures		62
Separation of the epiphysis for the head of the femur		3
Fracture of the greater trochanter		1
Fracture of the lesser trochanter		0.5

or above it. If the trochanter is elevated it lies below the umbilicus.

- (d) Normally lines joining the two anterior superior iliac spines and the tips of the two trochanters are parallel. If the trochanter is elevated they are angulated.

3. The trochanter may be nearer the mid line than normal. This is best measured with callipers, but it may be roughly taken by measuring from the mid line to the anterior border of the trochanter.

4. Testing hip movements.

- (a) Flexion. Flex the sound leg fully to overcome compensatory lordosis, and for comparison. A fixed flexion deformity may become obvious.

- (b) Extension. Lift the limb off the couch with the patient lying on his face, or carry the limb backwards on the arm with the patient lying on the side. Normally 15° .

- (c) Rotation. Roll the calf on the couch with the flat of the hand and compare with the other side using the foot as a convenient indicator of degree.

- (d) Abduction. Abduct the leg, steadying the pelvis and compare.

- (e) Adduction. Cross the thigh over the thigh of the opposite side. Normally it should cross the middle third.

Physical signs in fracture of the upper end of the femur. In order to avoid repetition the general features which are common to all fractures will be outlined and the differences of individual fractures mentioned under their own heads.

HISTORY. Characteristically one of slight violence in old people. The average age for fractures of the neck is about ten years less than for pertrochanteric fractures, where the highest incidence is between sixty and seventy years. The strain is usually a rotational one caused by stumbling with the foot fixed, e.g., against a step. Less frequently there is a fall on the extended leg. Abduction fractures are frequently associated with falls on to the outer aspect of the great trochanter, characteristically seen when a bus starts suddenly and throws the patient to the floor on the side. Any elderly person who sustains a fall from which he is unable to rise, and after which the use of one leg is lost, has in all probability a fracture of the upper end of the femur, and this must be proved or disproved by radiography.

INSPECTION. This will show a patient suffering a variable amount of shock, often not very great, lying with the limb flat on the bed and the leg externally rotated.

DISABILITY. This is least in abduction fractures with which the patient may have made some attempt to walk. In most cases it is complete and the patient cannot make any movement of the limb at the hip.

SHORTENING. This may be measured by the elevation of the trochanter or the alteration in the length of the limb. It varies from an undetectable amount to 2 inches. At the same time the

leverage of the limb, increases the stress and strain to which the repair line of the fracture is subjected. As in fractures elsewhere impaction strain aids union, but shearing strain delays it. In fractures of the neck of the femur the nearer the fracture line is to the vertical the less the impacting strain and the greater the shearing strain. A minor factor acting in the same manner is the angle of the femoral neck, the more oblique the neck the more the weight will act through the fracture line, and will tend to impact. Fractures just below the head (medial, subcapital or intracapsular) are more frequently oblique and show a greater tendency to unite than the vertical fracture which is more characteristic of the lateral (extracapsular) fracture of the neck. Distinguishing between these two types of fracture has been shown to be unimportant and unjustified as the so called "extracapsular" fracture is intracapsular anteriorly. The degree of obliquity of the line of fracture is far more important than its site.

Any tendency of the upper fragment to be abducted would increase the impacting force of the body weight, and so promote union. This is seen in the classical abduction fracture which is always combined with impaction. The fracture unites readily, and with a good result. Treatment to obtain union of the fractured neck of the femur is therefore directed towards two objects:

- 1 Fixation of the fragments and avoidance of a shearing strain.
- 2 Impaction of the fracture, or the alteration in the line of transmission of the body weight so that it acts largely as a compression force on the fracture site.

The influence of this last-mentioned factor is seen in the union of old ununited fractures of the neck of the femur after a Lorenz or McMurray osteotomy. Only one line of treatment conforms to these principles and that is operative fixation with impaction of the fracture, which is most efficiently carried out with the Smith-Petersen nail.

The examination of the hip. A summary of the most important clinical observations to be made is given, but these are often of academic interest only and radiographs are of the greatest importance.


- 1 Measuring the length of the limb. This is measured from the anterior superior iliac spine to the internal malleolus with both legs extended, the tape running on the inner aspect of the patella and with the pelvis level, to avoid error from adduction or abduction of the legs.

- 2 Estimating the position of the trochanter.

(a) Nelaton's line. A line from the anterior superior iliac spine to the ischial tuberosity crosses the tip of the great trochanter.

(b) Bryant's triangle. This consists of dropping a vertical line from the anterior superior iliac spine in the recumbent patient and measuring the distance the tip of the trochanter lies below it.

(c) Shoemakers line. A line prolonged from the great trochanter through the anterior iliac spine normally crosses the mid line at the umbilicus.



tests for the elevation of the trochanter and its approximation to the mid-line may be applied. The restoration of the limb to its normal length and its maintenance is an important guide to the reduction and retention of the fracture.

PAIN This is variable. It is minimal in the impacted abduction fractures where movements of the hip may be passively elicited. The pain may be referred to the knee. Tenderness is always present and the situation of maximum pain, over the head of the femur or over the trochanter, may help to localise the fracture.

SWELLING In fractures of the neck it is maximal over Scarpa's triangle, and in the pertrochanteric fractures in the lateral aspect of the thigh around the trochanter. Bruising appears in 1 to 3 days at these sites.

Other signs are the relaxation of the ilio tibial band due to shortening, which allows the fingers to be pressed in more deeply over the tip of the trochanter if the sign is not obscured by swelling. Rotation of the thigh at the fracture site instead of through the hip is painful to elicit and difficult to observe. Telescopic movement is also painful and obscured by muscle spasm or impaction.

IMPACTED FRACTURES An impacted fracture may occur in both the neck and in the pertrochanteric region. The signs, such as pain, shortening and swelling all tend to be less obvious. Movements at the hip may be passively elicited and crepitus is absent. The impaction can usually be seen radiologically. Abduction fractures are always impacted, due to a combination of the action of the force producing them and the direction of the fracture line which is almost at right angles to the line of transmission of the body weight, and this tends to further impaction on weight bearing.

To distinguish clinically between pertrochanteric fractures and fractures of the neck of the femur is not usually easy, though the following points may help. Owing to the bone on the posterior aspect of the trochanter being softer there is a greater eversion of the limb in pertrochanteric fractures. The shortening is greater and the swelling and pain is localised to the trochanteric region.

X-RAYS As with fractures elsewhere correct orientation can only be obtained with films taken in the antero-posterior direction and in the lateral direction. An apparently good position in the A.P. film may show gross displacement on the lateral plate. Similarly care must be taken over the rotation of the limb, not only in reduction, but in the diagnosis of the actual fracture. With the limb everted the plate shows a prominent lesser trochanter, and the intertrochanteric line which is posterior crosses the neck of the femur, while in the inverted limb the lesser trochanter passes behind



FIG 468 Anteroposterior film of the normal hip in inversion. Note the disappearance of the lesser trochanter, the increased density of the calcar femorale and the fact that the intertrochanteric line no longer crosses the neck of the femur.



FIG 469 Anteroposterior film of the normal hip in eversion for comparison with the previous figure.



FIG 470 Ununited fracture of the neck of the femur in the young.



FIG 471 The same case after bone grafting showing satisfactory union (Mr. Summott's case). The shadow of the bone graft site can be seen though the graft has been incorporated into the femur.

the femur, the calcar femorale becomes more a
 antitrochanteric line lies lateral to the neck (Figs 4c

CAUSES OF DEATH IN FRACTURES OF THE UPPER
 FEMUR Shock, 4 per cent Associated injuries, 1
 Bronchopneumonia and other chest complications, 13
 Circine failure, 35 per cent Bedsores, 8 per cent Other
 5 per cent

Abduction Fractures of the Neck of the Femur

Characteristically impacted, with mild signs and symptoms,
 they are most commonly due to falls on the side, driving the great
 trochanter inwards. In the X-ray the head will be found to be
 pushed over the upper aspect of the neck, thus apparently shortening
 it, while the lower curve, lacking the projection of the head, appears
 flattened. The fracture line being almost at right angles to the line
 of the body weight, we can encourage weight bearing, knowing that
 the weight will only impact the fracture further. The impaction
 prevents shearing strain, and all that is required is a guard to
 prevent sudden rotational strains. Union occurs rapidly in six to
 eight weeks, and the disability is small, the only movements lost
 being the final degrees of abduction and internal rotation, while
 slight eversion of the foot usually persists.

Treatment This consists of the application of a short walking
 plaster spica, and in the cases where it is possible the early encourage-
 ment of walking. The plaster, applied with the standard padding
 is well moulded around the pelvis and comes only to the level of the
 costal margin and as far as the knee. To prevent swelling of the leg
 an Unna's paste stocking may need to be applied from the webs
 of the toes upward to the knee, and an elastic knee cap given.
 No attempt at disimpaction or correction of the overversion of the foot
 must be made.

In an active, thin patient walking is easily learnt (Fig 125). The
 plaster is worn for ten to twelve weeks, and then completely dis-
 carded. In old and fat patients a hip spica is very difficult to apply,
 and when applied the patient cannot use it on account of its weight.
 It is much better to keep such patients in bed and give them active
 exercises. No retentive apparatus is required, and after three weeks
 the patient can usually sit out of bed. Weight bearing is not allowed
 for six to eight weeks.

Adduction Fractures of the Neck of the Femur

Medial (Subcapital, intracapsular) }
 Lateral (So-called extracapsular) } Discussed together

The medial fracture is the more common, but there is often

COMPLETE OUTLINE OF FRACTURES

difficulty in deciding to which group a case belongs, owing to the obliquity of the fracture line. Generally speaking, medial fractures tend to be more oblique, while lateral fractures tend to be vertical. More trouble with the blood supply to the head can be expected in medial fractures. The vertical fracture is, however, more difficult to impact, and more subject to shearing force, and because of this union is less readily obtained.

The principal difficulty with these fractures arises from the type of patient in which they occur, and the complications arising from



FIG 472 Fracture of the neck of the femur of the adduction type




FIG 473 The same case after a few days skeletal traction showing the external rotation in part corrected and the fracture line to be at right angle to the axis of the neck of the femur

the prolonged immobilisation of the patient. These are so frequent and distressing that the mortality rate of operative treatment, which enables the patient to have greater freedom, is much better than that of non operative treatment. If we add to this the fact that the results of operative treatment are better, the conclusion that it is the correct treatment is inevitable. Further, the alternative, i.e., a plaster spica, is no simple procedure in an old person and productive of almost as much shock as a simple operation.

The choice of treatment lies between (1) Continuous traction; (2) fixation in a plaster of the Whitman type, (3) operative fixation of the fragments.

The difficulties of nursing elderly patients are the onset of complications such as bronchopneumonia cardiac or renal failure the development of pressure sores slow mental and physical deterioration from confinement to bed, with the development of bowel and bladder incontinence and nocturnal noisiness and restlessness. It will be seen that all these difficulties prejudice one in favour of operative treatment wherever possible and no one should be denied the consolation of the Smith Petersen nail without mature consideration.

We may commence our discussion by saying that in all cases treatment by traction should be instituted at once. By placing the leg on a Braun's splint and inserting a Kirschner wire through the tibial tuberosity on which is placed a weight of one-seventh the body weight, one can relieve the patient of much pain and render the nursing easier. The whole proceeding can be done under local anaesthesia, and does not add to the shock. With efficient traction the majority of fractures can be slowly reduced, which simplifies the next stage when it is ready to be done. Certain cases will succumb to shock or other injuries in twenty-four to seventy-two hours. The majority will improve in condition and in them the possibility of operative treatment must be considered. Time is given to estimate the patient's resistance and to investigate the cardiovascular and renal system. Experience shows that most cases denied operation on account of their general condition die from bronchopneumonia or heart failure. Of those submitted to operation a very small percentage die as the result of the operation (2 per cent) and a few succumb later from chest and cardiac complications. Ninety per cent of the patients recover, and lead a life comparable in length to that expected before operation, but with a vastly more comfortable existence. A high percentage obtain bony union with a functioning hip. While operative treatment has added certain small complications it has removed so many grosser ones that it has become the treatment of choice.

Continuous traction. Traction by a wire or pin in the lower end of the femur will reduce the majority of fractures, but continuous traction tends to over-reduce, that is, separate the fragments, and so results in non-union. It is, however, the least dangerous treatment so far as life is concerned. Its use as a preliminary to other methods of treatment has been outlined. It makes the patient comfortable, allows more movement in the bed than a plaster spica, and enables the patient to carry out some physical exercises.

Such treatment is best maintained by a pin in the lower end of the femur, which gives greater control of the eversion of the leg, and allows freer knee exercises. A wire in the tibial tuberosity is,

however, frequently put in first while the case is under consideration. Such a wire should not remain more than three weeks to avoid stiffness of the knee. At the end of this time it is moved to the lower end of the femur, and at the end of a further three weeks Unna's paste extension is substituted for it (Fig 501). The latter allows complete exercise of the limb which is carried out once daily. The amount of extension used varies with the weight of the patient, being approximately one-seventh of the body weight, and this is increased or decreased according to the changes seen in the X-ray plate. At the end of six weeks the weight is reduced to 10 lbs on the thigh extension and 4 lbs on the leg extension. At the end of twelve weeks the patient is sat out of bed and a walking calliper fitted. Non-union is a common result of such treatment, but it is surprising how well the calliper is handled in active cases in spite of this. Union when it occurs is in good position and very satisfactory. For this reason in young patients (under eighteen

years), in whom non-union is not to be feared, the method is still a good one, and to be recommended. At present in old people the method is applied to patients unfit for operative treatment, and so its results are poor.

Whitman's plaster. This method is not a satisfactory one as the proportion of unions obtained in the best hands is only 60 per cent, and the method is liable to lead to stiffness of the knee and hip on the affected side. Added to this it is not an easy method to apply to an old patient, and while the patient can be moved more easily the patient himself finds more difficulty in moving. A few active thin patients can



FIG 474 The reduction of a fracture of the femoral neck by manipulation. First stage Traction



FIG 475 Second stage Traction combined with internal rotation

walk in a Whitman plaster with a walking iron applied to the plaster and the heel on the sound side built up. If this can be done many of the objections to the method are done away with, but it is rarely so (Fig. 124).

METHOD. The fracture, if reduced by continuous traction, will require little manipulation when the patient is on the orthopaedic table, which saves the patient some shock. If unreduced the hip is reduced by manipulation, the leg being forcibly extended, inwardly rotated, and abducted, while the other leg is pulled on to fix the pelvis. The feet are then attached to the foot pieces, and the legs held in slight abduction and internal rotation. An X-ray is taken to be certain reduction has been carried out. If this is satisfactory the leg is relaxed a little, and the neck impacted by some heavy blows with a hammer on a felt pad held over the greater trochanter. Others attempt to do the same thing by pushing on the abducted leg against counter pressure on the opposite hip. A firm plaster is now applied, using the padding previously described (page 173), from the toes to the chest, holding the leg in internal rotation and slight abduction. Such a plaster is maintained for three months. On removal the patient requires some exercises to restore movements to the injured limb, and as soon as possible is fitted with a walking caliper which is worn for a further three to six months. X-ray control is exercised throughout the proceeding. Swelling of the leg after removal of the plaster is controlled by an elastic knee cap and an Unna's paste stocking below.

If the patient is able to get about in his plaster the proceeding is the same, but if non-union is present at the end of three months it is reasonable to re-apply the plaster for a further three months.

This method is suitable for the rare case of fracture of the neck of the femur in young children when the plaster is required for ten weeks only, the child being kept in bed.

Operative fixation of fractures of the neck of the femur. After reduction of the fracture by traction and the investigation of the patient's general condition, the decision to operate is made, and as the cases refused operation nearly all die from complications, it is permissible to take some risks. The choice of operation lies between the following methods, each suitable to particular cases.

1 **OPEN OPERATION**, exposing the hip joint and fracture, accompanied by a Smith-Petersen pin. The exposure of the hip increases the shock of the operation greatly, and has been superseded by X-ray controlled methods. It may be necessary in the few cases of fracture which cannot be reduced by continuous traction or manipulation.

2 **INSERTION OF A BONE GRAFT.** This usually is an autogenous peg cut from the fibula. While encouraging union, it does not

prevent the shearing strains at the fracture site, and the results are not so satisfactory as from nailing, though it may be the method of choice in young patients (Figs 470, 471)

3 SMITH-PETERSEN NAIL This nail of stainless steel has three flanges which obtain a good grip on the head and so prevent rotation. It serves as a guide over which accurate and forcible impaction can be carried out and produces a high percentage of bony unions (90 per cent). Carried out by a "blind" method using X-ray control the method is not productive of shock, and by allowing the patient "the freedom of the bed" materially increases his comfort and reduces the number of complications.

4 SMITH-PETERSEN NAIL ACCOMPANIED BY A BONE GRAFT This is an endeavour to combine the advantages of methods 2 and 3. It may be used in ununited fractures, or fractures of some standing in which there is absorption of the neck, and it has been used in recent fractures where the verticality of the fracture line suggests difficulty in obtaining union by a nail alone.



FIG 476 Smith Petersen nail, showing the central canal for the guide



FIG 477 The first step in the nailing of a femoral neck. The guide wires are introduced either by using one of the many guides on the market or by the estimation of position from surface anatomy or under the screen. Most important is the lateral view of the neck.

To describe in detail the various operative methods is beyond the scope of this book, but a brief outline of the established methods is given below. The development of the X-ray controlled technique has brought many instruments to light designed to facilitate the insertion of the nail. The superiority of one method over another is debatable, the most important part of any technique being the surgeon's familiarity with it, and its limitations. As a general guide the simplest of methods will be outlined.

1 Reduction This is done by continuous traction beforehand if



FIG. 475 Watson Jones guide

possible, but if this is not satisfactory the patient is manipulated on the table. Leadbetter's manoeuvre, consisting of strong traction combined with forced internal rotation is often used. Reduction is tested by noting whether the foot externally rotates when placed on a flat surface.

2 The highest point of the femoral head is now marked by taking a point $\frac{1}{2}$ inch below the mid point of a line joining the symphysis pubis and the anterior superior iliac spine. A skin clip is placed here, with, if preferred, a further clip an inch on either side of it, on a line parallel to Poupart's ligament. If desired clips may be placed over the greater tuberosity.

3 Antero-posterior and lateral X-rays are now taken. These show the reduction of the fracture and the relation of the head to the clips. The correct angle for the insertion of the nail in the frontal plane can now be appreciated. The slight forward angulation of the neck may be allowed for by directing the wire towards the anterior superior iliac spine of the opposite side.

It is however much easier to invert the limb till the neck of the femur is parallel with the top of the table, and insert the wire in this line.

4 An incision is now made over



FIG. 479 The lateral view of the neck being satisfactory the pin is driven home over the wire

the great trochanter, under local or general anaesthesia. The bone is exposed below the line of attachment of the vastus lateralis to the trochanter. The point of entry for the guide is $\frac{7}{8}$ to 1 inch below this. A small area of cancellous bone is removed here with a wide ($\frac{1}{4}$ inch) drill or a small gouge. A thick Kirschner wire or a Watson Jones graduated guide is now pushed into the bone from this point in the calculated direction. If desired a second wire at a slightly different angle may be inserted. The procedure may be facilitated by doing it under the X ray screen.

5 Further X rays are now taken in the antero posterior and lateral direction. On these the correctness of the position of the




FIG. 480. Cross piece of wood attached to the heel of a plaster shoe to prevent eversion of the foot. The same effect may be achieved by nailing it on to the heel of an ordinary shoe.

guide is judged, and the most suitable guide selected. The other is removed. The ideal position of the guide is central in the lateral view, and running nearer the lower border of the neck but parallel with the centre line of the neck, in the antero posterior film. The length of nail necessary can be calculated directly from the Watson-Jones guide, or if Kirschner wires of a fixed length are used from the amount of wire extending beyond the trochanter. A nail $\frac{1}{2}$ inch short of the distance between joint line and trochanter is selected. This is to allow for impaction of the fracture over the nail.

6 The nail is now placed on the guide wire and driven home over it. The guide wire is withdrawn and the position checked in antero posterior and lateral X rays. If satisfactory the fracture is now impacted by several blows on the trochanter with the impacting instrument after traction is relaxed. This should cause the nail head to protrude a little from the surface, and it is then driven home. The wound is then closed.

After treatment This has varied in various clinics to a remarkable degree. A plaster shoe may be placed on the foot, with a small lateral bar to prevent lateral rotation, otherwise the patient is left free in the bed. Movements and exercises are encouraged as soon as possible. Dehite arises principally over the time which should elapse before weight bearing can be allowed. It is the practice of some to allow it immediately, others insist on three months' rest in bed. The effect of weight bearing depends to a great extent on the



FIG. 451 The final position of the pin in the lateral film



FIG. 452 The final position of the pin in the antero-posterior film

angle of the line of fracture, and it is our practice to allow it at the end of a month when the line is transverse, but to delay it for two months if the line is more vertical. Thus, of course, is subject to the X ray showing evidence of satisfactory position, impaction, and later, union.

The Technique of Nail Insertion

The simple method described is a composite method, points being taken from various techniques. The aim of all special techniques is to devise a method for inserting the wire accurately in the femoral neck, allowing for the angulation of the neck of the femur.

the great trochanter under local or general anaesthesia. The bone is exposed below the line of attachment of the vastus lateralis to the trochanter. The point of entry for the guide is $\frac{3}{4}$ to 1 inch below this. A small area of cancellous bone is removed here with a wide ($\frac{1}{2}$ inch) drill or a small gouge. A thick Kirschner wire or a Watson-Jones graduated guide is now pushed into the bone from this point in the calculated direction. If desired a second wire at a slightly different angle may be inserted. The procedure may be facilitated by doing it under the X-ray screen.

5 Further X-rays are now taken in the antero-posterior and lateral direction. On these the correctness of the position of the




FIG. 481. Cross-piece of wood attached to the heel of a plaster shoe to prevent eversion of the foot. The same effect may be achieved by nailing it on to the heel of an ordinary shoe.

guide is judged, and the most suitable guide selected. The other is removed. The ideal position of the guide is central in the lateral view, and running nearer the lower border of the neck but parallel with the centre line of the neck, in the antero-posterior film. The length of nail necessary can be calculated directly from the Watson-Jones guide, or if Kirschner wires of a fixed length are used from the amount of wire extending beyond the trochanter. A nail $\frac{1}{2}$ inch short of the distance between joint line and trochanter is selected. This is to allow for impaction of the fracture over the nail.

6 The nail is now placed on the guide wire and driven home over it. The guide wire is withdrawn and the position checked in antero-posterior and lateral X-ray. If satisfactory the fracture is now impacted by several blows on the trochanter with the impacting instrument after traction is relaxed. This should cause the nail head to protrude a little from the surface and it is then driven home. The wound is then closed.

insection of the wire in both planes. The construction of the guide can be seen in the illustrations. A wedge shaped sector is canalised with converging square holes, between which lie ribs of




FIG 454 The technique of using the Hey Groves guide 1 The use of a hinged guide for calculating the angle of the neck in the frontal plane 2 Showing the use of the guide which corrects for the deviation of head from the frontal plane 3 Driving the nail over the guide 4 The nail driven home 5 and 6 The use of one variety of nail extractor

A ray opaque material. There are a double row of canals to obviate the difficulty which would arise if the attaching pin corresponds to the desired angle of inscription of the guide wire. The guide is attached

in the frontal plane, and the forward inclination of the head of 17 degrees from this plane. It is this latter inclination which is the most difficult to make allowances for.

The Bailey Guide

In this method a metal tongue is run along the anterior surface of the femoral neck by open operation. A wire inserted parallel to this will thus have the required forward inclination. The angle in the frontal plane which is comparatively constant is allowed for by a metal block from which the guide tongue juts out at the required angle. This block is pushed up firmly against the outer aspect of the trochanter, and carries the guide holes for the insertion of the Watson Jones guide. This method requires wider exposure of the parts than other methods.

The Hey-Groves Guide

This consists of a solid graduated square rod to which are attached (1) a short blunt upright fixed at the end, (2) a movable pointed upright, slightly longer than the first, (3) a director for the guide wire, which inserts it a fixed distance (equal to the radius of the femoral neck) below the pointed upright. In use the correct angle in the frontal plane is calculated from skin marking with clips, or the notched angle guide, or, if desired, the instrument can be used under the screen. Points on this line over the head and neck are marked, and the skin perforated with a sharp knife. The blunt point is then



FIG. 483 The Hey-Groves guide for accurate insertion of the guide wire.

forced through the subcutaneous tissues and muscles till it is in contact with the head of the femur, and the pointed upright likewise in contact with the neck of the femur. The guide piece is then attached, and an incision made over the great trochanter so that it can be pushed into contact with the bone and a Watson Jones guide inserted. This method is accurate if the anterior surface of the neck of the femur is reasonably smooth, i.e., the fracture has been reduced satisfactorily and there are no displaced fragments of bone.

The Engel-May Guide

The principle of this guide is the use of a calibrated sector, attached by a pin to the femur, in such a manner that it may be turned from the frontal to the transverse plane, and so guide the

is then read off, and the guide wire drilled down the appropriate canal. Correction has now been made for both angles of the femoral neck. The length of pin needed is calculated by simple proportion from the radiograph the length of the Engel May guide being known.

Many other names, Watson Jones, Brittain, Cassine, Henderson, to mention only a few, are associated with developments in the use of various methods. An appeal to the list of references at the end of the chapter will allow of further information being found.

Complications of Nailing

1 Use of too long nail. Allowance must be made for X-ray distortion and for impaction in calculating the required length of nail. If the final radiograph shows it to be obtruding on the acetabulum it must be partly withdrawn.

2 Tilting of the femoral head. This occurs from the blows of the hammer when the head is insufficiently fixed by the guide wire. A guide wire of sufficient strength not to bend, and inserted into the head to a sufficient depth to obtain a good hold are therefore necessary.

3 Penetration of the guide wire. If a Kirschner wire bends it may be carried deeper into the tissues by the nail. In a similar manner the serrations on the Watson Jones guide may catch on the point of the nail and so force it into the acetabulum. A pause must be made in hammering the nail and the guide wire checked up for a decrease in the amount protruding.

4 Fracture of the nail. This rarely occurs from metallic flaws, or incorrect insertion of the nail with early weight bearing.

5 Erosion of the nail. This process is due to ionisation. It results in loosening of the nail. Very occasionally with inferior alloys it may produce fracture of the nail. Nails of a special non-magnetic stainless steel must be used.

6 Extrusion of the nail. This occurs in an unexplainable fashion, even in correctly nailed cases. The forces of expulsion are considerable, and require a deeply buried cross pin to prevent their action.

Difficulties with fracture of the neck of the femur. 1 Necrosis OF THE HEAD. This is presumably an avascular necrosis shown by the increase of density of the head compared to the surrounding bone which has undergone disuse atrophy. It becomes apparent only about the sixth week. In certain cases it is possible for revascularisation of the head to occur when the uniform density of the bone will be replaced by circular clearer patches where the blood supply is being re-established. At the end of the process the head will appear of a similar density to the rest of the bone. Unless X rays have been taken at regular intervals this will be overlooked, though the head usually shows some irregularities from which it may be deduced. Such changes occurring in a head which has been

by a square pin to the outer aspect of the great trochanter in a position as correct as it is possible to achieve from clinical judgment. A radiograph with the guide lying in the frontal plane produces a




FIG. 485. The Engel May guide as it appears in the A.P. radiograph. Note its attachment to the trochanter by the central pin.

picture similar to that of Fig. 485. From this it is easy to read off the canal corresponding to the central line of the femoral neck. A new square pin is inserted down this canal, and driven a short




FIG. 486. The Engel May guide in use. The guide lies at right angles to the position shown in the previous illustration and is now ready for the radiograph showing the lateral view of the neck. (Left leg.)

distance into the cortex by a smart hammer blow. The first pin is removed, the guide turned through 90° on the second pin and fresh radiographs taken (Fig. 486). The correct angle in this plane

nailed obviously demand a delay in weight bearing till the circulation is restored, or evidence of permanent necrosis is established. If this has occurred it is useless to expect union, and some form of operative interference has to be undertaken to improve the efficiency of the hip. Should the head be reconstituted by new bone formation it always remains likely to develop traumatic arthritis, and in older patients this is an almost invariable complication. After pinning the difficulty in determining union necessitates leaving the pin in position otherwise one may get refracture and established non-



FIG 4-7 Ununited fracture of the femoral neck. Old fracture on the right with a viable head and arophied neck. More recent fracture on the left showing the avascular necrosis of the head of the femur.

union after removing it. For the same reason the use of a cross pin to prevent extrusion of the nail is desirable.

2. NON-UNION. This is shown by atrophy of the neck and an increase in the gap between the fragments. This is difficult to treat satisfactorily. In the old and feeble they can be encouraged to use a walking caliper or if this is too clumsy for them a crutch or sticks. Stronger patients handle a walking caliper well. In younger patients an attempt must be made to obtain bony union by a Smith-Petersen nail, alone or together with a bone peg. If non union follows a nailing operation, and the patient is fit, the neck may be renailed with the addition of a bone graft.

In patients fit for operation in whom non union is established by either necrosis of the head or atrophy of the neck, their condition may be improved by (a) in osteotomy below the trochanter with abduction of the leg of Lorenz or McMurray type, or (b) a reconstruction operation of the Whitman type, in which the head is removed, the neck rounded off and placed in the acetabulum, and the great trochanter moved down the shaft.

3 OSTEO ARTHRITIS OF THE HIP. This is a frequent sequel to any mode of treatment. The patient is rarely young enough to make an arthrodesis worth while. Older patients must be carried along with general measures, and possibly the assistance of a walking caliper.

Pertrochanteric Fractures

These fractures unite readily under correct treatment, and the difficulties with them depend on their association with an older age group than fractures of the neck, but are essentially the same. The fracture line is oblique, running from the trochanteric fossa to the medial aspect of the shaft either above or below the lesser trochanter. In some cases the fragments are comminuted, either or both trochanters separating. There is usually a *coxa vara*, which varies in degree, and the gross eversion of the foot is accounted for by the softer cancellous bone on the posterior aspect of the neck, which allows more impaction there than anteriorly. A number of the fractures are firmly impacted.

Treatment. In impacted fractures little requires to be done except to prevent increase in the *coxa vara* and encourage movements. The fracture is never disimpacted unless the deformity is very gross, and this is most unusual. In the young a pin through the lower end of the femur may be used to provide traction on the femur, which is rested on a Braun's or slung Thomas splint. A weight of one seventh the body weight is applied which serves to correct any tendency to *coxa vara*. This is maintained for four to six weeks and the patient then allowed free movements in bed. If there is doubt as to the firmness of the union Unna's paste extension (Fig. 501) is put on for a similar period. This can be relaxed daily for exercises. At the end of ten to sixteen weeks a walking caliper is supplied. This is worn for six months.

In very old patients even this degree of fixation is undesirable, and it is safer from the point of view of unwanted complications to give the patient a boot as shewn in Fig. 480, but leave the leg otherwise free in bed. After a week or two the patient is gently sat out of bed, but the same precautions about weight bearing are used as in other methods.

In unimpacted fractures with displacement the treatment is



FIG 488 Peritrochanteric fracture of the femur with a long spicule involving the lesser trochanter running down the shaft. This shows well the usual coxa vara present

of no account in these fractures to be taken into consideration. A few cases will occur in which on account of the desirability of early activity for the patient and the suitability of the fracture, a nail can be well employed.

FRUIN NAIL WITH PLATE. In an endeavour to overcome the technical difficulties of using a nail alone, a plate along the outer surface of the femur to which the nail is attached has been used. By this method the relation of the neck to the shaft is strongly controlled however comminuted the great trochanter. Early exercises can thus be commenced, with advantages in the old comparable to those from the use of the nail alone in fractures of the neck of the femur. The surgical procedure is a little more extensive, but in selected cases the results are excellent (Fig. 490).

Fractures of the great trochanter. In the young, fractures tend to occur at the epiphyseal line. They may be due to direct violence or to the pull of the gluteus medius and the gluteus minimus. In adults the fracture is more commonly combined with a peritrochanteric fracture. Characteristically there is local pain and swelling but the patient can put the affected leg to the ground. He is, however, unable to raise the good leg from the floor. The displacement is as a rule small and requires no reduction, but if marked the leg is treated in full abduction. Union is rapid and there is no disability.

Fractures of the lesser trochanter. These are due to the muscular pull of the ilio-psoas, and in the young take the form of an epiphyseal separation. Ninety per cent of the cases occur in adolescence. The patient is characteristically unable to flex the thigh further when in a sitting position. There is local pain and bruising, and pain on hyper extension of the thigh. The fragment is displaced upwards and the only possibility of reducing it is to flex the leg. This may be maintained by a plaster spica. Unless the displacement is gross this is not worth while, the fragment uniting rapidly and producing no disability (Figs. 490a and b).

Separation of the epiphysis for the head of the femur. It is necessary to include the description of this lesion here because of



FIG. 490 Fruin nail and plate for subtrochanteric and peritrochanteric fractures. (G. K. McKee.)

similar, a greater weight being required to reduce the fracture and retain it. Usually about a seventh of the body weight suffices. The femoral pin is recommended as it does not pull through the knee, which may become strained by a long pull through the tibial tuberosity, and the rotation of the femur can be better controlled. It also allows greater freedom of the movements of the knee. Counter traction is obtained in the usual way by elevating the lower end of the bed. This is maintained for four to six weeks, and after this Unna's paste extension with a lower weight substituted. At the end of eight to ten weeks in the young and ten to sixteen weeks in the old a walking calliper is fitted and worn for four to six months.

THE WELL LEG TRACTION SPLINT The principle of this splint depends on turning the sound leg into a solid rod by a plaster




FIG 489 The Well leg traction splint. A Pelvis tilted on the injured side. B Ptertrochanteric fracture. C Short plaster below the knee including the pin inserted through the lower end of the tibia. D Steinmann's pin. E Hinged cross bar. F Tightening screw. G Long thigh plaster to fix knee on the unaffected side. The fulcrum of the lever is firmly attached to the sole of this plaster.

applied from the thigh down to the toes. By incorporating a swivel at the foot to which a lever is fixed, and attaching the other end of this to the injured limb by means of a pin in the lower end of the tibia, extension can be applied to the injured limb. The pelvis tilts first so that the sound leg is adducted and the injured leg is abducted. When this reaches a maximum the injured leg is extended. The fracture is thus adequately reduced and immobilised. The advantage of the apparatus is that the patient can be easily moved, and can sit up immediately. Its disadvantages are the fixation of both knees and the development of pressure points in the plaster. It is not used extensively.

WHITMAN'S PLASTER This does not prevent corns developing even if the leg is well abducted and so has been abandoned in favour of traction. (For other disadvantages see p. 456.)

SMITH PETERSEN NAIL The advantages of nailing in fracture of the neck of the bone would be of value in fractures of the trochanter but there are certain difficulties

in its use. Firstly, the trochanter is likely to be comminuted and so is unsuitable to drive a nail through. In uncomminuted cases the nail may produce comminution. There is not the risk

its undoubted association with trauma. Cases may be divided into the following groups:

- 1 With a story of pain in the hip over a long period, followed by the development of a limp
- 2 Story of pain over a period followed by pronounced symptoms after moderate injury, or slight injury
- 3 No story of pain, the condition occurring suddenly as the result of severe trauma

The last type of case is the most uncommon, and it can be debated whether this lesion is not similar to the others, i.e., the end result of a series of changes in the neck of the femur of developmental, endocrine, or metabolic origin, rather than entirely traumatic. In the cases of slower development there is a frequently associated adiposity, and under development of the sexual characteristics. It occurs more commonly in males (five to two) at the adolescent period. A small percentage of the cases are bilateral.

DIAGNOSIS Acute cases resemble fracture of the neck of the femur, suspicion being aroused by the patient's age. The A.P. radiograph shows the head displaced downwards, so that the upper margin of the neck is continuous with the head of the femur, and the head forms a sickle-shaped protuberance on the lower side of the neck, which thus no longer shows the smooth curve continuous with the curve of the upper margin of the obturator foramen (Shenton's line). In subacute cases callus may be seen on the under surface of the neck. The changes in the head seen in Perthes's disease do not occur. In later years the hip may develop osteoarthritis.

TREATMENT In acute and in subacute cases of short standing an attempt to reduce the displacement must be made. According to Mau, if the displacement has existed for more than four weeks it will be impossible. Traction is made with a pin in the femur, and both legs abducted on Braun's splints, the bed being raised for counter-traction. A weight up to 30 lbs. may be used, which is decreased as soon as reduction has occurred, to one-seventh the body weight. This traction is maintained for eight to twelve weeks. Owing to the fact that incision of the foot produces apparent reduction in the radiograph, the importance of lateral films to establish complete reduction must be emphasised. The patient is then fitted with a walking calliper, which is worn for eight to twelve months. We prefer traction to treatment with a plaster spica in abduction, which does not abolish muscle spasm. The treatment of old standing cases is not the province of this book, but resembles that of the ununited femoral neck. Either a Lorenz osteotomy or an arthrodesis may be carried out. Open operation to restore the head is unsatisfactory.



FIG 490a Avulsion of the secondary centre for attachment of the ilio psoas



FIG 490b View of the opposite limb for comparison



FIG. 493 Slipped femoral epiphyses. The epiphysis on the right has slipped and not been restored. The epiphysis on the left has only recently slipped. The sickle shaped projection of the shadow of the head of the femur over Shenton's line can be seen more marked on the left than the right.



FIG. 494 Same case as in previous figure after skeletal traction with the legs abducted. The head is restored to almost normal position and Shenton's line reconstituted. For complete confirmation of this a lateral radiograph is required.

Fractures of the Shaft of the Femur

Thus, the largest long bone in the body, is subject to fractures of the same varieties as the other long bones, transverse, oblique and comminuted, with the disabilities attendant on each one. It combines with these, however, difficulties peculiar to itself, which are due largely to the huge muscle bulk surrounding the bone.

1 The large hæmatoma distends the fascial envelope of the thigh and prevents erection being effective for the first few days.

2 The muscle bulk prevents control of the fractured ends of the bones by lateral splintage for the first few weeks.

3 When the thigh has wasted from disuse, and only then, is plaster an effective method of control of the fracture.




FIG. 491 Distension of the inelastic fascial envelope of the thigh by blood prevents full reduction of a fracture of the femur. (After Charnley)




FIG. 492 After dispersion of the hematoma and wasting of the thigh muscles, over-extension is readily produced by the same weight.

The fracturing of such a heavy bone requires great violence, and so injuries to the soft tissues are common and may interfere with treatment. The displacements of the bone ends from the force, the spasm of muscle and leverage of the leg may be very great, and tend to produce a large hæmatoma in the quadriceps with later fibrosis and stiffness of the knee. To maintain reduction against the muscle tone which differs from the tone in muscles elsewhere in being of postural origin requires considerable weight, with the resultant risk of over-extension and non union. Any attempt to produce correction of the lateral or antero posterior displacement of the fragments by pressure pads is offset by the cushioning actions of the muscles and fat which are displaced more than the bone ends.

In young patients these difficulties are minimal, in old, fat patients they may be almost insurmountable.

The fracturing force may be direct or indirect. The displacement in all cases is principally shortening, but in fractures high in the shaft the pull of the iliopsoas is more effective and flexes the upper fragment, while in fracture in the lower third the tension of the gastrocnemius tends to rotate the lower fragment posteriorly.

DIAGNOSIS. These cases present all the classical features of fracture, often in an acute form, and no difficulty is given except in the case of an incomplete fracture of the shaft or fracture of a process. In these cases following injury there is persistent pain in the thigh following by bruising but there is little swelling. An X ray in one plane may overlook the fracture which may be oblique or spiral. An X ray in both planes will generally demonstrate the lesion and is essential in all cases.

Fractures of the shaft of the femur fall into three great groups each presenting particular difficulties. These are—

- 1 Fractures of the shaft of the bone in the middle third
- 2 Fractures of the upper third of the shaft (subtrochanteric fractures)
- 3 Fractures of the lower third of the shaft

Spiral or oblique fractures at these levels seldom cause trouble. It is the displaced transverse fracture or comminuted fracture which is so difficult to control.

It will be convenient to discuss the general methods of treatment which are available first, as these may be applicable to fractures in all three sites and then the special treatment available for fractures of the upper and lower thirds which present peculiar difficulties.

Methods of Treatment of Fractures of the Shaft of the Femur

- 1 Fixed traction
- 2 Continuous traction
- 3 Manipulative reduction and plaster fixation
- 4 Open operation and fixation
- 5 Combinations of these methods

All these methods have a place in treatment. We may commence by saying that as an emergency measure treatment by traction is most satisfactory as it requires little disturbance, and does not increase the shock. Under intravenous anæsthesia a wire is inserted in the tibial tuberosity or the lower end of the femur. Unless the fracture is in the lower third of the femur a pin above the knee is to be preferred for the same reasons as govern the choice of that site in pertrochanteric fractures. The risk of infecting the hæmatoma

ligamentous tension if retained too long. It is obvious that traction cannot be exerted on the ligaments when the shift is broken and that all traction is opposed by the muscles. Only when there is some bony or strong fibrous adhesions does the traction pull through the




FIG 496 Traction on the tibia in the early stages does not produce traction on the ligaments of the knee joint but separates the fracture. A Direction of traction B Fully developed quadriceps C Fracture hematoma D Joint space (After Charney)




FIG 497 When the fracture has united and the muscles wasted traction produces a pull on the ligaments of the knee joint. A Direction of traction B Wasted quadriceps C Increased joint space




FIG 498 Traction on the leg in a Thomas splint. The correct arrangement of forces. Note how the pad behind the knee produces a stable triangulation of forces as well as maintaining the anterior bowing of the femur

ligaments of the knee (Figs 496, 497). If the fracture is accompanied by a large hematoma and the fascial sheath of the thigh is distended traction of any kind is ineffective in the first few days. As the hematoma resolves it becomes effective in separating the

in fractures of the lower third is too great for a pin or wire to be used

Preliminary treatment by light traction is to be recommended whether it is to be continued or not, as it allows time for the swelling to subside, time for recovery from shock and for accurate diagnosis and deliberation. In combating the shock of the original injury the value of novocaine injected into the hæmatoma is not to be forgotten. Shock may be severe in old people, and novocaine infiltration is easy and particularly effective in these cases.

If continuous or fixed traction is to be employed the use of a skeleton splint to support the leg is necessary. Either the Thomas



FIG. 495. Fracture of the femur treated by skeletal traction in the femur and skin traction on the leg supported on a Thomas splint with knee flexion piece.

splint or the Braun's splint may be employed. The Thomas splint is more adaptable, and may be used straight, with the end attached to the foot rail of the bed or slung from pulleys from an overhead beam of a Balkan frame or a Pearson's bed. The slung Thomas is to be recommended for general use, as it allows the patient much greater freedom of movement in bed without disturbing the fracture, and, as he recovers, a far greater range of exercises. The Thomas splint may be employed bent at the knee or with a knee flexion piece, if flexion at the knee is desirable.

Traction. This in itself is insufficient to immobilise any fracture of the femur, however strongly it is applied. In all compound fractures its use alone is to be avoided except as an aid to reduction and stability at the time of operation. It has the further disadvantage of tending to over-distract and of damaging the knee by

two point suspension of the limb to produce stability, and a third force must be employed. This is provided by a large pad behind the knee, which by flexing the knee against gravity and muscle tension, stabilises the system (Fig. 498). It is, however, essential if fixed



FIG. 501. Fracture of the shaft of the femur in a late stage under skin traction with Unna's paste. Traction applied in the direction of the femoral shaft and of the leg. Stockinette over the foot with a weight attached is used to prevent foot drop.

traction is to be effective that the fracture be reduced first. If the thigh is distended with blood this is impossible in the first few days and treatment with continuous traction is indicated. If reduction



FIG. 502. Same case as in the previous figure but with the Braun's splint removed for exercises over the knee exercise bar.

is possible the reduced femur is put up by fixed traction and then should maintain itself, with but slight adjustments. (Compare application of fixed traction in transport plasters, p. 133.)

Continuous Traction. The elaboration of continuous traction is

bone ends and, as the muscles of the thigh waste, more effective through lack of opposition (Fig 492) It is obvious that gradual reduction of such a fracture by continuous traction is the only satisfactory method of treating such cases. If fixed traction is used it is ineffective to begin with and when the hematoma has suffi-




FIG 499 Method of retaining a fracture of the femur in position using a skeletal pin and fixed traction. A plaster may be used at the same time to control a fracture of the leg. (After Charnley.)

ciently diminished soft tissue adhesions may make restoration of full length difficult.

FIXED TRACTION The method of fixed traction as devised by H. O. Thomas has been undesirably abused by the partisans of skeletal traction. The principle of the method has been misunderstood, and it has been considered as a method of reduction rather than a method of retention. It is a method of fixation, in which the force




FIG 500 Traction on the leg in a Braun's frame or Thomas splint with knee flexion piece. Forces incorrectly balanced. Pad placed under fracture and not below. Traction in the line of the femur must be balanced by traction on the leg in the line of the tibia as in Fig 506 when the Braun's splint is used—or as in Fig 498 when a Thomas splint is used.

of muscular contraction tending to shorten the leg at the site of fracture is opposed by the fixation of the leg (by skin traction in the original method, but often by skeletal traction nowadays) to the lower end of the splint and of the counter pressure exerted by the ring of the Thomas splint on the ischial tuberosity. In a closed system like this only the tone in the muscles can be responsible for maintaining tension, and the resultant pressure on the ring of the Thomas splint cannot be excessive. It may be diminished by elevating the foot of the bed. It is, however, insufficient to rely on

The forces engaged in the system are governed by the weights applied and excite a corresponding tension in the muscles and soft tissues around the fracture site. To commence with they may be exerted in compressing the hematoma in the muscles if this is large. As it subsides the pull is opposed by the muscles, and finally as these waste, and the soft tissues around the bones become more organised, the pull is transmitted through the ligaments and bone of the limb. It follows that with all these variable factors the weight employed has to be carefully calculated and continually adjusted. If no hematoma is present—due perhaps to the wound being an open one, a weight of 10 lbs. may be sufficient from the beginning. On the



FIG. 404. Fracture of the shaft of the femur under skeletal traction in the tuberosity of the tibia combined with skin traction on the leg.

other hand, in a powerful thigh a weight of 20 to 30 lbs. may be necessary to prevent shortening, and this must be reduced over the first three weeks to 10 to 12 lbs. if over distraction is not to occur.

Satisfactory results may be achieved by either method in experienced hands. While fixed traction corresponds to the ideal of complete immobilisation and is therefore more satisfactory for compound fractures with continuous traction earlier concentration on the quadriceps tone and exercise of the knee joint are possible. The success of treatment of a fractured femur is primarily to be gauged by the function of the knee, and secondarily by the position obtained. There is no evidence to show that early movement of the knee joint delays union of the femur, though the movement at the fracture site in an energetic patient is sometimes alarming. It is certain, however

due to the development of skeletal traction, as the forces employed are more than skin traction can support. For satisfactory continuous traction a resultant force in the line of the femur must be generated, and this necessitates flexing the knee. This may be accomplished on the Braun's frame, on the Thomas splint bent at the knee, or provided with a knee flexion piece, or by the Hamilton Russell method.

It is an unstable system until a third force has been introduced. In the case of the Braun's splint this is provided by skin traction on the leg, which flexes the thigh over a pad above the knee (Fig. 506). A similar pad may be used on the bent Thomas splint. In the Hamilton Russell method the pad behind the knee and the pull on the leg make the system fairly stable if the leg is not excessively




FIG. 503 Oblique fracture of the femur showing its position on a Braun's splint under skeletal traction

flexed (Fig. 511). The disadvantage of the Braun's frame is the lack of fixation of the upper end of the thigh, which is also to be noted in the Hamilton Russell method. The patient is thus afraid to move for fear of hurting himself in the early stages, with increased nursing difficulties, or in the later stages when the fracture is painless is continually altering his alignment. The Thomas splint thus has advantages, if continuous traction is used, over other splints. If slung from the bed and properly balanced it enables the patient to move freely with little disturbance of the fracture. In continuous traction the splint is used as a cradle only and ring pressure should not occur. It is necessary however to make sure that it remains in contact with the tuberosity of the ischium by having the pull of the cord supporting the upper end of the splint running obliquely towards the upper end of the bed.

The forces engaged in the system are governed by the weights applied, and excite a corresponding tension in the muscles and soft tissues around the fracture site. To commence with they may be excited in compressing the hematoma in the muscles if this is large. As it subsides the pull is opposed by the muscles, and finally as these waste, and the soft tissues around the bones become more organised, the pull is transmitted through the ligaments and bone of the limb. It follows that with all these variable factors the weight employed has to be carefully calculated and continually adjusted. If no hematoma is present, due perhaps to the wound being an open one, a weight of 10 lbs. may be sufficient from the beginning. On the



Fig. 201. Fracture of the shaft of the femur under skeletal traction in the tubercity of the tibia combined with skin traction on the leg.

other hand in a powerful thigh a weight of 20 to 30 lbs. may be necessary to prevent shortening, and this must be reduced over the first three weeks to 10 to 12 lbs. if over distraction is not to occur.

Satisfactory results may be achieved by either method in experienced hands. While fixed traction corresponds to the ideal of complete immobilisation and is therefore more satisfactory for compound fractures with continuous traction earlier concentration on the quadriceps tone and exercise of the knee joint are possible. The success of treatment of a fractured femur is primarily to be gauged by the function of the knee, and secondarily by the position obtained. There is no evidence to show that early movement of the knee joint delays union of the femur, though the movement at the fracture site in an energetic patient is sometimes alarming. It is certain, however,

that the adhesions which form a serious block to movement form in the first six weeks, and it is during this period that active use of the quadriceps should be encouraged. If a small free range of knee joint movement has been preserved for this period, subsequent immobilisation will be much less serious in its consequences. Active concentration of the quadriceps and movement of the knee should therefore be




FIG 505 Backward displacement of the lower end of the femur from incorrect positioning of the Braun's splint




FIG 506 The displacement shown in the previous figure corrected by moving the angle of the Braun's splint much nearer the fracture site traction on the leg and a pad behind the knee

encouraged in all methods from the earliest possible moment. In the early stages faradism may help. In the later stages knee bending exercises over a bar may be employed in patients in whom there is some doubt as to the strength of union.

Deformity Five deformities may occur, rotation, lateral displacement, posterior bowing, angulation or shortening. Sufficient has already been said with regard to the control of shortening, which must be checked regularly with radiographs. Measurement is unsatisfactory with the knee flexed.

ROTATION There is a tendency for the upper fragment to be externally rotated. This can be checked by radiographs of the neck of the femur and comparison of position of the inter trochanteric line on the two sides (Figs. 468, 469). The position of the foot can then be arranged to correspond to the degree of external rotation observed. This is seldom a troublesome feature except in fractures of the upper third of the femur.

LATERAL DISALIGNMENT This can be discounted up to three quarters of the width of the bone. If the radiograph in the opposite plane shows sound alignment and the central axes of the shaft remain parallel. Attempts may be made to control it by the use of lateral pressure by slings attached to one of the Thomas splint, or by clamps which attach to the side bars of the splint. If the deformity is gross and persistent it is probable that muscle fibres have become interposed and non union may result.

POSTERIOR BOWING It is most important to correct this and maintain it corrected. The femur has normally quite a marked anterior curvature which must not be lost if knee movements are to be satisfactory. It is maintained by the use of a large pad behind the knee and traction on the leg in the line of the tibia (Figs. 498, 500).

ANGULATION This is difficult to control in some cases, but is a difficulty particularly met with in fractures of the upper and lower third. If troublesome and when it cannot be controlled by slings and pads it is necessary to apply a plaster hip spica. If a satisfactory position is not obtained at first this is wedged under careful radiological control.

Manipulative reduction and plaster fixation The immediate use of a plaster spica may be valuable in compound fractures of the femur, where adequate fixation of both bone and soft tissues is necessary. It can only be applied when the patient can be kept under continuous observation and needs to be done as soon as the swelling of the limb subsides. For this reason a preliminary period on fixed traction, or continuous traction, is usually advisable. The modified transport plaster described on p. 139 deals adequately with this stage. In children who are too old to be slung up by Bryant's method, and in whom stiffness is unlikely to occur, the early application of a plaster spica in which they can get about on crutches is valuable.

Open operation and fixation This method has the advantages of any operative method of treatment, perfect reduction, and early function. In the femur there is a disadvantage which cannot be entirely overcome, namely, the weight of metal which must be inserted, and the subsequent adhesions of the quadriceps when this is done through a wide approach. Perfect reduction is not so



FIG 507 Comminuted fracture of the shaft of the femur with displacement




FIG 508 Antero posterior view of the previous case under treatment showing satisfactory position under traction




FIG 509 Lateral view of the same case showing the satisfactory position in both planes

important in the femur if the alignment of the limb is maintained. For this reason operative treatment should be limited to the cases in which failure to obtain a reasonable position raises the suspicion of interposition of muscle and non-union. The approach used is that of A. K. Henry (Appendix IV) and the plating carried out in



FIG. 509a. An oblique fracture of the shaft of the femur, the type suitable for fixation with the Kuntscher nail. (Mr. David Trevor's case.)

FIG. 509b. The Kuntscher nail in position showing accurate reduction of the fracture. (Mr. David Trevor's case.)

FIG. 509c. Healing of the fracture with the Kuntscher nail still in position showing well-organized deposits of subperiosteal new bone. (Mr. David Trevor's case.)

the usual manner. A bone graft may be used if desired, or if secondary reasons make it likely to be of value. Modifications in which the bone ends are reduced, and only lightly fixed to avoid lateral displacement and shortening, and an external splint relied on to prevent deformity may be used.

KUNTSCHER'S INTRAMEDULLARY NAIL. The use of a larger diameter intramedullary nail is a logical extension of the intramedullary Kirschner wire, and was first employed by Kuntscher in

1941 Its introduction to German surgeons was at first unfavourable, and there are still sharp divisions on its uses and value. The nail, modified by various surgeons, consists of a metallic rod of varying length, triangular or diamond shaped, or even circular on section. Some nails are slightly curved at either end to facilitate their introduction. The nail is introduced through the sites of easy approach to the marrow, such as the radial styloid, the greater tuberosity of the humerus, the great trochanter, and the tibial tuberosity.

There are two methods of using the nail, either reduction can be accomplished manually, and with or without the assistance of radiography the nail can be slid across the fracture site, or open reduction of the fracture can be carried out, and the nail slid across the fracture under direct vision, this entailing a separate incision for its introduction. For its effective use a good selection of nails is necessary varying in both length and diameter, as it is essential that the nail should grip the medullary cavity without jamming. A nail one millimetre smaller than the diameter of the medullary cavity is chosen. Skeletal traction may be used to reduce the fracture, and some surgeons prefer to use screening. In the tibia and the femur a guide may be used to facilitate the introduction of the nail. Accurate reduction of the fracture, is the primary basis of easy and successful nailing. External support of some type is employed in most cases. There is a slight risk of fat embolism in elderly people. Technical difficulties may arise from fracture of the nail, bending of the nail, penetration of the cortex, and distraction of the fragments. The strength of union is difficult to gauge with the nail in position.

Experience with the nail suggests that it is a useful addition to the surgical armoury for certain fractures, notably the transverse fractures of the shaft of the femur, with deformity. The difficult fracture below the lesser trochanter with cocking up of the short proximal fragment is easily controlled. The nearer the fracture to the knee, the less suitable the method. Fractures of the tibia may also be readily dealt with but these are satisfactorily controlled by the methods already available. For the upper extremity the method is a little clumsy. Closed introduction is best, but where closed reduction can be achieved further treatment is often unnecessary. In open reductions the advantage of a smaller wound over the fracture is offset to a slight extent by the additional incision for introduction of the nail. Full assessment of the nail is dependent on its more general use.

COMBINATIONS OF METHODS The method employed must be adapted to suit the case. A combination of methods is frequently useful. Thus to commence with a period of continuous skeletal traction may be used. At the end of three weeks this may be changed

to have traction or more probably the continuous traction under reduced weights will continue and active quadriceps and knee exercises practised. If union is progressing satisfactorily, but there is some angulation which it is desirable to correct, a hip spica may be applied at this time and the patient got up on crutches. At the end of twelve weeks this is removed and in the average case clinical union will have taken place. The question of weight bearing then arises. An attempt to gauge the strength of union should be made. If considered firm a week's non weight bearing exercises may be given in bed and the condition of the limb observed. If satisfactory, weight bearing on crutches may be allowed. If unsatisfactory union is present the provision of a calliper may be considered. This enables earlier weight bearing to be permitted at the same time that knee exercises are continued. In other cases where union is sound and in good position at the end of the tenth week, a plaster walking calliper may be made. This has the disadvantage of preventing knee exercises, but if a reasonable degree of knee mobility has been returned this is not a serious matter. It enables the patient to get about earlier and at the end of the fourteenth week the femur is soundly enough united to permit unsupported weight bearing.

Fractures of the upper third of the femoral shaft (Subtrochanteric fractures) These fractures are peculiarly difficult because of the flexion and external rotation which may occur in the upper fragment. Alignment is not achieved by nursing the patient with increased flexion of the thigh in most cases. The upper end may be controlled by a Kirschner wire passed in an antero posterior direction through the great trochanter. The limb may then be aligned under radiographic control and the whole limb including the wire incorporated in a hip spica. The alternative method is open operation which in this region well away from the knee is not such a serious matter.

Fractures of the lower third of the femoral shaft (Supracondylar fractures) This fracture is commonly transverse and shows posterior displacement of the lower fragment. This displacement is not due to the pull of the gastrocnemius, as usually described, but to the pull of the quadriceps, which tends to push the femoral condyles backwards out of the way. It is consequently difficult to reduce and maintain reduction. Reduction can nearly always be accomplished by turning the patient over on his face and suspending the foot from the ceiling. The knee is thus flexed at right angles. Slight traction is applied to the tibial tuberosity. Digital control of the fragments can then usually be obtained and the limb incorporated in plaster, with the knee flexed. Nursing is easy if the limb is

1941 Its introduction to German surgeons was at first unfavourable, and there are still sharp divisions on its uses and value. The nail, modified by various surgeons, consists of a metallic rod of varying length, triangular or diamond shaped, or even circular on section. Some nails are slightly curved at either end to facilitate their introduction. The nail is introduced through the sites of easy approach to the marrow, such as the radial styloid, the greater tuberosity of the humerus, the great trochanter, and the tibial tuberosity.

There are two methods of using the nail, either reduction can be accomplished manually, and with or without the assistance of radiography the nail can be slid across the fracture site, or open reduction of the fracture can be carried out, and the nail slid across the fracture under direct vision, thus entailing a separate incision for its introduction. For its effective use a good selection of nails is necessary varying in both length and diameter, as it is essential that the nail should grip the medullary cavity without jamming. A nail one millimetre smaller than the diameter of the medullary cavity is chosen. Skeletal traction may be used to reduce the fracture, and some surgeons prefer to use screening. In the tibia and the femur a guide may be used to facilitate the introduction of the nail. Accurate reduction of the fracture, is the primary basis of easy and successful nailing. External support of some type is employed in most cases. There is a slight risk of fat embolism in elderly people. Technical difficulties may arise from fracture of the nail, bending of the nail, penetration of the cortex, and distraction of the fragments. The strength of union is difficult to gauge with the nail in position.

Experience with the nail suggests that it is a useful addition to the surgical armoury for certain fractures notably the transverse fractures of the shaft of the femur, with deformity. The difficult fracture below the lesser trochanter, with cocking up of the short proximal fragment, is easily controlled. The nearer the fracture to the knee, the less suitable the method. Fractures of the tibia may also be readily dealt with, but these are satisfactorily controlled by the methods already available. For the upper extremity the method is a little clumsy. Closed introduction is best, but where closed reduction can be achieved further treatment is often unnecessary. In open reductions the advantage of a smaller wound over the fracture is offset to a slight extent by the additional incision for introduction of the nail. Full assessment of the nail is dependent on its more general use.

COMBINATIONS OF METHODS The method employed must be adapted to suit the case. A combination of methods is frequently useful. Thus to commence with a period of continuous skeletal traction may be used. At the end of three weeks this may be changed

to fixed traction, or more probably the continuous traction under reduced weights will continue and active quadriceps and knee exercises practised. If union is progressing satisfactorily, but there is some angulation which it is desirable to correct, a hip spica may be applied at this time and the patient got up on crutches. At the end of twelve weeks this is removed and in the average case clinical union will have taken place. The question of weight bearing then arises. An attempt to gauge the strength of union should be made. If considered firm a week's non-weight bearing exercises may be given in bed and the condition of the limb observed. If satisfactory, weight bearing on crutches may be allowed. If unsatisfactory union is present the provision of a calliper may be considered. This enables earlier weight bearing to be permitted at the same time that knee exercises are continued. In other cases where union is sound and in good position at the end of the tenth week, a plaster walking calliper may be made. This has the disadvantage of preventing knee exercises, but if a reasonable degree of knee mobility has been retained this is not a serious matter. It enables the patient to get about earlier and at the end of the fourteenth week the femur is soundly enough united to permit unsupported weight bearing.

Fractures of the upper third of the femoral shaft (Subtrochanteric fractures) These fractures are peculiarly difficult because of the flexion and external rotation which may occur in the upper fragment. Alignment is not achieved by nursing the patient with increased flexion of the thigh in most cases. The upper end may be controlled by a Kirschner wire passed in an antero-posterior direction through the great trochanter. The limb may then be aligned under radiographic control, and the whole limb including the wire incorporated in a hip spica. The alternative method is open operation, which in this region well away from the knee is not such a serious matter.

Fractures of the lower third of the femoral shaft (Supracondylar fractures) This fracture is commonly transverse and shows posterior displacement of the lower fragment. This displacement is not due to the pull of the gastrocnemius, as usually described, but to the pull of the quadriceps, which tends to push the femoral condyles backwards out of the way. It is consequently difficult to reduce and maintain reduction. Reduction can nearly always be accomplished by turning the patient over on his face and suspending the foot from the ceiling. The knee is thus flexed at right angles. Slight traction is applied to the tibial tuberosity. Digital control of the fragments can then usually be obtained and the limb incorporated in plaster, with the knee flexed. Nursing is easy if the limb is

1941 Its introduction to German surgeons was at first unfavourable, and there are still sharp divisions on its uses and value. The nail, modified by various surgeons, consists of a metallic rod of varying length, triangular or diamond shaped, or even circular on section. Some nails are slightly curved at either end to facilitate their introduction. The nail is introduced through the sites of easy approach to the marrow, such as the radial styloid, the greater tuberosity of the humerus, the great trochanter, and the tibial tuberosity.

There are two methods of using the nail, either reduction can be accomplished manually, and with or without the assistance of radiography the nail can be slid across the fracture site, or open reduction of the fracture can be carried out, and the nail slid across the fracture under direct vision, this entailing a separate incision for its introduction. For its effective use a good selection of nails is necessary, varying in both length and diameter, as it is essential that the nail should grip the medullary cavity without jamming. A nail one millimetre smaller than the diameter of the medullary cavity is chosen. Skeletal traction may be used to reduce the fracture, and some surgeons prefer to use screening. In the tibia and the femur a guide may be used to facilitate the introduction of the nail. Accurate reduction of the fracture, is the primary basis of easy and successful nailing. External support of some type is employed in most cases. There is a slight risk of fat embolism in elderly people. Technical difficulties may arise from fracture of the nail, bending of the nail, penetration of the cortex and distraction of the fragments. The strength of union is difficult to gauge with the nail in position.

Experience with the nail suggests that it is a useful addition to the surgical armoury for certain fractures notably the transverse fractures of the shaft of the femur with deformity. The difficult fracture below the lesser trochanter with cocking up of the short proximal fragment, is easily controlled. The nearer the fracture to the knee, the less suitable the method. Fractures of the tibia may also be readily dealt with, but these are satisfactorily controlled by the methods already available. For the upper extremity the method is a little clumsy. Closed introduction is best but where closed reduction can be achieved further treatment is often unnecessary. In open reductions the advantage of a smaller wound over the fracture is offset to a slight extent by the additional incision for introduction of the nail. Full assessment of the nail is dependent on its more general use.

COMBINATIONS OF METHODS The method employed must be adapted to suit the case. A combination of methods is frequently useful. Thus to commence with a period of continuous skeletal traction may be used. At the end of three weeks this may be changed



FIG. 110 Treatment of fracture of the femur in a child
Bryant's method




FIG. 111 The principles of the Hamilton Russell method of traction on the femur A Pulleys B Balkan frame C Direction of the resultant pull D Mattress

loss from damage to the deep femoral vessels. Wound excision is practised according to the usual principles, and care is taken to see that there is an adequate opening in the fascia by transverse incision

allowed to hang over the side of the bed. A disadvantage of this method is the fact that should the quadriceps become adherent to the fracture, it becomes adherent in extension of the knee and it cannot be freed by manipulative methods. This is a more theoretical than practical objection if the prepatellar pouch has not been grossly damaged. In order to avoid a possibility of trouble the knee should be gradually straightened on a Thomas splint as soon as sufficient new bone has occurred around the fracture, somewhere between the fourth and sixth weeks. Active quadriceps exercises are encouraged from the beginning.

Open operation on such cases is technically difficult owing to the difficulties of a posterior approach, but may be carried out in exceptional circumstances.

Fractures of the Femur in Children 1 *Bryant's method* This is the method of choice for very young children. Strapping or Unna's paste extension is applied from thighs to ankles of both legs, which because of the greater skin area available and the lighter weight of the body is quite efficient. Both legs are then held vertically by weights attached to cords passing over pulleys on a Balkan beam, and are so balanced that the buttocks are just off the bed. The child soon adapts himself to this position and the femur automatically pulls out into a good position. Union is rapid in children and at the end of three to four weeks the child can be allowed to lie in bed and weight bearing allowed at the end of six weeks.

2 *Hamilton Russell method* This makes use of the resultant of a force acting under the knee in a vertical direction, and one acting along the line of the horizontal leg. If the knee is slightly flexed this resultant corresponds to the line of the femur. Considerable extension may thus be exerted, but there is little control of sagging, or lateral movement. It may be a useful temporary measure, the details of which are apparent from the diagram.

Hamilton Russell's method may be used successfully in adults. By making the direction of pull on the sling behind the knee a little more oblique towards the head the posterior bowing of the leg may be corrected. The system does not provide firm fixation for the femur, but allows early exercises to be carried out.

Compound Fractures of the Femur

These present certain special difficulties, due in part to the difficulties of immobilisation of the femur, and in part to the depth of tissue surrounding the bone, and the strong fascial intermuscular planes. Shock in the early stages may be pronounced, as may blood

fractures of the lower end of the femur Infection of the blood clot is liable to occur

6 The use of a traction stirrup in which the pin cannot rotate The movement of the pin encourages infection

7 The use of too small traction weights The weight should commence with one seventh of the body weight and be increased in the next few hours to 25 to 30 lbs

8 The use of too great a traction weight As soon as reduction has occurred the weight is again reduced to one seventh the body weight

9 Failure to raise the lower end of the bed to get adequate counter extension

10 Failure to use a foot rest against the lower end of the bed, the patient thus being unable to use his sound leg to raise himself or maintain his position on the splint (Fig 505)

11 Failure to have a bar over the patient's head which he can grip to raise himself

12 Failure to apply traction to the foot which results in foot drop (see Figs 501 550)

13 Neglect of exercises General exercises are carried out as soon as possible, and at the end of the third or fourth week exercises of the injured limb are commenced

14 The use of traction below the knee for too long a period, i.e., over four weeks, which stretches the capsule of the knee

15 Failure to fix the Braun's splint to the bed so that it slides down to the end of the bed

Fractures of the Lower End of the Femur

1 Separation of the lower epiphysis

2 T shaped fractures into the joint

3 Separation of the lateral or medial condyle alone

4 Separation of part of a condyle

Separation of the lower femoral epiphysis The lesion may occur between the ages of eight and eighteen, and is due to a hyper-extension strain on the joint The epiphysis is displaced forwards, with resultant pressure of the lower end of the femur into the popliteal space and possible damage to vessels Partial obstruction of the popliteal artery is inevitable, and may lead to gangrene of the leg if the fracture is not reduced in reasonable time The fracture line is intra articular anteriorly and the knee becomes distended with blood It is rarely compound

DIAGNOSIS The end of the femoral shaft may be palpated in the popliteal space The ridge of the displaced epiphysis may be palpated above the patella, and the anterior displacement of the

Drainage is made dependent if possible, as pus tends to track up towards the hip joint even if there is an adequate opening anteriorly. Postero lateral incision in front of the lateral intermuscular septum is safe and satisfactory for drainage.

Immobilisation is by a complete leg plaster attached to a Thomas splint by two cuffs of plaster (Fig 512), or a "Tobruk" plaster (p 139). The Thomas splint may then be slung up in the usual manner, giving the patient much more freedom of movement in the bed. For wounds of the upper third of the thigh a plaster hip spica extending to the knee may be useful and the immobilisation of the leg carried out by putting a Thomas splint over the thigh plaster and attaching it by plaster cuffs. The leg is then rested in slings in the usual manner and the foot supported by a foot piece at right angles to the leg.



FIG 512 Complete leg plaster fully split and attached to Thomas splint by a double plaster cuff. Skin traction below plaster and separated from the plaster by a layer of cotton wool. One variety of transport plaster.

Where continuous supervision of a case is not possible the points discussed under transport plasters must be borne in mind (p 138).

Summary It will be seen that the choice of treatment for a fracture of the femur is wide, and depends not only on the points discussed, but to a lesser extent on the type of fracture. Transverse fractures, which can be easily opposed end to end, are more conveniently treated by fixed extension, while oblique and comminuted fractures may respond better to continuous traction. In any form of treatment care and attention to detail is important, and common errors in treatment of fractures by continuous traction on a Braun's splint, as summed up by Bohler, may conveniently close the subject.

- 1 Failure to use local anaesthesia in period of shock
- 2 Failure to use antero posterior and lateral radiographs
- 3 The use of a bed without fracture boards
- 4 The use of a badly bandaged Braun's splint
- 5 The use of skeletal traction wires or pins above the knee

pulative methods. The degree of damage to the condyles however may not make it worth while attempting a more perfect reduction. Should the condyle fractured be intact and separated by a single fissure, operative reduction and screwing of the fragment back into position is desirable. To do this opening of the knee joint may be unavoidable, but this is not to be feared provided the operative conditions are good.

FRACTURES OF PART OF A CONDYLE These fractures are uncommon, but the posterior half of a condyle may be fractured into the inter condylar notch and lie free in the joint. Other smaller fragments may be broken off and be loose. They should be removed by open operation and the knee treated in a similar manner to that following meniscectomy, that is to say, early movements should be encouraged to avoid stiffness at the knee joint.

Small fractures of the condylar surface make up a proportion of the cases of internal derangement of the knee, and it is probable that the incomplete separation of a flake of bone and cartilage is responsible for the condition of osteochondritis dissecans of the knee.

REFERENCES

General

- RUSSELL, R. HAMILTON "Fracture of the Femur, A Clinical Study," *Brit J Surg*, 1923-24, 11, 491
- LEA and VEAL "The Russell Extension Method in the Treatment of Fractures of the Femur," *Surg Gynæ and Obstets*, 1921, 32, 527
- KINO, T. "The Closed Operation for Intracapsular Fracture of the Neck of the Femur," *Brit J Surg*, 1939, 26, 721
- WATSON JONES "Fractures of the Neck of the Femur," *Brit J Surg*, 1936 23, 787
- HENBY and BAYUMI "Fracture of the Femur with Luxation of the Ipsilateral Hip," *Brit J Surg*, 1934 22, 204
- LEADBETTER "A Treatment for Fracture of the Neck of the Femur," *J Bone and Joint Surg* 1933 15, 526 1938 20, 108
- SVEN JOHANSEN "Operative Treatment and Results in Fracture of the Neck of the Femur," *Brit M J* 1937, 2, 361
- SANTOS "Changes in the Head of the Femur after Complete Intracapsular Fracture of the Neck," *Arch Surg* 1930, 21, 470
- WHITMAN R. "The Abduction Treatment of Fracture of the Neck of the Femur," *Surg Gynæ and Obstets* 1918 27, 578
- SPEED KELLOG "An Analysis of the Results of Treatment of Fractures of the Femoral Diaphysis in Children under Twelve Years of Age," *Surg Gynæ and Obstets* 1921 32, 527
- CHARNLEY J. "Fractures of the Femoral Shaft: Mechanics of Reduction and Fixation," *Lancet* 1944 2, 235
- BRUNNER W. "Unsere Erfahrungen Mit Der Marknagelung Nach Kuntzsch," *Zeit F Unfallmed U Berufskrank* 1947 40 103-120
- MACAULAND W R. "Medullary Nailing of Fractures of the Long Bones," *Surg Gynæ and Obstets* 1947 84 85-89
- BOYD, H B AND GEORGE I L. "Complications of Fractures of the Neck of the Femur," *J Bone and Joint Surg* 1947 29 13-18

whole of the leg in relation to the femoral shaft may be obvious. The adductor tubercle is not altered in level as in supracondylar fractures, as it is attached to the diaphysis.

Swelling usually makes this point difficult to determine.




FIG 513A Fracture of the medial condyle of the femur. Upward displacement associated with adduction of the leg.

FIG 513B The correction of this displacement shown in the previous figure by adduction of the leg at the knee.

TREATMENT Reduction is made as soon as possible by traction, combined with antero-posterior pressure on the fragment. Following reduction the knee is fully flexed to settle the epiphysis into position. Retention may be difficult, but is best obtained by flexing the knee to 90° and fixing it in a plaster spica. This is applied with the patient on his face and the foot held with the sole uppermost. It is maintained for four weeks and then the limb gradually straightened. Weight bearing is allowed at the end of eight weeks. There is no interference with growth if the separation is correctly reduced.

Fractures of a single condyle These are due to forced abduction and adduction movements of the knee, rarely to direct

violence. Fracture of the medial condyle is brought about by adduction. Less commonly this produces a ligament traction fracture at the insertion of the external collateral ligament of the knee into the condyle. A similar lesion can occur with the internal collateral ligament in forced abduction. For ligament traction fractures a resting plaster from thigh to ankle, in which the patient can walk (Fig 127), is required for three to four weeks.

In the more extensive injury the whole condyle is separated, the fracture line running through the intercondylar notch. The condyle may be pushed up to some extent, less commonly rotated, or, if the foot is displaced, it may be pulled down. The knee is distended with blood which should be aspirated before reduction is attempted.

REDUCTION The collateral ligaments remain attached to the condyles, and so forced abduction or adduction of the leg may be made to pull the condyle down into position. Compression is rarely required. For correct observation of these fractures the Braun's splint is unsuitable as the flexed knee destroys to some extent the value of the antero-posterior X-ray control, and also masks abduction or adduction of the leg. A Thomas splint will be found more satisfactory. Perfect reduction is rarely accomplished by mani-

CHAPTER XXVIII

FRACTURES OF THE PATELLA

Surgical anatomy The patella is to be regarded as a sesamoid bone in the tendon of the quadriceps. In spite of the statement by Brooke that the patella is either absent or vestigial in the faster moving quadrupeds, and is, therefore, "phylogenetically inherited and its presence is not determined by function," we believe that it serves three useful purposes. It protects the articular surface of the femur in flexion of the knee, it takes some of the frictional strain on the ligamentum patellæ, and by holding the ligament away from the anterior surface of the femur increases the efficiency of the quadriceps in the last stages of extension.

Development The patella is ossified from one centre as a rule, but occasionally there may be separate centres for the upper and outer portions of the bone. These are usually bilateral, and are not to be confused with fracture (Fig. 521).

Fractures of the patella are a particularly good example of the fact that the fracture is often a guide to the soft tissue injury, which is the most important injury in the majority of fractures and of paramount importance in this case. The principal factor with which we are concerned is the quadriceps expansion, and whether it is intact or not. The patella lies within this, being in, but yet not of

The quadriceps insertion and its expansion which form the extensor mechanism of the knee, may be ruptured at various levels. The attachment of the muscle may be pulled from the upper margin of the bone, and this may be indicated later by the formation of new bone in this area. The transverse fracture near the centre of the bone due to muscular violence is accompanied by ruptures of the fibrous expansion of the muscle on either side. Fractures of the lower pole of the bone at the attachment of the ligamentum patellæ are also sometimes accompanied by a similar rupture, though they often occur without displacement. Finally fractures of the tibia around the insertion of the muscle complete the series of injuries to which the expansion is liable.

Fractures unassociated with damage to the extensor mechanism are due to direct violence, and consist of single chips from the margins of the bone, multiple fissures, or gross comminution of the bone. It must not be forgotten that damage to the femoral surface



FIG. 514. Fracture of the patella by muscular violence. The patella is broken over the lower surface of the femur.

Slipped Epiphysis

- McCAUSLAND, A R "Separation of the Capital Femoral Epiphysis," *J Bone and Joint Surg*, 1935, 17, 353
- WARDLE, E N "Etiology and Treatment of Slipped Epiphysis of the Head of the Femur" *Brit J Surg*, 1933-34, 21, 313
- KEY "Epiphyseal Coxa Vara," *J Bone and Joint Surg*, 1926, 8, 53 (Full summary with extensive references)
- MILCH "Epiphysiolysis or Epiphysal Coxa Anteverta," *J Bone and Joint Surg*, 1937, 19, 97
- POMERANZ and SLOANE "Slipping of the Proxima Femoral Epiphysis," *Arch Surg*, 1935 30 607
- MAU "Zur Frage der Reposition der traumatischen Epiphysenlösung an Oberschenkelhals," *Arch f Orthop u Unfall Chir* 1926-27, 24, 52
- WILSON "The Treatment of Slipping of the Upper Femoral Epiphysis with Minimal Displacement," *J Bone and Joint Surg* 1938, 20, 379 (Recommending Smith Petersen Nail)

Nailing Operations Various Techniques

- HEX GROVES "Modern Treatment and Results of Treatment of Fracture of the Neck of the Femur," *Brit M J*, 1937, 2, 359
- BAILLY, E T "Treatment of Fracture of the Neck of the Femur," *Lancet* 1937, 1, 375
- SMITH PETERSEN "Treatment of Fractures of the Neck of the Femur by Internal Fixation," *Surg Gynec and Obstets* 1937, 64, 287
- ENOEL and MAY "Two Plane Direction Finder for Nailing Fractures of the Neck of the Femur" *Surg Gynec and Obstets*, 1938, 66, 495
- ENGLER and MAY "Two Plane Direction and Range Finder for Nailing Fractures of the Neck of the Femur" *J A M A*, 1938, 110, 1828
- BRITAIN H A "Fracture of the Neck of the Femur," *Brit M J*, 1938 1, 773
- LYRE BROOK, A L and PRIDIE, K H "Intracapsular fractures of the Neck of the Femur Final Results in 75 Consecutive Cases" *Brit J Surg*, 1941, 29 115

Reconstruction Operations

- WHITMAN R "The Reconstruction Operation for Ununited fracture of the Neck of the Femur," *Surg Gynec and Obstets* 1921 32, 479
- HILLOCK "A Study and End Result Report of Seventy Arthroplasties and Reconstruction Operations on the Hip" *Surg Gynec and Obstets* 1939 68, 106
- COLLONA "A New Type of Reconstruction Operation for Old Ununited Fractures of the Neck of the Femur," *J Bone and Joint Surg*, 1935 17 110
- BRACKETT "Reconstruction Operation for Old Ununited fractures of the Neck of the Femur," *J Bone and Joint Surg* 1938 20, 93
- LORENZ "Über die Behandlung der irreponiblen angeborenen Hüftluxationen und der Schenkelhals pseudoarthrosen mittels Gabelung Bifurkation des oberen Femurendes" *Wien Klin Wochenschr* 1919 32, 997
- McMURRAY T P "Ununited Fracture of the Neck of the Femur," *J Bone and Joint Surg* 1936 18 319
- COMPERE and LEE "The Restoration of Physiological and Anatomical Function in Old Ununited Intracapsular Fractures of the Neck of the Femur," *J Bone and Joint Surg* 1940, 22 261

Petrochanteric Fractures

- ANDERSON ROGER "New Method for Treating Fractures Utilising the Well leg for Counter Traction" *Surg Gynec and Obstets*, 1932 54 207

rhage are usually visible in the subcutaneous tissues, and the two separate fragments may be felt to move independently of each other while the gap between them is unmistakable



FIG 516 Fracture of the patella with displacement



FIG 517 The same case as in the previous figure after suturing the expansions and the bone

Treatment Operative repair of the torn expansion of the quadriceps is essential, at the same time the likelihood of the development of sub patella arthritis must be borne in mind, particularly in the old. Preliminary treatment consists of the aspiration of the

of the bone may occur without any changes being visible in the radiograph, and that this may occur from the patella being forced violently across the outer femoral condyle, such as occurs in dislocation of the patella

Varieties of Patella Fracture

- | | |
|---|--|
| 1 Transverse fracture of the body | } With separation, accompanied by rupture of the quadriceps expansion |
| 2 Transverse fracture of the lower pole | |
| 3 Transverse fracture of the body | } Without separation of the fragments, expansion intact, due to direct violence, or leverage |
| 4 Transverse fracture of the lower pole | |
| 5 Comminuted fractures | } Due to direct violence |
| 6 Chip fractures | |

- 1 **TRANSVERSE FRACTURE OF THE BODY OF THE PATELLA** This fracture is the most serious of the fractures due to muscular violence. This is due to the widespread rupture of the fibrous expansion of the muscle on either side of the patella, and the fact that the fracture line is near enough to the centre of the bone to be a constant irritation to the femur in flexion of the knee, however well it is reduced. The later development of patello femoral arthritis is therefore to be expected.




FIG 315 Rupture of the extensor mechanism of the knee

- A Attachment to upper border of patella
- B Transverse fracture of the patella
- C Rupture of the attachment of the patella tendon together with separation of small non articular fragment
- D Rupture at attachment of the tibial tubercle accompanied by fracture of the tibial tubercle

The fracture is due to sudden strain on the quadriceps, usually with the knee in the semiflexed position. The patella is caught across the anterior surface of the femur is stripped, and continuation of the flexion of the knee together with muscular contraction tears the expansions of the muscle and the two fragments of the bone widely apart.

Signs and Symptoms These are usually dramatic and unmistakable. There is a loss of control of the knee and an inability to raise the leg with the knee straight. There is a rapid effusion of

blood into the knee joint which is distended, and usually an effusion into the prepatella bursa which is also distended and sits on the swollen knee like a small hill on a larger one. Bruising and hæmor

through the quadriceps expansion around the patella and fastened to itself with catgut

This may be sufficient to retain certain fractures of the patella in which the fragments interlock in satisfactory position, but more often to obtain perfect reduction of the two halves of the bone these must be fixed to each other. Wiring through the two halves of the bone has not proved satisfactory. The wire tends to break and reduction is not always perfect. A single screw may be inserted parallel with the articular face of the bone. This is simple, satisfactory, and can always be removed later. Oblique holes can be made with an awl on either side of the fracture line and the two halves sutured with catgut (Fig 520)

If a fragment is eversed the patella tendon is attached to the fracture surface by the last named method

EXCISION OF THE PATELLA Through a curved vertical or transverse incision (curved with base down to avoid the prepatella bursa being involved in the scar) the patella fragments are freed as close to the bone as possible. The two portions of the patella tendon are then united by strong catgut sutures, which are first placed in position (six to ten of them) and then tied while the two portions are held together with sharp hooks. Complete obliteration of the space left by the patella is fairly easy, and the suture line may often be reinforced by overlying fascial layers. The skin is then closed, a stab drain for the first twenty four hours being advisable.

After treatment (all cases) A firm pressure bandage over wool is applied which prevents much flexion of the knee. A Cramer wire splint may be used to support the knee for the first few days if desired. Quadriceps contractions and gentle faradism are begun at once and the patient encouraged to flex the knee as far as possible in the bandage. At the end of three weeks this is removed and active flexion exercises commenced. Weight bearing is permitted about the end of a month. Flexion to a right angle should be possible between this time and the eighth week. Full recovery of flexion is slow, particularly in the aged.

Prognosis This is uniformly good in all cases as far as the immediate results are concerned. In old patients in whom the




FIG 520 Another method of patella suture. A Transverse fracture of the patella. B Oblique drill hole. C Knotted catgut tied through drill holes. This method obviates any suture lying on the articular surface. If wiring is employed it is inserted through drill holes passing from the lateral aspect of the patella.

knee, which is then firmly bandaged over cotton wool and placed on a Cramer wire back splint. After a few days for the bruising to subside, and for adequate preparation, repair of the quadriceps is undertaken. The decision as to the fate of the patella depends on (1) The age of the patient, (2) The presence of osteoarthritis, (3) The size of the fragments. Thus in an elderly patient with osteoarthritis the patella is best excised. In old people in whom patellofemoral arthritis is likely it is also excised. In young people who have not ceased growing it may be completely repaired, while in young adults it may be best, especially if the fragments are unequal in size to excise the smaller one and attach the patella tendon to



FIG 518 Incision employed in fascial repair of the torn quadriceps expansion




FIG 519 The operation for fascial repair
A Fascial strip woven around the patella
B Fissure fracture of the patella C Suture in the torn quadriceps expansion
D Suture of the incision in the fascia lata from which the strip was obtained

the larger one. This method has the advantage of retaining part of the patella without the subsequent risk of arthritis.

REPAIR OF THE PATELLA Numerous methods of operation have been devised since Lister first placed a wire suture in the bone. A highly satisfactory method is that employing a suture of fascia lata. A J shaped incision is made, with the limb of the J on the lateral side of the patella and the foot curving around the lower margin of the patella. The patella is exposed and the fracture surfaces cleaned of clot and tags of fibrous tissue. The lateral expansions are explored and trimmed and united by a series of strong catgut mattress sutures, which are only tied when the two patella fragments are held in apposition by two sharp hooks inserted above and below. A strip of fascia lata is now cut down from the upper end of the wound, leaving the lower end attached to the side of the patella. This is then woven with a large needle




FIG 521 Congenital abnormalities of the patella. The patella ossifies from two centres which fail to fuse. This is often mistaken for marginal fracture of the patella.



FIG 522 Fracture of the epiphysis for the tibial tuberosity when this develops as a down growth from that for the tibial plateau.



FIG 523 Separation of the epiphysis for the tibial tubercle.



FIG 524 Old Osgood-Schlatter's disease with persistent fragmentation of the tibial tubercle susceptible to strain.

be compound. If the chip is intra-articular, or involves the articular surface in an irregularity because of its displacement, it should be removed. If in good position they are left. Cure is to be taken to avoid confusion with the congenital abnormality seen in Fig 521. This is usually bilateral and involves the upper and outer angle of

patella is not excised patello femoral arthritis will develop In cases in which the halves of the patella are not firmly approximated, union by fibrous tissue is likely to occur This is compatible with a good functional result until the development of arthritis

2 TRANSVERSAL FRACTURE OF THE LOWER POLE WITH SEPARATION The small fractured fragment has the main bulk of the patella ligament attached to it, but in the majority of cases the fracture line does not cross the articular area of the bone, lying just at the lower margin of the articular surface If this is so no danger of subsequent sub patella arthritis need be felt if the fragment is fixed back in position If the articular area is involved, the smaller lower fragment may be excised The ruptured lateral expansions of the quadriceps are repaired with care as in transverse fractures of the body

3 TRANSVERSE FRACTURES OF THE BODY AND 4 TRANSVERSE FRACTURES OF THE LOWER POLE WITHOUT SEPARATION These cases may be due to direct violence, or more commonly to the patella being caught across the condyles of the femur and snapped without the displacement of the knee proceeding any further The extensor mechanism is intact and the fragments not displaced Aspiration of the knee is followed by early active use of the knee This is the type of case in which the irregularities of blood clot or fibrinous bodies in the prepatella bursa may cause diagnostic confusion The absence of bruising in these latter cases or of effusion into the knee should aid in the differential diagnosis, while it should be remembered that chronic prepatella bursitis is usually bilateral

5 COMMINUTED FRACTURES These are due to severe direct violence and the anterior surface of the femur suffers as well The collision of a motor cyclist with a vehicle, or the knee being thrown against a dashboard are common methods of producing the fracture, and it may be associated with fractures of the femur Owing to the grave risk of subsequent sub patella arthritis the patella should be excised in all cases Preliminary aspiration of the joint, a few days' rest and adequate preparation are desirable, but the frequency of abrasions or of compound wounds often forces emergency operation The principles of treatment of open injuries are similar to those elsewhere Should it be considered that there is serious risk of infection of the knee joint, great care should be taken to sew up the synovial membrane Approximation of the fibrous expansion of the quadriceps can be left to a later date as the large body of buried catgut may cause serious trouble if sepsis occurs Drainage is wise for the first twenty-four hours in all cases as pressure of blood in the prepatella bursa may produce gangrene of skin over the bursa, but if desired the wound may be left open

6 CHIP FRACTURES These occur due to direct violence and may

the bone. Confusion arises because the shadow of the fracture line cannot be thrown clear of the femoral shadow, but when it can it has the characteristics of a congenital abnormality.

Fractures of the tibial tubercle. It seems appropriate here to add a note on fractures of the tibial tubercle. This arises as a tongue-shaped extension of the tibial epiphysis and not infrequently has a separate centre of ossification. This fuses with the shaft at the age of eighteen. The epiphysis is liable to osteochondritis commonly called Osgood Schlitter's disease. This shows the characteristic changes of density and fragmentation, and may result in a failure of the tubercle to unite with the shaft properly, a separate small bony fragment remaining (Fig 524). This condition is often bilateral and characterised by excessive prominence of the tubercles, which may be tender to touch.

If they are submitted to long continued strain, such as route marching, complaint of pain will be made. The condition may then be diagnosed as a fracture. Careful inspection will show it to have all the characteristics of well-organised bone (p 27).

It is in youth when the epiphyseal line presents a weak area through which separation may occur that injuries to the tubercle are common. If a separate centre for the tubercle is present it may be avulsed, or if the whole epiphysis is ossified as one the tongue like depression over the upper end of the tibia may be avulsed. In such cases operative repair is necessary. The fragments can usually be held in position by suturing the surrounding fibrous tissues, or by a single drill hole in the fragment, and a strong catgut suture through bone. Screwing may be carried out (Fig 524b), but the screw should be removed in the young as soon as the fractured fragment is firmly attached.

REFERENCES

- BROOKE. The Effect of Removal of the Patella for Simple Transverse Fractures on the Function of the Knee Joint," *Proc Roy Soc Med*, 1937 30, 203
- BROOKE. The Treatment of Fractured Patella by Excision. A Study of Morphology and Function," *Brit J Surg*, 1937, 24, 733 (Advocates complete removal in all cases)
- BLODGETT and FAIRCHILD. Fractures of the Patella' *J A M A*, 1936, 106 2121 (This comprehensive article advocates more conservative treatment though not denying the value of complete excision in certain cases. Full references)
- ADAMS and LEONARD. "A Developmental Anomaly of the Patella, frequently Diagnosed as Fracture" *Surg Gynec and Obstets*, 1925, 41, 601
- LAPIDUS. 'Longitudinal Fractures of the Patella," *J Bone and Joint Surg* 1932, 14, 351
- TODD and MCCALLA. "Defects of the Patella Border," *Ann Surg*, 1921, 74, 775
- COLEMAN H M. 'Recurrent Osteochondrol Fracture of the Patella" *J Bone and Joint Surg*, 1948 30b, 153-157



FIG 524a Avulsion of the tibial tuberosity



FIG 524b Reduction of the fracture and fixation with single screw

cruciate ligament may be damaged by blows on the tibia with the knee flexed driving the tibia backward

2 FRACTURE OF THE TIBIAL SPINE This is due to a blow from the inner surface of a condyle, as one or other side of the intercondylar notch is moved across against the spine To allow this degree of movement either one or both collateral ligaments of the knee must be severely sprained or ruptured

3 To complete the summary of the condition, lesions associated with comminuted fractures of the tibial condyles must be mentioned

DIAGNOSIS There are three characteristics of the lesion, a hæmarthrosis, with some limitation of the knee movements, a bony block to full extension of the knee, not always present, and some associated relaxation of the ligaments of the knee If the anterior cruciate is torn, abnormally free antero-posterior movements of the extended knee are possible If a collateral ligament of the knee is ruptured abnormal abduction or adduction movements of the knee are allowed The diagnosis can only be made by radiography, as a simple hæmarthrosis, loose bodies, or other fracture into the knee may cause confusion

TREATMENT In the majority of cases, full extension of the knee after aspiration of the joint causes the fragment of bone to slip back into position and maintains it there Some manipulation may be required to get the knee into full extension, some rotatory movements of the foot with the knee semiflexed usually causing it to slip back The knee is then immobilised on a Cramer wire back splint with a pressure bandage to the knee At the end of five to ten days a plaster cast as for fractures of the patella is applied, and walking permitted This is removed at the end of six weeks and gentle exercises commenced

Occasionally the fragment fails to slip back into position, or cases may be seen which are not diagnosed till the fragment has united in a position limiting extension In such cases the fragment must be replaced and the knee fully extended In these cases it is occasionally found that a



FIG 525 Fracture of the spine of the tibia Elevation of the attachment of the anterior cruciate due to the femur being forced back on the fixed tibia Treated by forcing the knee into full extension

CHAPTER XXIX

FRACTURES OF THE TIBIA AND FIBULA ALONE

Surgical anatomy Development The fibula is the exception to the rule that the centre of ossification first to appear is the last to unite. Primary centres for the shafts appear in both bones in the seventh and eighth weeks. Secondary centres appear as follow

Tibia

Upper end	Just after birth	Unites eighteen to twenty
Lower end	In second year	Unites after puberty

Fibula

Upper end	In third year	United before the twenty fourth year
Lower end	In second year	Unites about the twenty first year

The tibia is a characteristic long bone, the upper end being an expanded cancellous tissue plateau for the support of the femoral condyles. The triangular shape of the shaft on section predisposes to sharp corners at a fracture site, while its subcutaneous surface makes them readily compound. The upper epiphysis has a tongue like prolongation anteriorly which carries the tibial tubercle, and the articular area for the fibula is localised to it. Owing to the fact that most of the ligaments of the region are attached to the bone below the epiphysis it is very rarely separated. If a secondary centre is present for the tongue of the epiphysis to which the patella ligament is attached this may be fractured, and rarely the tongue may be avulsed.

The anterior cruciate ligament runs from the anterior portion of the tibial spine to the medial intercondylar surface of the lateral femoral condyle. It is tight in extension and if ruptured allows excessive forward mobility of the tibia. The posterior cruciate ligament runs from the posterior aspect of the tibial spine to the anterior medial aspect of the inner femoral condyle, and is tight in flexion. Rupture allows excessive backward mobility of this tibia on the femur. Both these ligaments should be tested for with the knee flexed to a right angle the foot on the table and the thigh muscles completely relaxed.

The lower epiphysis of the tibia is much more susceptible to injury than the upper, and is not infrequently displaced. The fibula epiphysis may be displaced at the same time or the displacement may be accompanied by the fracture of the fibula.

Fractures of the Upper End of the Tibia

- 1 Fractures of the tibial crest
- 2 Fractures of the tibial condyles
- 3 Fractures below the condyles
- 4 Fractures of the tibial tuberosity (p 501)

Fractures of the tibial crest 1 **FRACTURES OF THE ANTERIOR TUBERCLE** This lies anterior to the spine, and is the site of attachment of the anterior cruciate ligament. The fracture is an avulsion, or ligament traction fracture, due to a blow on the anterior aspect of the femoral condyles with the knee flexed, which drives the femur backward on the fixed tibia. In a similar manner the posterior

that of injury to the femoral condyles. They both, if incorrectly replaced, have a deleterious effect on the joint function, altering the line of stress through the joint, and distorting movement so that a large number of cases end with a severe traumatic arthritis. To avoid this accurate reduction is a *sine qua non*.

Further, owing to the ligament damage, adequate rest (ten weeks) must be given for these to heal and during this time it is important to maintain quadriceps tone, by all means at your disposal. If the




FIG 528 The mechanism of fractures in the knee region from indirect violence. A Direction of force offered by the resistance of the femur. B The site of the fulcrum. C Direction of leverage exerted by forced abduction of the tibia. The arrows show the strain on the medial collateral ligament. The conditions are reversed in adduction fractures.




FIG 529 Ligament strain fracture of medial condyle of the tibia, from abduction violence to the leg. The opposite lesion from adduction strain is shown in Fig 689 while rupture of the ligament alone is shown in Fig 688.

knee is unstable owing to the ligamentous and bony damage, only the power of the muscles will maintain it in satisfactory working order. Any irregularity of the tibial plateau surface is still another contributory factor to the onset of traumatic arthritis and demands as far as possible that the tibial plateau be restored to its old level and regularity.

Blows on the outer aspect of the leg are much more common than on the inner aspect, and are characteristically produced by the bumper bars of a car. Abduction fractures of the knee are thus

torn or displaced meniscus is preventing reduction or full extension of the joint. It is debatable whether it is of value to fix the anterior end of the cruciate ligament with a bone peg or suture, passed by drilling the tibial condyle from below. The results of cases treated without fixation seem equally satisfactory. The post operative treatment is the same as for fractures of the patella requiring operation.

Fractures of the tibial condyles

1 FRACTURES OF THE TIBIAL PLATEAU ON THE MEDIAL OR LATERAL SIDE (a) Involving the outer edge of the plateau only (Fig 526)

(b) Involving the whole medial or lateral plateau surface, which is angulated but not depressed or fragmented. This fracture may be accompanied by rupture of a collateral ligament.




FIG 526 Fracture of the outer margin of the tibial plateau leaving most of the articular surface intact (Compare Fig 532). This may occur with (as shown) or without rupture of the medial collateral ligament—for mechanism compare Fig 528.




FIG 527 Fissure fracture of the outer half of the tibial plateau with little displacement. The absence of this is due to the rupture of the medial collateral and anterior cruciate ligament.

(c) Depressed fissure fractures or comminuted fractures of the plateau, which may take several forms (Figs 537, 538), may be accompanied by collateral ligament rupture and because of the severe intra articular damage have a bad prognosis.

2 COMMINUTED FRACTURES OF BOTH CONDYLES (Fig 539) The importance of injuries to the tibial articular surface is as great as

expended in depressing, comminuting, or splitting off the condyle of the opposite side

It follows that the collateral ligament may be found intact or ruptured in either of the two groups of cases, though the greater the depression of the tibial plateau the more likely it is to be ruptured. In all cases steps should be taken to prove or disprove this by examination under anesthesia and control radiography. In some cases the cruciate ligaments may be ruptured as well. It is probable that the two groups are dependent on whether the blow on the outer side of the leg is struck above or below the knee. If the blow is just below the knee the tibia moves in under the femoral condyle and the plateau is depressed as a whole (Fig 532). If the blow is struck on the femur, the femur moves inwards and the sharp outer edge of the femoral condyle splits or depresses the tibial plateau.




FIG 532 "Bumper fracture"

The mechanism and fracture varies according to whether the bumper strikes above or below the knee. If below and the ligaments remain intact a depressed fracture of the outer side of the tibial plateau and of the fibula at the neck occurs—if the force strikes above the knee as in Fig 526 depressed fractures of the plateau without fracture of the fibula tend to occur.

Sprain fractures of the tibial attachment of the medial collateral ligament. When the medial collateral ligament ruptures it may give at the femoral attachment, stretch opposite the joint line, or at the tibial attachment. Occasionally a small flake of bone is avulsed from the tibial condyle. The flake is seldom much displaced and is restored by manipulation and full adduction of the knee, after aspiration of the joint. The knee should be immobilised in plaster for six weeks, quadriceps tone being maintained. The prognosis, when there is an accompanying fracture, is better than when the ligament itself is torn and the repair more rapid. Complete ligament ruptures without fracture require ten to twelve weeks' rest.

Sprain fractures of the styloid process of the fibula. This lesion corresponds to the fracture described above and occurs during adduction strains on the knee. The displacement is variable, one case being recorded in which the fragment was caught in the knee joint in an analogous manner to that of the medial epicondyle in the

much more common than adduction fractures. With the abduction lesion the upper end of the fibula is sometimes damaged by direct violence, though more frequently it is fractured by depression of the lateral femoral condyle. In adduction fractures the fibula is damaged by ligament strain. Compression fractures of the tibial plateau are less common, and with a firmly extended knee may cause compression of the cancellous bone below the articular surface.




FIG. 530. Pressure fracture of the tibial plateau with fracture of the neck and displacement. A characteristic lesion when the intact ligaments provide sufficient leverage.




FIG. 531. Diagram indicating the necessary forces to reduce the fracture shown in the previous figure. AB, Direction of compression. C, Forced adduction of the leg producing tension in the fibula collateral ligament. D, Traction on the leg further increasing this tension and separating the joint surfaces.

without distortion of the articular surface. More commonly there is some slight angulation, or gross distortion of the joint surface, with separation of both condyles and comminution.

In angulation injuries there is a balance of damage shared between the collateral ligaments of the joint on the one side and the condyle of the tibia of the opposite side. If the ligament tears, the knee joint opens on that side more easily and there is less energy expended in driving the sharp edge of the femoral condyle into the upper surface of the tibia. If the ligament holds the force is



FIG. 534 Fracture of the lateral process of the talus

FIG. 533 Abduction fracture of the neck of the femur. Treated by early walking in a short hip spica



FIG. 535 Small os marginale. Often mistaken for fracture of the rim of the acetabulum or osteophytic outgrowth



FIG. 536 Depressed fracture of the outer half of the tibial articular surface for the lateral femoral condyle. Restored to normal position by forced adduction and plaster retention

elbow joint Satisfactory position is usually achieved by full extension and the leg should be fixed in plaster for six to eight weeks (Fig 689)

FRACTURES INVOLVING THE OUTER EDGE OF THE TIBIAL PLATEAU In these fractures the ligaments are intact, the outer condyle of the femur having merely pressed on the outer margin of the tibia, depressing it till with the support of the stronger central portion of the plateau the femur is sufficiently opposed to prevent further damage The outer margin being unattached to ligaments cannot be elevated by forced adduction or in the case of the medial side by forced abduction of the tibia The depression is usually small (Fig 526) and the main part of the tibial plateau remains undamaged The lesion may be accompanied by damage to the associated cartilage

TREATMENT This is conservative The joint is aspirated and bandaged firmly After a few days quadriceps exercises are begun and at the end of a week non weight bearing exercises started Should early weight bearing be considered necessary, a knee fixation plaster may be applied and active exercises in this commenced This is worn for a month to six weeks A satisfactory functional recovery is to be anticipated with either method, the disability persisting longer if plaster is used on account of the stiffness of the joint

FRACTURES INVOLVING ONE HALF OF THE TIBIAL PLATEAU In these fractures the pressure imparted by the femoral condyle is applied evenly over the surface of one tibial condyle This is more likely to occur if the tibial surface is under the femoral condyle at the moment of pressure, as occurs when it is first driven inwards by impact below the knee (Fig 532) The ligaments, by remaining intact, contribute to this by preventing displacement and preventing further tilting of the femoral condyle After depression has occurred they may be ruptured, permitting continued displacement of the bones on each other Fracture of the fibula is inevitably associated with this lesion if it affects the outer plateau, though in some cases this may be produced by the actual violence It is then more likely to be accompanied by paralysis of the peroneal nerve

Treatment The ligaments fixed to the condyle and the fibula enable it to be elevated by forced abduction or adduction (Fig 531) The fracture line usually involves the intercondylar region and there is less risk of early traumatic arthritis than in cases in which comminution of the plateau is present Reduction may be aided by the use of a lateral clamp of the Böhler type, or the Phelps Gocht clamp More convenient than this is the use of an Esmarch bandage by means of which great compressive force may be applied Reduction



FIG 533 Abduction fracture of the neck of the femur. Treated by early walking in a short hip-spica



FIG 534 Fracture of the lateral process of the talus



FIG 535 Small os marginale. Often mistaken for fracture of the rim of the acetabulum or osteoplytic outgrowth



FIG 536 Depressed fracture of the outer half of the tibial articular surface for the lateral femoral condyle. Restored to normal position by forced adduction and plaster retention



even if not perfect usually produces a good functional result. The meniscus may be damaged and require removal later, but this is less common than in the succeeding group of cases.

The limb is put in plaster and active quadriceps exercises begun immediately after aspiration and reduction of the fracture. Weight bearing is not permitted for some weeks (four to six), depending on the extent of the depressed area, and then only in a well fitted plaster. During this period the knee is actively exercised. At the end of ten to twelve weeks the plaster is removed and active flexion exercises begun. It is rare that this group of cases needs operative reduction, but occasionally it is necessary to do this. Through an interolateral or antero-medial incision the condyle is replaced, any loose body removed from the joint, and the cartilage excised if affected. The after treatment is similar to that in cases non-operatively treated.

DEPRESSED AND COMMINUTED FRACTURES OF A TIBIAL CONDYLE

When the force employed is greater, or strikes the femur instead of the tibia, and particularly if ligamentous rupture has occurred, the sharp edge of the femoral condyle (in particular the lateral condyle) may split off the outer margin of the condyle (Fig 526). This fracture is inevitably accompanied by damage to the collateral ligament but the fibula may remain intact. Damage to the tibial plateau on the medial side of the fracture occurs and the surface is depressed here. Reduction of this type of fracture is similar to that described above, the small depressed area described remaining unreduced (Fig 536). Lateral compression is usually sufficient to reduce it if combined with adduction. Operative treatment is rarely necessary, nor is the introduction of pins laterally through the condyle and into the tibial substance to lever up the condyle needed.

Where the plateau fails to split, comminution and depression of the plateau occurs. This may leave an intact margin as shown in Fig 538, or the whole condyle may be grossly comminuted with inevitable damage to the meniscus. In these cases the collateral ligament will often be found intact, the depression and comminution of the tibial plateau taking most of the force. It is obvious that the reconstruction of the plateau is not likely to be very easy or successful in these cases. The fragments of bone once loosened are deprived of a blood supply and are poorly supported by other fragments. More damage is likely to be done by the operation than good. Comminuted fractures may therefore be divided into two groups, those in which an approximately normal appearance can be restored by the measures described above and those in which no satisfactory restoration can be accomplished. In these last cases open operation to remove fragments which would block flexion or extension is desirable.

Comminuted fractures of both condyles Such fractures can only be reduced by a combination of traction and compression. Traction should be commenced from the first, and is best applied through a pin in the lower end of the tibia. A pin in the calcaneus is in this case less satisfactory. The leg is held on a Thomas splint in extension, the knee joint being aspirated and surrounded with a compression bandage. A pull of 10 lbs is used to commence with, and is increased or decreased according to the change seen in the radiographs. At the end of ten days the case is reviewed. In a few cases the traction will have settled the condyles in fair position,




FIG 537 A comminuted fracture of both condyles of the tibia indicating the directions of application of force to restore approximate position of the fragments (compare Fig 539)




FIG 538 Depression of the articular surface of the tibia (B) leaving an intact outer wall of the tibia (A)

but in the majority it must be aided by compression with a clamp. This is applied for a moment and screwed tight, being immediately released. A control X ray is taken and if satisfactory the knee is firmly bandaged and replaced on the Thomas splint in extension. In order to retain some mobility in the joint early flexion and quadriceps exercises are essential, and these are commenced from the moment the joint is aspirated, immediately after being first seen. The weight employed for traction is gradually diminished and abolished about the end of the fifth week. If the knee is to be satisfactory, flexion to 30 degrees should be possible at this time. Flexion exercises with no splint and without weight bearing are continued,

the patient being got up on crutches. At the end of ten to twelve weeks the patient is fitted with a walking calliper and allowed out. The calliper is worn for six to nine months. With such cases perfect knee function cannot be expected, but it is often surprising what movement returns to an apparently completely disorganised knee. The development of a late arthritis is almost inevitable, but a young patient may have many years good use out of a knee before this occurs.

The importance of treating all knee injuries in the extended position cannot be over emphasised. It gives accurate control both by vision and by X-ray over the fragments and the position of the



FIG 539 A comminuted fracture of the upper end of the tibia, showing marked displacement

joint. In the case of injuries to both condyles, if treated in flexion, the posterior displacement of the tibia on the femur is likely to be overlooked, but is easily seen in the extended knee, and adduction and abduction can be accurately controlled.

Fractures below the condyles. These are most commonly the result of direct violence below the knee, though they may occasionally be the result of leverage and impaction of the cancellous bone of the condyles over the compact bone of the shaft. The tibial plateau is not as a rule displaced, though it may be involved by passing into it. Displacement in non compound cases is small.

TREATMENT. Impacted cases should not be disimpacted unless there is gross deformity and shortening. The impaction gives one

the opportunity to concentrate on function of the knee without weight bearing for the first month. The limb is supported on a slung Thomas splint or in a plaster gutter splint, during this period. Having obtained a reasonable degree of knee movement, the immobilisation of the knee in plaster to allow weight bearing from the fourth week on need not be feared. A knee fixation plaster leaving



FIG. 540 Fracture of the upper third of the tibia and fibula

the foot free is sufficient. Union is rapid, being firm in eight to ten weeks.

In non impacted cases the alignment of the limb is corrected and maintained by a complete plaster cast from foot to groin. Active quadriceps drill is commenced from the beginning. If there is an effusion into the knee this should be aspirated before the application of the plaster. As soon as there is any evidence of commencing union the knee fixation plaster leaving the foot free is applied and weight bearing commenced. In the later weeks this may be guttered for the commencement of knee flexion exercises. Rarely in these cases is shortening a consideration, but if present the methods

employed in fractures of the shaft of the tibia should be utilised in its correction

One danger of fractures in this region requires to be mentioned. The posterior tibial vessels are held firmly in position as they pass under the fibrous origin of the soleus. They cannot consequently avoid the pressure of fragments of bone displaced posteriorly, or of excessive tension in the region. These fractures may therefore be followed by arterial obstruction of varying degree and paralysis of the posterior tibial nerve. This is one manner in which Volkmann's contracture of the leg may arise. Should the condition be recognised the vessels should be decompressed by a posterior incision exposing them.

FRACTURES OF THE SHAFT OF THE TIBIA ALONE

This fracture is not common as the sudden loss of the support of the tibia throws a heavy strain on the fibula which consequently fractures. It is therefore most likely to be seen where the fracture of the tibia is incomplete or permits little displacement, or in which the fracturing force has ceased to act after impact with the bone. A kick at football is a not uncommon method of producing a transverse fracture, often with minimal displacement. The fractures of the tibia alone commonly met with are

1 *Greenstick* fractures in children up to the age of fourteen (Fig 541). In them there may be very little to note except the child's reluctance to use the leg, local pain, and a history of injury. The lesion is revealed by radiography.

2 *Transverse* fractures without displacement. Usually due to blows and therefore sometimes compound. Angulation is to be feared if too early weight bearing is permitted. Some weeks in a non weight-bearing plaster is therefore necessary before this is allowed and a well-fitting plaster is essential. Union is slower than in helical or oblique fractures, but more rapid the nearer the fracture is to the ends of the bone. Firm union should be established in an adult in twelve weeks and in a child it may occur in half this time.

3 *Oblique* fractures, being due to strong bending violence, usually involve the fibula as well, and are treated in the same manner.



FIG 541 Spiral fracture of greenstick type not uncommon in children

as a helical fracture, the prevention of shortening and angulation being the chief concern

4 *Spiral* or helical fractures with little displacement may occur the elasticity of the fibula and its attachments permitting the tibia to be broken before it yields. Shortening in such cases is minimal but there may be angulation of the tibia towards the fibula. Even if not present at once it frequently occurs during treatment and a fracture from which a good result is anticipated may be disappointing. A second factor which is more difficult to correct is rotational deformity. This must be carefully watched for and checked clinically and radiologically whatever method of retention is employed. For this reason operative fixation with one or two screws, which with the slight displacement present is a very simple procedure, is to be recommended if there is any displacement. If this cannot be carried out the fracture should be controlled by a long leg plaster and weight-bearing avoided for four to six weeks, when it should be permitted in a fresh well-fitting plaster.

In fresh fractures the usual precautions in applying a complete plaster must be observed. If it is thought desirable to encircle the limb an even padding of cotton wool should be applied under a bandage. More satisfactory is the use of a wide unpadded slab bandaged on to the back of the limb and leaving a gap of three inches in front which can be split down easily if swelling is likely or oedema appears. It must not be forgotten that it is occasionally convenient to apply the slab to the front of the limb, *e.g.*, when lacerations or abrasions of the calf exist.

FATIGUE FRACTURE OF THE TIBIA

The yielding of bone to repeated stress without the history of a severe injury has now been recognised in many situations other than the metatarsals in which it was first described as "march fracture". Among the sites where it occurs are the neck of the femur, the lower third of the femur, the humerus, the first rib and the upper third of the tibia. For the fracture to be classed as a fatigue or stress fracture it must be possible to trace it through three stages

- 1 Subperiosteal deposition of bone, without fracture
- 2 Fissure fracture with increased density on either side of the fracture line
- 3 A healed stage with increased thickness of bone

The first two stages are characteristically shown in Fig 542, which shows a fatigue fracture of the tibia in one leg. The opposite tibia subsequently showed a similar series of changes. The condition is met with in adolescents undergoing severe exertion, *e.g.*, army training. The complaint is one of local pain aggravated by exertion.



FIG 542 Fatigue fracture of the tibia Note increased density at site of fine fissure fracture and sub periosteal new bone formation

and may be bilateral. Clinically there is local tenderness and swelling. The diagnosis is based on the radiological findings in the absence of an adequate history of injury. Treatment depends on the stage of the condition. In the acute phase it is usually sufficient to avoid over exertion on the legs till the healed stage is apparent. Owing to the fact that periosteal new bone formation may even precede the appearance of the fracture line, no danger of spontaneous fracture need be feared. The cause of the condition in the tibia runs approximately three months. Graduated physical training may then be recommenced.

FRACTURES OF THE FIBULA ALONE

A complete chapter could be devoted to the interesting varieties of fracture of the fibula by direct and by indirect violence. The catalogue of fractures which may occur is long enough. The fractures due to indirect violence have a particular interest in being dependent on the sequence of ligamentous injury, which determines their level and nature. In indirect violence the force is imparted to the lower end of the fibula by rotation of the foot and the consequent association with injuries to the ankle makes it more convenient to discuss the lesions under this head (p. 330). It must not be forgotten that the fibula has an appreciable and important range of movement, which contributes much to the elasticity of the ankle and that it can be dislocated at either end.

Fractures of the Fibula

- 1 Upper end
 - (a) Without displacement
 - (1) With tibial fracture
 - (2) Direct violence
 - (b) With displacement
 - (1) With an intact knee joint (Fig. 540)
 - (2) With a damaged knee joint (Fig. 530)
- 2 Neck
 - (a) Without displacement
 - (1) Associated with rupture of the anterior tibio fibular ligament (Maisonneuve's fracture) (Fig. 609)
 - (2) With rupture of the fibula collateral ligament of the knee (Fig. 689)
 - (3) Associated with fracture of the posterior tibial tubercle (i.e., rupture of the posterior tibio fibular ligament) (Maisonneuve's fracture)
 - (b) With displacement. Avulsion fracture by the tendon of the biceps femoris

- 3 Shaft
- (a) Direct violence Transverse oblique, or "butterfly," usually around the mid shaft
 - (b) Indirect violence
 - (1) Associated with rupture of anterior and posterior tibio fibular ligaments and tearing of the interosseous membrane
 - (2) Associated with rupture of the anterior tibio fibular ligament and the interosseous membrane (Dupuytren's fracture) (p 560)
- 4 Lower end
- (a) Oblique first degree external rotation fracture ("Mixed oblique fracture" of Destot) (p 541, Fig 566)
 - (b) Transverse fracture at level of tibial plafond
 - (1) Adduction p 553, Fig 599
 - (2) Abduction p 554, Fig 597

FRACTURES OF THE UPPER END OF THE FIBULA Undoubtedly the most common lesion is the spiral fracture of the neck of the bone due to rotational violence. In order for the rotational force to pass the limit of elasticity of the bone either the tibio fibular syndesmosis must be damaged or the tibia fractured. It is possible for the peroneal nerve to be caught in such fractures as it winds round the neck of the bone and to be severely crushed. Displacement of such fractures is minimal and the treatment is that of the primary lesion.

The head of the fibula may be crushed in direct violence by being squeezed against the tibia. The peroneal nerve may therefore be damaged. Treatment in such cases as are not compound consists of rest and the support of a firm bandage.

Where the fibula head is displaced the tibial condyle is usually displaced as well, and with the reduction of the plateau it is brought back into good position. The tip of the fibula corresponding to the attachment of the fibular collateral ligament and the biceps may be avulsed in adduction injuries of the leg as has been discussed before on p 507. An interesting variation is the fracture of the fibula neck below the insertion of the biceps which draws the upper fragment backward. The reduction and retention of this fracture is impossible without open operation. Spasm of the biceps maintaining the displacement. Fixation of the two bone ends in contact by a loop of wire or strong catgut maintains reduction.

FRACTURES OF THE SHAFT OF THE FIBULA This is due to direct violence, and is frequently transverse. There is no displacement, but a distressing feature is the persistence of pain. It may be the

pain which brings a patient to the doctor, when he has considered himself to be suffering from a bruise. The tracking of the blood-staining along the peroneal compartments in such a case should arouse suspicion. Immediate relief of the pain can be produced by an injection of novocaine into the hematoma. After treatment should consist of massage and exercises, or if there is little discomfort on walking of firm support with elastoplast or a crepe bandage. Though a minor fracture, pain is apt to persist for longer than expected, and can be relieved by repeated injections.

REFERENCES

Upper End

- CUBBINS, CONLEY and DIEHLERT "Fractures of the Lateral Tuberosity of the Tibia, with Displacements of the Lateral Meniscus between the Fragments" *Surg Gynec and Obstets*, 1929 48, 106
- PALMER, I "Compression Fractures of the Lateral Tibial Condyle and their Treatment," *J Bone and Joint Surg*, 1939, 21, 674
- ROBERT JONES and ALWYN SMITH "On Rupture of the Crucial Ligaments of the Knee, and on Fractures of the Spine of the Tibia," *Brit J Surg* 1913, 1, 70
- CLARKE, FRIPP, STAMM and FAIRBANK "Discussion on Fractures of the Tibia involving the Knee Joint," *Proc Roy Soc Med*, 1935 28, 1035
- STEUER "Fractures of the Tibia involving the Knee" *Ann Surg*, 1920, 89, 580
- COTTON "Fender Fractures" *Surg Gynec and Obstets* 1936 62, 442
- ELIASON and LEBELNO "Non operative Treatment of Fractures of the Tibia and Femur involving the Knee," *Surg Gynec and Obstets*, 1933, 57, 658
- CAVILL "Fractures of the Tibial Condyles Involving the Knee Joint" *Surg Gynec and Obstets* 1948 86, 289-294

Fatigue Fractures

- PROCTOR CAMPBELL and DOBILLE "March Fractures of the Tibia and Femur" *Surg Gynec and Obstets* 1944, 78, 415
- BURROWS H J "Fatigue Fractures of the Fibula" *J Bone and Joint Surg*, 1948 30b 266-279

CHAPTER XXX

FRACTURES OF BOTH BONES OF THE LEG

Of all the long bones the tibia is the most commonly fractured. Injuries to the leg are particularly frequent under modern industrial and traffic conditions, and because of the subcutaneous nature of the bone they are commonly compound, either directly or indirectly. The position of the bone lying, as it does, between the two hinged joints of the ankle and the knee is peculiar. These joints are carefully aligned by nature in their axes of movement, and the slightest disturbance of the alignment of the bone results in a redistribution of strain through the knee and ankle which, if severe enough or existing long enough, will eventually produce a traumatic arthritis at one or both joints. It is only in the young, where the continuation of growth will result in spontaneous rectification of any malalignment, that the results of fracture of the leg can be treated lightly. In the adult though the immediate results may be gratifying, the late results are very disappointing, while in a body of fit men the average fracture of the leg produces a very marked diminution in physical efficiency. This is due in most cases to the undesirable effects of imperfect alignment. In some cases soft tissue damage and adhesions are in part responsible particularly in infected fractures, while too long continued traction and inefficient immobilisation take their toll. It is nevertheless true that fractures of the leg bones being regarded as simple to treat, are in fact more unsatisfactory in the long run than many more complicated injuries. The introduction of skeletal traction, while it has improved immensely the position achieved in fractures of the leg, has brought with it many disadvantages. These may be summarised as follows —

- 1 Over traction and stretching of ligaments at the primary reduction
- 2 The continuous use of traction with continuous ligament stretch
- 3 Continuous over traction with delayed union
- 4 Fixed distraction with two pins with greater chances of non-union
- 5 The dangers of pin sepsis near a joint

Prolonged immobilisation without adequate movement of the knee or the ankle is undesirable in all cases, and it is not true to state that if the patient is weight bearing on the immobilised limb it is unimportant. Active use of the limb in plaster is to be recom

mended wherever possible, and it does reduce stiffness to a great extent. It is not, however, comparable with a method which leaves the joints free for exercises.

The ideals of treatment of fractures of the leg must thus be —

1 Perfect reduction. Both angulation and shortening are to be corrected, but rotation which is commonly neglected is still more important.

2 The avoidance of traction in any form if possible, and if it must be used, only as a method of immediate reduction and not of fixation.

3 The earliest use of the knee and ankle joints possible without risk of loss of alignment.

4 The use of the limb for weight-bearing as soon as possible.

It would seem that these ideals can only be satisfied by open operation and heavy plating. The disadvantages of plating bones heavily have been discussed in Chapter X, where the reasons for the adoption of single or double screw fixation have been described. This method, though probably adding a fortnight to the time taken for clinical consolidation of the bone, is the ideal under good operative conditions and in experienced hands.

ÆTIOLOGY Rotational violence produces helical or spiral fractures of both bones, the fractures sometimes being at the same level, but more frequently the fibula fracture is higher up, and may be missed if the X-ray film fails to include the upper end of the bone. These fractures tend to be indirectly compound, a sharp spicule of bone penetrating the skin over the subcutaneous border of the tibia. Direct violence usually produces a transverse fracture of both bones at the same level, and the fracture is often directly compound. **Comminution** may occur. Bending violence may produce double oblique fractures by the mechanism shown on p. 4. In all cases of fracture of both bones of the leg temporary splintage is more important than elsewhere owing to the great displacement which may occur and the possibility of this rendering the fracture compound.

DIAGNOSIS These cases present the classical signs of fracture and present no difficulties. Bruising is very variable, and may be immense. Injury to nerves is almost unknown, but injury to blood vessels is more common, and may account for a few cases of gangrene of the toes following fracture. Shortening and angulation are the most common displacements, but with rupture of the interosseous membrane it is possible for the bones to be widely separated.

Treatment This may be outlined in a skeletal manner as follows. It is very largely dependent on the direction of the fracture line.

Transverse	{ Manipulation and plaster gutter splint { Early walking plaster (i.e., in 10 to 18 days) { Plating
Slight obliquity	{ Single screw fixation { Plating
Part oblique, part transverse (Fig 6)	{ Manipulation and gutter splint { Walking plaster a little delayed (3-4 weeks) { Angulation often best corrected at the end of ten days
Spiral or helical (Fig 3)	{ Single screw fixation { Plating
Oblique (Fig 2)	Continuous traction in plaster to commence with then a complete plaster
Comminuted (Fig 73)	Walking plaster considerably delayed till callus firm and shortening cannot occur (4-6 weeks)

Transverse fractures (a) WITHOUT DISPLACEMENT In the absence of any risk of shortening treatment becomes simple. As a preliminary a posterior plaster slab is applied encircling two thirds of the limb. A simpler substitute for this is a well-moulded Cramer wire splint, which with side pieces may be strapped to a Braun's splint. The limb is elevated until swelling has subsided, when a complete circular plaster is applied from the thigh to the toes. The plaster may stop at the metatarsal heads leaving the toes free to exercise. The patient is encouraged to get about on crutches, and at the end of the fourth week a fresh close fitting plaster is applied and weight-bearing permitted. This is best done through some form of shoe taking the weight on heel and toe through a sponge rubber sole. Some softening of the sole of the plaster is no disadvantage as it allows more normal metatarsal movements. Careful radiological control is maintained to prevent angulation, and if this occurs it can best be corrected by wedging the plaster. The continuation of the plaster above the knee may not always be necessary in fractures of the lower third of the bone. Union should be clinically firm in ten to twelve weeks when the plaster should be removed and active rehabilitation begun.

(b) WITH DISPLACEMENT Displacement can often be reduced by manipulation under anaesthesia alone. Such cases are treated after reduction in the same way as undisplaced fractures. Swelling and soft tissue injury is likely to be greater, and consequently the date on which a close fitting plaster can be applied is delayed. Where reduction is not satisfactory by manual methods the use of a Böhler or Watson Jones traction frame is necessary. Skeletal traction is applied through the os calcis or the lower end of the tibia (pre

ferably the latter) and the fracture disimpacted and reduced. Radiological control before the application of a plaster may be helpful. Care must be taken that the rotation of the foot is correct, and the interdigital cleft between the first and second toes is in line with the mid line of the patella.

The leg is then plastered on the frame. The Kirschner wire or pin is removed and in high fractures of the shaft the plaster continued above the knee with the knee in slight flexion. A displacement of a quarter of the width of the tibial shaft can be neglected if the alignment is good. This is controlled by wedging later if neces-




FIG 543 Angulation of a fracture in plaster




FIG 544 Correction of the angulation by division of the plaster at level of the fracture with a saw and opening up the plaster (Wedging the plaster)

sary. If a non-padded plaster cast has been used it should be split down the antero lateral aspect. Alternatively, light padding may be included around the fracture area to allow for swelling. The patient will be more comfortable if the limb is slung. This is most easily done by putting a Thomas splint over the limb and attaching it by a double cuff of plaster. The after treatment is similar to non-displaced fractures once the swelling has subsided and early union has prevented the possibility of lateral displacement of the bone. The plaster need only be maintained above the knee if the fracture is in the upper two thirds of the bone and in the early stages of treatment.

(c) WITH IRREDUCIBLE DISPLACEMENT This is uncommon, but

fractures may get locked out of position by soft tissues or by fragments of bone. After attempts at reduction have failed by the ordinary method open operation should be carried out. The alternatives presenting themselves then are interlocking of the bone ends without fixation, light plating and external splinting, and heavy plating without external support. This is a matter for decision on the conditions present and personal preference. Transverse fractures can occasionally be maintained in position by an oblique screw.

Oblique fractures In this group of fractures lateral displacement and shortening and angulation are likely to occur. This includes fractures from bending violence, fractures in which the fracture line is half oblique and half transverse (Fig. 7), and fractures in which a butterfly fragment has not fully separated (in other words, a half oblique, half transverse fracture in which the oblique fragment is incompletely separated by a fissure). These cases lend themselves to simple measures of operative fixation with perfect reduction of the fracture, and this is to be recommended where conditions are satisfactory. A single or double screw may be used and a moderate degree of stability achieved. These fractures are not uncommonly indirectly compound and immediate operative fixation may well be combined with excision of the wound. Where there is risk of infection it is not yet certain whether the introduction of even the minimal amount of metal is justifiable. It is probable, however, that a single screw can do little harm in an open wound.

TECHNIQUE After adequate rest and preparation of the patient (which does not mean complete removal of his clothes, and preparation of the wound area) the patient is taken to the theatre. The sooner this can be done after the infliction of the injury and treatment of shock the better. Here, when under the anæsthetic, the clothes are removed and the wound prepared. The technique is described on p. 129. The limb is wrapped in a sterile towel and an Esmarch bandage applied to exsanguinate the limb, and a second Esmarch as a tourniquet. The wound is then excised in the usual manner and the open reduction of the fracture by the use of Lane's forceps and manipulation proceeded with. Inspection of the fracture ends determines the correct position of the screw or screws which should run as far as possible at right angles to fractured surfaces. A drill hole, one sixty-fourth of an inch smaller than that of the screw, is made in the correct direction and followed by a screw. A second screw is inserted if necessary. The periosteum and soft tissues are drawn together by a few interrupted stitches and the skin carefully closed. In the leg hæmostasis is usually satisfactory but

elsewhere the tourniquet should be released and haemostasis established. If any incision remains a drain should be inserted for twenty-four hours. The limb is then firmly wrapped in a thin layer of cotton wool and bandaged. Over this a light plaster cast is carried up to the knee and the limb is rested on a Braun's splint.

AFTER TREATMENT In this type of fracture the rigidity imparted by the screws to the limb is variable and the after-treatment is modified to suit the degree of rigidity obtained. Early movements are the goal of treatment, but adequate rest must be given for the wound to heal. Accordingly at the end of the seventh to the tenth day the plaster is guttered, and if the wound is satisfactory and the leg firm active exercise to the knee and ankle are begun in the bed. The plaster gutter splint is worn at night and if the patient is allowed up on crutches. At the end of the sixth week the movements of the ankle are satisfactory, and no harm ensues if the patient is given a weight-bearing plaster. It is usually sufficient if this comes only as far as the knee. This is removed at the twelfth week when union is usually firm. Where the fracture is not firm enough for early exercises a long leg plaster may be applied and weight-bearing begun. As the fracture gains in rigidity this may be reduced to a below the knee plaster, or the plaster gutter splint be substituted and exercises to the ankle commenced.

Spiral or Helical Fractures

Provided that there is no comminution of the sharp ends of the bone these fractures lend themselves particularly to fixation by screws. The fracture is so shaped (Fig. 3) that it interlocks firmly, and provided it cannot be rotated it resists deformation. It is therefore very convenient to treat these cases by single or double screw fixation in the manner previously described. A rigid limb is obtained which can be given exercises very early and in which it is unnecessary to use a plaster cast. If early weight-bearing is desired a walking plaster may be applied between the fourth and the sixth week. Consolidation takes ten to twelve weeks.

At operation definite evidence of the difficulties of non-operative reduction may be seen in the form of displaced fragments of bone or interposed soft tissues. Perfect reduction by any other method except in cases where the fracture is subperiosteal and needs only closing by the correct rotation of the foot is almost impossible. Similar conditions apply to oblique and half-oblique fractures.

NON-OPERATIVE REDUCTION OF OBLIQUE AND TRANSVERSE FRACTURES The difficulty in these cases is the prevention of shortening. Angulation and rotation can be controlled more easily and are



FIG 545 Spiral (helical) fracture of both bones of the leg—due to external rotation violence



FIG 546 Perfect reduction of previous case with a single screw



FIG 547 Skeletal traction in reduction of a fracture of the leg—ready for plastering (Hawley Scanlon table)

both important, particularly rotation which is apt to be neglected. Some form of skeletal traction is necessary for reduction and continuation of traction is usually necessary for retention as there is a

tendency for the leg to shorten inside the plaster as the swelling subsides. In order to overcome this the use of two pins incorporated in the plaster has been suggested. This method, though excellent for retention, is apt to produce permanent distraction of the fragments with resultant delay in union. More satisfactory is the use of one pin through the plaster and tibial tuberosity to prevent sliding of the plaster on the leg and the control of the lower fragment by the plaster around the foot. Less forcible distraction is likely to result if this is done. Reduction is carried out on the Braun's frame by means of a wire through the os calcis or the lower end of the tibia. Shortening can usually be corrected by clinical observation, but if



FIG 548 Bohler's leg traction apparatus in use for the reduction of a fracture of both bones of the leg. The accurate control of the fracture and the ease of plastering are well demonstrated.

there is any doubt radiological control should be sought. The tibial tuberosity is transfixed by a Steinmann's pin and the foot and both pins and wire incorporated in the plaster. If the fracture is fresh and swelling is anticipated a thin cotton wool padding should be employed. In any case a turn of flannel bandage should be taken around the malleoli and over the dorsum of the foot which are liable to pressure. The Kirschner wire is removed from the heel and the leg rested on a Braun's splint. Correction of rotation and angulation may be made by making a circular cut through the plaster at the level of the fracture, and either rotating the lower fragment or wedging the plaster. The patient is able to get about on crutches, the plaster being continued above the knee if the fracture is in the upper third of the tibia. As soon as consolidation

starts, about the sixth week, the upper pin may be removed and a fresh weight bearing plaster applied

Continuous traction This is an alternative method by which the



FIG 549 An oblique fracture of the shaft of the tibia with a fibula fracture higher up under treatment by skeletal traction in the calcaneus the whole leg being supported in a light plaster




FIG 550 A The malposition developed in an unsupported leg lying on a Braun's splint B The position correctly maintained by traction support to the foot and the correct bandaging of the splint so that the calf can rest a little into the bandages Foot drop is prevented by strapping based along the sole of the foot over the transverse bar and along the dorsum and bandaged on




FIG 551 The method of securing a comminuted fracture of the tibia by double pinning A Collar on upper pin B and C Upper and lower Steinmann's pins D Plaster covering lower pin E Collar on lower pin to prevent rotation F Walking plaster

effect of the upper pin is replaced by a continual pull on the leg It is undesirable if the pull is taken through the os calcis as the ankle joint is then under continuous tension and considerable stiffness of

the joint results. Traction through a pin in the lower end of the tibia is not so open to objection. In both cases knee movements will be restricted by the necessity to continue the plaster above the knee with the knee in slight flexion to control rotation. The weight employed will vary with the individual's weight, being about a tenth of it (10 to 15 lbs). The weight is gradually reduced till at the end




FIG 552 An oblique fracture of the tibia showing the satisfactory position obtained by plaster when the patient was recumbent



FIG 553 The same case showing the effects of too early weight bearing in a walking plaster. Note the high fibula fracture

of the third week it is 7 to 10 lbs. About the sixth week a long walking plaster is substituted and weight bearing commenced.

Comminuted fractures The problem is usually essentially the same as that of an oblique fracture, but slightly increased difficulty is met with due to the greater loss of lateral stability. Occasionally a comminuted fracture of the type shown in Fig 554 is met with, or a double transverse fracture in which shortening is not much in evidence and which can be controlled by a simple plaster cast. More commonly reduction by skeletal traction and pin transfixion of the upper fragment is necessary.

The grossly comminuted fracture is unsuitable for open operative reduction (Fig 73). Non union is an uncommon sequel, comminuted fractures usually consolidating well. In the butterfly type of fracture, in which one large fragment is lying free, operative fixation by double screws (Fig 554) may be desirable. Comminution is often combined with an open wound and excessive removal of

loose bone fragments should be avoided. Even if the larger fragments are completely detached they should be left, as they encourage the formation of new bone.

Compound fractures Compound fractures of the leg are particularly common. They are very commonly indirect compound fractures from the perforation of the skin by a sharp spicule of bone. Should the spicule be seen externally and be small it may be advisable to cut it off before excising the wound in the usual manner. Indirect compound fractures (which was the injury from which Percival Pott himself suffered) have a good prognosis as far as infection is concerned, and adequate excision of the wound should result in all of them healing by first intention. Operative fixation of such fractures can thus be safely undertaken at the time of operation.

Gross compound fractures are treated on the lines previously described. Owing to the subcutaneous nature of the bone drainage is usually satisfactory and dependent drainage seldom necessary. Immobilisation of such fractures must be

complete and the plaster must extend above the knee. If there is danger of shortening continuous skeletal traction may be employed, or if there is no risk in insertion a pin should be put through the tibial tuberosity. Elevation of the leg is important and the patient should be made comfortable by slinging the leg on a Thomas splint rather than resting it on a Braun's splint.

Fractures of both bones of the leg in children These fractures



FIG 554 The double oblique (or butterfly) fracture of the tibia with a fracture of the fibula high up treated in plaster with continuous traction

are commonly greenstick and in the milder case it may be sufficient to keep the child off its feet until it shows a desire to get up on them again. In more painful cases a plaster cast to the knee is necessary. In most other fractures a satisfactory position can be obtained by manipulation and plaster. Minor degrees of deformity can be neglected as they will be corrected by growth. The plaster should in all cases be carried above the knee as no danger of stiffness is present and children soon loosen any plaster.

Difficulties with fractures of both bones of the leg **DELAYED UNION** Union is often slow. The best treatment is repeated walking plasters, which may be accompanied in some cases by an osteotomy of the fibula, which if united may be holding the tibial surfaces apart.

Non-union The junction of middle and lower thirds of the tibia is a classical site for this to occur, and any of the factors mentioned in the general discussion of this subject may be responsible while the treatment is also discussed there (Fig. 54).

ANGULATION In late cases this is usually due to too early weight bearing. In recent cases it is best corrected about the tenth to fourteenth day by a fresh plaster and wedging (Fig. 54).

PRESSURE SORES on the heel and malleoli. A small pad of felt may be put over the heel to avoid any risk of this. The malleoli are commonly affected when the traction is released on the heel after the plaster has set. They then displace slightly inside the plaster and develop pressure points. A turn or two of flannel bandage gives sufficient room to avoid this.

EXTERNAL POPLITEAL (PERONEAL) PALSY This commonly arises from the pressure of the upper rim of the plaster on the nerve. It is avoided if a strip of felt is placed over the head of the fibula and the plaster always continued up to the level of the fibula head and not stopped short over the fibula neck.

REFERENCES

Shaft

- WATSON JONES "Fractures of the Shafts of the Tibia and Fibula. A New Tibia Traction Apparatus," *J Bone and Joint Surg*, 1932, 14, 591.
 WATSON JONES "The Treatment of Fractures of the Shafts of the Tibia and Fibula," *J Bone and Joint Surg*, 1932, 14, 591.
 CALDWELL "Treatment of Compound Fractures," *Arch Surg*, 1937, 35, 368.

CHAPTER XXXI

FRACTURES OF THE LOWER END OF THE TIBIA AND FIBULA

Surgical anatomy The capsule of the ankle joint is attached to the tibial epiphysis, the epiphyseal line lying completely above it. To appreciate the more complicated points of lesions of the ankle a detailed knowledge of the anatomy of the bony surfaces of the region is essential. We can only mention the more important points here. The tibio fibular mortice is much deeper on the outer side, corresponding to the lower position of the fibular malleolus, which lends lateral support to the ankle. This is compensated for medially

by the strength of the deltoid ligament. Posteriorly the tibial articular surface is deeper than anteriorly, and this is increased by the lateral malleolar ligament. The upper surface of the talus is convex, with a sharp lateral margin and a curved medial margin, and it is broader anteriorly than posteriorly, so that lateral movements at the ankle are impossible in the dorsiflexed foot but possible in the plantar flexed, when the narrow posterior portion is engaged in the tibial mortice. These are the only movements occurring at the ankle joint, inversion and eversion of the heel take place at the subtaloid (subastragoid) joint, while inversion and eversion of the forefoot are usually combined with adduction and abduction and take place at the intertarsal and tarso metatarsal joints.

In 4 per cent of cases, however the fibular collateral ligament is unusually lax and on inversion of the foot the talus twists in the tibio fibular mortice. This must be borne in mind in examination




FIG. 553. Transverse section of the tibia and fibula immediately above the ankle joint. A-B axis of movement of the ankle joint. C-D, malleolar axis. The angle of 30 degrees made by this with the axis of the ankle is shown also the relationship of the anterior and posterior tuberosity of the tibia to the fibula in an A.P. radiograph (see Fig. 466).

of ankles under inversion strain to determine the degree of ligamentous damage present.

The ankle joint depends on its stability on the strong bony mortice supported by the collateral ligaments of the ankle. The ankle joint is weakest anteriorly and posteriorly, and it is through these weak areas that dislocation of the talus most commonly occurs. As the grip of the mortice on the talus is only relaxed in plantar flexion it follows that it is only in this position that complete dislocation of the talus can occur without fracture of the ankle. Incomplete dislocation of the talus is not uncommon and its degree is the

really important feature in lesions in the ankle region, as it is the true measure of the amount of damage done

The range of movement of the ankle joint is surprisingly limited. Dorsiflexion and plantar flexion of the foot take place through an arc of 40 degrees, the apparently greater range being due to additional movement at the tarsal joints. Of particular importance in the study of the lesions of the ankle is the tibiofibular syndesmosis. This joint imparts an elasticity to the mortice which would otherwise be lacking. If the tibiofibular mortice is firmly closed by a screw passing across it, dorsiflexion of the foot will be prevented. There are three chief ligaments responsible for maintaining the apposition of the fibula and they are important as on the sequence of their rupture, and




FIG 556 The ligaments of the tibio fibular syndesmosis seen from the lateral aspect —

- A Anterior tibio fibular ligament
- B Posterior tibio fibular ligament
- C Anterior talo fibular ligament
- D Posterior talo fibular ligament
- E Calcaneo fibular ligament

If the ligament ruptured, the many variations of fracture of the fibula depend on the ligaments are —

1 The anterior tibio fibula. This is a short and strong ligament which runs from the anterior tubercle of the tibia to the anterior aspect of the fibula. It permits the two millimeter upward and backward movement present.

2 The posterior tibio fibular ligament. This is a longer ligament spreading out on the back of the posterior tibial tubercle, and which is slacker than the anterior. Part of the ligament deepens the mortice, and is known as the lateral malleolar ligament. Division of the anterior ligament allows the tibia to be separated from the fibula for one centimetre, the condition often present in diastasis.

3 The interosseous membrane This is ruptured in its lower portion in a few cases where the anterior ligament is torn It can only be ruptured completely if the anterior and posterior ligaments are torn

It is important to note the fact that the axis of movement of the ankle and the bi malleolar axis make an angle of 30 degrees with each other (Fig 555), and that if the tibio fibular joint is to be accurately seen the foot must be




FIG 557 The ligaments of the ankle from behind —

- A Commencement of the interosseous membrane
 - B Posterior tibio fibular ligament
 - C Transverse ligament of the ankle joint—a continuation of the posterior tibio fibular ligament deepening the tibial surface for the talus
 - D Posterior talo fibular ligament
 - E Calcaneo fibular ligament
 - F Posterior talo tibial ligament
 - G Calcaneo tibial band
- } 2nd and 3rd parts of deltoid ligament

turned inwards for 30 degrees so that the bi malleolar axis is parallel with the plate

It is also important to note that the anterior tubercle of the tibia is always the more prominent tubercle in the radiograph though it gives the impression to casual inspection of lying behind the fibula (Fig 466)

Introductory The lesions occurring around the ankle joint are simple in origin though complex in variety An understanding of the mechanism makes the appreciation of the large variety of lesions met with fairly easy, and is well worth the trouble spent It will be found that the forces occurring can be resolved into four main

groups, though most often occurring in combination. These are (1) External rotation, (2) Abduction, (3) Adduction, (4) Compression. The lesions following the application of these forces follow a pattern due to the sequence of ligamentous rupture, or the yielding of the malleoli.

The serious consequences of ankle injury are dependent, firstly, on damage to the weight bearing portion of the ankle, and, secondly, on ligamentous injury. It is extremely important to bear in mind the fact that ligamentous injury may occur without bone damage. In any case in which the degree of bruising is disproportionate to the radiological evidence of damage ligamentous lesions must be excluded. It is therefore necessary to examine all such cases radiographically under strain to test for separation of bone surfaces (Fig 538). This is best done under pentothal anaesthesia and comparison with the opposite side should not be neglected. It has been mentioned already that 4 per cent. of patients will show some twist of the talus in the tibio fibular mortice in both ankles (hypermobile ankles).

The strains usually employed are —

- 1 Adduction strain. Rupture of the fibular collateral ligament
- 2 Abduction strain. Rupture of the deltoid ligament
- 3 External rotation strain. Rupture of the anterior tibio fibular ligament and diastasis
- 4 Plantar flexion. Rupture of the anterior fasciculi of both collateral ligaments, and diastasis

Fractures of the Lower End of the Tibia and Fibula

- 1 Supra-malleolar injuries
- 2 Separation of the lower tibial epiphysis
- 3 External rotation fractures of the ankle, first, second and third degree (with diastasis)
- 4 Abduction fractures of the ankle. First, second and third degree (with diastasis)
- 5 Adduction fractures of the ankle. First, second and third degree (no diastasis)
- 6 Ligament traction (sprain) fractures (no diastasis)
- 7 Marginal fractures of the lower end of the tibia. Anterior and posterior
- 8 Compression fractures

DIAGNOSIS Owing to the subcutaneous nature of the bones, and the comparative simplicity of the gross movements at the ankle, lesions of the bones can usually be diagnosed with accuracy by clinical examination unless the case is seen late when swelling, which is often gross, renders any examination difficult. This



FIG. 558. Severe sprain of the ankle. Rupture of the fibular collateral ligament without fracture. The dislocation of the talus is only seen if the ankle is X-rayed in strong inversion. The severity of the injury would consequently not be appreciated in the usual X-ray.



FIG. 559. Fracture of the lower end of the tibia involving the ankle joint due to direct violence.



FIG. 560. The same case after reduction by manipulation and fixation in plaster.

swelling is due to venous rupture accompanied by œdema from the dependency of the leg, and the preliminary treatment of all cases includes elevation of the leg and fixation of the foot till

accurate investigation is possible. Routine examination then includes

1 *History* The accurate details of the accident shed much light on the probable fracture.

2 *Inspection* Deformity is usually present in any serious lesion, but bruising may be extensive in the absence of severe injury. Abrasions should be noted, particularly as regards their site.

3 *Palpation* This may reveal bony irregularities, crepitus, and particularly areas of deep tenderness.

4 *Movements* In sprain upward pressure on the sole is usually



FIG 561 Fracture separation of the lower tibial epiphysis. The posterior displacement of the epiphysis with an attached fragment of the diaphysis and the fibula is well shown.



FIG 562 The same case after reduction.

painless, while in fracture it is usually painful. Inversion and eversion will produce pain over the injured malleolus. Lateral movement in the ankle joint may be detected.

The most important examination to be made is a true antero-posterior and true lateral radiograph of the joint. It is possible in such films to overlook a "mixed" oblique fracture of the fibula with no displacement if the fibula is entirely hidden by the tibia. This indicates an oblique film, the fibula lying just behind the tibial shadow in the true lateral radiograph (Fig 571).

Supplementary radiological examinations which may be helpful in difficult cases are —

(a) The bi malleolar film, which shows up the syndesmosis, giving evidence of minor degrees of diastasis

(b) Radiographs under strain, previously mentioned

(c) A radiograph of the opposite ankle in inversion, to exclude the hypermobile ankle, necessary in cases which are clinically hypermobile

(d) A radiograph of the upper end of the fibula to exclude fracture of the neck associated with rupture of the anterior tibio fibular ligament (Maisonneuve's fracture) (Fig 609)

Supra-malleolar fractures Such fractures are the result of



FIG 603 Uneven growth of the tibial epiphysis after a fracture of seco degree adduction type There has been a vertical fracture of the medial malleolus and a sprain fracture of the tip of the fibula which has failed to unite

direct violence in adults, but in children they are often due to indirect violence In these cases the relationship of the bony points around the ankle will be normal unless the fracture has run down into the joint, and abnormal mobility will be elicited above the joint level If the joint surfaces are not involved the outlook is good, as it is easier at this level to restore the correct alignment of the leg Union is rapid Frequently the fracture line is oblique, but in spite of this reduction by manipulation and retention by

plaster alone is possible. Occasionally one has to use skeletal traction through the calcaneus. For further details of treatment the chapter on fractures of the tibia should be consulted.

Separation of the lower tibial epiphysis. Complete or incomplete separations are not uncommon in children occurring up to the age of sixteen years. Usually a wedge shaped portion of the diaphysis accompanies the epiphyseal fragment. The common directions of displacement are medial, anterior and posterior. The presence of the fibula prevents lateral displacement, though this may occur if accompanied by fracture of the fibula.

Manipulative reduction is usually simple, the epiphysis



FIG 564 Reduction of a posterior displacement of the lower tibial epiphysis over a padded wedge




FIG 565 The epiphyseal line at the lower end of the tibia showing how it is involved in adduction fractures and the medial malleolus which may lead to premature synostosis where the fracture crosses the epiphyseal plate

being forced back in the appropriate direction by the pressure of the palm. In posterior displacements (Fig 561) it is often easiest to turn the patient over on his face and reduce the deformity over a wedge (Fig 564). After reduction a plaster slab is applied and control radiographs taken. If these are satisfactory, as soon as swelling has subsided a walking plaster is applied. Union is firm in six weeks.

On rare occasions the epiphysis may be fractured in the centre from compression violence. There is little separation as a rule, and the treatment is similar. With severe adduction strain the medial malleolus may be separated from the epiphysis, often taking a small metaphyseal chip with it. The lesion resembles a first degree

adduction fracture and if displaced is treated in the same manner (Fig 595)

Interference with growth rarely follows this fracture but may occur (Fig 563) It is more common following compression lesions of the epiphysis In each case the mechanism is the same, premature synostosis of both sides of the plate occurring at the site of fracture and restricting growth at this area

FRACTURES AND FRACTURE DISLOCATIONS OF THE ANKLE

It is an interesting fact that in spite of several authoritative articles on these fractures, the types and mechanism are still, if not ill-understood, at least badly described in most textbooks on the subject (See note below) Authors are content to describe abduction (fibula flexion) and adduction (tibial flexion) injuries, but do not distinguish the injuries due to external rotation of the foot They are usually discussed together with abduction lesions as the mechanisms are sometimes combined There are, however, a series of well-recognised lesions due to external rotation alone, and their recognition is essential to the appreciation of the mechanism of all other lesions The multiplicity of lesions possible has perhaps daunted the student and so prevented the true appreciation of their mechanism, but it will be seen that all lesions are capable of comparatively simple grouping

The injury in the majority of cases is due to forced external rotation of the foot, or, what amounts to the same thing, internal rotation of the tibia on the fixed foot Forced abduction and forced adduction are of less frequent occurrence Internal rotation of the foot can be neglected as a separate mechanism, as on the application of internal rotation force the foot passes into adduction This is favoured by the mechanical construction of the ankle and the slope of the metatarsals Strong external rotation, however, turns the foot into a rigid lever, and if to this movement is added dorsiflexion, the foot tends to pass into an abducted position These points can be verified by anyone on their own foot This tendency of the dorsiflexed foot to pass into abduction accounts in part for the combined lesions which are seen In 70 per cent of all cases, however, the mechanism is one of external rotation alone, and in 33 per cent of all cases of ankle injury the lesion is a "mixed oblique" (see note below) or first degree external rotation fracture

Fractures and fracture dislocations will therefore be discussed under the following grouping

Note—Fractures of the ankle are commonly lumped together under the name of 'Pott's fracture' or 'Dupuytren's fracture' Unfortunately both these men worked without the aid of radiography and both described a

fracture which it is difficult to recognise to day as they did not give sufficient detail of the ligamentous rupture accompanying it. The commonest fracture of the ankle which both Pott and Dupuytren thought they were describing is the first degree external rotation fracture, first accurately described by Maisonneuve in 1840. His name, which should be perpetuated in the name of this fracture, is attached to the rarer torsional fracture of the fibula just below the head, for which a preliminary tibio fibular diastasis is necessary.

The term "mixed oblique" fracture for this first degree external rotation lesion has been coined by Desrot. It is called "mixed" because the fibula is involved both above and below the tibio fibular syndesmosis.

FRACTURES IN WHICH THE TIBIO-FIBULAR SYNDESMOSIS REMAINS INTACT

Fractures by External Rotation

- 1 First degree Mixed oblique " fracture of the fibula
- 2 Second degree " Mixed oblique " fracture of the fibula together with
 - (a) Rupture of the deltoid ligament
 - (b) fracture of the medial malleolus
- 3 Third degree Either second degree lesion together with fracture of the posterior articular margin of the tibia (Diebrowan's third malleolus)

Fractures by Abduction Fibular flexion

- 1 First degree Transverse fracture of the medial malleolus only. As a variant rupture of the deltoid ligament
- 2 Second degree Fracture of the medial malleolus or rupture of the deltoid together with
 - Fracture of the fibula below the tibio fibular ligaments (Bi malleolar fracture)
- 3 Third degree Any second degree lesion associated with a fracture of the posterior margin of the tibia

Fractures by Adduction Tibial flexion

- 1 First degree Transverse fracture of the lateral malleolus below the tibio fibular syndesmosis.
 - Vertical linear fracture of the medial malleolus
- 2 Second degree Both first degree lesions together with some or no displacement (Bi malleolar fracture)
- 3 Third degree Second degree lesion together with fracture of the posterior margin of the tibia

Fractures by Compression

- Anterior marginal fractures
- T and Y shaped fractures and comminuted fractures
- Posterior marginal fractures (Diebrowan's third malleolus) distinct from fractures of the posterior tubercle

FRACTURES IN WHICH THE SYNDESMOSIS YIELDS COMPLETELY OR IN PART (DIASTASIS)

The three ligaments holding the fibula to the tibia may yield singly or in combination. They are only ruptured by external rotation or abduction violence, and the ligaments injured can be deduced from the fracture.

1 First degree Rupture of the anterior tibio fibular ligament, with fracture of the fibula high up, below the neck (Maisonnevieu's fracture (Fig. 609))

2 Second degree Rupture of the anterior ligament and the interosseous membrane, with a fracture of the fibula $2\frac{1}{2}$ inches above the malleolus (Dupuytren's fracture) (Fig. 612)

3 Third degree Rupture of anterior and posterior ligaments and of the interosseous membrane, with fracture of the shaft of the fibula high up and wide separation of the syndesmosis (Fig. 615)

4 Fracture of the posterior tubercle of the tibia. This amounts to a detachment of the posterior tibio fibular ligament, but is due to external rotation combined with plantar flexion. Fracture of the fibula may occur above the syndesmosis due to rotation of the lower end of the fibula around the intact anterior tibio fibular ligament. Displacement is small due to the intact interosseous membrane (Figs. 608, 611)

This classification is based on mechanism, but fits in with the radiological and anatomic pathological classification. It is backed by the experiments on the cadaver carried out as long ago as 1877 by Hohlgeschmied, and the three degrees of injury run parallel to the severity of the damage, the treatment and the prognosis, besides showing a similarity from group to group.

First degree external rotation injury The conversion of the foot into a rigid lever by external rotation results in a twisting of the talus in the mortice of the tibio-fibular syndesmosis. Mechanical principles determine that the strain will fall on the anterior margin of the fibular malleolus to a maximal extent. This push on the anterior margin of the fibula is supplemented by the pull on the posterior margin or the posterior tibio fibular ligament. These combined forces produce a torsion strain on the lower end of the fibula, which is attached most firmly to the tibia by the anterior tibio-fibular ligament. As a result the fibula snaps in a characteristic manner. A torsional fracture is produced (Fig. 568), which is obviously spiral, or else oblique and runs from the posterior surface of the fibula downwards and forwards to end on the anterior aspect of the lateral malleolus just below the level of the lower tibial articular surface. This course leaves the anterior tibio fibular ligament intact, which unites the sharp end of the proximal fragment to the tibia. The fracture line thus runs obliquely between the anterior and posterior tibio fibular ligaments, being extra capsular above and intra-capsular below (hence the term Mixed Oblique fracture). It will be noted that the talus remains attached to the lower end of the fibula and that this is attached to the tibia by the posterior tibio fibular

ligament This allows a small range of movement depending on the damage to surrounding soft tissues, and it is obvious that if the




FIG 566 A P diagram of a first degree external rotation fracture ('mixed oblique') of the fibula

- A Shading indicating plane of fracture
- B shadow of anterior tuberosity
- C shadow of posterior tuberosity




FIG 567 Lateral view of a first degree external rotation fracture

- A Attachment of anterior tibiotalar ligament (sometimes pulled out forming Pilleaux's third fragment)
- B The strong posterior tibiotalar ligament




FIG 568 Mixed oblique fracture of the fibula showing the ligamentous attachments to the fragments



FIG 569 Section of Fig 568 at A showing line of fracture of the fibula between the anterior and posterior tibiotalar ligaments




FIG 570 Section of Fig 568 at B showing the mechanism of fracture. The pressure of the talus at A and the pull of the posterior tibiotalar ligament at B develop a couple acting on the lower end of the bone

posterior tibiotalar ligament was ruptured the condition would be similar to that seen in a diastasis

The degree of damage done depends on whether the force ceases to act after the fibula has snapped. We may thus get —

- 1 Subperiosteal spiral fracture with no displacement
- 2 A fracture with moderate displacement (Fig. 571)
- 3 A fracture in which there has been marked displacement probably spontaneously reduced, but indicated by the signs of damage to the anterior fibres of the deltoid on the opposite side of the ankle (Fig. 572)



FIG. 571 First degree external rotation fracture. This fracture is typical but differs from the more commonly seen lesion in that the fracture line is unusually oblique and there is more separation of the fractured surfaces. The X P film shows no diastasis and no displacement (Compare with Fig. 567)

Treatment The displacement of the fragments in this first degree lesion is, as a rule, minimal, indicating that the periosteal sheath of the fibula is probably intact, and the mechanics of the ankle will be little disturbed. The weight-bearing capability of the joint is undiminished, and consequently the fracture can be treated in a number of cases by a supporting bandage, it being sufficient to avoid further external rotational strain.

LOCAL ANESTHESIA This is primarily directed to the relief of pain, and satisfactory results will be obtained by the immediate injection of the fracture line with local anesthetic, bandaging, and the early use of the limb. The pain of the injury having been relieved by local anesthesia, the next essential is the prevention of swelling by firm bandaging of the ankle over cotton wool, and

elevation of the limb. Immediate strapping with elastoplast is often painful as it does not expand sufficiently to accommodate the amount of swelling which may occur. The most essential part of the treatment is the encouragement of the patient to exercise the ankle after the pain has been abolished. Without this the value of the injection is problematical. Early radiant heat and massage should be given, and if the pain is not completely relieved a further injection should be given (10-20 ccs. 1 or 2 per cent novocaine). According to the amount of pain, the degree of swelling present and the



Fig. 372 First degree external rotation fracture of the ankle with lateral dislocation



Fig. 373 First degree adduction fracture



Fig. 374 Second degree external rotation fracture. Compare the torsional fracture of the fibula with that in the figure above. (See Fig. 370.)



Fig. 375 Same case as in previous figure after reduction

The degree of damage done depends on whether the force ceases to act after the fibula has snapped. We may thus get —

1 Subperiosteal spiral fracture with no displacement

2 A fracture with moderate displacement (Fig 571)

3 A fracture in which there has been marked displacement probably spontaneously reduced, but indicated by the signs of damage to the anterior fibres of the deltoid on the opposite side of the ankle (Fig 572)



FIG 571 First degree external rotation fracture. This fracture is typical but differs from the more commonly seen lesion in that the fracture line is unusually oblique and there is more separation of the fractured surfaces. The AP film shows no diastasis and no displacement (Compare with Fig 567)

Treatment The displacement of the fragments in this first degree lesion is, as a rule, minimal, indicating that the periosteal sheath of the fibula is probably intact, and the mechanics of the ankle will be little disturbed. The weight bearing capability of the joint is undiminished, and consequently the fracture can be treated in a number of cases by a supporting bandage, it being sufficient to avoid further external rotational strain.

LOCAL ANESTHESIA This is primarily directed to the relief of pain, and satisfactory results will be obtained by the immediate injection of the fracture line with local anesthetic, bandaging, and the early use of the limb. The pain of the injury having been relieved by local anesthesia, the next essential is the prevention of swelling by firm bandaging of the ankle over cotton wool, and

elevation of the limb. Immediate strapping with elastoplast is often painful as it does not expand sufficiently to accommodate the amount of swelling which may occur. The most essential part of the treatment is the encouragement of the patient to exercise the ankle after the pain has been abolished. Without this the value of the injection is problematical. Early radiant heat and massage should be given, and if the pain is not completely relieved a further injection should be given (10–20 ccs 1 or 2 per cent novocaine). According to the amount of pain, the degree of swelling present, and the



FIG. 572 First degree external rotation fracture of the ankle with lateral laceration



FIG. 573 First degree adduction fracture



FIG. 574 Second degree external rotation fracture. Compare the torsional fracture of the fibula with that in the figure above (See FIG. 576)



FIG. 575 Same case as in previous figure after reduction

weight, age, and ability of the patient, a decision is made at the end of a few days as to when weight bearing in a boot can be commenced.

Alternative lines of treatment are a light plaster walking cast or use of an Unna's paste stocking after swelling has subsided. Both these methods fail to get rid of the oedema and swelling so rapidly as novocaine injection and early exercises.

Where the displacement has been marked as indicated by swelling, haemorrhage, and possibly persistence of deformity in the radiograph, the ankle is not stable and is unsuitable for early weight bearing and exercises. An injection of novocaine can be given to




FIG 576 Second degree external rotation fracture of the ankle—A.P. view




FIG 577 Lateral view of same case. Note that the oblique fracture of the fibula is partly intra articular partly extra articular

reduce pain and enable massage to be given, but the ankle will need support in a posterior gutter splint, and as soon as swelling has subsided should be put in a short walking plaster for three weeks. At the end of this period some rehabilitation will be required and a crepe bandage will be necessary to control the oedema around the ankle. The use of an Unna's paste stocking makes massage impossible though quite satisfactory in the younger case.

The prognosis in this type of case is excellent. Many mild cases will be walking well at the end of the first week. In the more serious group six weeks may elapse before recovery takes place completely. There should be no persistent disability.

Second degree external rotation injury. A. With rupture of the

deltoid (tibial collateral) ligament B Associated with fracture of the medial malleolus

In these cases the deforming force has continued to act after the torsion fracture of the fibula has occurred, and the displacement of the talus moving with the lower fibula fragment puts strain on the deltoid ligament, which ruptures or more commonly fractures the



FIG 578 First degree external rotation fracture of the fibula accompanied by rupture of the attachment of the deltoid ligament—the equivalent of a second degree injury. Note the ligament separates at its periosteal attachment



FIG 579 Second degree external rotation fracture. A mixed oblique fracture of the fibula complicated by rupture of the deltoid and displacement of the talus. There is a partial diastasis present due to rupture of the posterior tibiofibular ligament

medial malleolus by traction leaving a transverse fracture line (Fig 576)

Further displacement may result in the rupture of the posterior tibiofibular ligament (Fig 579) and a partial diastasis, which permits further outward displacement. With this degree of deformity and displacement of the talus it is obvious that the lateral stability of the ankle is destroyed, though the weight-bearing surfaces are still intact. The fracture must accordingly be treated more carefully to obtain a perfect result and to avoid redisplacement from too early weight bearing, or too loose a plaster.

TREATMENT Difficulty is again encountered from swelling which often necessitates several plasters before a firm close fitting walking plaster can be applied. When first seen the fracture is readily enough reduced by manipulation, which on account of the intact talo fibular ligament, and the small overhanging fragment of the medial malleolus, cannot be over reduced by strong medial pressure applied to the outside of the foot, with counter pressure by the hand on the medial aspect of the tibia. Care must be taken that the force applied moves the whole talus across, and does not merely invert the ankle. A plaster retaining slab is then applied to encircle the foot and leg for two thirds of its circumference, holding the fracture reduced, and the foot in dorsiflexion and unrotated. This is held in position with a gauze bandage, and the controlling manipulation continued till the plaster has set. The foot is then elevated on a Braun's splint, and control radiographs taken. Should the position be unsatisfactory the ankle is remanipulated, if local anæsthesia has been used, preferably before this has worn off. Once satisfactory reduction is obtained, the leg is carefully watched, and, if necessary replastered, till swelling has subsided sufficiently for a close fitting skin tight walking plaster to be applied. This is usually about the end of the second week. After the patient has walked in the plaster cast for a few days a control radiograph is taken through the plaster to see if redisplacement has occurred. The tendency most frequently seen is for the talus to become everted, so that some inversion of the heel in applying the plaster is no disadvantage, but the foot must be at right angles to the leg, and unrotated. Any tendency to redisplace in the plaster demands further rest, reduction and plaster. With injuries of this severity the plaster must be worn for some six to eight weeks from the date of the accident, and its removal will need to be followed by an elastic stocking, elastoplast or Unna's paste stocking for two to three weeks, during which time exercises are encouraged. At the end of this time free full movement of the ankle should be possible. After the removal of the plaster it is an advantage to give the patient a valgus insole to wear for a few months till the normal muscle tone of the leg has returned.

Third degree external rotation injury The continuation of the force separates the posterior aspect of the lower tibial articular surface (Trethowan's third malleolus). This lesion is occasionally seen alone (Fig 617) when there is no displacement of the foot backwards, and is then due to compression injury. In the third degree rotation fracture the lesion is due to a combination of compression injury, and a backward resultant force developed by the rotation of the cylindrical upper surface of the talus on the curved

lower surface of the tibia The fracture line runs vertically from the ankle joint to the posterior surface of the tibia, and a variable area of the articular surface may be involved The lower fibular fragment invariably moves with the detached tibial fragment owing to the strength of the posterior tibio fibular ligament, and the talus also moves backwards with the fibula because of the unbroken talo fibular ligament (Fig 587) In 25 per cent of cases the fracture is present without displacement, consequently it is considered that




FIG 580 Third degree external rotation fracture—long oblique fracture of fibula Note oblique and involvement of the anterior surface of the tibia in the fracture of the medial malleolus characteristic external rotation fracture of this process




FIG 581 A third degree external rotation fracture of the ankle after reduction showing fracture of the posterior tibial tubercle Compare with the more serious third degree lesion in which the articular surface is involved in a posterior marginal fracture (Fig 587)

displacement when present is due to the continuation of the injuring force

Posterior marginal fracture The posterior marginal fracture which characterises a third degree lesion, and allows backward and upward displacement of the talus, has to be carefully distinguished from fractures of the posterior tubercle of the tibia A much smaller fragment of tibia is involved in this case corresponding to the posterior wall of the groove in which the fibula lies and the attachment of the posterior tibio fibular ligament (Fig 581) It is a much less serious lesion, as the articular surface is barely involved, and the shallow curve of the lower surface of the tibia remains intact

That posterior marginal fractures are due to a combination of compression and rotation of the talus under pressure can be seen from the fact that they are most commonly associated with external rotation fractures and seldom with abduction fractures, while with adduction fractures they are extremely rare.

TREATMENT The most important feature of this lesion is the destruction of the weight bearing ability of the ankle, which remains intact in first and second degree lesions. The degree of interference with weight bearing will depend on the area of posterior articular surface detached, so that the seriousness of the condition is determined by the position in which the vertical fracture line enters the joint. If the fracture chips off only a small area from the posterior aspect of the joint, leaving the greater part of the curve of the lower articular surface of the tibia intact, then the interference with weight bearing is minimal (Fig 581). If, on the other hand, the fracture line enters the joint at the summit of this curve, then the stability of the joint will be completely lost, and the fracture line will be in a position where it is subject to maximum pressure in weight bearing, and so will be more likely to give rise to a later traumatic arthritis (Fig 586).



FIG 582 Appearance of the ankle in third degree lesions with posterior dislocation of the talus—third degree external rotation fracture

Accuracy of reduction of this fragment is therefore very important, and in certain cases will justify the opening up of the fracture and pegging the fragment in place. In 25 per cent of cases there is no displacement to reduce, and it suffices to treat these as second degree lesions, but weight bearing must be deferred in accordance with the degree of destruction of joint stability.

In the cases in which a large fragment is displaced (Fig 586), one of the following methods is adopted

- 1 Reduction and plaster by Robert Jones' method
- 2 Reduction and plaster under skeletal traction
- 3 Open operation

ROBERT JONES' METHOD This is a simple and effective method useful when working single handed and when no apparatus is available. The patient lies with the injured limb over the end of the table. A sling is tied over the anterior aspect of the tibia, consisting of a strong calico bandage of a length convenient to be held under the foot. A second similar but shorter sling is now

passed under the heel and over the surgeon's neck, so that on straightening his back he can exert pressure against the heel, the counter-traction being applied by the sling over the tibia (Fig 583) If a stockinette sling is placed over the foot and left long the patient or an assistant can readily maintain dorsiflexion by traction upon it. The surgeon's hands are thus left free to control the



FIG 583 The manual method (Robert Jones) of reduction of a third degree fracture of the ankle. Under local anaesthesia the patient is able to maintain his own dorsiflexion by pulling on the stockinette covering his foot. By straightening the back the dorsal dislocation is reduced and kept reduced while the two hands are left free for plastering and correcting lateral deformity. The bandages are cut away after the plaster has set.

lateral displacement. A plaster is applied over the bands which are cut after it has set.

SKELETAL TRACTION. By inserting a wire in the calcaneus and placing the limb under traction on a Böhler frame the upward displacement of the talus can be controlled. The continuous distraction leaves the hands free for controlling the lateral displacements and maintains dorsiflexion. It is convenient to apply the plaster over the Kirschner wire, which is later withdrawn. In

fresh cases the plaster is split down at once, or a posterior plaster slab may be applied followed by a long U shaped slab on the sides of the limb to control lateral movements. This leaves an unplastered area for expansion. The Kirschner wire is left in position and a weight of 7 to 10 lbs attached to it. This weight serves to separate the joint surfaces. The pin aids in retention and is convenient if further manipulation or plaster is needed. It is removed when the walking plaster is applied. This usually cannot be done till a period of four to five weeks has elapsed, if the stability of the joint is destroyed, though there is no objection to the patient getting about on crutches. The usual precautions with regard to swelling



FIG 354 First degree abduction fracture of the medial malleolus. Note transverse line of fracture. Compare with adduction and external rotation fractures of the medial malleolus.



FIG 355 The more common variety of second degree abduction fracture (One variety of bimalleolar fracture)



FIG 356 A third degree abduction fracture lateral radiograph

and oedema are taken with redoubled care. A walking plaster will need to be worn a further four to five weeks, making a total period of disability in the worst cases of twelve weeks, followed by a period of re education in which the limb is first put in strapping for three weeks and then freely exercised without the strapping.

OPERATIVE INTERFERENCE. It is usual for manipulative methods to fail, and in a number of cases it will be necessary to operate to obtain satisfactory reposition of the posterior fragment. A posterior approach is used and the fragment screwed into place. Complete visualisation of the fracture may be difficult, but if the upper margin can be seen and replaced the screw will close the lower fracture line in the joint. Radiological control at operation

may be used conveniently. It is possible to replace the fragment through a posterior medial incision where more care must be used on account of the posterior tibial vessels and nerves, and this approach may be conveniently used when it is necessary to fix the medial malleolus at the same time. The

after treatment is that of fractures reduced by manipulation.

Prognosis This is governed by the degree of ligamentous damage, the age of the patient, and the size of the displaced posterior fragment, together with



FIG 587 Third degree external rotation fracture. Note the posterior displacement of the talus to which the fibula has remained attached. The fibula shows a rotational fracture with a small triangle of bone separated. The medial malleolus is intact indicating rupture of the deltoid ligament. Tibio fibular diastasis has of course occurred.



FIG 588 Second degree abduction fracture of the ankle.

its response to attempts at reposition. If the fracture line runs high across the joint it is inevitable that there will be some dysfunction and the later development of traumatic arthritis.

Abduction fractures of the ankle. FIRST DEGREE Fracture of the medial malleolus only. (Rarely rupture of the deltoid ligament.)

SECOND DEGREE Fracture of the medial malleolus or tear of the



FIG. 589 AP radiograph of a first degree abduction fracture of the ankle. Note the almost transverse line of fracture.



FIG. 590 Lateral view of same case. Note that the displacement which appears minimal in the A P view is marked in this view.



FIG. 591 Same case fixed with a single screw.

second with fracture of the fibula below the tibio-fibular syndesmosis (B) malleolar fracture) (Fig. 588)

THIRD DEGREE Any second degree lesion plus fracture of the posterior margin of the tibia

The mechanism of abduction fractures is straightforward, and it has only to be remembered that this movement may be combined with external rotation, producing a combined lesion. Strain by abduction is first imposed on the deltoid ligament, which may yield,

but more commonly tears away the medial malleolus producing a transverse fracture line. The more external rotation is combined with abduction the more oblique the fracture line. This corresponds to the first degree lesion, and the torn deltoid may be overlooked if in suspicious cases the foot is not X rayed in inversion.

When either of these lesions have occurred the strain now falls on the inner aspect of the tibial malleolus, and the resultant fracture will depend on whether the tibio-fibular syndesmosis gives way. If it yields then the fibula fractures by flexion above the joint level. If it remains intact then the fibula snaps off below



FIG. 392 Fracture of the medial malleolus by adduction. The pisiform and soft tissues fall in between the fractured surfaces.




FIG. 393 On spontaneous reduction of the separation they remain caught between the fractured surfaces causing non union.

the joint level, producing a bi-malleolar fracture. The lesion associated with distraction and flexion fracture of the fibula above the joint is that most nearly akin to the lesion described by Pott.

In the third degree lesion there is an associated fracture of the posterior aspect of the tibia due to compression.

TREATMENT The treatment runs parallel to that of the corresponding external rotation lesions. The displacement being outward is corrected by forcing the foot medially on the fixed tibia. Care must be taken that the foot is moved across, and not merely inverted. The length of immobilisation, prognosis, and

after treatment is that of the corresponding external rotation lesion

Fracture of the Medial Malleolus This fracture is apt to fail to unite and remain a persistent source of discomfort. It is particularly the transverse fracture due to abduction which is liable to this complication which is due to the inclusion of soft tissue between the fracture surfaces (Fig 592). Where close apposition of the medial malleolus cannot be obtained by manipulation, open operation should be carried out and the fragment pegged into place (Fig 591) or screwed. Exposure and technique are easy. The higher the fracture and the more oblique the more likely the fracture is to unite without operation. In the vertical fracture due to adduction,



Fig 594 Transverse abduction fracture of the medial malleolus




Fig 595 Vertical adduction fracture of the medial malleolus




Fig 596 Spiral oblique fracture of the medial malleolus due to a combination of abduction and external rotation violence

operation is never necessary because of the risk of non union, though it may be desirable on account of the displacement

Fractures of the lower end of the fibula associated with abduction and adduction injuries. For details of the fractures when diastasis occurs p 530 must be consulted. When the interosseous ligaments hold the fibula snaps transversely through the syndesmosis. In adduction injuries it is broken just below level of the tibial surface by being bent over the lower margin of the tibia. In abduction injuries the fracture is a little higher, and if the lower portions of the anterior and posterior ligaments tear it may be above the level of the tibial articular surface. It remains, however irregularly transverse. Although in the majority of cases reduction of the malleolus is satisfactory there are a small group of cases in which, like the medial



FIG. 597 Ununited abduction fracture of the fibular malleolus



FIG. 598 The same case united after intramedullary bone peg

malleolus, a satisfactory position is not achieved due probably to the interposition of soft tissue. Non union may occur and if mani-




Fig 599 A first degree adduction fracture. First variety.
 Fig 600 Second degree adduction fracture occurring where the weight falls on the medial malleolus.
 Fig 601 A second degree adduction fracture (Second type of bimalleolar fracture) (Compare Fig 597).
 Fig 602 A P radio graph of a third degree adduction fracture (Compare Fig 603).

pulative reduction has failed, and the position is unsatisfactory, open operation and pegging of the fibula should be undertaken. It is best



Fig 603 Third degree adduction fracture of the ankle

to insert an intramedullary bone graft through the lower end of the fibula (Fig 598).



Fig. 604 Antero-posterior radiograph of a third degree adduction fracture



Fig. 605 Lateral film of the same case to show the separation of the posterior fragment but little displacement

Adduction fractures of the ankle **FIRST DEGREE** Transverse fracture of the lateral malleolus below the tibio-fibular ligament
 Vertical linear fracture of the medial malleolus

SECOND DEGREE Both first degree lesions together with some displacement (Bi malleolar fracture)

THIRD DEGREE A second degree lesion together with fracture of the posterior margin of the tibia

In adduction fractures the mechanism is the opposite of the abduction lesions, but there is one important variant. Adduction first puts strain on the fibula which snaps over the edge of the tibia, producing the first degree lesion with little displacement. This allows strain to fall on the medial malleolus which fractures from pressure on its joint side, characterised by the fracture line running vertically. This allows medial displacement of the ankle as a whole, the second degree lesion. The third degree lesion is a very rare accompaniment of adduction injury. It consists, as before, of a combination of the second degree lesion with fracture of the posterior margin of the tibia.

The important variant in this group is the vertical fracture of the medial malleolus which occurs alone in many cases, particularly the young in whom the elasticity of the fibular ligaments allows force sufficient to cause fracture to be developed without fracturing the lower end of the fibula. There is no displacement with this lesion which is classed as a first degree lesion. The additional possibility of rupture of the fibular collateral ligaments replacing the fracture of the fibula has to be considered, but on account of the strength of these ligaments its occurrence is of great rarity.

TREATMENT This resembles the treatment of the first, second and third degree external rotation lesions. The corrective force on the foot must however be applied in a lateral direction. Owing to the position of the fracture of the medial malleolus it is impossible to over correct the displacement though deformity may occur if the foot is everted rather than left in the neutral position.

TIBIO-FIBULAR DIASTASIS

Diastasis of the tibio fibular syndesmosis results from either external rotation strain or abduction strain, the former being the more common cause. The separation of the two bones varies according to the ligaments which rupture, and it is possible to recognise three degrees of diastasis.

1 Rupture of the anterior tibio fibular ligament which is short and tense, or fracture of the anterior tibial tubercle

2 Rupture of the anterior and posterior ligaments

3 Rupture of the anterior and posterior ligaments and of the interosseous membrane

4 A fourth rupture may be considered here, though the

mechanism is not strictly comparable, that of the attachment of the posterior tibio fibular ligament, the posterior tibial tubercle which is commonly separated alone, and allows rotation of the lower end of the fibula around the anterior tibio fibular ligament

The type and level of fibular fracture is determined by the sequence and degree of ligamentous rupture and the ligaments injured may conversely be diagnosed from the fractures present

Diastasis is shown on the radiograph by increased space between the tibia and fibula, and for the correct determination of this it is important that the radiograph should show the bi malleolar plane (Fig 555) and that radiographs of both ankles should be available for comparison. This is necessary as the depth of the groove in




FIG 606 The radiology of the tibio fibular syndesmosis. If the groove is deep the central ray cannot pass through uninterrupted. Note the angle of 30° between the bi malleolar axis and the angle of movement of the joint




FIG 607 When the tibial groove is shallow a clear space can be seen. This may be seen in diastasis and mistaken for separation of the bones

which the fibula lies varies. It has been stated that it is impossible for a gap to exist between the bones radiographically, in the normal ankle, and that any appearance of gap is an indication of diastasis. This is emphatically not so. The only indication of diastasis is increased gap in comparison with the opposite side (Figs 606, 607)

Factors suggesting diastasis may be noted in the ordinary radiograph. Thus the shadow of the anterior tubercle which normally overlies the fibula may barely appear to touch it. A more important point suggesting the condition is the increase in space between the medial malleolus and the medial side of the talus. This may, however, be deceptive and produced by external rotation alone.

Diastasis when complete is dramatic, but in itself is a comparatively harmless lesion, as it does not involve any weight bearing surface in a fracture, and with adequate treatment the torn liga-

ments heal soundly. It is important however in paving the way for severe damage to soft tissues and for fracture of the fibula.

Sprain fracture in association with diastasis. As a guide to the occurrence of diastasis it is important to remember that the portion of bone to which any ligament is attached may be avulsed instead of the ligament rupturing. The significance of such fragments must be recognised. They are sometimes called the "third fragment of Tillaux," after the man who first emphasised their significance, though they were recognised at the end of the eighteenth century. The fragments which may be separated are —

1 The whole fibular groove, *i.e.*, both anterior and posterior tubercles joined by the bone lying between them. This permits a complete diastasis (Fig. 608).

2 The anterior tubercle alone. This may indicate a partial or complete diastasis.

3 Rarely the fibular attachment of the anterior tibio-fibular ligament is avulsed.

4 The posterior tubercle. This may be avulsed, but is commonly split off by the pressure of the fibula on the back of the groove, when it occurs alone without displacement from kicks on the outer aspect of the fibular malleolus (Fig. 608).

Fractures of the Fibula associated with Diastasis

1 **Maisonneuve's fracture.** This is a fracture which is commonly overlooked. Rupture of the anterior tibio-fibular ligament allows



FIG. 608. Fractures of the anterior and posterior tubercles of the tibia gutter of the fibula—the third fragment.

sufficient rotation strain to be imparted to the shaft of the fibula for it to fracture just below the head of the bone. The pressure is imparted to the lower end of the fibula by the anterior edge of the talus and by the pull behind of the posterior talo-fibular ligament.

The only symptoms may be local bruising over the anterior tibio-fibular ligament, which is very tender, and pain over the upper end of the fibula, this may be slight and only elicited on pressure. The radiograph of the ankle in the normal antero-posterior plane is usually negative, and it requires either a film in the bi-malleolar

plane or a film of the upper end of the fibula to determine the lesion. A very rare complication is the inclusion of the peroneal nerve in the upper fracture line with a peroneal palsy and foot drop.

TREATMENT The principal disability arising from a failure to




FIG. 609. Fracture of the fibula in the upper third by diastasis—Marion's fracture. Either the posterior tubercle (Fig. 609) can fracture or the anterior tibio fibular ligament as in this case can rupture allowing sufficient rotation for the fibula to fracture at its weakest spot. The first degree of diastasis.




FIG. 610. Marion's fracture—high fracture of the fibula accompanied by diastasis.



FIG. 611. High fracture of the fibula accompanied by fracture of the posterior tibial tubercle.

treat this lesion is a slight increased width in the tibio fibular mortise and persistent pain over the anterior tibio fibular ligament. To avoid this it is necessary to immobilise the ankle in a walking plaster for four to six weeks. A satisfactory skin tight plaster can

only be applied after the swelling has subsided, so that elevation and bandaging of the limb is a necessary preliminary for a few days. Rehabilitation after removal of the plaster is rapid and easy, and no disability should persist.

2 Dupuytren's fracture Fracture of the fibula $2\frac{1}{2}$ inches above the syndesmosis with rupture of the anterior tibio fibular ligament and the interosseous membrane. The mechanism is one of external rotation combined with some abduction, so that pressure continues




FIG 612 Fracture of the fibula by diastasis the posterior tibio fibular ligament shown by dotted lines remaining intact. The second degree of diastasis. Note level of the fracture and that in the lateral view the fracture line runs in the opposite oblique to that of the common mixed oblique fracture Dupuytren's Fracture



FIG 613 Dupuytren's fracture Fracture of the lower third of the fibula together with an incomplete diastasis (rupture of the anterior tibio fibular ligament)

on the anterior end of the fibula which is forced out and back. The rupture of the anterior tibio fibular ligament is followed by a tearing of the interosseous membrane which allows the tibio fibular syndesmosis to open up to the full extent permitted by the slack posterior tibio fibular ligament, and this is followed by snapping of the fibula at the upper level of the tear in the interosseous membrane, $2\frac{1}{2}$ inches above the malleolus. It is to be noted that unless the syndesmosis is damaged in some manner fracture of the fibula above it, except by direct violence, is impossible, as the fibula comes to be against the

tibia before its limit of elasticity is passed. It is also to be noted that the fracture line in such cases usually slopes in the opposite direction to the "mixed oblique" fracture, namely, from above and in front downwards and backwards.

A similar lesion may occur in association with fracture of the posterior tubercle of the tibia, though the mechanism is slightly different. (See below.)

TREATMENT Owing to the intact posterior tibio fibular ligament displacement is limited, and reduction of the diastasis is straight forward. The lesion is, however, often accompanied by either rupture of the deltoid ligament or a transverse fracture of the medial malleolus with separation. The medial malleolus should under these circumstances be pegged back into position with a bone peg or a screw. Through the intact ligaments attaching it to the fibula it assists materially in maintaining the reduction of the syndesmosis. It is unnecessary to fix the fibula and tibia together by a screw in this type of case. The post operative care and the care of the case which has been reduced manually is similar. Weight bearing must be delayed owing to the danger of the talus slipping over into eversion and pushing the fibula away. A short leg plaster is therefore applied as soon as swelling has subsided and activity on crutches permitted for the first six weeks. At the end of this time the leg is re-plastered and weight bearing permitted. The plaster is removed between the tenth and twelfth weeks. Satisfactory function should return to the joint, provided the damage on the medial side has not been too extensive. Some minor disability may persist for a time and it will be necessary to wear a crepe bandage for some weeks to control the swelling of the ankle.

Complete diastasis This is produced by severe abduction violence, or by external rotation followed by abduction of the foot. All three attachments of the fibula to the tibia are torn and the anterior or posterior tubercle frequently accompanies them. Wide separation of the bones is permitted (Fig. 615) the talus sometimes riding up between them when it may then be described as dislocated upwards between the two bones. The fracture of the fibula is usually in the middle third of the shaft and corresponds to the upper limit of the tearing of the interosseous membrane. The severe signs and symptoms present enable it to be diagnosed readily.

This fracture may be accompanied by fracture of the medial malleolus or a rupture of the deltoid, one or the other being necessary to allow the lateral displacement of the foot. Sometimes the posterior margin of the tibia accompanies the fibula instead of just the tubercle being involved, producing a third degree lesion (Fig. 587).

TREATMENT This is essentially similar to that for second degree

lesions (Dupuytren's fracture), but as the posterior tibio fibular ligament is also involved reduction is not so easy or so stable. Reduction may be considerably assisted by operating on the associated fractures if these are displaced. Thus a medial malleolus should be pegged back and if the posterior margin is involved it should be accurately reduced. The lower end of the fibula is thus retained in position by its attached ligaments. Reduction when first seen is




FIG 614 Single screw fixation for diastasis. Note the oblique insertion of the screw which does not tend to rotate the lower fragment of the fibula if not inserted at the correct level.




FIG 615 Fracture of the fibula by complete diastasis. Note the separation of the anterior tubercle as the third fragment.

manipulative, and it is from a consideration of the control radiographs that a decision as to further treatment is made. Careful reduction and fixation of the associated fractures combined with elevation of the limb, and replaster as soon as the swelling has subsided, usually results in a satisfactory reduction of the diastasis which should be checked by a bi malleolar radiograph of both ankles. If reduction of the space between the two bones is unsatisfactory, it may sometimes be influenced during the first week by the applica-

tion of a firm Esmarch's bandage around the ankle. The heavy pressure built up forces the fibula back into the tibial groove. The bandage should only be left on for a few minutes and the ankle then re-plastered.

Failure to reduce the fracture satisfactorily is uncommon and may be due to the interposition of soft tissue or a fragment of bone. Under these conditions operative reduction is necessary and the syndesmosis should be exposed by an anterior incision, cleared, and fixed by an oblique screw. This screw must be inserted at the correct level and not over-tightened. Over-tightening may result in tilting of the lower fragment, or of narrowing the mortice. The oblique screw is less liable to do this than the transverse. The screw should be removed at the end of treatment. Post-operative treatment demands freedom from weight bearing for six to eight weeks or longer if a posterior marginal fracture is associated. Consolidation is usually sound between twelve and fourteen weeks.

It is one of the advantages of operative fixation of the fibula that a plaster gutter splint may be made, and early exercises of the ankle carried out for the first six to eight weeks. By this time there is little danger of adhesions, and a walking plaster can be applied for a further six weeks in the secure knowledge that the ankle movements on its removal will be good.

Fracture of the posterior tubercle of the tibia. It is necessary to mention this here as the weakening of the posterior edge of the fibula gutter allows leverage to be developed around the anterior tibio-fibular ligament which may produce a fracture of the fibula above the syndesmosis, the characteristic evidence of diastasis. The fragment corresponds to the attachment of the posterior tubercle, but more bone commonly separates than in a pure sprain fracture. The lesion may be produced without displacement by a direct kick on the fibular malleolus. It is then of little moment and can be treated by early exercises and weight bearing as the stability of the ankle is not upset.

Where it results from the backward pressure of the fibula on the tibial groove the fibula is liable to yield above. The foot in external rotation and abduction presses on the anterior margin of the fibula which without the support of the posterior lip of the gutter, rotates around the anterior tibio-fibular ligament causing the fibula to bend anteriorly. Here it is not supported by the tibia and a flexion fracture often of the 'butterfly' type results. Owing to the intact interosseous membrane and anterior tibio-fibular ligament displacement is small. The fracture is treated in the same manner as Dupuytren's fracture, from which it is distinguished by the shape of the fractured surfaces and the involvement of the posterior tibial tubercle.

The posterior tibial flake It is not uncommon to see in radiographs after old injuries, and appearing in radiographs a few weeks after recent injuries, a small flake of bone lying behind the tibial tubercle. It resembles in many ways the flake of bone seen lying at the attachment of the medial collateral ligament to the femoral condyle. It is smooth, dense, and separated from the bone by a clear area. This clear area is occupied by some fibres of the posterior tibio fibular ligament and the flake represents an ossification on the surface of this ligament. It may follow any severe injury to the ankle which results in a hematoma being formed in this region. It is of no significance, but should not be mistaken for a recent fracture.

Sprain or ligament traction fractures It is more common for a ligament to yield completely by avulsion of its bony attachment than by complete rupture of its fibres. Small flakes of either malleolus are likely to be detached by the pull of the fasciculi. The anterior fasciculi of the deltoid may pull away the anterior tubercle to which it is attached (Fig 580). Similarly the anterior fibres of the fibular collateral ligament (the anterior talo fibular ligament) may avulse a flake from the anterior margin of the fibula (rare). Most common, however, is the avulsion of the tip of the fibula from sprain of the calcaneo fibular ligament (Fig 563).

The ligament traction injuries in association with diastasis have already been outlined.

TREATMENT This is similar to that of a severe sprain. If a large flake of the medial malleolus is detached the condition approaches a first degree abduction fracture, and indeed there is no sharp line between the two conditions. Large flakes should if displaced, be pegged back in position. For the severe sprains in which rotation of the talus can be demonstrated radiologically under pentothal, immobilisation in plaster is necessary for five weeks. Walking can of course be permitted. Infiltration with local anæsthesia may be used in the first few days to diminish pain and enable the bruising to be dispersed by massage.

Compression injuries

- 1 Posterior marginal fractures
- 2 Anterior marginal fractures
- 3 Comminuted fractures of the lower end of the tibia

Anterior and posterior marginal fractures may result from falls on the foot. With the foot in plantar flexion the force is transmitted to the posterior lip of the lower surface of the tibia and a posterior marginal fracture results. This fracture is apt to be followed by displacement and if the fragment is large enough it may carry the posterior lip of the tibial gutter with it and if the anterior tibio-fibular ligament separates wide displacement with a third degree

fracture may result. In practice both compression and external rotation usually act together. Occasionally the posterior margin may be split off by the rotation of the cylindrical talus in the curve of the tibia, under pressure. This may produce a line fissure with very little separation, though if the force continues a third degree lesion may result.

Anterior marginal fractures result from falls in which the foot passes into dorsiflexion and the tibia tends to slide backwards. This accident is less common than falls in plantar flexion and the shallowness of the anterior lip does not allow such pressure to be developed on the anterior margin as the posterior. A fissure fracture may occur.



FIG 616 An anterior marginal fracture of the tibia due to compression. In marginal fractures due to forced dorsiflexion a much smaller chip of bone is displaced or the anterior margin is merely crushed.



FIG 617 Posterior marginal fracture of the tibia occurring alone due to sudden compression strain.

which in the same manner as a posterior marginal fracture destroys the stability of the joint. Compression fractures of the anterior margin of the tibia may occur from pressure against the neck of the talus, which may be fractured.

As these fractures, with the exception of the last named, involve the weight-bearing surface of the bone, it is important for the avoidance of subsequent traumatic arthritis that they be reduced perfectly and this often necessitates open operation. An anterior approach is used for anterior marginal fractures and a postero-

lateral approach for posterior marginal fractures. A single screw is used under radiological control.

Post operatively after a week's rest in a complete plaster early exercises are commenced if the lesion is an isolated one. In those few cases without displacement, a similar regimen may be tried. No weight bearing is permitted for ten to twelve weeks to allow the joint surface to heal satisfactorily. In spite of this the accident is likely to be followed by traumatic arthritis in a longer or shorter time.

Gross comminution of the tibial surface may occur after such accidents as land mine explosions, or the tibial surface may be involved in fractures running down from the shaft. These latter cases may not show much displacement. Where displacement is gross and



Fig. 618. Ligament traction fracture of the medial malleolus. This can be regarded as a minor variety of the first degree abduction fracture.

the joint surface is destroyed reduction of the parts under manual traction or skeletal traction is carried out and the foot immobilised at right angles and in the mid position between inversion and eversion. A painless ankylosis is hoped for in this position. If there is any possibility of return of function at the ankle joint open operative restoration of the parts has to be considered. If this is out of the question the ankle should be treated by skeletal traction and early non weight bearing exercises.

Mal-united fractures in the ankle region. Fractures may be seen some time after their occurrence, and in the absence of any treatment union may have occurred in poor position. The most common deformity is an eversion of the heel, with a valgus deformity of the ankle due to the talus moving laterally with the angled fragment of the fibula. The most important single cause of this is too early walking, particularly in ill fitting plaster

casts applied before the swelling around the ankle has subsided. It is for this reason that the late application of the plaster and the careful use of control X rays has been insisted upon in second and third degree fractures.

If a period of not longer than six to eight weeks has elapsed, it is possible to correct the deformity by forcible manipulation with a Thomas's wrench or the osteoclast. The aim is to get the upper surface of the tibia in alignment with the lower surface of the tibia and parallel to the ground. After reduction the ankle is treated as for a fresh fracture.

In older cases the benefit likely to occur from operation must be carefully weighed. In the presence of a traumatic arthritis no improvement need be expected, and if serious disablement is present an arthrodesis may be necessary. In cases in which the principal defect appears to be a valgus deformity, and the joint is normal, an osteotomy of the tibia above the joint may improve the mechanical function of the joint and save the development of a later arthritis. More elaborate operations on both malleoli to recreate the conditions of the fracture are not satisfactory.

In a few cases fractures of the medial malleolus are reluctant to unite owing to the inclusion of soft tissues between the fracture surfaces. Open operation with freshening of the fracture surfaces and a small bone peg driven in from below will result in rapid union and restoration of painless function of the ankle. Rarely the fibular malleolus has to be treated in the same way (Fig. 598).

REFERENCES

- D ARCY POWER "Pott's fracture" (a record of Pott's own case), *Brit J Surg*, 1922-23, 10, 433
- ✓ ASHURST and BROMER "Classification and Mechanism of Fracture of the Leg Bones involving the Ankle" (a full and thorough review of ankle lesions with copious bibliography on which part of this chapter is based), *Arch Surg*, 1922, 4, 51
- ✓ HENDERSON and STUCK "Fractures of the Ankle. Recent and Old," *J Bone and Joint Surg*, 1933, 15, 882
- SPEED and BOYD "Operative Reconstruction of Malunited Fractures about the Ankle Joint," *J Bone and Joint Surg*, 1936, 18, 270
- AIRKEN "The End Results of the Fractured Distal Tibial Epiphysis," *J Bone and Joint Surg*, 1936, 18, 685
- McFARLAND "Traumatic Arrest of Epiphyseal Growth at the Lower End of the Tibia," *Brit J Surg*, 1931, 19, 78
- CONWELL "Acute Fracture Dislocations Around the Ankle Joint," *Ann Surg*, 1929, 89, 439
- DICKSON "Posterior Marginal Fracture of the Tibia," *Surg Gynec and Obstets*, 1933, 56, 525
- CAMPBELL W G "The Treatment of Ankle Fractures," *Lancet*, 1938, 2, 872
- BONNIN J G "The Hypermobile Ankle," *Proc Roy Soc Med*, 1944, 37, 282
- BERRIDGE and BONNIN "The Radiographic Examination of the Ankle Joint, including Arthrography," *Surg Gynec and Obstets*, 1944, 79, 353

CHAPTER XXXII

FRACTURES OF THE TARSUS, METATARSUS, AND TOES

Surgical anatomy Of the tarsal bones, the talus and calcaneus stand out as of exceptional interest. The remaining bones are irregularly quadrilateral, cancellous tissue bones covered with a thin layer of compact bone, which are consequently only liable to compression and ligament traction fractures.

Talus The most interesting point to be noted about this bone apart from the well known fact that it is the only bone without any muscular attachments is that three fifths of its surface area is articular. This obviously necessitates some special mechanism in addition to strong ligaments to retain the bone *in situ*. This is found in the deep nature of the tibio fibular mortice, and the opposed lines of the talo navicular joint, and the posterior talo calcaneal joint which thus surround almost all of the bone with an irregularly quadrilateral bony wall. The lateral surfaces are further guarded by the strong collateral ligaments of the ankle passing to the calcaneus. The anterior and posterior aspects are less well protected and are the regions through which dislocation occurs. The weakest point of the bone is the neck, where the compact bone is very thin and the bone is grooved by the deep sulcus of the talus. The posterior and lateral processes of the talus require mention as they are liable to injury.

Development The most important point to notice is the occasional ossification of the posterior process of the bone from a separate centre. This may give rise to suspicion of fracture. In a certain number of cases this centre remains unfused with the body forming the os trigonum, which may also cause confusion. (Fig 27)

Calcaneus The irregular shape of this bone renders it liable to a multiplicity of fractures. It is important to note the slight curve on the bone which looks medially, and into which the reniform clamp face of the compression clamp fits, lying just below the sustentaculum tali. In normal bones the line made by joining the upper margin of the tuberosity and the highest point of the posterior talo calcaneal joint with a line joining this point and the angle of the bone is known as the salient angle (joint tuberosity angle). It varies from 20° to 40° and is a useful measure of the depression of the posterior talo calcaneal joint in compression fractures of the calcaneus. Its variability demands a control picture of the opposite leg for comparison.

Development An epiphysis for the posterior surface of the bone appears about five to eight years, and unites at sixteen to twenty two years.

Accessory bones of the foot The frequent occurrence of accessory bones in the foot is important, as if one is not aware of them fracture is often suspected. Such bones may be sesamoid bones which normally appear at certain sites or they may be true accessory bones which represent persistent phylogenetic remnants. They have the following characteristics

- 1 They appear at known sites
- 2 They are usually bilateral
- 3 They have clear and well defined peripheries

From these points it is clear how they should be detected. The accurate

examination of the film, combined with a comparative X ray of the normal foot will exclude fracture. Common accessory bones are

- 1 The os trigonum, resembling a fracture of the posterior process of the talus
- 2 The os Vesalianum, at base of the fifth metacarpal (See later)



FIG 619 Lateral view of the calcaneus showing the salient angle or joint tuberosity angle which varies from 20° to 40° . A sesamoid bone is also to be seen in the tendon of the peroneus longus which has been mistaken for a fracture of the anterior end of the calcaneus

- 3 Accessory navicular. A small bone occasionally present in the region of the navicular tuberosity (Os tibiale externum)
- 4 The talo navicular bone. Lying on the dorsum of the foot between the talus and the navicular

These are the most common accessory bones but there are some sixteen other rarer ones

Fractures of the Talus

- 1 Fracture of the neck
- 2 Fissure fractures of the body
- 3 Crushing of the head with fragmentation
- 4 Fractures of the posterior process
- 5 Traction fractures of ligamentous insertions
- 6 Fractures of the medial and lateral inferior borders

The question of fractures of the talus is closely bound up with dislocation of the talus, which may occur at the ankle, the sub-taloid joint, and the talo navicular part of the mid tarsa joint. The

common usage of the term sub taloid dislocation ignores the involvement of the talo navicular joint. When the neck of the talus is fractured and the body of the talus dislocated the talo navicular joint and anterior talo calcaneal joint remain intact, and the posterior talo calcaneal joint and the ankle only are involved.

Numerous combinations of fractures and dislocations are possible, and the classification of such lesions presents some difficulty. The prime purpose of a classification is a guide to ordered thought and an aid to memory. The more facts which can be brought into line with any classification the better unless the classification is rendered too



Fig. 620 Dislocation of the talus at the ankle without fracture. Primary dislocation of the talus without fracture.

cumbrous. It is tempting to classify lesions under their causative violence as has been done for injuries to the ankle. Desirable though this is, the complicated lesions being due in many cases to a combination of forces, or a succession of injuries such a classification is too simple to be correct. It is therefore suggested the dislocations and fracture dislocations of the talus should be classified on an anatomical basis which, if academic, has the virtue of being familiar, simple, and covering more contingencies than one based on mechanism.

Classification PRIMARY. Involving one joint only. This is only possible at the ankle, and the injury may be due to any combination of the forces described in the previous chapter. For

simplicity primary dislocation of the talus is usually limited to dislocation at the ankle joint without fracture. If a fracture has occurred it is described as a fracture dislocation of the ankle.

SECONDARY Two joints are involved —

1 Without fracture Sub taloid (subgastragaloid) dislocation. The injury which may be due to forced inversion or eversion of the foot with medial or lateral dislocation of the talus, involves the talo calcaneal and talo navicular joints (Fig. 621).

2 With fracture of the neck of the talus. These injuries most commonly occur as the result of forced dorsiflexion of the foot ("Rudder bar injuries"). The first stage of the lesion is the fracture of the neck of the talus without displacement. A continuation of the forces acting produces dislocation at the posterior talo calcaneal joint and a variable degree of displacement of the body.

TERTIARY In this group all three joints are involved, the equivalent of total dislocation of the talus.

Any of these lesions may be complicated by fractures of the processes or margins of the bone or damage to the mid tarsal joint.

Fractures of the Talus

Fracture of the neck of the talus This is a dorsiflexion injury, and occurring without dislocation of the body of the bone will be described here. The attachments of the bone being intact there is no danger of avascular necrosis. Damage to the anterior margin of the tibia may be serious and result in traumatic arthritis of the ankle joint. More commonly the damage is only of a minor character which has to be carefully sought for.

TREATMENT This consists in immobilising the foot in plaster in the normal plantigrade position for eight weeks without weight bearing when there is no displacement. The usual remedial exercises are begun after this and some weeks may elapse before the resulting stiff foot returns to normal.

Great care must be taken that an accompanying dislocation of the posterior sub taloid joint which has reduced itself incompletely is not overlooked. It is necessary to immobilise such cases in plantar flexion to reduce the deformity. Fracture of the neck of the talus with displacement of the body is twice as common as without.

FISSURE FRACTURES OF THE BODY These may occur from compression and remain undisplaced. Treatment is similar to fractures of the neck of the talus. Compression fracture of the head of the talus is irreducible and has to be treated in a similar manner.

FRACTURES OF THE POSTERIOR PROCESS Great care has to be taken not to confuse the ununited secondary centre of the posterior

tubercle with this fracture. This is the so called os trigonum illustrated in Fig 27. The lesion when present is due to forced plantar flexion, and in the absence of other injuries can be treated by early mobilisation of the foot and weight bearing. Traction fractures of the ligamentous insertions are not as common as the similar lesions of the malleoli. Treatment is similar (p 565). Fractures of the medial and lateral margins should raise suspicion of marked displacement which has spontaneously reduced itself. Rarely they occur alone. They require a short period of rest and then mobilisation.

Subtaloid (subastragaloid) dislocation (secondary or incomplete)

(a) With medial displacement of the foot

(b) With lateral displacement of the foot (rare) (Fig 621)

As the result of either inversion strain or eversion combined with rotation the calcaneus and navicular are twisted from the lower surface of the talus. This probably occurs with the foot in the plantigrade position under some pressure, or else the talus would dislocate at the ankle joint. The talus returns its normal position, but the rest of the tarsus is drawn up on one or other side of it. If laterally, the tip of the fibula is often fractured. The navicular is drawn up anteriorly by the tension in the tibialis anterior, with increase in the longitudinal arching of the foot and apparent plantar flexion of the talus.

The signs and symptoms are gross, and while they may resemble a total dislocation of the talus (qv) the condition is easily recognised by radiography.

TREATMENT Manipulative reduction is usually easily carried out, and once reduced the condition is stable. The foot is immobilised in plaster in the normal plantigrade position. Weight bearing should not be permitted for the first month and the plaster should be retained for eight weeks. A satisfactory recovery follows, but persistent stiffness of the hind foot and mid tarsal arthralgia after walking may remain. A surgical shoe with a built in vagus insole should be provided in such cases. Avascular necrosis of the talus does not follow this accident.

Fracture of the neck of the talus with dislocation of the posterior talo-calcaneal joint. The knowledge of this classical flying accident has recently been considerably increased by the study of the cases in the R A F. The injury is a dorsiflexion one in which the neck of the talus is sheered off against the lower margin of the tibia, which frequently shows signs of damage. As a result of the forward pressure on the foot at the time of the accident the fractured neck of the talus is often impacted into the body, and on plantar flexion of the foot to a right angle the body of the talus is drawn down into plantar

flexion. The only method of disimpacting the fragments and getting them into normal position is to forcibly plantarflex the foot, when following disimpaction, the fragments usually slide into position. In



FIG. 621 Antero-posterior view of the same case




FIG. 622 Secondary dislocation of the talus. Lateral view of a sub-taloid (sub-astragaloid) dislocation of the tarsus

a few cases they will not reduce satisfactorily, due to wedging of comminuted fragments between the neck and the body. Two groups of cases can be recognised according to the displacement of the body of the bone

1 Those in which the talo fibular and talo tibial ligaments retain the body of the bone in position

2 Those in which all the ligamentous attachments of the body are ruptured and the body assumes one of many diverse positions

The distinction is important, as in the first group of cases a very limited percentage of the cases (under 50 per cent) will undergo avascular necrosis, while in the second group it is almost inevitable. It is, however, worth noting that necrosis does not necessarily occur, and a clinical trial should be given before arthrodesis of the ankle, in all cases. I have recorded one case which was not followed by avascular necrosis, and there is one case in the literature in which the talus was removed, washed in saline and reinserted and survived.

Treatment WHEN THE BODY LIES IN NORMAL POSITION The head of the talus is brought into line with the neck of the bone by plantar flexion and slight inversion or eversion. The position of inversion or eversion assumed is opposite to the displacement at the time of the injury. Careful check radiography is necessary to be certain the fracture is reduced in both planes. Union is apt to be slow and the plantar flexed position must be maintained for eight to ten weeks. A plaster in the plantigrado position follows for a further fortnight, and if radiological evidence of union is satisfactory weight bearing is permitted in it for a further fortnight. It is then removed and rehabilitation commenced.

WHEN THE BODY IS DISPLACED The displacement of the body is variable. It is most commonly postero-medial (Fig. 628), but may be postero-lateral or anterior. Reduction must be carried out immediately to avoid sloughing of the skin over the displaced body, undesirable pressure on vessels and nerves, and avascular necrosis. Reduction may be manipulative, or operative, and it is worth remembering that skeletal transfixion of the body by a thin Steinmann's pin may assist. In general, owing to the numerous minor complicating factors present, such as fracture of the medial malleolus, comminution of fragments, open operation is to be recommended. While the possibility of reducing the vascular supply of the bone still further exists, undesirable soft tissue tension can be eliminated by evacuation of the hæmatemas. Retention of the talus after open reduction may be by plaster, but control of the fragments may only be obtained by the insertion of a screw through the neck of the talus into the body. Fracture of the medial malleolus, if associated, should be pegged back into position.

Avascular necrosis is shown by an increase in the density of the body of the bone (Fig. 623) compared with the surrounding bones. If the bone is immobilised replacement with living bone will slowly follow. There is, however, every chance that, though the function of

the ankle in twelve months' time may be good, early degenerative arthritis will set in. Should weight bearing be permitted during this period the compression of the bone and arthritis is inevitable. When



FIG. 623. Avascular necrosis of the body of the talus following a mine explosion underfoot. Fracture of the neck of the talus without displacement.

painful and advanced, arthrodiesis of the ankle must be carried out. Tibio calcaneal fusion, leaving the head *in situ*, is most satisfactory. *Late and irreducible cases.* When contraction of tissue and




FIG. 624. The mechanism of posterior fracture-dislocation of the talus. The arrow shows the direction of the resultant forces in the dorsiflexed foot.




FIG. 625. One position of the dislocated body of the bone. The more usual displacement is shown in the succeeding figure.

adhesions have occurred reduction of the body may be impossible and excision is inevitable. It should be followed by immediate tibio-calcaneal fusion.

Total dislocation of the talus (tertiary or complete)

This uncommon lesion is usually the result of falls with the foot in inversion. Rupture of the fibular collateral ligament allows the



FIG. 626 Tertiary dislocation of the talus. Antero-posterior film showing antero-lateral dislocation of the body of the bone which lies in front of the fibula.



FIG. 627 Lateral view of the same case showing the long axis of the talus lying in the transverse plane.

escape of the talus in front of the fibula, and dorsiflexion of the foot causes it to lie across the foot in front of the anterior tibial margin. This is intero-lateral dislocation (Fig. 626). Antero-medial dislocation

tion from eversion injuries accompanied by rupture of the deltoid ligament occur. The position of the talus is very variable, and it has been found completely reversed on its long axis. (The axis running from the posterior tubercle through the centre of the neck.) Complete posterior dislocation is recorded but is extremely rare.

SYMPTOMS AND DIAGNOSIS There is always a history of a fall from a height, but this may be merely that from a chair. Gross




FIG. 628 Drawing to represent the position of the talus found at operative reduction of a posterior medial fracture dislocation.

A Peroneus longus B Flexor hallucis longus C Peroneus brevis D Peroneal retinaculum E Articular capsule of the ankle F Cut tendo Achilles G Tuber calcanei H Tendon of flexor hallucis longus I Displaced talus J Tendon of tibialis posterior K Flexor digitorum longus

swelling and deformity are present. The displaced body of the talus may be palpated lying anteriorly or posteriorly, where it may be obscured to some extent by the tendo calcaneus. It can be recognised by the feel of its saddle shaped articular surface. In compound cases this is frequently visible through the wound. If the skin is not broken it is under great tension and requires urgent attention to avoid the onset of gangrene. With the anterior dislocations the strain on the skin is greater than with posterior cases as there is

more room behind the ankle posteriorly. Posterior dislocations may produce pressure on the posterior tibial nerve or on the tendons of the flexor hallucis longus and flexor has been completely severed from its attachments. There are at least two recorded cases where the loose talus has been washed in saline and returned to its position with complete success.

Reduction is most readily accomplished by skeletal traction. Antero-medial dislocations slip back more easily than antero-lateral ones which are obstructed by the deep anterior margin of the fibula. In posterior dislocations there may be difficulty owing to the bone becoming button-holed by the tendons previously mentioned. In either anterior or posterior lesions if manipulative reduction fails one should proceed at once to operative reduction, which is best carried out on the traction frame so that the skeletal traction can be continued. The reduction is carried out through a vertical incision over the displaced bone. In posterior dislocations the traction frame must be turned on its side to facilitate the approach. By making a clear exposure the obstructing bony points or the stretched ligaments can be seen, and the bone slipped back with levers. The wound is then closed with the usual precautions and the leg plastered. In compound cases the wound is excised and then the bone replaced under observation, before suture. The wire in the calcaneus may be left if desired for light traction. In fresh cases the plaster is split, or padded.

After treatment The limb is rested on a Braun's or Thomas splint. When the wound has healed and swelling has subsided, the leg is put in a plaster to the knee. Walking is not permitted till there is evidence of good union of any fracture, or a restored blood supply in cases of dislocation of the body or whole bone. At the end of five to six weeks, however, the plaster may be guttered and exercises to the ankle commenced if the X-ray findings are satisfactory. These were more fully discussed in an earlier chapter. If avascular necrosis has commenced weight bearing will hasten the dissolution of the bone. The patient must rest till either the circulation is restored, or the bone has degenerated.

Late cases Where the case is seen some time after the accident the chances of survival of the bone are much diminished. After forty-eight hours' displacement the majority of cases undergo avascular necrosis even if reduced. It is, however, always worthwhile trying up to the end of the first week, after which tibio-calcaneal arthrodesis is to be recommended, either partial or complete.

Fractures of the calcaneus Any person who falls from a height

tion from eversion injuries accompanied by rupture of the deltoid ligament occur. The position of the talus is very variable, and it has been found completely reversed on its long axis. (The axis running from the posterior tubercle through the centre of the neck.) Complete posterior dislocation is recorded but is extremely rare.

SYMPTOMS AND DIAGNOSIS There is always a history of a fall from a height, but this may be merely that from a chair. Gross




FIG. 628. Drawing to represent the position of the talus found at operative reduction of a posterior medial fracture dislocation.

A Peroneus longus B Flexor hallucis longus C Peroneus brevis D Peroneal retinaculum E Articular capsule of the ankle F Cut tendo Achilles G Tuber calcanei H Tendon of flexor hallucis longus I Displaced talus J Tendon of tibialis posterior K Flexor digitorum longus

swelling and deformity are present. The displaced body of the talus may be palpated lying anteriorly or posteriorly, where it may be obscured to some extent by the tendo calcaneus. It can be recognised by the feel of its saddle shaped articular surface. In compound cases this is frequently visible through the wound. If the skin is not broken it is under great tension and requires urgent attention to avoid the onset of gangrene. With the anterior dislocations the strain on the skin is greater than with posterior cases as there is

the talus into the body of the calcaneus just anterior to the posterior talo calcaneal facet. The lateral wall of the calcaneus breaks here, just above the peroneal tubercle. The weight then falls on the sustentaculum tali which is broken so that the whole weight is taken by the posterior articular facet which is either fragmented sometimes with a long sagittal fracture running to the tuberosity (Fig 634), or driven deep into the cancellous tissue of the bone. In either case the salient angle is obliterated, though to greater degree in the latter case. In lesser injuries the bone may have a process broken off, or it may fissure in the line of the lamellæ with no displacement. The anterior end of the bone is remarkably infrequently injured. In severe lesions the bone is fragmented, broadened, the salient angle completely obliterated, and the head of the talus partly dislocated in an upward direction. The fractures of the bone may be summarised as follows

- 1 "Beak" fractures (5 per cent) (Fig 631)
- 2 Fractures of the medial tuberosity (13 per cent) (Fig 632)
- 3 Fractures of the sustentaculum tali alone (4 per cent)
- 4 Fractures of the body without displacement of the joint surfaces (25 per cent)




FIG 631 "Beak" fracture of the calcaneus. A Triangular fragment of bone. B Areas of the tuber calcanei in contact with the bursa below the tendo Achilles. C Tendo Achilles.

- 5 Fractures of the body involving depression of the posterior articular area alone (30 per cent) (Fig 633)
- 6 Fractures involving the displacement of the whole of the posterior articular facet, fracture of the sustentaculum tali, fissuring of the bone, and obliteration of the salient angle, with or without dislocation of the talo navicular joint (26 per cent)

X RAY EXAMINATION Accurate lateral views of the bone are necessary together with a plantar view of the bone, taken with the foot in dorsiflexion and the tube at an angle of 45° to the plate which lies under the heel. Only in this film can fractures of the sustentaculum be seen, and shortening and broadening of the calcaneus be appreciated. It is advisable to have two similar views of the sound heel taken at the same time for comparison.

ANÆSTHESIA In fresh cases local anæsthesia can be used, but it is not as satisfactory as when used elsewhere, and requires to be supplemented by gas for the compression of the bone. More satisfactory is intravenous or spinal anæsthesia obviously the choice in bilateral cases. General anæsthesia is satisfactory, and though the

of three feet or more on to their heels and complains of persistent pain afterward should be suspected of a fracture of the calcaneus. The fracture which may occur varies from a fissure without displacement to a gross crushing injury. The sequelae are apt to be disproportionately severe if the clinical and radiological appearances of deformity are taken as the criteria of judgment. Although several well-recognised varieties of fracture occur, due either to the structure of the bone or the uniformity of mechanism, there are two great clinical groups of cases.

1 In which the posterior talo calcaneal joint is not involved. This includes fractures of the tuberosity and processes and minor fissures without displacement. Serious sequelae do not occur.

2 In which the posterior talo calcaneal or sub taloid joint is fractured or altered in alignment. This group is liable to be followed by a sub taloid arthritis which may be seriously disabling, and in any case is followed by limitation of movements at the sub




FIG. 629 Mechanism of fracture of the calcaneus. First stage.



FIG. 630 Second stage. The bone is fissured, and the posterior articular surface driven into the cancellous bone of the body.

taloid joint and an inability to walk comfortably over irregular ground.

SIGNS AND SYMPTOMS. The deformity may be either negligible or very gross. When obvious it consists of shortening and eversion of the heel and flattening of the arch. Frequently this is obscured by gross swelling of the ankle. The local pain and tenderness is often acute, amounting to hyperæsthesia. In a few cases it may be possible to appreciate with the fingers the shortening of the distance from the sustentaculum tali to the medial malleolus. In some cases the broadening of the bone is shown by a swelling behind the lateral malleolus. The condition is frequently bilateral and in falls on to the feet from a height, or mine explosions at sea where there is a violent upward thrust of the deck, the common association of a compression fracture of the 12th dorsal or 1st lumbar vertebra must be borne in mind.

MECHANISM. The weight of the body drives the sharp angle of

two to three days' rest with a compression clamp. A walking plaster is then applied for three to five weeks.

Cases with no displacement may be treated by early exercises. Weight bearing will be avoided on account of pain for the first week, but can be commenced as soon as it is comfortable.

4 FRACTURES OF THE BODY WITHOUT DISPLACEMENT These require rest and elevation till swelling has subsided. Weight bearing is not permitted, but active non-weight bearing exercises are carried out. The patient is allowed up on crutches with the ankle supported by a firm bandage. A decision as to when weight bearing should be permitted is based on the position and extent of the fracture, the mobility of the hind foot, and the amount of pain on pressure on the heel. The time will vary from four to eight weeks. Persistent trouble of a serious nature should not follow this type of injury.

5 FRACTURES OF THE BODY WITH DEPRESSION OF THE POSTERIOR TALOCALCANEAL JOINT (Fig 633) Even pressure on the articular facet may drive it deeply into the cancellous tissue of the body of the bone. Slightly uneven pressure with the foot inverted may shear off the lateral half of the posterior facet. The fracture lines often run back to the tuberosity as in Figs 633, 634.




FIG 633 Fracture of the calcaneus with displacement of the lateral side of the posterior talocalcaneal joint. A Fractured fragment B Posterior talocalcaneal joint

The total deformity of the calcaneus is not gross. Elevation of the articular facet is impossible by lateral compression, and difficult by traction. Although the salient angle is reduced the disability is to some extent countered by slight plantar flexion of the talus and flattening of the angle of the calcaneus.

Such cases do not require manipulation and should be treated by elevation, massage, and early non weight bearing exercises. Weight bearing must be avoided for two to three months. In the majority of cases, though the inversion and eversion of the heel may be limited or absent, a reasonably satisfactory functional result is achieved. In those in which pain persists, sub taloid arthritis is occurring and the end result resembles the unsatisfactory cases of Group 6.

6 SEVERE CRUSHING FRACTURES OF THE CALCANEUS Owing to the severe disability which is apt to follow such a lesion these fractures have gained a bad reputation, and to try and minimise the period of disability heroic measures have been adopted, such as immediate subastragaloid arthrodesis, or early weight bearing with

duration of the anæsthetic may be long the patient does not need to be kept deep

1 "BANK" FRACTURES In these cases a small triangle of bone is elevated from the dorsum of the tuberosity. The base of the triangle corresponds to the bursal area of the tuberosity, so that tendon traction can play no part in the lesion and its mechanism is uncertain. It is possibly due to lateral pressure. Reduction is usually easily accomplished by relaxing the tendo Achilles by



FIG. 632 Fracture of the medial tuberosity of the calcaneus (os calcis)

flexing the knee, and plantar flexing the foot, and pushing firmly with the thumbs on either side of the tendon. The foot is then put up in slight plantar flexion for three weeks in a walking plaster which is moulded carefully around the ankle.

2 FRACTURES OF THE SUSTENTACULUM TALII Displacement is medial and small. The line of fracture is sagittal and runs through the groove for the flexor hallucis longus. After swelling has subsided a plaster is applied for three weeks, to prevent inversion.

3 FRACTURES OF THE MEDIAL TUBEROSITY These usually show little displacement, but if it is present it is corrected at the end of

adequately treated by the methods outlined will obtain a reasonably useful and painless foot

The deformities met with in serious injuries may be

1 Shortening of the bone on its long axis

2 Broadening of the bone

3 Angulation of the bone open medially, an increase of its normal curve

4 Depression of the posterior articular surface and obliteration of the salient angle, due either to this or to fracture of the body, with angulation open upwards

Only when these are gross is a specific attempt made to reduce them. Reduction *per se* is unlikely to reduce the amount of subse-



FIG 630 Loss of the normal concavity of the tendo Achilles after untreated compression fracture of the calcaneus

quent arthritis, but may reduce the strains imposed on the arthritic joints by restoring normal alignment. In particular, an attempt is made to reduce shortening and flattening of the calcaneus.

Various methods of reduction have been devised and the important ones will be outlined.

1 **PHELPS GOCHT CLAMP** The action of this clamp is best explained diagrammatically. The clamp is so adjusted that pressure is applied above the neck of the talus, to the upper surface of the tuberosity of the calcaneus and to the under surface of the calcaneus. By tightening this pressure the salient angle of the calcaneus can be partly restored. Reduction by this method can never be complete.

2 **BY A POSTERIOR PIN** A Steinmann's pin is driven into the calcaneus from the posterior aspect. Control X-rays are taken. By comparison with the normal foot and assuming the posterior

no attempt at reduction in order to encourage arthrodesis. This is to abandon at once any effort to obtain a normal foot. While not



FIG. 634 Fracture of the body of the calcaneus with displacement of the lateral portion of the posterior articular surface (retouched)



FIG. 635 Severe compression fracture of the calcaneus with obliteration of the salient angle

denying that a small number of cases will come to arthrodesis, such a nihilist attitude is not justified by the number of cases which

cases this method may be effective. The after-treatment is similar to the next method.

Both the above methods correct only the obliterated salient angle, and require to be combined with compression to correct the broadening and angulation.

3. BY SKELETAL TRACTION AND COMPRESSION. This is the most useful method, and can be combined with continuous traction as after treatment.

Method. A Kirschner wire or a thin Steinmann's pin is inserted in the upper posterior angle of the calcaneus. This position is necessary to avoid the pin being in the way of the compression clamp. The leg is then put up in the Böhler traction frame and the stirrup attached by a spring balance to the tightening screw. The bar under the knee has previously been well padded and an extra support bar is placed over the lower third of the tibia.

From this a piece of webbing or calico is tied around the leg so as to support its lower third (previously pins were inserted in the tibia,



FIG. 639. Severe crushing fracture of the calcaneus. The correct position for the pin.



FIG. 640. The pin in position. The shortening and broadening of the calcaneus is well shown.

fractured portion of the calcaneus moves with the pin, it should be possible to calculate the angle through which the pin must be moved




FIG 637 The action of the I helps Cocht osteoclast in reducing fractures of the calcaneus. The arrows indicate the sites of the padded rollers of the clamp and the general direction of their pressure (Clamp shown in Fig 108)



FIG 638 An alternative method of reduction of fissure fractures of the calcaneus with displacement. A sharp metal spike is introduced from behind and forced downward till the salient angle is restored

to restore the fragment to normal. This is then forcibly accomplished, and the pin incorporated in the plaster. Unfortunately the pin does not always move the posterior fragment. In simple

ing of the bone. While this pull is maintained the compression clamp is applied to the calcaneus, with the reniform pad on the



FIG. 643 The final result with the calcaneus restored to almost normal appearance and a normal salient angle

medial side. It is screwed up to a distance of 35 mm. apart, the average width of the calcaneus, and then immediately relaxed



FIG. 644 The reduction of a fracture of the calcaneus. Ready for the longitudinal pull

Control X rays may now be taken, and while they are being developed the traction is once more brought in line with the leg and tightened. A plaster slab is placed on the extensor surface of

but this is unnecessary) Traction is now made in the direction of the leg up to 40 to 60 lbs This reduces the impaction of the sul-



FIG 641 The same case after traction in the direction of the tuberosity has been applied and the calcaneal compression clamp has been used

astragaloid joint and restores the salient angle The pull is now relaxed and line of pull altered to the line of the tuberosity of the



FIG 642 Lateral view of the calcaneus under continuous skeletal traction

calcaneus, approximately 45° to the line of the leg The screw traction is now tightened to 30 to 40 lbs This reduces the shorten-

ing of the bone While this pull is maintained the compression clamp is applied to the calcaneus, with the renform pad on the



FIG 643 The final result with the calcaneus restored to almost normal appearance and a normal salient angle

medial side It is screwed up to a distance of 35 mm apart, the average width of the calcaneus, and then immediately relaxed



FIG 644 The reduction of a fracture of the calcaneus Ready for the longitudinal pull

Control X rays may now be taken, and while they are being developed the traction is once more brought in line with the leg and tightened A plaster slab is placed on the extensor surface of

the limb and bandaged on. When this has set the limb is placed on a Braun's splint and a weight of 10 to 15 lbs placed on the stirrup.

Treatment after reduction. The forces tending to reproduce the displacement are the pull of the tendo calcaneus and the weight of the body. Weight bearing can easily be avoided, but the pull of the tendo calcaneus is constant and difficult to counteract. Flexion of the knee is not sufficient. One may counteract this force by continuous traction, or one may incorporate the calcaneal pin in the plaster together with another one below the tibial tuberosity, which by maintaining a fixed distance between the pins counteracts any



FIG 645 Reduction of a fracture of the calcaneus. Traction being applied in the direction of the tuberosity of the calcaneus.

tendency to compression. Both these methods have the disadvantage of producing great stiffness in the hind foot. It is possible that in this lies their success, as if the movement of the subtalar joint is restricted or the joint ankylosed it is pain free.

In general the deformity if well reduced will not recur to its original degree and often will remain reduced if weight bearing is avoided for the first two months.

(A) CONTINUOUS TRACTION. The extensor plaster slab, as described above, is bandaged on, leaving the heel free and holding the foot in slight dorsiflexion. These bandages may be reinforced by plaster bandages if desired. The traction of 5 to 12 lbs is maintained for four weeks if the reduction is satisfactory. The pin

is then removed and the limb placed in a leg plaster for a further four weeks. At the end of the eighth week weight bearing is permitted. At the end of the twelfth week the plaster is removed and an Unna's paste stocking substituted for it, and exercises for the ankle are given.

(B) CONTINUOUS DISTRACTION. If this method is to be adopted a second pin is inserted below the tibial tuberosity. At the end of reduction a complete leg plaster is applied, incorporating both pins. When this is done care must be taken that the distracting force on both pins is not too great, and the tension must be reduced to 20 to 30 lbs., and the position preferably checked by X-rays before




FIG 646 The application of a plaster on the anterior surface of the limb leaving the heel free

the plaster is applied. After a few days a walking iron or rubber heel is applied, and the patient allowed to get up. The plaster is worn for eight weeks, and then an ordinary walking plaster applied for two to four weeks, followed by an Unna's paste stocking.

There has been considerable discussion as to the time when reduction should be performed. It is often inadvisable in the first few days on account of shock or abrasions or other injuries, but there is no necessity to wait ten or more days. Unless there is some contra-indication such as an abrasion, it is carried out on the second or third day. Gross swelling is massaged away before the clamp is applied.

Cases in which it is considered unnecessary to reduce the

deformity may be of two kinds. Those in which deformity is so gross that it is unlikely to be benefited by reduction and in which



FIG. 647. The leg resting on a Braun's splint under continuous traction. Foot drop is prevented by the anterior plaster slab.



FIG. 648. Same case showing the restoration of the salient angle under skeletal traction with a Kirschner wire.

ankylosis of the subtalar joint is likely to occur, and those in which there is insufficient deformity to justify reduction. These cases are

treated by elevation and early massage and non-weight-bearing exercises. These are persisted in till a stable and relatively painless foot results when weight bearing is recommenced gradually.

PROGNOSIS Three groups of cases will be found

1 Those in which a firm bony or fibrous ankylosis results which is pain free or reasonably comfortable

2 Those in which a small range of pain free movement returns

3 Those in which increased use of the limb produces increased pain, usually followed by radiological changes of sub taloid arthritis. These cases have persistent or increasing disability and eventually demand a sub taloid arthrodesis.

It must be remembered that a small number of cases in which damage is done to the posterior talo calcaneal joint will also go on to arthritis.

After-treatment The average disability period for a fracture of the os calcis of any severity is twelve months. The patient may be permanently crippled for hard manual labour. Ankle movements are unaffected, but owing to the destruction of the sub-taloid joint with subsequent traumatic arthritis there is a loss of inversion and eversion of the heel. This makes walking diagonally on a slope and on rough ground particularly troublesome. If there is no attempt at reduction made this is further complicated by the short inverted heel and flat foot. A new occupation may thus have to be found for the patient and the period of rehabilitation is likely to be long.

Fractures of the Navicular

Fractures of the navicular are the only other lesions commonly met with, though compression injuries may damage a number of bones together, or any single bone. Navicular fractures arise from severe dorsiflexion strain on the foot which fractures the bone and squeezes the fragments on to the dorsum of the foot. Reduction is made by plantar flexion combined with dorsal pressure, and the foot is plastered at right angles. In a few cases this is not sufficient to reduce the fragments, and the talus and cuneiforms must be pulled apart by skeletal traction. A wire is inserted in the calcaneus and another in the bases of the metacarpals and traction made on the traction frame. Firm pressure is now made on the dorsum, if necessary, with a clamp. This is followed by a plaster incorporating both wires, and retained for three weeks.

Fractures of the tuberosity are occasionally met with, and the confusion which may arise from an accessory navicular tubercle has been mentioned already. A walking plaster may be required to rest the leg.

deformity may be of two kinds. Those in which deformity is so gross that it is unlikely to be benefited by reduction and in which



FIG. 647 The leg resting on a Braun's splint under continuous traction. Foot drop is prevented by the anterior plaster slab.



FIG. 648 Same case showing the restoration of the salient angle under skeletal traction with a Kirschner wire.

ankylosis of the sub-taloid joint is likely to occur, and those in which there is insufficient deformity to justify reduction. These cases are

and of tissue destroyed. Provided the injury has produced no gross disturbance of the foot posture, and there is not an excessive loss of the skin on the sole, the results will be satisfactory. Late difficulties in healed cases arises chiefly from

- 1 Pressure on prominent bony areas
- 2 Loss of sensation with the development of trophic ulcers
- 3 Disturbances in the vascular supply, with œdema, skin lesions and pain

4 Recrudescences of infection

In grossly infected cases the prognosis is uncertain. In spite of a reasonably normal appearance of the foot the function is always gravely impaired. If there is gross destruction of small joints and erosion of the cancellous bodies of one or two small bones, or of the body of the calcaneus, it is probable that amputation will be needed in the end and the patient may be saved much suffering by coming to an early decision on this matter. In particular, these remarks apply to the complicated foot injuries resulting from land mine explosions in modern warfare.

Fractures of the Metatarsals

These are similar in type to fractures of the metacarpals. They are most frequently due to crushing injuries, and so are frequently compound. With severe blows one or more metatarsals are often broken transversely at the level of the blow. Owing to the ligamentous and muscular attachments there is usually little displacement. Following such injuries it is wise to keep the foot elevated to avoid swelling of the tissues which rapidly occur in the dependent limb. Two special types of fracture will require mention, the "march" fracture and the fractures of the base of the fifth metatarsal.

FRACTURES OF THE METATARSALS WITH NO DISPLACEMENT

These are not uncommon and though the immediate pain is apt to be more severe than that from a march fracture, for reasons given under that head, the same treatment is recommended.

FRACTURES OF THE METATARSALS WITH DISPLACEMENT These are usually accompanied by soft tissue damage which requires the treatment meted out to compound lesions elsewhere. It is still more important in these cases to elevate the foot and avoid swelling. The fractures are reduced by manipulation and the leg plastered. The limb is then placed on a Braun's splint. Where difficulty is met in reduction strong traction combined with the manipulation should be tried. Traction is obtained by passing stainless steel wire or strong silkworm gut through the pulps of the toes and attaching it to a wooden bar on which one may pull. While a pull is maintained

Fractures of the Other Tarsal Bones

Compression fractures and fractures from direct violence are not uncommon, due to the dropping of weights on the foot. Avulsion of a flake from the cuboid is a not uncommon accompaniment of severe sprain of the mid-tarsal joint.

Small flakes of bone are often pulled out from the dorsum of the tarsal bones by excessive plantar flexion. This is most commonly seen in the navicular and not to be confused with the talo-navicular accessory bone. The treatment of ligament traction fractures of this type depends on the degree of associated damage.

TREATMENT In general, unless there is a specific reason such as a compound fracture, progress is more rapid if the patient can be



FIG. 649. Compression fracture with anterior dislocation of the navicular.

rested and given Faradic foot baths, massage and non weight-bearing exercises. If it is important that the patient should be up and about without crutches rapidly a light walking plaster may be applied. The long period of rehabilitation which must follow any immobilisation of the foot in plaster, before the patient is fit for much activity on the feet, is a serious disadvantage, and where possible rest and early active non-weight bearing exercise is to be recommended.

Compound fractures of the tarsus The blood supply of the foot is good, and the majority of injuries will therefore do well if primary closure of the wound can be carried out. The plaster should extend beyond the toes to prevent contraction, which occurs in injuries to the sole and calf, and to relieve the toes of the weight of the bed clothes. If the wound has to be packed and left open the prognosis is less satisfactory, and depends on the extent of the inflammation.

fractures by immobilisation in plaster is to be deprecated. It results in further deterioration in muscular tone and necessitates a long period of rehabilitation on removal of the plaster. It occurs most commonly in young active adults, often associated with a sudden increase of activity, after a sedentary existence, such as typically occurs in training a recruit to march. There is no definite history of trauma, but often one of tiredness or aching in the foot for some time before the onset of acute symptoms. The patient complains of pain, usually over the second or third metatarsal, rarely the fourth. First this causes him to rest the foot, and finally to seek advice. On examination the foot may be generally swollen, and there may be a visible or palpable swelling in the region of the shaft of the affected metatarsal. An X ray reveals one of three conditions. (1) A little rarefaction of the shaft or neck of the



FIG. 652. Transverse fracture of the base of the fifth metatarsal.

affected metatarsal. (2) There is an oval shadow with a fracture of the metatarsal at its centre. (3) The shaft of the metatarsal is surrounded by a spindle shaped shadow resembling callus, and no fracture is visible. The first is the early stage before fracture, accompanied by aching feet. The second is the established stage most commonly seen, in which fracture has followed changes in the bone. It is obvious that the pathology of the condition must have been in existence long before the radiograph was taken. The third stage is the healing stage, in which the fracture line has been obliterated by healing.

TREATMENT This falls into two divisions, corresponding to the clinical severity of the case.

The Acute Case Characterised by acute pain, sudden onset, swelling of the foot, and a recent fracture line in the X ray. The foot should be elevated and rested for a few days, and as soon as the acute phase is over, treated as the subacute case.

an attempt is made to mould the displaced fragments into position. When this is done a leg plaster is applied. In order to retain the fragments the continuation of slight traction may be necessary. This is best carried out by the incorporation of a wire in the sole of the plaster and attaching the toe to it as in the manner of a finger wire. Slight flexion of plaster and attached toe puts traction on the metatarsal. Where possible this should be avoided and if retention of position is satisfactory early exercises should be commenced to all toes. The length of immobilisation should be no longer than necessary for the metatarsal to settle in position. At



FIG. 670 Fractures of the shafts of the first second and third metatarsals with displacement



FIG. 671 The same case after digital extension

the end of this period of seven to ten days the plaster should be removed and exercises commenced of a non weight bearing type. Weight bearing may be commenced as soon as signs of consolidation commence, usually between the third and fourth week.

March fractures This fracture is the most common of the fatigue fractures of bone and shows the characteristic features of fatigue fractures in general. The incidence of the condition can be definitely related to the severity of exertion undertaken and the length of time the strain continues. At the same time it must be realised that "march" fracture is only one sign of severe foot strain, and that it is accompanied by a defective muscular tone throughout the foot and leg. For this reason the treatment of "march"

Fractures of the Phalanges of the Toes

The most commonly injured phalanx is the terminal phalanx of the great toe. As this is usually due to crushing injuries it is not infrequently compound, and accompanied by abrasions which makes strapping fixation impossible. Cases which to the casual glance do not appear compound are often indirectly compound below the nail. For this reason we believe in removing the nail in all serious crushing injuries of the toes and evacuating the



FIG 654 Fracture of the tip of the base of the fifth metatarsal



FIG 655 Oblique fracture of the proximal phalanx of the great toe involving the joint

hematoma. This relieves the patient of pain and cuts down the incidence of infection by removing a readily infected nidus and allowing the nail bed to dry up. Such a removal is followed by a light sole plaster bandaged to the foot, extending to just beyond the toes, and the resting of the leg on a Braun's splint, while the toe is exposed to radiant heat or the air. Under such circumstances the toes rapidly dry up and the patient can be given a walking boot or shoe with the toe cap removed.

Non compound fractures with little displacement can be

The Subacute Case The patient should be taken off heavy activity on the feet. A valgus insole with a sponge rubber metatarsal pad should be provided. As a cheaper substitute a felt pad may be strapped under the metatarsal bases. Faradic foot bath and toe stretching exercises are given and light activity in boot encouraged. The condition settles down in two to four weeks from the date of complaint under this regime.

Fracture of the base of the fifth metatarsal This is due to sudden inversion of the foot, or blows on the outer aspect of the foot. It usually takes the form of a transverse fracture behind the tuberosity of the bone, but smaller chips may be broken off the region



FIG 653 Normal epiphysis at the base of the fifth metatarsal

of the tuberosity and interest attaches to them as they may be confused with any of the following conditions

- 1 A normal epiphysis which unites at puberty (Fig 653)
- 2 A persistent ununited epiphysis in an adult (Rare)
- 3 The os Vesalianum, a small vestigial remnant which lies opposite the tip of the bone
- 4 Sesamoid bone in the region (In tendon of peroneus longus)

To differentiate these requires careful examination of the films and X rays of the opposite side for comparison.

The treatment of any fracture in this region is similar to that of a march fracture. In acute cases great relief of pain will follow infiltration of the fracture line with novocaine. This enables early massage and activity to remove oedema and swelling. Wearing a stiff soled boot will be of assistance in relieving pain on walking in the later stages. Immobilisation in plaster is rarely required.

long continued pain in the foot may result. The only symptoms are pain in the foot which is localised to the sesamoid region, with some swelling and bruising in acute cases. They are recognised




FIG. 657 The varieties of ossification of the sesamoids. M Medial side
I Lateral side.

by the X-ray, but one may require an oblique view to establish a doubtful case, together with a view of the opposite side, as the sesamoids may ossify irregularly, and as this is invariably bilateral



FIG. 658 Fracture of the medial sesamoid bone

a comparative X-ray will rule out this condition. If unusual ossification has occurred it is the medial sesamoid which is most commonly involved. It may be divided into two, three or four sections. If the lateral sesamoid is involved it is divided into two only

supported by a few turns of strapping over a narrow pad of felt which comes well under the ball of the toe. This usually makes the toe susceptible to pressure from the shoe, and the most satisfactory method of getting over this is to cut the toe out of an old shoe and wear it till the swelling has gone, usually in two to three weeks' time. Further rest to the toe can be obtained if desired by incorporating a metal bar in the sole below the great toe.

Fractures of toes other than the great toe cause little disability as a rule, and require strapping only.

Fractures with displacement of any moment occur only in the proximal phalanx of the great toe, where any deformity is a disability. In the presence of abrasions skeletal traction must be employed by



FIG 656 Finger wire incorporated in a walking plaster for the extension and immobilisation of the great toe in fractures of the metacarpal and proximal phalanx of any severity.

passing a stitch through the pulp of the toe, or the use of stainless steel wire. This is attached to a wire incorporated in a leg plaster. In ordinary cases it will be sufficient to strap the toe to the wire and then bend wire and toe as in the case of finger fractures (Fig 656).

The treatment of compound lesions has already been described, elevation of the toes and absolute rest being important after excision and suture under local anaesthesia. The long disability which follows infected lesions of the toes makes every care worth while, and the condition itself is not without danger. Malgaigne in the pre-aseptic era having reported seven deaths in compound fracture of the great toe in a total of 41 cases.

Fractures of the sesamoids of the great toe. These bones are rarely fractured but are important as, if overlooked and untreated,

CHAPTER XXXIII

DISLOCATIONS OF THE JAW AND UPPER EXTREMITY

Dislocations of the Mandible

DISLOCATIONS of the mandible may be unilateral or bilateral. Only the unilateral lesion arising from a blow on the side of the jaw is likely to be complicated by a fracture of the condyle or, less frequently, of other portions of the jaw. The bilateral lesion may occur spontaneously on yawning or on attempting a large bite. In full opening of the mouth the condyle slides forwards on to the eminentia articularis, and with slight further strain may slip over to the anterior aspect of this, and remain fixed there.

In bilateral lesions the jaw is fixed open, and the patient is unable to swallow, so he dribbles saliva. Depressions in front of both ears are palpable where the condyles normally lie. In unilateral lesions the jaw is not held so widely open, and the chin deviates to the uninjured side. Reduction in either case is usually readily brought about by grasping the lower jaw firmly in a towel, with the thumbs over the



FIG. 659 Reduction of a dislocation of the mandible

molars and the fingers outside. The jaw is first depressed and the whole mandible then pushed directly backwards. Reduction is nearly always possible without an anæsthetic. The after-treatment consists in the avoidance of gaping, the necessity for which is impressed on the patient by giving him a four tailed bandage under the chin.

Fracture dislocations are often difficult to reduce, but in spite of failure to do so the movements of the jaw are quite good. If the condyle cannot be reduced by manipulation operative interference is unwise owing to the technical difficulties, and the poor results obtained do not justify it. Should a bad result be obtained from conservative treatment, and this is unusual, the condyle may always be excised later.

TREATMENT In acute cases the foot must be rested in a walking plaster for three to four weeks in the hope of obtaining union. At the end of this time the plaster is removed and the patient given a metatarsal arch support. This is followed by a course of Faradic foot baths and exercises. In chronic cases the effect of a metatarsal arch support is first tried for a month, and if this fails to relieve the condition excision of the bone is advised.

REFERENCES

Anatomy

THURSTAN HOLLAND "The Accessory Bones of the Foot" Robert Jones Birthday Volume Humphrey Milford, London, 1928 P 157 (Also summarised in Lee McGregor's 'Surgical Anatomy' John Wright)

Talus

SMITH H "Subastragalioid Dislocation," *J Bone and Joint Surg*, 1937, 19, 373

MILCH "Astragulo scaphoid Dislocation" *Ann Surg*, 1929, 89, 427

GRAHAM and FAULKNER "Astragalectomy for Fractures of the Astragalus," *Ann Surg* 1929 89, 435

BONNIN J G "Dislocations and Fracture Dislocations of the Talus," *Brit J Surg* 1940-41, 27, 88

COLTART, quoted by WATSON JONES "Bone and Joint Injuries," 3rd ed Livingstone Edin, 1943 Vol II

Calcaneus

CORNN, H R "The Treatment of Fractures of the Os Calcis" (Method not recommended but good bibliography), *J Bone and Joint Surg*, 1935, 17 392

SCHOFIELD "Fracture of the Os Calcis" *J Bone and Joint Surg*, 1936 18, 566

HERMANN "Conservative Therapy for Fracture of the Os Calcis," *J Bone and Joint Surg* 1937 19, 709

EASTWOOD "Fracture of the Os Calcis," *Brit J Surg*, 1938, 25, 636 (Advocating conservative treatment)

BROOMHEAD HOSFORD and Others "Discussion on Fractures in the Region of the Ankle Joint" *Proc Roy Soc Med* 1932, 25 (2), 1082

PALMER, I "The Mechanism and Treatment of Fractures of the Calcaneus" *J Bone and Joint Surg*, 1948 30a, 2-8

Tarsus

WILSON, P D "Fractures and Dislocations of the Tarsal Bones" *South M J*, 1933, 26 833

Metatarsals

MEYERDING, H W "March Fracture" *Surg Gynec and Obstets*, 1938, 67, 234

LEWIN, G "Fractures of the Metatarsals," *Proc Roy Soc Med* 1938, 31, 789

DRUMMOND R "March Fracture Report on a Case involving both Feet" *Brit M J*, 1940 2 413

The more serious lesion is the complete dislocation of the joint, which can only occur when the conoid and trapezoid ligaments are torn. The whole weight of the limb then drags the acromion away from the clavicle. The deformity is much more marked clinically than that due to subluxation, and an X-ray shows a wide separation of the joint surfaces. The treatment is similar to subluxation, for the aim is the same, the complete relief of the joint from the weight of the limb, but the immobilisation must be maintained much longer to give the damaged ligaments time to heal. A period of four to six weeks must elapse before this occurs and throughout this time care must be taken never to allow the support of the strapping to relax. (See Chapter XIX)

The difficulties of retention with strapping demand continuous supervision and some stiffness of the elbow and shoulder may follow. To avoid this open operation and fixation of the clavicle by a single screw passed through it into the coracoid process has been employed. The screw must not be fixed firmly in the clavicle or it will fracture with movement, and must have a washer to prevent it pulling through the clavicle. After consolidation of the ligaments, it is removed, usually at the end of three months. Undoubtedly the best results are achieved by this method, but perfect function is possible with some deformity and it is not often carried out. In the rare cases in which pain persists at the acromio clavicular joint excision of a $\frac{1}{4}$ inch of the end of the clavicle will give relief.

Persistence of pain after strain or subluxation or after the more serious lesion of dislocation may be considerably relieved, and in some cases abolished altogether, by the infiltration of the joint and ligaments with novocaine. In long-standing cases an oily solution such as "Proetocaine" may be employed as its effects last longer. Such treatment needs to be followed by immediate movements, assisted if possible through the full range, and a continuation of physiotherapy for two weeks.

Dislocations of the Shoulder

Stability is sacrificed in the shoulder joint to freedom of movement, and the price of this is the liability to dislocation, which makes the shoulder the most frequently dislocated joint in the body. The shallow glenoid cavity, the lax ligaments, and the long lever of the humerus all take a part in facilitating dislocation.

The causative violence may be direct or indirect, more commonly the latter, the usual accident being a fall on the extended abducted

Dislocations of the Clavicle

The sterno-clavicular joint The path of the dislocated medial end of the clavicle is insuperably resisted in one direction only, that downward and posterior, where it comes into collision with the first rib. It may pass in any other direction, but, owing to the strength of the articulation and of the costo-clavicular ligament, dislocation in any direction is rare. The injury is due to a fall on the point of the shoulder, or to direct violence. (See Fig 224.)

Posterior dislocations These are rare, and chiefly interesting because the pressure may deform the trachea and cause shortness of breath, or, if on the veins, cause venous engorgement of the arm.

Upward dislocations These are uncommon as the position is unstable, and the bone slips down to its normal position.

Antero inferiorly This is the common lesion. The medial end of the bone appears to be very prominent and lies at a lower level than usual. A variable amount of bruising appears around the joint. The dislocation is readily reduced by any of the manoeuvres which reduce a fractured clavicle, but it is difficult to retain in position. In practice this is unimportant as there is little disability if the bone is left in its abnormal position. An attempt to retain the position may be made by a pad over the medial end of the bone, held in place by a circular plaster applied over the injured shoulder and under the opposite axilla. This is supplemented by a figure eight bandage to draw the shoulder back. If successful this will have to be retained for three to four weeks. Operative reduction and fixation by fascial slings is not warranted till later evidence of dysfunction has accumulated.



FIG 660 Complete dislocation of the acromio-clavicular joint indicating rupture of the coracoid and trapezoid ligaments

The acromio-clavicular joint This joint is not infrequently injured in falls on the shoulder, the lesion being either a sprain, a subluxation or a complete dislocation. With the sprain there is merely local pain. In the subluxation some increase in prominence of the injured clavicle will be palpable and may be shown in the X-ray.

A small local chip or fissure fracture into the joint may be present. This lesion requires rest in Robert Jones' strapping for two to three weeks (see Fig 237).

2 INFERIOR Sub glenoid This is the primary lesion in most cases and is further displaced anteriorly or posteriorly (Fig 661)

Luxatio erecta In this rare lesion the head passes through the lower portion of the capsule, and the arm is then over-abducted, so that it slips down the axillary border of the scapula, and the arm remains fixed over the head



FIG 662 Dislocation of the shoulder showing the flattening of the shoulder and the abduction of the elbow The grip on the wrist is a characteristic one to prevent pain from movement and is seen in many lesions of the shoulder and arm

3 POSTERIOR Sub acromial } Both rare
Sub spinous }

In all cases but luxatio erecta there are certain common physical signs

- 1 Flattening of the normal deltoid contour (Fig 662)
- 2 Inability to place the elbow against the side (Dugas' sign)
- 3 Prominence of the acromion with an unusual emptiness below it
- 4 The head of the humerus may be felt to rotate under the fingers in an abnormal position
- 5 Hamilton's ruler test A ruler may be made to touch the acromion and the lateral condyle of the humerus Normally it is prevented from this by the head of the humerus

arm which levers the humerus against the acromion, and forces the head of the humerus through the lower weak portion of the capsule. The head may remain there, but more commonly it is further displaced. In direct violence the head of the humerus is forcibly torn away from the glenoid, pushing the capsule off the bone.



FIG. 661 Subglenoid dislocation of the humerus

Such force may be transmitted from the elbow, or be due to a blow on the anterior or posterior aspect of the arm, especially if the elbow is fixed at the moment of impact. This type of injury is associated with fracture of the glenoid, or the tuberosities, or of the upper end of the humerus.

Dislocations may be classified

- 1 ANTERIOR Sub coracoid (See Figs 253, 254)
 Sub clavicular

2 INFERIOR Sub glenoid This is the primary lesion in most cases and is further displaced anteriorly or posteriorly (Fig 661)

Luxatio erecta In this rare lesion the head passes through the lower portion of the capsule, and the arm is then over abducted, so that it slips down the axillary border of the scapula and the arm remains fixed over the head



Fig 662 Dislocation of the shoulder showing the flattening of the shoulder and the abduction of the elbow The grip on the wrist is a characteristic one to prevent pain from movement and is seen in many lesions of the shoulder and arm

3 POSTERIOR Sub acromial } Both rare
Sub spinous }

In all cases, but luxatio erecta there are certain common physical signs

- 1 Flattening of the normal deltoid contour (Fig 662)
- 2 Inability to place the elbow against the side (Dugas' sign)
- 3 Prominence of the acromion with an unusual emptiness below it
- 4 The head of the humerus may be felt to rotate under the fingers in an abnormal position
- 5 Hamilton's ruler test A ruler may be made to touch the acromion and the lateral condyle of the humerus Normally it is prevented from this by the head of the humerus

humerus (see Fig 249) This produces a characteristic syndrome Following the reduction there is complete instability of the joint




FIG 666 Kocher's manoeuvre (c) Stage of adduction of the elbow

which very easily redislocates again This lesion may be produced by excessive violence in reducing a dislocation Open operation is usually



FIG 667 Kocher's manoeuvre (d) Stage of internal rotation

satisfactory in restoring the movement of the shoulder and arthrodesis may be necessary

(c) *Subacromial bursa* Adhesions and partial ruptures of the short rotators lying in its floor are productive of much stiffness (see p 313)

INJURY TO THE NOSE See Fracture Dislocations, Chapter XXI

Treatment Reduction as soon as possible is the first aim Not only does this relieve the patient from pain, but there is a period immediately after the injury in which there appears to be a mild anæsthesia, and consequently less muscle spasm, and in which reduction without an anæsthetic is considerably easier

METHODS Now that muscle spasm can be so easily abolished for the short time necessary for reduction by intravenous anæsthesia this should always be used if available When relaxed the head of the humerus will often slip back easily by gentle traction on the fixed elbow and slight outward pressure on the head from a hand in the axilla Failing this Kocher's or the Hippocratic method is used

Kocher's This method aims at making the head of the humerus retrace its path, and is most suitable for sub-coracoid dislocations Though probably based on incorrect anatomical considerations, it is nevertheless effective In many cases it can be carried out slowly and gently without anæsthesia Whenever difficulty is encountered the first step to overcome it is general anæsthesia to abolish muscular spasm

(a) For a short period traction is applied to the arm in the slightly flexed and abducted position

(b) The patient's forearm is then used as a lever and with the elbow steadied at the side the humerus is slowly fully externally rotated It is this proceeding which should be done slowly and steadily, as it tenses the untorn subscapularis

(c) The elbow is now adducted across the chest while the external rotation is maintained

(d) Finally, with the elbow still steadied, the arm is internally rotated by sweeping the hand across the face to the opposite shoulder It is during this movement that reduction usually occurs

Hippocratic method If the above method fails, and under anæsthesia this is seldom the case, traction is applied to the arm This may be carried out with the arm in various positions (1) the arm may be slowly brought above the head and almost vertical traction be applied (2) The arm may be pulled upon when at right angles to the body with a counter traction band around the chest (3) In the classical Hippocratic method the unbooted heel is placed in the axilla for counter-traction, and is used as a fulcrum after a short period of traction by adducting the arm over it This

humerus (see Fig. 249). This produces a characteristic syndrome. Following the reduction there is complete instability of the joint




FIG. 666 Kocher's manoeuvre (c) Stage of adduction of the elbow

which very easily re-dislocates again. This lesion may be produced by excessive violence in reducing a dislocation. Open operation is un-



FIG. 667 Kocher's manoeuvre (d) Stage of internal rotation.

satisfactory in restoring the movement of the shoulder and arthrodesis may be necessary.

the olecranon, which may give the humerus the appearance of being bowed backwards. A valgus or varus deformity may be associated. Pronation and supination is partly lost. It is distinguished from a



FIG. 668. Posterior dislocation of the elbow showing posterior displacement of the head of the radius.



FIG. 669. Lateral view of a posterior dislocation of the elbow.



FIG. 670. Posterior view of the same case to show the broadening of the elbow.

fracture of the humerus by the features described and by the alteration in the normal relationship of the olecranon to the epicondyles. (See p. 320.) An X ray must be taken in all cases to determine the associated bony injury, which may be

manœuvre exerts considerable force, and care must be taken not to convert a dislocation into a fracture dislocation

After treatment The arm is kept in a sling for three weeks, exercises, massage and movements being commenced at the end of the first week. In these movements full abduction is avoided, but external and internal rotation insisted upon. It is found that an arm capable of full internal and external rotation is capable of almost full abduction

LONG STANDING CASES After a short time there is shortening and contraction of muscles which makes reduction difficult and, if forced, dangerous. No exact period as to the date after which reduction is impossible can be given, but after the fourth week efforts to reduce the dislocation are not likely to succeed. Under these circumstances it is necessary to submit the case to operative reduction through an anterior incision, which may be a difficult procedure, and may end up with an excision of the head of the humerus. It is often remarkable how good is the function of an unreduced dislocation, and such cases are certainly better left in the elderly

Dislocation of the Elbow

The elbow follows the shoulder in order of frequency of dislocation, but while in shoulder lesions the patient is usually adult, in elbow dislocations a high percentage occur in children and adolescents owing to the undeveloped state of the coronoid and olecranon processes

Dislocations may be

- 1 Posterior The most common lesion
- 2 Anterior A rare lesion, accompanied by olecranon fracture
- 3 Lateral or medial
- 4 Divergent dislocations in which the upper radio ulnar joint is also dislocated
- 5 Dislocations of the head of the radius alone

POSTERIOR DISLOCATIONS These occur from falls on the hand in which the force, had it been transmitted more directly to the humerus, would produce a supra-condylar or shaft fracture. The head of the radius moves with the ulna, owing to the annular ligament being intact. Fracture of the coronoid may occur, and the brachialis anticus is always separated to some extent, which may lead to some calcification in it later on

Diagnosis The appearance of the arm if not obscured by swelling is typical. The patient holds the forearm by the wrist in incomplete extension (135°). The elbow appears broadened from behind, and the forearm is shortened. There is a hollow above

action of the musculature of the arm, and all forced movements, weight carrying and the like are forbidden. Gentle and persistent active exercises are encouraged. Full movement is usually restored in six weeks. The treatment of dislocation complicated by fracture is the treatment of the fracture after the dislocation has been reduced.

OTHER DISLOCATIONS OF THE ELBOW In the rarer lesions the displacement is usually obvious, and should be confirmed by an X ray. In anterior dislocations there is usually an associated fracture of the olecranon.

Medial dislocation may involve the ulna alone if the orbicular ligament is detached, but usually the two bones move together. The sigmoid notch rests on the edge of the epicondyle, and is readily returned to normal position by extension on the flexed elbow and medial pressure.

Lateral dislocation may be accompanied by tearing of the orbicular



FIG 672 Lateral dislocation of the elbow showing anterior dislocation of the head of the radius. The same case as in Fig. 673.



FIG 673 Lateral dislocation of the elbow. The cross on the skin lies over the olecranon. The X ray of this case is shown in Fig. 672.

ligament and dislocation of the head of the radius. It is interesting as it is the probable mechanism of fracture of the medial epicondyle with displacement into the joint. (See Chapter XXI.) In many of these cases the displacement is incomplete or spontaneously

reduced and the position of the displaced fragment may be overlooked. If the displacement is noted before the dislocation is reduced an attempt may be made to keep it out of the joint by pulling on the bellies of the extensor muscles as the dislocation is reduced.

- 1 Fracture of the head of the radius
- 2 Fracture of the coronoid process
- 3 Fractures of the capitellar surface of the humerus
- 4 Fracture of the medial epicondyle (See Figs 286, 287)
- 5 Other more extensive fractures of the lower end of the humerus

The rapid onset of swelling in the elbow may obscure the diagnosis, and is an added reason for early reduction

TREATMENT This consists of early reduction which is usually



FIG 671 Medial dislocation of both bones of the forearm Intact upper radio ulnar joint

simple and carried out by the method outlined in Chapter XXI for the reduction of flexion fractures of the humerus. The manipulations with the fingers will obviously differ, but the grip recommended gives the best control. After traction with the elbow bent the humerus is pushed back with the thumbs, and readily slips into the sigmoid notch.

After treatment The elbow is retained in a cuff and collar or high sling in moderate flexion for three weeks and then transferred to a low sling. The patient is then encouraged to move his elbow to the full extent allowed by the sling for a week, and it is then dispensed with. The return of movement to the elbow is left to the

movement cannot be carried out the reduction is not complete. If complete the elbow is immobilised in this position with a posterior slab, and sling.

Two complications are met with in this group of cases. Firstly, cases which are easy to reduce but difficult to retain, and, secondly, cases in which manipulative reduction is impossible. In the first group the head of the radius can usually be controlled by adequate flexion, but if this fails at the end of several attempts operation must be carried out. Failure of reduction is due to the interposition of soft tissues, usually the orbicular ligament. Retention is simple once the obstruction is overcome. The second group of cases shows no very obvious reason for the failure of reduction, but an X ray will usually reveal a lower radio-ulnar subluxation, with the lower end of the radius caught in the lower margin of the ulna. This can only be released by section of the posterior ligament of the joint, which can be done with a tenotomy knife after which the head of the radius fits back into place.

An interesting and related lesion is "pulled elbow," a condition met with in children from two to six years of age after sudden traction on the forearm. The child complains of pain in the elbow, refuses to use it, and holds it in pronation. On examination, flexion and extension will be found to be free, but supination is limited. The X ray is usually negative. The theory of its aetiology is that the cartilaginous head of the radius is pulled through the orbicular ligament which closes down between the head of the radius and the capitulum. The treatment is forced supination which produces a slight click and full restoration of movement. This may sometimes be managed without anaesthesia.

Dislocation of the lower radio-ulnar joint. This is an unusual lesion occurring alone, when it arises from direct violence, but it is not uncommonly associated with other lesions. (1) fracture of the shaft of the radius in the lower third, (2) severe Colles's fractures, (3) dislocation of the head of the radius. (See Figs 311a and 311b).

Fracture of the shaft of the radius alone is not difficult to treat in the absence of dislocation at the lower radio-ulnar joint, though one may require skeletal traction to obtain correct apposition. When the joint is dislocated, however, the lesion is very unstable, and the radius tends to displace toward the ulna and the hand to pass into radial deviation.

This tendency to deviate may be resisted by several methods.

(a) The hand may be plastered in ulnar deviation and traction placed on the thumb. This is not advised as the traction is likely to leave a stiff thumb.

(b) After reduction by skeletal traction a wire may be passed

An X ray is taken after reduction and if the epicondyle is still in the joint it is removed by open operation

Divergent dislocation In this lesion the shaft of the humerus is forced between the two bones of the forearm with resultant tearing of all the ligaments of the joint. The ulna slips up posteriorly and the head of the radius to the lateral side so that the forearm becomes locked in almost complete extension. Reduction is carried out by extension in the line of the arm till the sigmoid notch is engaged, and then flexion of the elbow while the head of the radius is forced down by pressure. The arm is then immobilised in moderate flexion by a posterior plaster gutter splint. The after treatment is that of other dislocations of the elbow.



FIG. 674. Medial dislocation of the head of the radius. An unusual case with damage to both median and ulnar nerves, the radial nerve escaping damage. Operative reduction is necessary in such a case.

Dislocation of the head of the radius alone For this to occur the orbicular ligament must be ruptured. The head may then pass anteriorly, posteriorly, medially or laterally, and during any of these movements the deep branch of the radial nerve is likely to be injured. If the head of the radius is displaced to any extent associated injuries are usually present.

- 1 Fracture of the ulna (Monteggia fracture, see Chapter XXIII)
- 2 Fracture of the radius
- 3 Dislocation at the lower radio ulnar joint

The symptoms consist of pain and local bruising and swelling, deformity due to displacement of the head of the radius which can be felt to rotate in an abnormal position, and loss of mobility. In the case of anterior dislocations flexion is very limited. The loss of the supporting action of the radius allows abnormal abduction at the elbow.

TREATMENT Reduction is made by traction on the extended and adducted elbow, while local pressure is made over the displaced head in the required direction. As soon as it is felt to flick back in front of the capitellum the elbow is flexed and supinated. If this



FIG 675 Dislocation of the first carpo metacarpal joint Lateral view




FIG 676 A P view of the same case



FIG 677 Lateral dislocation at an inter phalangeal joint



FIG 678 Posterior dislocation of the terminal phalanx of the thumb

through the radius and ulna below the fracture to hold it in the correct position and incorporated in the plaster

(c) The fracture may be fixed by open operation, and screwing or plating (Fig 313)

After reduction careful control X-rays are necessary at short intervals to check recurrence of the deformity, and the arm must be replastered as swelling subsides. If mal-union occurs the condition can be very crippling. Operative fixation will be found to give the most satisfactory results.

Subluxation and dislocation of the joint should be watched for particularly in comminuted fractures of the Colles's type. Accurate lateral X rays are important in this connection as small degrees of displacement can be obscured by an oblique film. The reduction of the fracture reduces the dislocation as a rule, but there is likely to be excessive mobility of the lower end of the ulna as a sequel. This produces little disability.

Dislocations of the wrist. This, together with fracture dislocations, has been discussed in Chapter XXIV.

Carpo-Metacarpal

Metacarpo-phalangeal and Inter-phalangeal Dislocations

Dislocations at the metacarpo phalangeal and inter-phalangeal joints are readily reduced by traction. Those affecting the thumb are the most interesting. The fracture dislocation of the metacarpo-carpal joint of the thumb has already been discussed (Chapter XXV). In dislocation without fracture the symptoms, diagnosis and treatment are similar, and the condition can only be detected with certainty by an X ray. Once reduced the condition is much more stable than a Bennett's stove fracture, and the strapping method of fixation suffices to retain it.

Of the metacarpo phalangeal dislocations only that of posterior dislocation of the thumb is of particular interest, as in these cases one may meet with unexpected resistance to reduction. The condition arises from excessive strain on the abducted thumb and the base of the phalanx becomes pulled dorsally over the head so that the two bones are almost at right angles. Traction accompanied by flexion reduces the lesion in many cases, but in a certain number the anterior aspect of the joint is buttonholed around the head of the metacarpal, and attempts to reduce the dislocation only increase the tightness of the grip of the tissues. Such cases should be submitted to open operation through an antero lateral incision. After partial division of the tense bands and judicious levering the dislocation may be reduced. It is then put up on a padded finger




FIG 680 Posterior dislocation of all four metacarpo phalangeal joints of the palm—compound into palm



FIG 681 X ray appearance of previous case

splint, flexed. At the end of a fortnight stripping is substituted for the wire splint. In four weeks' time the joint is stable and moderately freely movable. If manipulative reduction has been successful it is sufficient to strap the thumb with several turns of figure eight stripping.

Metacarpophalangeal dislocations of the fingers are usually dorsal and are readily reduced by traction and pressure. The use of a flexed padded wire finger splint is much more satisfactory than flexion of the fingers over a bandage, as the movement of only one finger is affected by it (see Fig. 41).

A compound dislocation at all four metacarpophalangeal joints is shown in Figs. 680, 681. This occurs occasionally from forced hyperextension of all four fingers. Reduction after adequate wound toilet is easy and stable. Finger movements are commenced at the end of the first week.




FIG. 674. Padded wire finger splint applied on the flexor aspect of the thumb for an interphalangeal dislocation.

Interphalangeal dislocations. These may be associated with the fractures which have been described in Chapter XXV. In all cases X-ray is advisable to exclude them. The displacement may be either dorsal or volar or lateral. The diagnosis is obvious and reduction is straightforward. The finger is rested on a padded finger wire splint for a week, and then stripping is substituted.

Carpometacarpal dislocations. These are seldom complete, either the fourth and fifth metacarpal being separated from the hamate or the first and second from the capitate, trapezium and trapezoid. They reduce easily by pressure. Subluxations with pain and swelling over the base of the second metacarpal are common, but clear up with light use. Occasionally chip fractures of the styloid process of the second metacarpal accompany subluxation.

REFERENCES

Shoulder

- BANKART, A. S. B. Dislocations of the Shoulder Joint. Robert Jones Birthday Volume. Oxford Medical Publications 1928 p. 307.
 BOSWORTH, D. M. Shoulder Lesions. *J. Bone and Joint Surg.* 1940, 22, 369.



FIG. 650. Posterior dislocation of all four metacarpophalangeal joints of the palm—compound into palm.



FIG. 681. X-ray appearance of previous case.

- NASH "The Status of Kocher's Method of Reducing Recent Anterior Dislocation of the Shoulder," *J Bone and Joint Surg* 1934, 16, 535
(An article criticising justly Kocher's method on anatomical grounds With full bibliography)
- NICOLA "Recurrent Dislocation of the Shoulder," *Am J Surg*, 1929 6, 815
(Advocating the use of the long head of the biceps in fixing the head of the humerus in position For a full bibliography of the other methods see Kellogg Special "Fractures")
- REICH R "Traumatic Dislocation of the Shoulder" *J Bone and Joint Surg*, 1932 14, 73
- VARIOUS AUTHORS "Recurrent Dislocation of the Shoulder," *J Bone and Joint Surg* 1948, 30b 9-48

Elbow

- CONN "Forward Dislocation of Both Bones of the Forearm at the Elbow," *Surg Gynec and Obstets* 1922, 35, 776
- GEIST and HENRY "Dislocations and Simple Fractures of the Elbow," *Minnesota Med* 1928 11, 509
- WILSON "Fractures and Dislocations in the Region of the Elbow," *Surg Gynec and Obstets*, 1933, 56, 335 (Long and complete article)

Acromio-clavicular and Sterno-clavicular Joints

- HENRY M O "Acromio Clavicular Dislocations," *Minnesota Med*, 1929, 12, 431
- RICHARD "Zur Behandlung der Luxatio Sternoclavicularis" *Zentralb f Chir* 1930 57 1660 (Recommending the use of the menses for plastic procedure)
- NIFSSLY H "Zur Behandlung der Retrosternalen Luxation der Clavicula," *Deutsche Ztschr f Chir* 1930, 231, 405
- FRYNN A H "Treatment of Fractures of the Outer End of the Clavicle" *Surg Gynec and Obstets* 1933 57 118 (Recommends the use of the Bohler clavicle splint)
- FRYNN A H "Dislocation of the Acromio clavicular Joint" *J Bone and Joint Surg*, 1932 14 421

CHAPTER XXXIV

DISLOCATIONS OF THE LOWER EXTREMITY

Dislocations of the Sacro-iliac Joint and Pubic Symphysis

Very rarely there may be a separation of both joints together with a complete dislocation of one half of the pelvis. More commonly either the sacro-iliac joint or the pubic symphysis is injured in association with a fracture of some other part of the pelvis (page 429). This produces the same displacement, is treated in the same manner and liable to the same complications as double fractures of the pelvis, which are described in Chapter XXVI.

Dislocations of the coccyx This lesion is readily reduced by a finger in the rectum. Early abdominal breathing exercises and radiant heat are advisable to avoid persistent pain. Novocaine injection may be of value.

Dislocations of the Hip

Compared with dislocations of the humerus, dislocations of the hip are only one-tenth as common.

The posterior type of dislocation is not infrequently associated with fractures of the acetabulum, particularly when the femur is driven backwards against the deepest part of the socket. The most serious type of fracture accompanies central dislocation of the hip, when the head of the femur is driven through the floor of the acetabulum, a condition described in Chapter XXVI.

Types of dislocation of the hip

- | | | | |
|---|------------------------|---|--|
| 1 | Posterior | (a) Iliac
(b) Sciatic | } Associated with fracture of the acetabulum (Fig. 681a) |
| 2 | Anterior | (a) Pubic
(b) Obturator | |
| 3 | Central (see page 439) | Associated with fractures of the acetabular floor | |

Posterior dislocations Violence applied to the leg in the position of flexion, adduction and internal rotation forces the head of the femur against the lower posterior portion of the capsule. This is the weakest area, and if the force is sufficient it tears the capsule and drives the femoral head on to the surface of the iliac bone (*iliac dislocation*). In cases in which the body is more flexed on the thighs at the moment of impact, the head passes downward towards the great sciatic notch, the so-called *sciatic dislocation*. Here the sciatic nerve is liable to injury. Such violence typically occurs when a

passenger sitting in a car with his legs crossed is thrown forward against the dashboard and strikes it with his knee, when the car is brought to a sudden standstill.

Whether the dislocation is sciotic or iliac, the clinical signs are much the same. There is loss of hip movement, and the leg is held flexed, adducted and internally rotated. This position is maintained owing to the pull of the ruptured Y-shaped ligament. The great trochanter is more prominent, and the whole buttock

appears larger. Comparative measurement of the limb is impossible owing to its flexed position. On attempted movement of the hip "elastic rigidity" is encountered and unless there is an associated fracture there is no crepitus. In this subject the head may be palpated in an abnormal position.

TREATMENT This consists of immediate reduction. The simplest method is that of Stimson, in which the patient is placed face downward on an operating couch, so that the legs hang over the end sufficiently to allow the injured hip



FIG. 651a. Posterior dislocation of the hip together with undisplaced fracture of the posterior margin of the acetabulum.

to flex to a right angle. The uninjured leg is steadied by an assistant. The foot of the injured leg is grasped between the surgeon's knees, and one hand is used to make downward pressure behind the knee, while the other on the buttock follows the course of the reduction. By this method gravity is used to aid in the reduction.

The more commonly used modification of this method is that with the patient lying on his back on the floor and the pelvis steadied by an assistant. The surgeon then attempts to lift the head of the femur forward with the leg in a neutral position.

Bigelow's method of circumduction is the last resort. The patient is placed on the floor, and the pelvis steadied in a similar



FIG. 682 The reduction of a posterior dislocation of the hip by Stimson's method



FIG. 683 The reduction of a posterior dislocation of the hip by traction and lifting the head forward

manner. With the knee flexed the surgeon flexes the hip on the abdomen to a small degree and places traction on the femur by pulling on the bent knee. After a few minutes traction to relax

passenger sitting in a car with his legs crossed is thrown forward against the dashboard and strikes it with his knee, when the car is brought to a sudden standstill.

Whether the dislocation is sciotic or iliac, the clinical signs are much the same. There is loss of hip movement, and the leg is held flexed, adducted and internally rotated. This position is maintained owing to the pull of the unruptured Y-shaped ligament. The great trochanter is more prominent, and the whole buttock

appears larger. Comparative measurement of the limb is impossible owing to its flexed position. On attempted movement of the hip "elastic rigidity" is encountered and unless there is an associated fracture there is no crepitus. In this subject the head may be palpated in an abnormal position.

TREATMENT The consists of immediate reduction. The simplest method is that of Stimson, in which the patient is placed face downward on an operating couch, so that the legs hang over the end sufficiently to allow the injured hip



FIG. 681a. Posterior dislocation of the hip together with undisplaced fracture of the posterior margin of the acetabulum.

to flex to a right angle. The uninjured leg is steadied by an assistant. The foot of the injured leg is grasped between the surgeon's knees, and one hand is used to make downward pressure behind the knee, while the other on the buttock follows the course of the reduction. By this method gravity is used to aid in the reduction.

The more commonly used modification of this method is that with the patient lying on his back on the floor and the pelvis steadied by an assistant. The surgeon then attempts to lift the head of the femur forward with the leg in a neutral position.

4 *Myositis ossificans* This may occur around the hip, especially if the dislocation is accompanied by a fracture. The usual precautions to prevent this occurrence must be taken (See Chapter VI)

5 *Fracture of the femur* Associated injuries to the femur are rare, but the head, neck or shaft may be fractured. Occasionally the neck of the femur is fractured during manipulations to reduce a dislocation. In these cases the head is so grossly displaced that its blood supply is almost invariably damaged, and this is still further damaged by operative reduction, so that we are left almost only one alternative, excision of the head of the bone and insertion of the neck of the femur into the acetabulum (Whitman's operation). Dislocations associated with fracture of the shaft can best be reduced by Stimson's method.

6 *Failure to reduce the dislocation* may not be shown on the antero-posterior film if the position of the head coincides with the acetabular shadow. For this reason a lateral X-ray is advisable. If left unreduced for some time a false acetabulum may form and reduction become impossible. The new acetabulum may be deceptively like the real one and be overlooked in the antero-posterior film (Fig. 683a).

Anterior dislocations These are produced by violence applied to the limb in abduction, the neck of the femur levering on the rim of the acetabulum and forcing the head of the femur out anteriorly. Such injuries are less frequent than those producing posterior dislocations. The Y-shaped ligament remains intact and holds the leg in the characteristic position of abduction, slight flexion and external rotation. The adductors and obturator internus are usually torn, and the head comes to rest on the obturator externus or the pubic bone. The head of the femur is easily palpated in this position. The limb appears to be lengthened more than it actually is, the true lengthening being about 1 inch.

TREATMENT Reduction is carried out by one of the following methods.

1 *Traction* The patient is placed on a table and the hip flexed to 45° and abducted. Traction is applied in this position, and the return of the head to the acetabulum is assisted by downward and outward pressure over the adductors. Internal rotation and adduction then slips the head into the socket.

2 *Bigelow's manoeuvre* This is a similar method of circumduction to that used in posterior dislocations. The leg in this case is flexed, externally rotated, and then circumducted inward, being finally extended.

After treatment This is as for posterior dislocations.

the muscles the limb is then abducted, externally rotated, and finally circumducted outwards, to be brought down beside the other limb with a sweeping movement.

After treatment This is divided into two schools of thought, those who on account of the comparative stability of the reduced joint commence early exercises, and those who, taking into account the severity of the injury necessary to produce such a lesion and

the possible complications, prefer immobilisation in plaster. Taking all points into consideration it would appear that a fortnight's rest in bed, followed by a short walking hip spica of the type applied for abduction fractures of the head of the femur worn for a further three to five weeks, provides satisfactory care with the maximum freedom.

COMPLICATIONS 1 *Fracture of the acetabular rim* If a large portion is separated this may make the dislocation unstable, and after reduction a period of traction is necessary, or open operation and the pegging of a large fragment (See Chapter XXVI). More commonly only a small chip is displaced and can be neglected (Fig 681a).

2 *Arterial necrosis of the head of the femur* This is of rare occurrence. Stringently enough, it is of more common



FIG 683a Formation of a false acetabulum after an unreduced posterior dislocation of the hip. The occurrence of a dislocation was missed owing to shortening of the limb on the opposite side from a fracture.

occurrence in dislocations in the young and adolescent, who should be carefully watched for its occurrence and immediately relieved of weight bearing. Slow absorption of the head and replacement will occur but degenerative arthritis follows after some years. In children Perthe's disease has sometimes followed dislocation and has been ascribed to vascular interference, but the evidence is not yet completely convincing.

3 *Sciatic nerve pressure* This only occurs in posterior dislocations. It is usually bruising producing an incomplete lesion, and recovers rapidly.

Dislocations of the Knee

The knee relies for its strength on the ligamentous and muscular attachments surrounding it. It is very rarely completely dislocated, owing to the large area of its almost flat articular surfaces which demands great displacement. More frequently a subluxation occurs, with tearing of one or other of the ligaments, and these conditions are important as they may pass unrecognised at first.

Dislocation may be

ANTERIOR Due to forced hyper-extension, or blow on the upper end of the tibia behind the flexed knee.

POSTERIOR Due to direct violence applied in a backward direction to the head of the tibia, usually with the knee flexed.

LATERAL Due to a combination of abduction and adduction strain with direct violence.

The diagnosis in all cases of complete dislocation is obvious. The lesion may be compound. In posterior dislocation there may be pressure on the popliteal artery.

Reduction is easy owing to the complete ligamentous tearing when muscle spasm has been abolished by general anaesthesia. After reduction the knee is aspirated and a pressure bandage applied and the leg rested on a straight Thomas's splint for ten to fifteen days. At the end of this period a long walking plaster stretching from the groin to the toes is put on, with the knee in 10° of flexion. Weight bearing is permitted in this in three to four weeks. At the end of eight weeks the foot is allowed to remain free, a knee fixation plaster as used for fractures of the patella being applied. This plaster is persisted in until a stable knee results, which may take four to six months. At the



FIG. 486 Anterior dislocation of the knee.



FIG. 684 Anterior dislocation of the hip
Obturator type.



FIG. 685 The reduction of an anterior dislocation of the hip by traction and pressure over the upper end of the femoral shaft in a downward and outward direction.

Complications are similar except that the femoral artery is liable to damage in place of the sciatic nerve, and there is no tendency to fracture the acetabular rim.

are allowed. The disability is often not as gross as might be expected, but a permanently unstable knee may demand the support of a knee cage.

Injuries to the individual ligaments Unless one is on the look-out for these they may pass unobserved, especially if no X ray is taken with the ligament on the stretch.

It is therefore prudent to aspirate any knee in which there is any gross effusion. If it is at all heavily bloodstained and no fracture has been found to account for this a ligamentous injury is certain. Adequate clinical examination cannot be carried out on account of musculo spasm and pain, and examination under intravenous anaesthesia is essential. This should be combined with radiological examination with the suspected ligament under strain.

1 **THE ANTERIOR CRUCIATE LIGAMENT** This runs from the medial surface of the outer condyle of the femur to the anterior tibial spine, and is tightened by extension. It can consequently be ruptured by hyperextension or any forward displacement of the tibial plateau. Rupture of the ligament allows excessive forward mobility of the knee joint. (See Fig 525)




FIG 667 Testing the knee for rupture of the cruciate ligaments

2 **THE POSTERIOR CRUCIATE LIGAMENT** This runs from the lateral face and anterior aspect of the medial

condyle backwards and outwards to the posterior tibial spine. It is tense in flexion and is injured by the same direct violence to the tibia with the knee flexed, which produces posterior dislocation of the knee. If it is ruptured excessive backward mobility of the tibia on the femur is permitted.

DIAGNOSIS A hemiarthrosis always follows the injury, which may be accompanied by other minor fractures. The abnormal mobility of the upper end of the tibia is best tested for by grasping the upper end of the tibia with the knee flexed and attempting backward and forward movements.

TREATMENT This consists of complete immobilisation of the knee after aspiration of the joint by a knee fixation plaster running from the groin to just above the ankle with the knee slightly flexed. If the anterior ligament is torn some surgeons increase the flexion, but this produces no better result and is less comfortable for the patient. Throughout treatment walking and quadriceps drill are

are allowed. The disability is often not as gross as might be expected, but a permanently unstable knee may demand the support of a knee cage.

Injuries to the individual ligaments. Unless one is on the look-out for these they may pass unobserved, especially if no X ray is taken with the ligament on the stretch.

It is therefore prudent to aspirate any knee in which there is any gross effusion. If it is at all heavily bloodstained and no fracture has been found to account for this, a ligamentous injury is certain. Adequate clinical examination cannot be carried out on account of muscle spasm and pain, and examination under intravenous anaesthesia is essential. This should be combined with radiological examination with the suspected ligament under strain.

1 THE ANTERIOR CRUCIATE LIGAMENT. This runs from the medial surface of the outer condyle of the femur to the anterior tibial spine, and is tightened by extension. It can consequently be ruptured by hyperextension or any forward displacement of the tibial plateau. Rupture of the ligament allows excessive forward mobility of the knee joint. (See Fig 725.)




FIG 687 Testing the knee for rupture of the cruciate ligaments

2 THE POSTERIOR CRUCIATE LIGAMENT. This runs from the lateral side and interior aspect of the medial condyle backwards and outwards to the posterior tibial spine. It is tense in flexion and is injured by the same direct violence to the tibia with the knee flexed, which produces posterior dislocation of the knee. If it is ruptured excessive backward mobility of the tibia on the femur is permitted.

DIAGNOSIS. A hæmarthrosis always follows the injury, which may be accompanied by other minor fractures. The abnormal mobility of the upper end of the tibia is best tested for by grasping the upper end of the tibia with the knee flexed and attempting backward and forward movements.

TREATMENT. This consists of complete immobilisation of the knee after aspiration of the joint by a knee fixation plaster running from the groin to just above the ankle, with the knee slightly flexed. If the anterior ligament is torn some surgeons increase the flexion; but this produces no better result and is less comfortable for the patient. Throughout treatment walking and quadriceps drill and

exercises are encouraged. The plaster must be worn ten to twelve weeks, and after this a long Unna's paste stocking, extending to the knee, is worn for a further fortnight. The knee joint is stable after such treatment, even if there is some excessive laxity in the antero-posterior plane. The results of operative reconstruction of the ligaments are no better as the tissue used stretches.

3. THE MEDIAL COLLATERAL LIGAMENT. This occurs following abduction of the leg such as may occur in being struck on the



Fig. 688. Rupture of the medial collateral ligament of the knee. An X-ray must be taken with the knee in forced abduction to show the

leg by the bumpers of a car, or on the collapse of a narrow beam on a workman's legs. It is distinguished from a strain of the ligament by the size of the ecchymosis, the increased pain, the effusion into the knee joint, and characteristically by the ability to dislocate the tibia on the femur. If an X-ray is taken and there is no ligament traction fracture present, the film may appear normal. The X-ray with some attempt to abduct the leg at the knee will show an increased width of the joint space on the medial side of the knee, thus giving the correct diagnosis. After such an accident, and possibly after repeated minor trauma, ossification may

pound, the joints frequently being exposed. Treatment follows the lines for sub taloid dislocations, or those for compound fractures.

Dislocations at the tarso-metatarsal joints. The first and the fifth metatarsals are the most commonly involved, but the lesion is uncommon. The dislocation is usually dorsal and the prominence of the base of the metatarsal is easily recognised. Traction on the toe with pressure on the metatarsal base reduces the displacement, after which it is immobilised in plaster for two to four weeks.

Dislocation of a metatarsal. In compound injuries this may occur. It is of rare occurrence in the intact foot (fig. 692). Reduction by manipulation should be attempted, but the proximal end of the bone may be difficult to reduce and open reduction required. Immobilisation in plaster is necessary, but should not be persisted in longer than is necessary for the bone to form a stable bed for itself. After weight bearing exercises, massage and fardic foot baths should be given till a painless foot results and then weight bearing is resumed.

Dislocations of the metatarso-phalangeal and inter-phalangeal joints. These resemble the similar lesions of the hand. The dislocation is usually dorsal, and is easily reduced, showing little deformity. Stripping around the metatarsus with a pad secured by a wire phylax is usually sufficient fixation. In the case of those involving the big toe, especially if compound, a plaster cast with fixation of the great toe may be necessary.

- CONWELL and ALDREDGE "Complete Dislocation of the Knee Joint," *Surg Gynec and Obstets*, 1937, 64, 94 (With bibliography)
- KLEINBURG "Traumatic Lateral Dislocation of the Patella," *Ann Surg*, 1932, 95, 635
- HEY GROVES "The Cruciate Ligaments of the Knee Joint," *Brit J Surg*, 1919-20 7, 505
- JONES and SMITH "On Ruptures of the Cruciate Ligaments of the Knee, and on Fractures of the Spine of the Tibia," *Brit J Surg*, 1913, 1, 70
- GALLIE and LEMESURIER "The Repair of Injuries to the Posterior Cruciate Ligaments of the Knee," *Inn Surg*, 1927, 85, 592
- RITTER "Dislocation of the Knee Joint," *J Bone and Joint Surg*, 1932, 14, 391
- ROBBINS "Forward Dislocation of the Knee," *Inn Surg*, 1932, 95, 306 (One case)
- PATTERSON "Anterior Dislocation of the Knee" *Ann Surg*, 1934, 99, 521 (One case)

Fibula

- BUTLER, W J "Isolated Traumatic Dislocations of the Fibula Head" *Univ Hosp Bull (Ann Arbor)* 1946 12, 73-75

Foot

- BOYIN, J G "Dislocations and Fracturo Dislocations of the Talus" *Brit J Surg* 1940-41, 27, 88
- SHANDS, A R "The Incidence of Subastragaloid Dislocation of the Foot, with the Report of One Case of the Inward Type," *J Bone and Joint Surg*, 1928, 10, 306
- BOYIN, J G "The Hypermobility Ankle," *Proc Roy Soc Med* 1944, 37 282

pound, the joints frequently being exposed. Treatment follows the lines for sub-taloid dislocations, or those for compound fractures.

Dislocations at the tarso-metatarsal joints. The first and the fifth metatarsals are the most commonly involved, but the lesion is uncommon. The dislocation is usually dorsal and the prominence of the base of the metatarsal is easily recognised. Traction on the toe with pressure on the metatarsal base reduces the displacement, after which it is immobilised in plaster for two to four weeks.

Dislocation of a metatarsal. In compound injuries this may occur. It is of rare occurrence in the intact foot (Fig. 692). Reduction by manipulation should be attempted, but the proximal end of the bone may be difficult to reduce and open reduction required. Immobilisation in plaster is necessary, but should not be persisted in longer than is necessary for the bone to form a stable bed for itself. Active non-weight bearing exercises, massage and faradic foot baths should be given till a painless foot results and then weight bearing is commenced.

Dislocations of the metatarso-phalangeal and inter-phalangeal joints. These resemble the similar lesions of the hand. The dislocation is usually dorsal, and is easily reduced, showing little tendency to recur. Strapping around the metatarsus with a pad over the dislocated phalanx is usually sufficient fixation. In the more serious cases involving the big toe, especially if compound, a walking plaster with fixation of the great toe may be necessary.

REFERENCES

Sacro-iliac Joint

BROOMHEAD Dislocation of the Sacro-iliac Joint Reduced by Hooks
Traction *Proc Roy Soc Med*, 1933, 27 (1) 576

Hip

FUNSTEN, KNISER and FRANKEL "Dashboard Dislocations of the Hip"
J Bone and Joint 1928 20, 124

- 5 Retention Plaster
 Continuous traction
 Special splints
- 6 Re-education Massage
 Active and passive movements
 Electrical stimulation of muscles
 Exercises and weight bearing
- 7 Length of immobilisation, likely disability, and later sequelæ
- 8 Complications In outline only

2 Discuss the diagnosis of, e.g. fracture of the neck of the femur
This includes

- The general signs and symptoms of fractures
- The special signs and symptoms of this particular fracture
- A brief outline of the differential diagnosis

3 Discuss the complications of fracture of the shaft of the humerus
This includes

- The immediate complications
- The intermediate complications
- The late complications and sequelæ

And a brief outline of their treatment

APPENDIX I

FRACTURE QUESTIONS AND PAPERS

The art of answering an examination paper has been brought up to a high pitch, and to do justice to oneself and the paper one must adopt a settled approach to it. This approach is based on the facts that in the first few minutes after perusing the questions matter comes to mind which may be found difficult to remember later, that while answering one question, the "subconscious" is busy assembling facts for the next, and that equal answers to all questions obtain the highest marks, and so equal distribution of time over the answers is important. Most examinees adopt the following scheme, or some slight modification of it.

In a three hour exam the first fifteen minutes is devoted to the consideration of the paper, firstly, the questions selected for answering, secondly their relative difficulty to oneself, and thirdly, to scheme out an answer to the easiest and at the same time jot down any ideas occurring to the mind about the other questions. A further quarter hour is deducted from the time for use at the end of the exam to re-read questions correct if necessary, and add the finishing touches to a question which has taken longer than allowed. The remainder of the time (two and a half hours) is divided equally among the questions. The easiest question is answered first and this may result in saving some time for a difficult question at the end of the paper. The set out of the question is important, and it is a good plan to include the summary on which one has built up the answer at the head of the answer. Accurate division into paragraphs corresponding to the summary is then possible.

Fracture questions are limited in form if not in variety and they will be found to fall among the following types

1 Discuss a fracture, *e.g.*, fractures of both humeri of the forearm

This is a very long question, and a complete summary of an answer to such a question is given, as more frequently some component part such as the diagnosis or treatment, is asked for

It includes

- 1 Introduction Brief description of type and structure of the bone
Enumeration of the fractures affecting it and outline of the common mechanisms and occupational hazards if any responsible
- 2 Symptoms and signs (a) General (See Chapter III)
(b) Special for the particular fracture
- 3 Displacement (a) The exciting causes
(b) The influence of gravity
(c) Muscles
(d) First aid prevention of further displacement

- 4 Reduction { Immediate } Method { Manipulation
 { Delayed } { Continuous traction
 { Operation
 Suitable type of anaesthesia

APPENDIX II

FRACTURE INDEX AND DISABILITY TABLES

The endeavour to fix a definite disability period for each fracture is fruitless and quite impossible owing to individual variation in the lesions. It is, however, sometimes useful to have a rough guide against which one can compare one's own results, and which may draw attention to certain inequalities in healing time in apparently similar bones. More important than the disability period is the ordered terminology of the lesions which enables a fracture cross index to be kept, and which should be standardised to facilitate comparison of various clinics.

USE OF TABLES

In the first column are given the periods of usual recumbency, following this is the period of non weight bearing and weight bearing fixation. In the next column is the period of exercises in the "Massage" department necessary to restore function sufficiently for light work. In the fourth column the approximate period of light work necessary before the patient is fit for heavy work is given. In many cases the period of "exercises" can be included in this, thus shortening the total disability. In the last column is given the total period, including all the previous periods, before the patient is restored to full work. Taking an oblique fracture of the tibia treated by skeletal traction as an example we see that it requires two to four weeks in bed with skeletal traction, which is followed by a plaster for four to six weeks (extending to the ischium) in which the patient is encouraged to walk. On removal of this an Unna's boot or similar stocking is necessary for three weeks while it takes the patient eight to twelve weeks to get used to walking on his injured leg during which period he may be regarded as fit for light work. At the best he will be unable to work for sixteen weeks (a young patient) and at the worst his average disability period is thirty weeks. Compare this with a transverse fracture plaster and an oblique fracture treated with a single screw.

Fracture (Arranged in order suitable for indexing)	Recumbent Period	Non Weight bearing Plaster — 1	Ambulant Plaster (Weight bearing)	Re education		Total Dis- ability
				Period of Exercises	Light Work	
SKULL Fractures with complications without complications	All periods	expressed	d in weeks are 1 -	approximate and may 1 day		overlap
FACE AND JAW						
Orboma	Depends on asso- ciated injuries	—	—	—	—	1-5
Maxilla		—	—	—	—	1-12
Nasal bones		—	—	—	—	2/7-2
Mandible Simple		—	—	—	—	6-12
Compound		—	—	—	—	12-78

Trunk

- Lying Trunk rotation, with arm and shoulder movement, arm being swung over the side of the bed
- Trunk rotation with head and shoulder lifting, the arm being held to the side
- Shoulder lifting
- Back arching
- Sitting Reach long sitting, forward bending, touching alternate ankles
- Arm circle swinging with ankle grasp

Uninjured leg

- Straight leg raising
- Hip flexion
- Knee flexion
- Quadriceps drill
- Foot Dorsi and plantar flexion
- Inversion and eversion
- Circumduction
- Toe flexion and extension

Injured limb

As many of the above exercises are carried out as is possible without disturbing the retention. This is generally limited to ankle and toe exercises with the later addition of hip and knee movements.

Ambulant patients Similar exercise in the standing and sitting positions are given, with considerable enlargement, including the full range of movement of every unfixed joint.

ARM EXERCISES

Exercises are limited by the extent of the plaster. Shoulder movements are possible with the arm and forearm plaster, and in all cases the full range of finger movements outlined in Chapter XXII should be carried out. With the elbow immobilised the following exercises can be carried out.

- Abduction
- Forward swing (Flexion)
- Backward swing (Extension)
- Arm behind head (External rotation)
- Arm behind back (Internal rotation)

When the movements are only limited by a forearm plaster, class exercises can be carried out on the usual lines.

- Arms forward raise, hands on shoulders, hands out
- Arms lateral raise hands on shoulders, hands out
- Arms upward raise, hands on shoulder hands upward raise

And to these very many variations of free shoulder movements may be added, such as free arm swinging, alternate arm swinging and combinations with trunk exercises.

In special cases many special exercises may be devised, always remembering that encouraging the patient to use his muscles against the action of gravity, or the pull of adhesions, is as a rule better than pulley and rod exercises in which excessive movement may be forced, and so produce reactionary effusion.

APPENDIX III

EXERCISES IN RELATION TO FRACTURES

It must be constantly borne in mind that the active movement of the limb by the patient for a few minutes is worth hours of massage. The massage department, unless specially instructed, often lulls the patient into a false sense of security in which, feeling that something is being done for him, he will not do much for himself. The importance of this must be explained to the patient and the massage staff. It is far better where possible to have a few masseurs dealing solely with injuries than spreading their attention over other cases such as rheumatic cases which demand an entirely different approach. Massage is used as little as possible and class exercises where the stimulus of competition, the use of the team spirit, and the inspiration of the activities of other patients with similar lesions can be exploited to the full substituted where possible. Massage in my own clinic is limited to cases in which there is still effusion into the tissues, and movements are consequently inadvisable, and to the treatment of complications.

The exercises following are brief and incomplete and meant only as a general guide, to be modified according to the age of the patient, his physical condition and recovery rate, and to be added to and enlarged as the experience of the masseur suggests. In larger clinics general exercises must be designed for all types of recumbent patient and all types of ambulatory patient working together, and so the exercises given are limited in scope and may be enlarged where the masseur can give attention to the individual case. After the class exercises special exercises are given to the damaged limb of the individual case.

EXERCISES FOR RECUMBENT CASES

These exercises are gone through twice daily by all cases, and more often by patients on advanced exercises.

Breathing

- Half lying breathing Deep inspiration Deep expiration
- Half lying side bending, to L to R, with breathing
- Half lying, two arm side raising with inspiration
- Half lying hands on hips, inspiration and expiration

Neck

- Head raising
- Head rotation
- Neck rotation

Trunk

- Lying Trunk rotation, with arm and shoulder movement, arm being swung over the side of the bed
- Trunk rotation with head and shoulder lifting, the arm being held to the side
- Shoulder lifting
- Back arching
- Sitting Reach long sitting, forward bending, touching alternate ankles
- Arm circle swinging with ankle grasp

Uninjured leg

- Straight leg raising
- Hip flexion
- Knee flexion
- Quadriceps drill
- Foot Dorsi and plantar flexion
- Inversion and eversion
- Circumduction
- Toe flexion and extension

Injured limb

As many of the above exercises are carried out as is possible without disturbing the retention. This is generally limited to ankle and toe exercises with the later addition of hip and knee movements.

Ambulant patients Similar exercise in the standing and sitting positions are given, with considerable enlargement, including the full range of movement of every unfixed joint.

ARM EXERCISES

Exercises are limited by the extent of the plaster. Shoulder movements are possible with the arm and forearm plaster, and in all cases the full range of finger movements outlined in Chapter XXII should be carried out. With the elbow immobilised the following exercises can be carried out.

- Abduction
- Forward swing (Flexion)
- Backward swing (Extension)
- Arm behind head (External rotation)
- Arm behind back (Internal rotation)

When the movements are only limited by a forearm plaster, class exercises can be carried out on the usual lines.

- Arms forward raise, hands on shoulders, hands out
- Arms lateral raise hands on shoulders, hands out
- Arms upward raise, hands on shoulder, hands up and raise

And to these very many variations of free shoulder movements may be added, such as free arm swinging alternate arm swinging, and combinations with trunk exercises.

In special cases many special exercises may be devised, always remembering that encouraging the patient to use his muscles against the action of gravity, or the pull of adhesions is as a rule better than pulley and rod exercises in which excessive movement may be forced, and so produce reactionary effusion.

APPENDIX III

EXERCISES IN RELATION TO FRACTURES

It must be constantly borne in mind that the active movement of the limb by the patient for a few minutes is worth hours of massage. The massage department, unless specially instructed, often lulls the patient into a false sense of security, in which feeling that something is being done for him, he will not do much for himself. The importance of this must be explained to the patient and the massage staff. It is far better where possible to have a few masseurs dealing solely with injuries than spreading their attention over other cases such as rheumatic cases which demand an entirely different approach. Massage is used as little as possible, and class exercises, where the stimulus of competition, the use of the team spirit, and the inspiration of the activities of other patients with similar lesions can be exploited to the full substituted where possible. Massage in my own clinic is limited to cases in which there is still effusion into the tissues, and movements are consequently inadvisable, and to the treatment of complications.

The exercises following are brief and incomplete and meant only as a general guide to be modified according to the age of the patient his physical condition and recovery rate and to be added to and enlarged as the experience of the masseur suggests. In larger clinics general exercises must be designed for all types of recumbent patient, and all types of ambulatory patient working together, and so the exercises given are limited in scope and may be enlarged where the masseur can give attention to the individual case. After the class exercises special exercises are given to the damaged limb of the individual case.

EXERCISES FOR RECUMBENT CASES

These exercises are gone through twice daily by all cases, and more often by patients on advanced exercises.

Breathing

- Half lying breathing. Deep inspiration. Deep expiration.
- Half lying side bending, to L. to R., with breathing.
- Half lying two arm side raising, with inspiration.
- Half lying hands on hips, inspiration and expiration.

Neck

- Head raising.
- Head rotation.
- Lateral flexion of the neck.

Arms

- Lying. Straight arm raising (Abduction).
- Straight arm vertical raising.
- Elbow flexion. Abducted arm.
- Vertically held arm.

Trunk

- Lying Trunk rotation, with arm and shoulder movement, arm being swung over the side of the bed
- Trunk rotation with head and shoulder lifting, the arm being held to the side
- Shoulder lifting
- Back arching
- Sitting Reach long sitting, forward bending, touching alternate ankles
- Arm circle swinging with ankle grasp

Uninjured leg

- Straight leg raising
- Hip flexion
- Knee flexion
- Quadriceps drill
- Foot Dorsi and plantar flexion
- Inversion and eversion
- Circumduction
- Toe flexion and extension

Injured limb

As many of the above exercises are carried out as is possible without disturbing the retention. This is generally limited to ankle and toe exercises, with the later addition of hip and knee movements.

Ambulant patients Similar exercise in the standing and sitting positions are given, with considerable enlargement including the full range of movement of every unfixed joint.

ARM EXERCISES

Exercises are limited by the extent of the plaster. Shoulder movements are possible with the arm and forearm plaster, and in all cases the full range of finger movements outlined in Chapter XXII should be carried out. With the elbow immobilised the following exercises can be carried out.

- Abduction
- Forward swing (Flexion)
- Backward swing (Extension)
- Arm behind head (External rotation)
- Arm behind back (Internal rotation)

When the movements are only limited by a forearm plaster, class exercises can be carried out on the usual lines.

- Arms forward raise hands on shoulders, hands out
- Arms lateral raise hands on shoulders, hands out
- Arms upward raise, hands on shoulder, hands upward raise

And to these very many variations of free shoulder movements may be added, such as free arm swinging, alternate arm swinging, and combinations with trunk exercises.

In special cases many special exercises may be devised, always remembering that encouraging the patient to use his muscles against the action of gravity, or the pull of adhesions is as a rule better than pulley and rod exercises in which excessive movement may be forced, and so produce reactionary effusion.

APPENDIX III

EXERCISES IN RELATION TO FRACTURES

It must be constantly borne in mind that the active movement of the limb by the patient for a few minutes is worth hours of massage. The massage department, unless specially instructed, often lulls the patient into a false sense of security, in which, feeling that something is being done for him, he will not do much for himself. The importance of this must be explained to the patient and the massage staff. It is far better where possible to have a few masseurs dealing solely with injuries than spreading their attention over other cases such as rheumatic cases which demand an entirely different approach. Massage is used as little as possible and class exercises, where the stimulus of competition, the use of the team spirit, and the inspiration of the activities of other patients with similar lesions can be exploited to the full substituted where possible. Massage in my own clinic is limited to cases in which there is still effusion into the tissues, and movements are consequently inadvisable and to the treatment of complications.

The exercises following are brief and incomplete and meant only as a general guide, to be modified according to the age of the patient, his physical condition and recovery rate and to be added to and enlarged as the experience of the masseur suggests. In larger clinics general exercises must be designed for all types of recumbent patient and all types of ambulatory patient, working together, and so the exercises given are limited in scope and may be enlarged where the masseur can give attention to the individual case. After the class exercises special exercises are given to the damaged limb of the individual case.

EXERCISES FOR RECUMBENT CASES

These exercises are gone through twice daily by all cases, and more often by patients on advanced exercises.

Breathing

- Half lying breathing Deep inspiration Deep expiration
- Half lying side bending to L to R with breathing
- Half lying, two arm side raising with inspiration
- Half lying hands on hips inspiration and expiration

Neck

- Head raising
- Head rotation
- Lateral flexion of the neck

Arms

- Lying Straight arm raising (Abduction)
- Straight arm vertical raising
- Elbow flexion Abducted arm
- Vertically held arm

APPENDIX IV

SURGICAL EXPOSURE OF THE LONG BONES

1 HUMERUS AND SHOULDER JOINT The humerus is more difficult to approach than the femur, though not surrounded by such a depth of muscle. This is due to the double layers of muscle overlapping the upper and lower ends of the bone, and the close relationship of the neurovascular bundle medially, the radial nerve dorsally, and the musculocutaneous nerve anteriorly.

1 A Henry's Approach This may be used to approach the whole length of the bone. The incision (Fig. 693) follows the course of the cephalic vein



FIG. 693 Henry's incision for complete exposure of the humerus




FIG. 694 The line of incision through the brachialis. A = The radial nerve

between the contiguous borders of the deltoid and pectoralis major, and then passes down the lateral side of the biceps. The incision is deepened through the fascia, and the humerus exposed at the lower border of the deltoid. The brachialis anticus, running down from this, is then divided so that a quarter of the muscle is left to the outer side protecting the radial nerve. If further exposure is desired the radial nerve is identified at the upper posterior lateral angle of the brachialis and retracted while the humerus is cleared with a rugue. The bone can be exposed below to two fingers' breadth above the lateral epicondyle without entering the elbow joint but in order to allow satisfactory retraction of the muscles the elbow must be flexed. In the upper

SPECIMEN SCHEME FOR CASES IN PLASTER JACKETS

Head

Prone head raising (Extension)

Supine head raising (Flexion)

Rotation

Lateral flexion

Arm

Exercises above possible, worked in with a Colles's fracture class

Leg

Supine Straight leg raising

Alternate leg raising

Knee flexion

Shallow cycling

Standing Knee flexion

Leg forward raise

Knee forward raise Leg extend

Marching Goose step

Forward bending

Lateral bending

Spine

Lying supine on table Legs raise hands grasp table Body raise
Legs held with arms to sides with arms extendedLying supine Back over edge of the table Legs held Hyper
extension of the spine body raising

Marching with a book or weight on the head

Balance walking

REHABILITATION CENTRES

In dealing with many patients of the working class an awkward intermediary period is encountered in which the patient though fit for light work is not fit for his original employment and as the employer wants the patient back fully fit or not back at all it has been necessary to organise further assistance in the form of rehabilitation clinics. The only way a man can re-adapt himself to his old job is to try himself out at it and keep trying at it till he can carry it out as before. In such a centre apart from the ability to care for the patient's general fitness it is possible to let him carry loads of bricks or wheel loaded barrows, or climb ladders or dig or otherwise employ himself at the job he used to have. Under suitable leadership these centres are not only places where sound social work can be done but send many a man back to work in a far shorter time than would otherwise be the case, and save many another from being classed as 'unemployable'. For details see page 35, Chapter IV.




FIG 698 Exposure of the elbow joint (Author's method) Retraction of the triceps shows the olecranon fossa Upward retraction of the radial extensor group and division of the supinator exposes the head of the radius Further division of the flexor group (A) exposes more of the anterior compartment of the joint as desired

quarters of an inch below the head to avoid risk of damage to the deep branch of the radial nerve in the supinator muscle The lower half of this incision is that employed for exposure of the head of the radius By extending the elbow and separating the triceps from the back of the humerus retraction enables the olecranon fossa to be viewed obliquely Division of the common extensor origin to the epicondyle enables the anterior aspect of the joint to be approached If the head of the radius has to be removed its removal gives sufficient exposure without this procedure

Posterior Approach Langenbeck's Method A vertical incision is placed in the mid line over the posterior aspect of the joint centred on the olecranon tip The triceps is divided in the line of the incision above and the anconeus below The joint is exposed by separating the muscles from the bone

Radius Head (see above) The whole of the shaft may be exposed by an incision along the anterior border of the brachio radialis which marks the line of division of the nerve supply between the radial nerve to the outer side and the median nerve to the inner side The radial artery and the superficial division of the radial nerve lie in the line of the incision below The artery is retracted medially and the nerve laterally The supinator may be cleared from the bone above by finding the edge of its attachment This is best done by following down the insertion of the



FIG 699 Langenbeck's incision for exposure of the elbow centred posteriorly on the olecranon

third retraction of the deltoid is unsatisfactory, and if the shoulder has to be approached a slip of the attachment of the deltoid to the clavicle is divided




FIG. 695 Exposure of the superficial muscles by Henry's incision. A The cephalic vein and musculocutaneous nerve



FIG. 696 Complete exposure of the humerus by Henry's approach. It is necessary to flex the elbow to visualise the lower third. A Radial nerve. B Small flake of clavicle reflected with origin of the deltoid

with a chisel and the deltoid turned back. This of course needs an extension of the primary incision towards the acromion (Fig. 693 A-B). If a partial exposure of the bone is needed a long superficial incision is necessary to allow adequate retraction.



FIG. 697 Incision for exposure of the elbow joint (Author's method)

radialis longus and brevis. Behind these over the head of the radius are a few fibres of supinator and the orbicular ligament. A firm incision is made from the epicondyle down to the neck of the radius stopping three

2 THE ELBOW JOINT *Modified Lateral Approach* An incision commencing 2 inches above the lateral epicondyle is continued along the anterior border of the brachio radialis i.e. a curved incision centred on the epicondyle with the elbow flexed to a right angle. The lateral intermuscular septum is exposed above with the triceps behind it. Arising from its lateral edge and continuing down to the epicondyle are the brachio radialis, the extensor carpi




FIG 698 Exposure of the elbow joint (Author's method) Retraction of the triceps shows the olecranon fossa Upward retraction of the radial extensor group and division of the supinator exposes the head of the radius Further division of the flexor group (A) exposes more of the anterior compartment of the joint as desired

quarters of an inch below the head to avoid risk of damage to the deep branch of the radial nerve in the supinator muscle The lower half of this incision is that employed for exposure of the head of the radius By extending the elbow and separating the triceps from the back of the humerus retraction enables the olecranon fossa to be viewed obliquely Division of the common extensor origin to the epicondyle enables the anterior aspect of the joint to be approached If the head of the radius has to be removed its removal gives sufficient exposure without this procedure

Posterior Approach Langenbeck's Method A vertical incision is placed in the mid line over the posterior aspect of the joint centred on the olecranon tip The triceps is divided in the line of the incision above and the anconeus below The joint is exposed by separating the muscles from the bone

RADIUS Head (see above) The whole of the shaft may be exposed by an incision along the anterior border of the brachio radialis which marks the line of division of the nerve supply between the radial nerve to the outer side and the median nerve to the inner side The radial artery and the superficial division of the radial nerve lie in the line of the incision below The artery is retracted medially and the nerve laterally The supinator may be cleared from the bone above by finding the edge of its attachment This is best done by following down the insertion of the



FIG 699 Langenbeck's incision for exposure of the elbow centred posteriorly on the olecranon

third retraction of the deltoid is unsatisfactory, and if the shoulder has to be approached a slip of the attachment of the deltoid to the clavicle is divided



FIG 695 Exposure of the superficial muscles by Henry's incision. A The cephalic vein and musculocutaneous nerve




FIG 696 Complete exposure of the humerus by Henry's approach. It is necessary to flex the elbow to visualise the lower third. A Radial nerve. B Small flake of clavicle reflected with origin of the deltoid

with a clasp and the deltoid turned back. This of course needs an extension of the primary incision towards the acromion (Fig. 693, A-B). If a partial exposure of the bone is needed a long superficial incision is necessary to allow adequate retraction.

2 THE ELBOW JOINT *Modified Lateral Approach* An incision commencing 2 inches above the lateral epicondyle is continued along the anterior border of the brachio-radialis, i.e. a curved incision centred on the epicondyle with the elbow flexed to a right angle. The lateral intermuscular septum is exposed above with the triceps behind it. Arising from its lateral edge and continuing down to the epicondyle are the brachio-radialis the extensor carpi

FIG 697 Incision for exposure of the elbow joint (Author's method)

radialis longus and brevis. Behind these over the head of the radius are a few fibres of supinator and the orbicular ligament. A firm incision is made from the epicondyle down to the neck of the radius stopping three



FIG 702 The approach to the femur
A Henry approach
B Lateral approach



FIG 703 The muscles of the thigh showing relation to Henry's incision



FIG 704 The vastus intermedius exposed after dissection of the gap between the rectus femoris and the vastus lateralis—line of incision indicated. Note the crossing of the vastus intermedius by the lateral circumflex vessels and the nerve to the vastus lateralis



FIG 705 The shaft of the femur exposed with the lateral circumflex vessels and the nerve to the vastus lateralis retracted upwards

biceps, the supinator edge being just beside this. The pronator quadratus is detached below and retracted in.

ULNA. This is exposed along the dorsal subcutaneous border.

WRIST. Dorsal Approach. The incision runs along the dorsal axis of the limb just radial to the extensor indicis proprius. The dorsal carpal ligament is divided, and the extensor pollicis longus retracted laterally, and the radial extensors with it. The joint is then opened.

Interior Approach. This is undesirable owing to the risk of tendon damage and damage to nerves. The incision runs along the border of palmaris longus and is deepened, exposing the median nerve. Retraction of the tendons



FIG. 700. Posterior approach to the wrist joint.



FIG. 701. Lateral (ulna) approach to the wrist joint.

then allows inspection of the carpal tunnel and the removal of the volar dislocated lunate.

Medial Approach. A vertical incision is made on the ulnar border of the hand centred on the ulnar styloid process, and extending from the middle of the fifth metacarpal to 2 inches above the lower end of the ulna. The dorsal branch of the ulnar nerve is met with at the proximal end of the incision. Extensor carpi ulnaris is then divided at its insertion into the base of the fifth metacarpal and the dorsal aspect of the carpus cleared by raising the extensor tendons. If an anterior approach is desired the pisiform and the hook of the hamate must be divided from the carpal bones.

FEMUR. Henry Approach. The incision runs from the anterior superior iliac spine to the lateral side of the patella. The space between the rectus femoris and the vastus lateralis is defined and the two muscles separated. The conjoint tendon below is divided by the knife. The vastus intermedius is thus exposed being crossed above the neurovascular bundle to the vastus




FIG 702 The approach to the femur
A Henry approach
B Lateral approach



FIG 703 The muscles of the thigh showing relation to Henry's incision



FIG 704 The vastus intermedius exposed after dissection of the gap between the rectus femoris and the vastus lateralis—line of incision indicated. Note the crossing of the vastus intermedius by the lateral circumflex vessels and the nerve to the vastus lateralis



FIG 705 The shaft of the femur exposed with the lateral circumflex vessels and the nerve to the vastus lateralis retracted upwards

biceps, the supinator edge lying just beside this. The pronator quadratus is detached below and retracted in.

ULNA. This is exposed along the dorsal subcutaneous border.

WRIST. Dorsal Approach. The incision runs along the dorsal axis of the limb just radial to the extensor indicis proprius. The dorsal carpal ligament is divided, and the extensor pollicis longus retracted laterally, and the radial extensors with it. The joint is then opened.

Interior Approach. This is undesirable owing to the risk of tendon damage and damage to nerves. The incision runs along the border of palmaris longus and is deepened, exposing the median nerve. Retraction of the tendons



FIG. 700. Posterior approach to the wrist joint.



FIG. 701. Lateral (ulna) approach to the wrist joint.

then allows inspection of the carpal tunnel and the removal of the volar dislocated lunate.

Medial Approach. A vertical incision is made on the ulnar border of the hand centred on the ulna styloid process, and extending from the middle of the fifth metacarpal to 2 inches above the lower end of the ulna. The dorsal branch of the ulnar nerve is met with at the proximal end of the incision. Extensor carpi ulnaris is then divided at its insertion into the base of the fifth metacarpal, and the dorsal aspect of the carpus cleared by raising the extensor tendons. If an anterior approach is desired the pisiform and the hook of the hamate must be divided from the carpal bones.

FEMUR. Henry Approach. The incision runs from the anterior superior iliac spine to the lateral sulcus of the patella. The space between the rectus femoris and the vastus lateralis is defined and the two muscles separated. The conjoint tendon below is divided by the knife. The vastus intermedius is thus exposed, being crossed above the neurovascular bundle to the vastus

piece between the gluteus minimus and the piriformis below is sought. The latter are separated from the trochanter or the trochanter with their attachments is chiselled off. Retraction of the obturator and the piriformis exposes the posterior aspect of the joint.

KNEE. There are a variety of approaches dependent on the procedure to be carried out. These are too numerous to be detailed here. The oblique incision for the removal of a meniscus is recommended and this may be



FIG 708 Approach to the knee. The incision for medial meniscectomy is indicated by the black line. Dotted lines indicate suitable extensions for more elaborate procedures—the incision for lateral meniscectomy may be similarly treated.




FIG 709 The exposure of the upper third of the tibia, showing the peroneal nerve winding around the neck of the bone to disappear into peroneus longus.

extended into the quadriceps expansion for further exposure, producing in effect the patella displacing incision of Timbrell Fisher.

POPLITEAL SURFACE. This may be exposed from the medial side by an incision in line with the tendon of the adductor magnus and free dissection behind that muscle or on the outer side, by an incision along the posterior border of the tibial band. The lateral intermuscular septum runs in from here and dissection along its posterior face exposes the popliteal space.

TIBIA. This is subcutaneous and can be exposed throughout its whole length by an anterior or antero-medial incision.

FIBULA. Rarely exposed. It is only necessary to remember that the peroneal nerve winds around the neck of the bone. The bone is exposed by an incision along its whole length and separation of the soleus from the peroneus.

medialis. This bundle is readily mobilised and retracted proximally. The vastus intermedius is then divided down to the bone, in the line of its fibres, and the muscle stripped from the femur. In order not to expose the suprapatellar pouch, which extends 3 inches above the patella, the incision through the crureus must not go below this level. The pouch can be separated from the bone by a rugine if desired, and a wider exposure obtained.

Lateral Approach. The incision runs from the greater trochanter to the lateral condyle of the femur. The tibial band is split throughout its length and the vastus externus divided down to the bone. Numerous vessels are encountered in this step, the perforating branches and the lateral circumflex artery. Muscle damage and hemorrhage make it an unpleasant approach to employ, and vision is restricted unless the patient is lying on the opposite side.

III Smith Peterson or Lateral Approach. The incision runs down from



FIG. 706 Smith-Petersen approach to the hip
Skin incision



FIG. 707 The incision
for the posterior approach to the hip

the anterior superior iliac spine and backwards along the crest of the ilium for 3 inches. The sartorius and rectus femoris are separated together on the medial side, and the tensor fasciae latae and gluteus minimus on the outer side.

The tensor fasciae latae and anterior parts of the glutei are then stripped from the outer aspects of the ilium. The superior surface of the joint and the femoral neck are thus exposed.

Posterior Approach (Kocher). Incision angled posteriorly over the great trochanter. The upper limb extends in the line of the gluteal fibres towards the posterior superior iliac spine, while the lower runs down the axis of the limb for 4 inches. The tendinous insertion of the gluteus maximus is divided in this line. The gluteus medius is then divided in the line of the opposite limb, thus being a rather hemorrhagic procedure due to numerous blood vessels being divided. The fat below the gluteus medius is separated and the

APPENDIX V

THE ORGANISATION OF A FRACTURE CLINIC

THE development of fracture clinics in line with recent ideas in treatment has resulted in a uniform scheme being adopted which is in force with minor variations in the hospitals where specialised units have been established. This scheme is set out in the report of the B M A Committee on Fractures under the head "A Model Fracture Unit". The essentials of such a unit are set out under four heads:

1 Segregation. The handling of cases by one specialised department is the prime essential in getting uniform results, and making the full use of experience. One single unit is capable of dealing with all fracture cases in any hospital of present day dimensions and can handle 2,000-3,000 cases a year with ease. The improvement in teaching which results from segregation under an interested staff scarcely needs amplification.

2 Continuity of treatment. This essential important in every case, is doubly so in fractures and is set aside in the usual arrangement of out-patient and in-patient surgery. The fracture unit should have full charge of in-patient beds and transfer out-patients to its own clinic.

3 After care. This emphasises the points discussed in Appendix III. Emphasis must be laid on the keeping of records, which are of importance in keeping the unit up to standard, and for accurate follow up of the results achieved.

4 Unity of control. Segregation implies this to some extent, what is really meant is expert individual supervision of all cases. The concentration of experience in one surgeon is not a short-sighted policy. Apart from the improved results achieved he is able to impart his richer experience to a wider circle of men, illustrated with a variety of teaching material not otherwise at his disposal. The staff of a "Fracture Unit" is built up as outlined below, and follows closely that of "professorial units" on the Continent.

A chief surgeon, honorary, or professor. He pays a weekly visit to the O.P. clinic, and reviews all cases of the previous week, and does a complete round of the I.P. beds.

A Registrar or First Assistant who is readily available for all serious cases and carries on a daily fracture clinic, in which all the cases of the previous day, and all the cases attending on that day, are seen. He does a daily ward round with the junior staff, and is responsible for most of the teaching.

Residents. In a large clinic Senior and Junior, their appointments being so arranged that the junior takes over the senior position on his departure. Frequently the resident's rôle has to be played by the Casualty Officer who sees the case first. This is not desirable as the resident carrying out a casualty job cannot become sufficiently "specialised" to give the efficient preliminary treatment demanded. The immediate handing over of all fracture cases to the fracture clinic is the ideal.

ANKLE—A direct approach by a curved incision over either malleolus is employed in dealing with fractures of the malleoli. The incision is curved anteriorly or posteriorly. Approach to the posterior aspect of the joint may be made on the lateral or medial side. The lateral side is free of vessels and




FIG. 710. Curved incision to expose the medial or lateral malleolus.

nerves but owing to the relationship of the bi-malleolar axis to the antero-posterior axis of the ankle gives a more limited exposure than the medial approach. For fractures of the posterior tubercle the lateral approach is used. For posterior marginal fractures the medial or lateral approach. In the medial approach the posterior tibial nerve and artery and the tendon of flexor hallucis longus has to be avoided (Fig. 628), and the direct view is obscured by the tendo Achillis. Complete exposure of the posterior aspect of the joint can only be achieved by division of the tendon.

3 A plaster room, unsterile, for the removal of plasters, application of Unna's paste and the like

4 An operating theatre, which can be kept sterile and from which the patient can be readily wheeled into the X ray or plaster room or which can




FIG 711 Plan of a conveniently designed fracture clinic

be used in conjunction with the X ray room for operations under the screen. It should also be in communication with nearby fracture wards.

The ancillary units, Record Almoner, Stenographer's Office, Massage and Gymnasium, should be in as close association with the clinic as possible to facilitate direct supervision.

MANAGEMENT

Keeping the records and running such a clinic demands the following stationery

1 A casualty record *This need only be a slip containing the patient's name and address, and the diagnosis and treatment used in referring the case to the fracture unit. To avoid unnecessary writing it can be adapted to run on to the fracture record card*

2 A fracture record card *On this the full information about the case including in patient and out patient notes is kept. In addition to the usual information on such a card, spaces are left for the following information*

- (a) Type of accident *Industrial, domestic, road*
- (b) Time elapsing between the accident and first visit to the unit
- (c) Time as an in patient
- (d) Date of return to full work (or period of treatment till return, but note that a patient may still be attending the clinic while working, so this does not correspond to the total disability period)
- (e) Total time of attendance at the clinic *(Total disability period)*
- (f) State on discharge
 - 1 No disability
 - 2 Permanent partial disability
 - 3 Permanent total disability

3 Preliminary instruction card *This is given to all patients on first attendance, and contains details of the clinic, emphasises the need for the patient's co operation, especially with regard to the follow up clinics. Its principal use, however, is that it contains information of the signs and symptoms which demand immediate return to the clinic, and details of handling and care of plaster casts*

4 Identification card *This may be combined with the instruction card mentioned above, and is numbered in parallel with the fracture record card*

5 Follow up cards which are sent to the patient six months, twelve months, or as is necessary, after the accident. If the patient does not attend a questionnaire may be sent

Letters to doctors sending patients to the clinic are best typed out individually, and not sent on a stereotyped sheet. A name index and a fracture index, including complications, are essential

DESIGN OF THE UNIT

There are many variations possible to adapt it to the size of the hospital and the space available. Where possible it should be completely independent of the rest of the hospital, but this is frequently impossible on account of expense and the general X ray department has to be shared, or the out patient hall

The most important feature of its construction is the close arrangement and easy accessibility one to the other of

1 An examination room, containing cubicles for patients who must undress and a suitable small room for those who require interrogation and inspection without undressing

2 An X ray room, complete in itself with its own dark room and fitted for screening

- Aspiration of knee 49, 602, 629
- Astragalus. See Talus
- Atlas vertebra fracture of 249
 - dislocation 249
 - hyperemic dislocation 248
- Atrophy acute bony 31
- Avascular necrosis of bone, 17
 - arthritis after 18
 - common sites of 20
 - femoral head 465, 626
 - increased density in 18
 - navicular, 331, 400
 - non union after 107
 - sequelae after, 29
 - of talus 175
- Axillary artery injury 608
- nerve injury 303, 608
- Axis fracture of 249

- 'Back fire' injuries, wrist, 311 333
- Bacteriology, after puncture, 79
 - of gas gangrene 102
 - of wounds 93
- Bailey guide 461
- Balkan frame 149
- Bamboo fracture 7 372
- Bandages plaster marking 161
 - handling 168
- Beaded wires use of 121
- Beak fracture calcaneus 352
- Beck's bone drilling 111
- Bedsore in paraplegia 274
- Bed blocks 149
 - fracture 149
 - plaster 185
- Bell Charles 84
- Bennett's stove fracture, 414
- Bigelow's, method dislocated hip 625 628
- Bismuth iodide paste 68 87
- Bladder injury in fracture of pelvis 446
 - infection in paraplegia 274
- Blood concentration in shock 41
 - pressure in shock 42
 - in cerebral compression 219
 - supply to neck of femur 448
 - of navicular 17 395
- vessels injury to, 48
 - plaster pressure on 59 169
 - in Volkmann's contracture 58
- Bohler abduction splint 156 305
 - calcaneal clamp 161
 - clavicle splint 291
 - modification of Braun's splint 153
 - traction frame 49 152
- Bone atrophy (Sudeck's acute) 61
 - disease, 61
 - sequele 2
 - avascular absorption of 11
 - disease, a cause of fracture 2
 - drilling (Beck's) 111
 - factors in formation of 15
 - fatigue, 5 144, 514
 - tibia 514
 - grafting causes of failure 117
- Bone grafts action of, 20
 - in fracture of femoral neck 457 458
 - radiological changes in 20
 - varieties of 117
 - vascular changes in 20
 - of carpal navicular 400
 - moulding in repair 14
 - microvascular 17
 - organisation in repair 15
- Bone's necessary, of foot 369
- B.M.A. report on operative treatment of fractures 131
- Brachial artery contusion 311
 - physis and thrombosis 189
 - injury 46
- Brain injury modes of 196
 - causes of death in 221
 - clinical groupings, 220
 - localising features 220
 - mattress escape of 203
- Brachyphymion after fractures 45
- Brook's theory (myositis fibrosa) 58
- Bryant's method fracture femur 486
 - triangle 450
- Bullet wounds skull 196
- Bumper fracture 305
- Bunyan Stannard envelope 99
- Burns with fracture 144

- Calcaneal clamp, 161 556
 - epiphysis 569
- Calcaneus anaesthesia in fractures 381
 - fracture of 146 369
 - radiography 356
 - salient angle, 390
 - sub taloid arthritis after fracture 393
 - surgical anatomy 569
- Calcium in bone formation 15
- Callus excessive 140
 - formation 13
 - nerve pressure from 47 264
 - radiography 17
- Capitulum epiphyseal separation 331
 - fractures of 329
- Cardiac contusion 284
- Carpal bones. See Individual bones
- Carpo metacarpal dislocation, 618
- Carpus fractures 393
 - surgical anatomy, 393
- Carrel Dakin method 94
- Cartilage cells in callus, 15
- costal injury to 281
 - slipping 282
 - radiographic difficulties 331
 - semilunar injury with fractures 509
- Castex 399
- Catgut avoidance in recent wounds 72
- Catheterisation in bladder injuries 446
- Cauda equina injury to in spinal fractures 275
 - in sacral fractures 444
- Cellulitis in compound fracture 92
- Cephal hydrocele 231
- Cerebral compression 215
 - blood pressure in 216

INDEX

- Abdominal distension—after fracture of spine, 271
window in plaster jacket 185
- Abduction fracture of ankle 550
of humerus 301
of neck of femur, 453
frame for shoulder Author's 162
Bohler's, 166
in treatment of shoulder injuries 305
osteotomy of femur 467
- Abnormal mobility of fracture 27
- Abrasions treatment and varieties 54
- Acceleration causing brain injury 194
- Necessary bone of foot 169
navicular 570
radiography 27
- Accidents grouping of 1 429 438
- Acetabulum fracture of, 429 438 626
- Acromial end of clavicle fracture of 292
- Acromio clavicular joint anatomy 281
dislocation, 297 604
subluxation 296
- Acromion, fracture of 296
- Adduction fracture of ankle 548
fracture of neck of femur 453
- Adenitis after compound fracture 94
- Adhesions etiology 62
shoulder 62 313
- Adhesive plaster varieties 149
stripping for fractured ribs 280
- Adolescent coxa vara 469
- Age factor in Colles's fracture 2
factor in fracture of upper end of femur 449
in healing fractures 16
susceptibility to fracture 1
- Air in fracture of skull 20
in wounds 103
- Alveolar margin of jaw fracture 240 244
- Amputations 82 91 146
closure of 142
in gas gangrene 103
- Anaerobes in compound fractures 100
- Anesthesia local in ankle fractures 542
for fractures 187
in Colles's fracture 315
in fractures of calcaneus 581
of ribs 281
in sprains of ankle 567
in uses 187
in wounds 72
- brachial plexus 189
in fractures of cervical spine 254
in fractures of nose 236
general 191
regional, 189
sciatic, 190
spinal 191 581
- Anderson, Roger, well leg splint 468
- Angulation correction of 31
by wedging plaster, 521
- Ankle abduction fracture 550
adduction fracture 556
anatomy surgical 550
approach surgical 557
arthrodesis after fracture 565
tibio calcaneal 576 579
classification of injuries 539
compression injuries 565
diagnosis of injuries 575
distasis of 540
dislocation of 571 637
Dupuytren's fracture 538, 540 61
epiphyseal injuries 577
external rotation fractures 540
fractures of 532
local anæsthesia for 542
ligaments of 531
mal united fractures 567
marginal malleolus 546
medial malleolus 553
operative approach 654
operative treatment 549
Pott's fractures 538
radiography of 533 535
sprain fracture 559
sprains 533
supramalleolar fracture 536
Anterior fossa of skull fracture signs 204
trans position of ulnar nerve 339 340
- Anti gas gangrene serum 103
- Antiseptic treatment 65
- Anti tetanic serum, 100
- Antium fracture into 237
- Apparatus 148
- Arm plaster 172
splints Author's 162
Thomas 154
- Arteriography 48
- Artery avulsion injury 605
bruising of 48
obstruction of in myositis fibrosa 58
of in plaster 50
rupture of 50
types of injury 48
- Arthritis traumatic general 50 63
of elbow 340
of hip 467
of knee 511
of wrist 366
sub taloid 593
- Arthrodesis ankle 565
tibio calcaneal 576 579
wrist 400
- Arthrography 28
- Arthrotomy of ankle 654
of elbow 648
of hip 650
of knee 653
of shoulder 647
of wrist 650
- Aseptic treatment 67

Cribiform plate in fractures of base of skull 201
 Cruciate ligaments repair of 207 630
 Crush syndrome 184
 Cubitus valgus ulnar nerve paralysis 340
 Curare 3
 Cyanosis after flat emboli in 47
 traumatic 283

Deafness after fracture of skull, 271
 Death after fracture of skull causes 214
 Debridement in compound fractures 88
 Decalcification causing dislocation of atlas 248
 of bone graft 20
 in diaphysis 17
 inflammatory 16
 in skull 2 449
 in Sudeck's atrophy 61
 Deceleration injuries brain 198
 Decubitate rigidity 203 204
 Deformity correction of 27 11
 Denter's nucleus 203
 Delayed union causes 101
 treatment 109
 Delirium after trauma 208
 Deltoid ligament rupture 511
 paralysis 303 608
 Depressed fracture skull 222
 Dermatitis plaster 96
 Desault 86
 Diagnosis of fracture 22
 errors in 26 27
 of skull errors 232
 Diastasis 510 517
 complete 562
 operative treatment 564
 radiography 518
 Digits See Fingers 104
 Diplopia in fracture maxilla 238
 zygoma 237
 Direct compound fracture 8
 violence 3
 Dislocations acromio clavicular 604
 anatomy surgical 246
 ankle 571 631
 astragalus 573 637
 atlas 250
 carpo metacarpal 403 611
 carpal 409
 cervical spine 248
 clavicle 604
 coccyx 442 623
 definition 1 51
 elbow 612
 fibula lower end 510
 upper end 634
 fingers 618
 head of radius 345 382 615
 hip 623
 knee 629
 lumbar spine 263
 lunate 468
 mandible 603

Dislocations acromio carpo phalangeal 618
 metatarsal 635
 Monteggia 382
 patella 637
 phalangeal hand 618
 foot 636
 pubic symphysis 430 623
 radio carpal 604
 radio ulna upper 616
 lower 351 618
 sacro iliac 430 623
 scapular 603
 shoulder 601
 sterno clavicular 604
 subacromial 573
 talus 570
 tarsal navicular 334 635
 tarsometatarsal 635
 wrist 404
 Dorsal spine fracture 236
 sternal fracture with 282
 Drainage of wounds 73
 of compound fractures 92 94
 Drilling bone 151
 Duck's 111
 Drop finger See Mallet finger
 foot 170
 Dupuytren's fracture 538 540 561
 Dura mater rupture in nasal fracture 234
 in fractured skull 224

Edenulous jaw, in fractured mandible, 244
 Elbow arthritis 340 349
 arthrotomy 648
 dislocation, 337 339, 375 612
 divergent dislocation 615
 epiphyseal injuries 325 331 336
 fracture dislocations 337
 glenohumeral 160
 myositis ossificans 53 339
 nerve lesions around 339
 splint Robert Jones 307
 traumatic arthritis 340
 Embolism fat 45
 Emphysema surgical in fractured clavicle 292
 ribs 232
 in gas gangrene 102
 Engel May gun 462
 Envelope Bunyan Stannard 99
 Epicondyles humerus lateral 325 330
 medial 336
 Epiphyseal coxa vara 470
 Epilepsy traumatic 231
 Epithysis separation of definition, 1
 crepitus in 7
 compression with fractures 27
 disturbed growth 537
 elbow 325 331 336
 femur head 448 469
 lower end 489
 humerus head 304, 311

- Cerebral compression cerebro spinal fluid
 pressure in 217, 221
 decompression for 222
 localising signs 220
 meningismus in 217
 middle meningeal haemorrhage 217
 227
 uddema syndrome 230
 onset stages 217
 pathology, 217
 physiology 219
 signs in 215
 stages of 215
 haemorrhage, diffuse, 217
 late 218
 localised 217 230
 time relations 220
 types 217
 ventricular 217
 irritation 208
 cerebro spinal fluid pressure in 210
 lumbar puncture in 211
 pathology physiology 210
 recovery stage 214
 symptomatology 209
 treatment 212
 Cerebro-spinal fluid escape of in
 fractured skull 204
 pressure in fractured skull 217 221
 spine 375
 Quackenbush's test 275
 Cervical rib syndrome 294
 spine, anatomy surgical 240
 atlas and axis 241
 compression fractures 251
 dislocations 251
 fractures of 247
 shoveller's fracture 260
 skull fracture 170
 spinous process fracture of 257
 Champoumure 29
 Check bone See Zygoma
 Chemotherapy in compound fractures
 83 93
 penicillin, 80
 dosage 81
 in skull fractures 244
 sulphonamide 76
 dosage 78
 in wounds 83
 Children epiphyseal injury 7
 fracture of clavicle 287
 of femur 484
 greenstick fracture 6
 local anaesthesia disadvantages 185
 Circulation in shock 42
 obstruction under plaster 48 94
 Circumflex nerve paralysis of 303
 605
 Clavicle anatomy surgical 285
 bilateral fracture 286
 Bohler's splint 290
 dislocations 604
 greenstick 287
 Sayre's method 290
 sternal end 292
 Clay shoveller's fracture 260
 Closed plaster technique 91
 complications in treatment, 94
 organ in under 92
 Coccydynia 442 623
 Coccyx fracture 442
 dislocations 623
 Collar's line 332
 Collateral ligaments knee 607 631
 Colles's fracture 351
 anaesthesia 358
 associated injuries 357
 comminuted 366
 complications 368
 incidence in women -
 local anaesthesia in 360
 mechanism 354
 plaster 361
 difficulties 364
 prognosis 364
 reduction 369
 reduction 365
 reversed 361
 swelling of fingers after 364
 Collesion splint 426
 Coma in fractures of skull 203 211
 Comminuted fractures etiology 7
 Colles's fracture 357
 retention of 32
 Compound fractures 8 87 See
 Individual bones
 chemotherapy 83
 closed plasters 91
 complications of 94
 from missiles 142
 persistence of infection 95
 skin loss in 89 94
 of skull base 204
 missiles 146
 vault 222 226 228
 Compression cerebral 21
 clamp for calcaneus 161 786
 fractures of ankle 361
 spine 260 268 261
 strain affecting union 6 14
 Concussion 206
 Condyles femoral 490
 humeral 329 336
 jaw 241
 Conoid ligament anatomy 284
 rupture 605
 Contra coup violence 196
 Contracture of fingers in acute bony
 atrophy 61
 in myositis fibrosa 56
 Coracoid process fracture 297
 Coronoid of ulna 374
 Costal cartilages injury 204
 Counter traction principles 31 150
 Coxa vara epiphyseal 470
 in pertrochanteric fracture 467
 Cramer wire 157
 Cranial nerves examination of 200
 injury in fractured skull 204
 Crepitus in fractures 24

Cribiform plate in fractures of nose, 244
of skull, 204
cruciate ligaments, repair of, 207 630
crush syndrome 144
Cubitus valgus ulnar nerve palsy is,
340
Curets 7
Cyanosis after fat embolism 45
traumatic 283

Deafness after fracture of skull, 211
Death after fracture of skull causes, 211
Displacement in compound fractures 88
Decalcification causing dislocation of
atlas 248
of bone graft 20
in diaph 17
inflammatory, 16
scule 2 449
in Sudeck's atrophy 61

Deceleration injuring brain 198
Decerebrate rigidity 203 201
Deformity, correction of 23 11
Dent's nucleus 203
Delayed union causes 108
treatment, 109

Delirium after trauma 208
Deltoid ligament rupture 144
paralysis 303 608

Depressed fracture skull 222

Dermatitis plaster 90

Desault 80

Diaagnosis of fracture 22
errors in 20 27
of skull errors 212

Diastasis 540 557
complete 562
operative treatment 564
radiography 558

Digits See Fingers toes

Diplopia in fracture maxilla 238
zygoma 237

Direct compound fracture 8
violence 3

Dislocations acromio clavicular 604
anatomy surgical 240

ankle 571, 615
astragalus 573 633
atlas, 270
carpo metacarpal 401 615

carpal, 403
cervical spine 248
clavicle 604

coccyx 442 623
definition 1 51

elbow 612
fibula, lower end 540
upper end 634

fingers 618
head of radius 345 382 615
hip 623
knee 629
lumbar spine 263

in locations metacarpal phalange of 618
mid tarsal 631

Monteggia 382

patella, 633

phalanges hand 618

foot, 636

pubic symphysis 430 623

radio carpal, 404

radio ulna upper 616

lower 371 618

sacro iliac 430 623

scapular 403

shoulder, 605

sternoclavicular 604

subtrochanteric, 573

talus 570

tarsal navicular 514 635

tarsometatarsal 635

wrist 404

Dorsal spine fracture, 206

sternal fracture with 282

Drainage of wounds 73

of compound fractures, 92 94

Drilling hole 151

Beck's 111

Drop finger See Mallet finger

foot, 170

Dupuytren's fracture 538 540, 561

Dura mater rupture in nasal fracture,
234

in fractured skull, 224

Edentulous jaw, in fractured mandible,
244

Elbow arthritis 340 349

arthrotomy 648

dislocation 337 339, 375 612

divergent dislocation 615

epiphyseal injuries 325 331 336

fracture dislocations 337

goniometer 160

myositis ossificans 53 339

nerve lesions around 339

splint Robert Jones' 307

traumatic arthritis, 340

Embolism fat 45

Empyema surgical in fractured
clavicle 202

ribs 242

in gas gangrene 102

Engel May guards 462

Envelope Bunyan Stannard 99

Epicondyles humerus, lateral 328 330
medial, 336

Epiphyseal coxa vara 470

Epilepsy traumatic 231

Epiphysis separation of, definition 1
crepitus in, 7

compression with fractures, 27

disturbed growth 537

elbow 325 331, 336

femur head 448, 469

lower end 489

humerus head 301, 311

- Epiphysis separation of, mechanism 7
 radius head 347
 lower end, 372
 tibia lower end 37
 upper end, 501
 ulna lower end 372
 Errors in diagnosis of fractures 26
 in radiography 26
 in diagnosis of fractured skull 232
 Ethmoidal bone fractures 215
 Ether use 191
 Ethyl chloride use 191
 Examination of fractures 22
 radiographic 24
 Excision carpal scaphoid 469
 head of radius 347 649
 ulcranon 380
 patella, 497
 talus 379
 subtalar joint 593
 ulnar styloid process 366
 wounds 73
 Excitement influence on shock 41
 Exercises arm, 645
 ankle 342
 for Colles's fracture 363
 after operative fixation 128
 metacarpal fractures 411 419
 March fracture 396
 importance of in fractured femur 479
 patella 497
 tibia 523
 re education, 34
 recumbent patients 644
 rehabilitation 36 38
 spinal 645
 Extensor pollicis longus rupture 366
 External popliteal nerve 47 529 653
 Extracapsular fracture neck of femur 450
 Extradural hemorrhage 217 227
 Extra peritoneal rupture of bladder 443

 Facial bones fractures, 233
 wounds 240
 False joint formation 108
 Fat embolism 45
 Fatigue of bone 5 144 514
 Felt varieties 158
 Femoral epiphysis upper 448 470
 lower 489
 Femur abduction fractures 411
 adduction fractures 411
 anatomy surgical 448 650
 avascular necrosis of head 625
 Bailey guide 462
 classification of fractures 448
 complications of nailing 465
 of fracture 465
 condyles fracture 490
 continuous traction 455
 corrosion of nail 465
 deformities after fracture 480
 Engel May guide 462
 Femur epiphysis of lower end, 489
 extra articular nailing 457
 fracture dislocation 626
 great trochanter 469
 head fracture 449
 inter trochanteric fracture 449
 lesser trochanter 469
 nailing 458
 neck fractures 449
 causes of death 451
 causes of non union 466
 physical signs 450
 sites of fracture 448
 treatment operative 457
 Whitman's plaster 456
 necrosis avascular of head 465 62
 peritrochanteric fracture 467
 radiography of neck 452
 shaft fractures 470
 Braun's splint 479
 Bryant's method 484
 children 483
 compound fracture 480
 don'ts in treatment 480
 Hamilton Russell method 483
 Smith Petersen nail 485 468
 supracondylar fracture 489
 surgical approach 650
 un united fracture of neck 466
 Fever traumatic 44
 Fibula anatomy surgical 602 653
 dislocation lower end 540
 upper end 634
 fractures 613
 and tibia fractures, 518
 Fibroblasts in repair, 11
 Cartilaginous changes in 13
 Fibrous union 108
 in fracture of clavicle 288
 of ankle (q t) 530
 of navicular 399
 Fingers claw Volkmann's 56
 collodion gauze splint 426
 dislocation 617
 exercises 365
 nail removal of 426
 operative treatment 412
 Sudeck's atrophy of 61
 wire splint 157
 Bennett's fracture 417
 fifth metacarpal 422
 metacarpals 420
 First aid in fractures 29
 femur 87
 spine 248
 Fissure fractures skull 226
 radius lower end 370
 upper end 348
 Floating maxilla 237
 Foot fractures 569 *See Individual bones*
 dislocations 630
 drop 170 529
 March fracture 596
 Forearm cross union in 391

- Forearm fracture of** 382
 plaster, 172
 Volkmann's contracture, 53
Foreign bodies avoidance in wound 73
 effects on union 107 142
 producing ulcers, 62
 removal of 143
Fracture dislocations ankle 38
 Bennett's 414
 carpus, 404
 elbow, 377 379, 373 612
 forearm 384
 hip 623
 pelvis 431
 radius lower end 351
 upper end 382
 scaphoid 406
 scapular 406
 shoulder 310 603
 spine cervical 233
 lumbar 263
 ulna lower end 381
 upper end 173
Fractures See Individual bones
 alcohol in 22
 anesthesia for 187
 Bamboo 7
 bending 6
 blisters 23
 classification 5
 comminuted 7 32
 complications 41 53
 compound 8
 crepitus in 24
 definition 1
 delayed union 106 103
 diagnosis 22
 errors in 27
 exciting causes 2
 exercises for 34 36
 greenstick, 6
 hematoma 10 11
 helical 4 32
 impacted 7
 incomplete, 6
 infraction 7
 ligament traction (sprain) 8
 line persistence of 27
 missed 27
 nerve injuries with 46
 open See Compound fractures
 operative treatment 121
 radiography 24
 reduction retention re-education 29
 repair 10
 signs symptoms 22
 simple 5
 spiral 440
 spontaneous, 2
 sprain 7
 transverse mechanism 4 32
 treatment general principles 29
Forearm abduction for arm 162
Froms syndrome 275
Frontal bone fracture 197
Galen, vein of 196
Gangrene gas 99 101
 from arterial obstruction 48
 types of 102
Gas and oxygen anæsthesia 191
General anesthesia in fracture 191
Glenoid scapula fracture of 298 603
Compound 160
Grafts bone, 113 See Bone grafts
Granulation tissue appearance of 92
 in compound fracture 93
 in fracture repair 12
 treatment of 84
Gravity effects of 30
Great trochanter fracture of 469
Greater tuberosity of humerus 312
 with dislocation, 310
Greenstick fracture, 6
 mechanism 6
 fractures of tibia 513
Groves Hey director 402
Gunn's fracture 217
Gundes Binky 462
 Engel May 402
 Hey Groves 462
 Watson Jones 459
Haemarthrosis, joints, 50
 knee 494 503
Hemastasis in fractures 73
 after operative fixation 129
Hematoma avoidance of 73
 in fracture of femur 472
 organisation 11
 ossifying 53
 pulsating 48
 subperiosteal 22
 in wound, 73
Hematomyelia 272
Hemoconcentration in shock 43
Hemoptysis in fracture of ribs 282
Hemorrhage anterior fossa of skull, 204
 influence on shock 43, 44
 intracranial varieties 217 227 229
 middle fossa of skull 204
 nasal 204
 orbital 204
 posterior fossa of skull 205
Hemothorax after fracture of ribs 283
Hamilton's ruler test 607
Hamilton Russell method 478 487
Hand See Wrist and individual bones
 dislocations in 612
Hanging plaster 316
Hawley table 150
Hey Groves guide 462
Headaches after fracture of skull 231
Head of radius 344
 dislocation 329
 excision 347
 of femur 449
 of humerus 300
Heart contusion 251
Helical fracture 4 32
Hemiplegia after fracture of skull, 203

- Hernia cerebri 230
 Henry's approach arm 617
 femur 650
 Hip anatomy surgical 448
 arthritis 467
 vascular necrosis affecting 465 626
 dislocation anterior, 627
 central 437
 complications 620
 posterior 623
 examination 450
 immobilisation of 142
 Kocher's approach 650
 Smith-Petersen's approach 652
 spica long 175
 short 177
 Hippocratic method in dislocation
 shoulder 611
 Hirschmann 540
 Humerus anatomy surgical 100
 capitulum fracture 330
 epiphyseal injury 332
 compound fracture 318
 condylar fracture 330
 epicondyle lateral 328
 medial 377
 epiphyseal injury 311 32, 331 336
 extension fracture 308
 flexion fractures 320
 fracture dislocations 310
 greater tuberosity 312
 impacted fractures 305
 lateral condyle 329
 ligament fracture fractures 312
 lower end fractures of 118
 mal union 340
 medial condyle 336
 epicondyle 231
 neck fractures See Upper end
 shaft fracture 314
 complications 317 339
 supracondylar fracture 320 324
 1 shaped fracture 324
 upper end fracture sites 301
 abduction 301 305
 adduction 301 307
 complete 302
 fracture dislocation 310
 impacted 308
 incomplete 304
 surgical exposure 647
 tuberosities 310
 Hunger influence on shock 41
 Hyperextension fractures of Atlas 249
 of spine 248
 dangers in fracture of spine 270
 Hyperpyrexia in fracture of skull 212
 Hypertonic saline in cerebral irritation
 211
 Ileus, paralytic, in plaster jacket, 270
 Iliac spine avulsion 451
 Ilium fractures of 440
 Immobilisation of fractures 32 75
 and bronchopneumonia 45
 and nephrolithiasis 66
 Impacted fractures general 7
 of femoral neck 453
 of humerus 308
 of radius 357
 Incontinence in fracture of skull 212
 Indirect compound fractures, 8
 violence 3
 Infected fractures complications 95
 delaying union 107
 gas gangrene in 99
 irrigation in 97
 organisms in 93
 Infraction fractures, 371
 Instruments for operative reduction of
 fractures, 132
 Intelligence alterations after fracture of
 skull 231
 Intercranial hemorrhage type 217,
 229
 pressure increased 213
 Internal fixation of fractures 127
 Interphalangeal joints ligaments 419 42,
 425
 fracture 425
 Intervertebral disc anatomy, surgical,
 247
 in fractured cervical spine 251
 lumbar spine 263
 injury to 271
 prolapse 271 273
 Intraepiphyseal fracture of neck of femur
 400
 Intramedullary Kirschner wires 131
 in ulnar 391
 Intra peritoneal ruptures of bladder 441
 Intravenous blood in shock 43
 anesthesia 191
 plasma in shock 43
 saline 43
 Iodine as skin antiseptic 70
 Ischemic contracture (Volkmann's) 53
 Ischium fracture of 442
 Jackel plaster 183
 Jacksonian fits 216 231
 Joint adhesions 62
 dislocations See Dislocations
 injury with fracture 50
 manipulation 50
 penetration diagnosis 51
 stiff causes 62
 stiffness after skeletal traction 121
 traumatic arthritis of 64
 Jones Roberts strapping 293 298
 for shoulder 293
 method reduction of ankle 638
 Kidney injury to, 261
 nephrolithiasis 66
 Kienbock's disease 403 406
 Kirschner wire drill 150
 in femoral neck 459
 in lower end of femur 437
 intra medullary 191
 strainer 151
 in ulna 339 391

- Knee aputation of 495 607 621
 anatomy of femur 602
 arthritis of 511
 cartilage injury in 608
 collateral ligaments repair 633
 rupture of 607, 631
 dislocation 629
 exercise bar 162
 fixation plaster 178
 fracture into 604
 of patella 494
 hemorrhage into 494 607 631 632
 rupture of cruciates 492
 sprains of 631
 stiffness after operative fixation
 fracture of shaft 481
 surgical approach, 607
 Koch 87
 Kocher's reduction of dislocated shoulder
 610
 Kummel's disease 266
 Kuntscher nail 127
 in fracture of the femur 483
 Kyphosis in fracture of lumbar spine
 266 262
- Laminæ, fracture of, 257
 Laminectomy indications 275
 Lane Arbuthnot 65 121
 Lane's plates 121
 Langenbeck elbow exposure 649
 Larynx 86
 Lateral displacement correction of 11
 Leachetter mandible 496
 Ligament traction fracture (sprain
 fracture) 8
 Ligaments ankle 531
 hip X shaped 624 627
 interphalangeal 420
 knee cruciates 630
 collateral, 631
 shoulder corioid trapezoid 604
 Lister 68 87, 121
 Liver rupture of 284
 Local anesthesia advantages 187
 technique 188
 Lower jaw fracture of 240
 dislocation of 693
 Lumbar puncture in cerebral irritation
 213
 after spinal injury 275
 Lumbar spine, surgical anatomy 246
 compression fracture 261
 treatment of 265
 fracture dislocations 261
 injury to nucleus pulposus 271
 Kummel's disease 257
 kyphosis after fracture 257 263
 plaster jacket 267
 scoliosis after fracture 264
 sites of fracture 258
 of lamina 258
 of spinous processes 258
 of transverse processes 261
 Lunate dislocations 406
 fracture of 403
- Lung massive collapse 284
 Lymphadenitis in compound fracture 94
 Lymphangitis in compound fracture 66
 94
- Madelung's deformity, 371
 Maisonneuve's fracture 339 340 349
 Malar bone fracture 276
 Malunions fracture of pelvis 429 431
 Mallesolar fracture medial 553
 lateral 516 510 553
 Mallet finger 426
 Malunion 117
 operative correction 118
 varieties 117
 Mandible dislocation 603
 ectodermis 244
 fractures 240
 fracture dislocation 603
 Manipulation in mal union 118
 of injured joints 62
 Mammillary sterni fracture of 27
 March fracture 146 596
 Massage in treatment 644
 Massive brain injury 221
 collapse of lung 286
 Mastoid 53
 Maxilla fracture malar 217
 floating 237
 Median nerve paralysis 339
 Meningismus in cerebral injury 217
 Meniscus of knee injury with fracture,
 508
 Metacarpals anatomy surgical 411
 Bennett's starve fracture 412
 Metacarpo phalangeal dislocations 618
 carpal dislocation 620
 Metatarsals fracture of 146 595
 dislocations 636
 Middle cranial fossa fracture 206
 meningeal hemorrhage 206 227
 Midtarsal joint 635
 Monoplegia 203
 Monteggia fracture 382
 Musculo spasm reduction of 30
 Muscular violence 5
 Musculo spiral nerve See Radial nerve
 Myositis fibrosa 56
 ossificans 53
- Nail Smith-Petersen, 456
 Nails finger 426
 toe 599
 Nasal bones fractured 231
 hemorrhage in fractured skull 204
 Navicular, carpal blood supply 17
 avascular necrosis 17 395
 with Colles's fracture 357
 fracture of sites 394
 non union, 399
 radiology, 401
 tuberosity 401
 grafting of 81
 Navicular tarsal 993

- Hernia cerebri 230
 Henry's approach arm 647
 femur 650
 Hip anatomy surgical 448
 arthritis 467
 avascular necrosis affecting 461 626
 dislocation anterior 627
 central 447
 complications 626
 posterior 627
 examination 446
 immobilisation of 142
 Kocher's approach 650
 Smith-Petersen's approach 652
 spica long 177
 short, 177
 Hippocratic method in dislocation
 shoulder 611
 Hombach's method 540
 Humerus anatomy surgical 300
 capitulum fracture 330
 epiphyseal injury 332
 compound fracture 318
 condylar fracture 330
 epicondyle lateral 328
 medial 337
 epiphyseal injury 311 321 331 336
 extension fracture 308
 flexion fractures 320
 fracture dislocations 310
 greater tuberosity 312
 impacted fracture 307
 lateral condyle 324
 ligament traction fractures 312
 lower end fractures of 318
 mal union 340
 medial condyle 338
 epicondyle 331
 neck fractures See Upper end
 shaft fracture 314
 complications 317 339
 supracondylar fracture 320 324
 1 shaped fracture 324
 upper end fracture sites 301
 abduction 301 305
 adduction 301 307
 complete 302
 fracture dislocation 310
 impacted 308
 incomplete 308
 surgical exposure 647
 tuberosities 310
 Hunger influence on shock 41
 Hyperextension fractures of Atlas 241
 of spine 248
 dangers in fracture of spine 270
 Hyperpyrexia in fracture of skull 212
 Hypertonic saline in cerebral irritation
 211
 Heus, paralytic in plaster jacket 270
 Iliac spine avulsion 451
 Ilium fractures of 440
 Immobilisation of fractures 32 75
 and bronchopneumonia 45
 and nephrolithiasis 66
 Impacted fracture general 7
 of femoral neck 453
 of humerus 308
 of radius 357
 Incontinence in fracture of skull 212
 Indirect compound fractures 8
 violence 7
 Infected fractures complications 95
 delaying union 107
 gas gangrene in 99
 irrigation in 97
 organisms in 93
 Infraction fracture 371
 Instruments for operative reduction of
 fractures 132
 Intelligence alterations after fracture of
 skull 271
 Intracranial hemorrhage, type 217
 229
 pressure increased 213
 Internal fixation of fractures 127
 Interphalangeal joints ligaments 419
 425
 fracture 421
 Intervertebral disc anatomy surgical
 247
 in fractured cervical spine, 241
 lumbar spine 263
 injury to 271
 prolapse 271 273
 Intracapsular fracture of neck of femur
 470
 Intra medullary Kirschner wires 131
 in ulnar 391
 Intra peritoneal ruptures of bladder 445
 Intravenous blood in shock 43
 anæsthesia 101
 plasma in shock 43
 saline 43
 Iodine as skin antiseptic 70
 Ischiatic contracture (Volkmann's) 53
 Ischium fracture of 442
 Jacket plaster 183
 Jacksonian fits 216 231
 Joint adhesions 62
 dislocations See Dislocations
 injury with fracture 50
 manipulation 50
 penetration diagnosis 51
 stiff causes 62
 stiffness after skeletal traction 121
 traumatic arthritis of 64
 Jones, Roberts strapping 293 298
 for shoulder 293
 method reduction of ankle 638
 Kidney injury to 261
 nephrolithiasis 66
 Kienbock's disease 403 406
 Kirschner wire drill 150
 in femoral neck 459
 in lower end of femur 437
 intra medullary 131
 strainer 151
 in ulna 339 391

- Phalanges hand dislocations 419
 operative fixation 412 426, 427
 toes 490
- Phelps (Cochit osteosynct 161, 187
- Phosphorus in formation of bone 15
- Physical training 38
- Physiotherapy 37
- Pin Smith Petersen, 457
 sites for insertion, calcaneum 187
 femur 437
 ilium 334
- Stemum ribs 144
- Plaster of Paris 166
 bandages 167
 beds 186
 casts construction 168
 padded and unpadded 168
 closed technique, 91
 difficulties 169
 discharge marker, 170
 drying 168
 instruments 162
 jacket 183
 looseness 170
 obstructing circulation 48
 organisms under 93
 pain under, 169 361
 parts from 170
 pattern method of construction 171
 removal of 183
 setting 168
 spicas 177
 thoraco brachial 138 174
 "Tobruk" 139
 transport 138
 varieties 170
 walking 179 182
 wedging 32 521
 Whitman's 174 416
 windows in 90 94
- Plates Lane's 125
 removal of 129
 Stamm's 125
- Pneumothorax in fracture ribs 281
- Polar contusion brain 210
- Posterior cranial fossa 205
- Pott's fracture 538
- Pressure sores, under plaster 169 529
 in paraplegia 272
- Provocational therapy, 39
- Primary closure of wounds 89
- Proflavine 82
- Propamidine 82
- Pubic symphysis dislocation 431, 438
- Pulled elbow 616
- Punch fractures 414 418
- Pupillary changes in concussion 204 215
- Quadriceps, adhesions after fracture, 481
 exercises 37
- Queckenstedt's test, 275
- Radial epiphysis head, 349
 injury in fractured humerus 303,
 315
- Radial epiphysis lower end, 170
 nerve plexus involvement, 318
 sensory branch 366
 styloid 367
 excision 401
- Rachocarpal joint dislocations 404
- Radiographic errors in interpretation, 26
 necessary qualities 25
 supplementary views 28
- Radiography indications for 24
 of column 381
 in diastasis 518
 films necessary 25
 in fracture of femoral neck 452 458
 ankle and after spasm 513, 515
 sacrum 443
 in maxillary fractures 397
 of tibia fibula syndesmosis 558
 ankle strain 24 28 213
- Radiological union 17
- Rachio ulnar joint dislocation lower
 351, 356, 617
 upper 346 352 615
- Rhinus, amotomy, surgical, 342
 anterior marginal fracture 367 404
 Colles's fracture 314 See Colles's
 fracture
 epiphyseal separation head 347
 lower end, 370
 fissure fracture 370
 fractures 342
 head fracture of 344
 complications of 349
 dislocation of 615
 excision of 347 649
 surgical approach, 649
 lower end fractures 354
 epiphyseal separation 370
 posterior marginal fracture, 367, 404
 shaft fractures, 350
 displacement by muscles 343
 with fracture of ulna 384
 with greenstick fracture 350
 styloid process fracture 367
- Recreational therapy 37
- Reduction deformities to be corrected, 31
 forces opposing 30
 methods in general 30
- Re education in fractures 34
 after Colles's fracture 364
- Regional anesthesia 189
- Rehabilitation 35
 centre 37
 timetable 39
- Renal stone after fracture 68
- Rest after injury 70
 after exercises 38
- Retention method in fractures, 32
 of urine in spinal cord injury 269
 in cerebral irritation 212
- Retinal lacerations in cerebral compression
 216
- Rhinorrhoea, 206 231 235
- Ribs fractures of 278
 complications 282
 stove in " 281

- Nelson's line 430
 Nephrolithiasis 67
 Nerves injuries to 46
 during treatment 47
 involvement in callus 418
 paresis from stretching 47
 from pressure 47 418
 surgical exploration 418
 suture in compound fracture 83
 Neuritis traumatic 47
 Neural arch fracture 230
 Non union 106
 absolute 108 109
 after metallic fixation 123
 atrophic 109
 false joint 108 109
 fibrous 10
 hypertrophic 105
 treatment 110
 varieties 105
 Nucleus pulposus acute injury 271
 Nutrient foramina simulating fracture 27

Oblique fracture, 1 71
 Occupational therapy 17 34
 Odontoid process fracture 249
 Oedema after fracture 63
 Olecranon fracture of 375
 excision 378
 Open fracture & definition 4
 Operative correction of mal union 118
 excision of patella 497
 of olecranon 378
 reduction advantages 122
 disadvantages 123
 femoral condyle 491
 general technique 124
 selection of cases 127
 repair of patella 493
 treatment 121
 ankle injuries 549
 dislocation lumbar spine 264
 fracture of femur 467 469 481
 of fingers 412
 of head of radius 347
 of humeral condyle 330
 of humerus 316
 of olecranon 378
 of radius and ulna 383 388
 of skull 222 223 226 228
 of tibia 522
 of zygoma 237
 instruments for 132
 non union 109
 oblique and spiral fractures 522
 Orbicular ligament in fracture head of
 radius 614 615
 in pulled elbow 615
 Orbital hæmorrhage in fracture of skull
 204
 Organisation of fracture service 655
 Orr Winnett 87
 Os calcis See Calcaneus
 Os good Schlaters disease 501
 Ossification around ankle 465
 around knee (Pellegrini Steda) 632
 essential conditions of 53
 in hematoma 53, 119
 near elbow 125
 in repair of fractures 1
 Osteoblasts in repair 12
 Osteoclast (Phipps Gocht) 161 585
 Osteochondritis ilio-tibialis 330 491
 Os tibiale extraneum 570
 Os trigonum 26 570, 573
 Os vesiculare 570
 Otorrhoea 206 231

Padded plaster casts 168
 Pain localisation of 22
 after Colles's fracture 364
 influence on shock, 41
 symptom of fracture 2
 under plaster 169
 Palatal anaesthesia 201
 Paralysis in spinal cord injury 272
 operative treatment 273
 Paralytic flus after fracture of spine
 266 270
 Pimples etiology, 271
 Brown Sequard syndrome 273
 care of blacker, 274
 emph. equina lesions 275
 cerebro spinal fluid 275
 treatment operative, 270
 Pure Ambrose 68 86
 Purhan's bands 127
 Pasteur Louis 68 86
 Patella anatomy surgical 493
 compound fracture 498
 congenital abnormality 499
 dislocation 633
 fracture of etiology, 493
 of excision 197
 Pathological fracture 2
 Patient examination of 24
 Pellegrini Steda's disease 632
 Pelvis anatomy surgical 428
 avulsion fractures 441
 coccygeal fracture 442
 complications 444
 double fracture of Malgaigne, 431
 fracture of acetabulum 439
 of individual bones 438
 mode of injury 429
 sacral injury 442
 varieties of fracture 429
 weak areas 429
 Penicillin chemotherapy 80
 dosage 81
 effects of 82
 intra articular injection 82
 organisms sensitive to 81
 varieties 80
 Periarthritis of shoulder 313
 Peroneal nerve paralysis from plaster
 170 529
 Pterochanteric fractures 467
 Phalanges anatomy surgical 423
 hand 423

use 139
 wing section, 468
 like rubber, use, 158 182
 traumatic fracture 2
 arm definition, 1
 fracture 8
 imp. balance 160
 min. plates, 121
 reh bandages 160
 nanam's pin 149 See Pin
 acroclavicular joint dislocation 604
 arm fracture 282
 ekmette 179
 toy in chest 251
 arm radiography, 24 28, 333
 apping varieties, 179
 eptomycin 83
 fold process radius 170
 ulna 357
 acromial bursitis 313
 basitragaloid joint See Subtaloid joint
 beapital fracture, femur 470
 beconjunctival hemorrhage 204, 283
 beorseoid dislocation of shoulder 605
 bdeftoid bursitis 311
 bdural hematoma 270
 bluxation definition, 1
 bperio-steal hematoma, 22
 in scalp 223
 btaloid joint arthritis 593
 arthrodesis 593
 dislocation 573
 fracture involving, 583
 btrochanteric fractures 469 472, 485
 cking wound chest 281
 deck's acute bony atrophy 61
 lphonamide therapy general 77 79
 in bronchopneumonia 46
 in compound fractures 77
 in gas gangrene 103
 toxic reactions 89
 ipracondylar fracture femur 489
 humerus 319
 ipramalleolar fractures 536
 ipra spinatus tendon rupture 313 608
 urgical anatomy calcaneus 509
 carpus 393
 clavicle 285
 face region 231
 femur 445 649
 fibula 503 530, 652
 humerus 300
 metacarpals 411
 patella 493
 pelvis 428
 phalanges 121
 radius 312
 ribs 278
 scapula 291
 skull 191
 spine 216
 st. man 118
 talus 530, 549
 tarsals 161

surgical anatomy, emphysema after
 fracture of ribs, 282
 clavicle, 292
 exposure bones and joints 616
 Sustentaculum tali, fracture of, 782
 Suture of wounds 74, 90
 Swelling after fracture, 22
 under plaster 169
 Symphysis pubis dislocations 431 622
 Symptoms of fracture 22
 Syphilis, effects on union, 107
 Talo calcaneal joint, 580 583
 Talo navicular accessory bone 770
 Talus anatomy, surgical 569
 Talus avascular necrosis, 575
 dislocation 571 576
 fracture of neck, 570
 of body 572
 subastragaloid dislocation 573
 tarsus fractures 569 594
 tarso metatarsal joint, dislocation, 634
 Teeth, in fracture line 285
 Temperature in cerebral compression, 216
 irritation 209
 in shock, 245
 in traumatic fever 44
 Temporo mandibular joint condylar
 fracture 241
 Tendons avulsion of extensor of finger
 426
 rupture of extensor pollicis longus 366
 of supraspinatus 608
 Tension pneumothorax 283
 Tetanus 100
 Thiersch grafts, 145
 Thomas H. O., strapping of clavicle, 292
 Thomas splint 155
 arm 154
 in use 139 475
 Thoracic injuries 278
 spine fracture 256
 Thoraco brachial plaster 138 174
 Three flanged nails 467 469
 Thrombosis deep tibial, 66
 Thumb dislocation carpo metacarpal,
 414 618
 metacarpo phalangeal, 618
 phalangeal 618
 fracture dislocation Bennett's, 414
 fractures 413
 rupture of ext. pollicis 366
 Tibia anatomy surgical 502
 anterior tubercle fracture 559
 marginal fracture 566
 in children 528
 comminuted fracture 509 527
 compound fracture 528
 condyles fracture 503
 crest 502
 epiphyseal injury 501
 fatigue fracture, 514, 514
 fractures alone 502

- Rulers, bone, 54
 Robert Jones' bent arm splint 161, 167
 method of reduction of ankle 718
 strapping. See H. O. Thomas
 Rocker sole, 182
 Rotation correction of 117
 importance in fingers 424
 Rocker bar injuries 572

Sacroiliac dislocation 429 622
 fracture, involving joint 431
 subluxation 129
Sacrum fracture 442
 child equina injury with 144
 radiology 443
Sayre's strapping, fractured clavicle 10
Scapulo humeral carpal See Navicular
 tarsal See Navicular
Scapula anatomy surgical 296
 acromion 298
 anatomical neck 297
 fracture of body 298
 of coracoid 298
 of glenoid 298
 of spine 298
 of surgical neck 297
 sites of fracture 295
Schultz collar 260
Sciatric dislocation of hip 624
 nerve anasthesia 190
 injury 620
Sclerosis of bone in avascular necrosis 17
 in ununited fracture of navicular 397
Screws varieties 126
Secondary suture 80 137
Semilunar, 403 406 See Lumbar
 cartilage injury 398
Scute atrophy of bone 2
Sesamoids of foot 609
 varieties 601
 radiology 27
Shearing strain non union 169
Shear's plaster 162
Shenton's line 471
Shock 41
 influence of local anaesthesia 187
Sherman screws 126
Shortening correction 118
Shoulder See Humerus Upper end
 dislocations 600
 complications 608
 fracture dislocations 310
 periarthritis of 313
 stiffness after injury 304 313
 surgical exposure 646
Shoemaker's line, 450
Shoveller's fracture 260
Signs of fracture 22
Simple fracture definition 5
Skeletal traction, advantages 33
 sites, calcaneus 587
 femur 437
 tibia 400
 ulna 339
 skin blistering after fracture 23
 traction disadvantages, 33
Skin grafts 85, 146
 in compound fractures, 99 146
 anatomy, surgical 193
 infection under plaster 95
 loss treatment of 85 124
 preparation after wounds 71 125
Skull calipers traction 24
Skull bullet wounds, 196
 depressed fractures 222
 depression fracture 226
 fracture base 199
 causes of death 214
 cerebral shock syndrome 271
 chemotherapy in 224
 clinical examination 199, 204
 complications 229
 compound 223
 deafness after 231
 errors in diagnosis 232
 gutter 225
 head pain after 231
 hernia cerebri 230
 indication for operation 229
 infection 229
 intelligence changes 231
 later subdural hematoma 230
 radiography 201
 rhinorrhoea after 204 205 231
 traumatic epilepsy 231
 types of violence causing 194
 vault 195
 with facial fractures 234
 with maxillary fractures 238
Smith's fracture 373 366
Smith-Petersen approach to hip 612
 anal 457
 complications of 465
 crochard of 465
 in petrochanthone fractures, 467
 infection 465
Spatulas use of 159
Spicas long short 177
Spinal cord injuries in fracture of spine
 271
 cervical spine 272
 shock 271
Spine anatomy surgical 247
 cervical 245 See Cervical spine
 dorsal 266
 fractures 270
 complications 271
 lumbar 247 See Lumbar spine
Spinous process fractures 257
Spiral fracture aetiology 4 32
 retention 32
Spleen rupture 284
Splints abduction 156 162
 Bohler's clavicle 290
 Braun's 102
 cap dental 239
 clavicle artificial 491
 dental cap 239
 finger wires 157 420
 plaster 170

- tibia shaft 140, 513 514
 spine 501
 subcondylar 511
 supramalleolar 511
 surgical approach 501 552
 tubercles 519
 tuberosity fracture 501
 tibia and fibula (fractures both bones
 leg) 518
 lower ends 530 See Ankle
 tibial flake 505
 Tillaux third fragment 559
 Tillaux's hypothesis 507
 Tobruk plaster 179 488
 toes dislocation 634
 fracture 509
 Tomography 24 28
 in spinal fracture, 271
 Toxinæ cause of shock 41
 Traction continuous for femur, 455
 473 476
 skeletal 33
 skin 33
 Transport plasters, 135
 Transverse fractures mechanism 4
 reduction 32
 Traumatic arthritis aetiology, 19 63 119
 ankle 509
 elbow 340 349
 shoulder 311
 wrist 366
 asphyxia 283
 bony atrophy 61
 cyanosis 283
 delirium 208
 epilepsy 231
 fever 44
 stupor 215
 Treatment, general principles 29
 Trephining 226 227
 en bloc 223
 Trethowan's third malloleus 545
 Triquetrum fractures 403
 Trismus 100
 Trochanter greater 469
 lesser 469
 Trueta 87
 Tubercles of tibia 554 559
 radiography 532 558
 Tuberosity of tibia 501
 of humerus greater 312
 lesser 312
 of navicular fracture 401
 Ulna anatomy surgical 374
 coronoid process 374
 intramedullary Kirschner wire 391
 olecranon 375
 shaft 381
 with dislocation of head of radius
 382
 with fracture radius (both bones)
 384
 styloid process 355 366 375
 persistent pain 366
 Ulnar nerve transplantation 378
 injury 115
 late varieties 338 340
 Unconsciousness in fracture of sk
 202
 Union of fractures 10 106
 after operative fixation 124
 delayed 106
 factor influencing 16
 in bad position 117
 radiological, 17, 106
 strength of 16
 Union's plate formulae, 158
 Unpadded plaster advantages 165
 Urethra rupture 445
 Urine extravasation 445
 Vascular disturbance after fracture
 under plaster 48 94
 injury & complicating fracture 41
 Venable screw 126
 Venous hæmorrhage in cerebral
 compression, 215
 Ventricular hæmorrhage 217
 Vertebra cervical 250 See Cervical
 spine
 dorsal 250
 lumbar 257 See Lumbar spine
 surgical anatomy 246
 Vesical injuries in fracture of pelvis
 Volvulus types of 3
 direct, 3
 indirect 4
 muscular 5
 Visceral injuries associated with frac
 31
 Vitallium plates 126
 Volkmann's ischæmic contracture
 Vomiting after sulphourea 80
 Walking iron 158
 plasters 179
 Wadsworth's forceps 234
 War (1914-18) influence 57 135
 surgery 131
 Watson Jones guide 459
 leg extension apparatus 153
 Wedging plaster 32
 plasters 21
 Well leg traction splint 468
 Wharton Hood's method in frac
 clavicle 290
 Whitman plaster construction 175
 fracture of neck of femur 456
 pertrochanteric fracture 468
 Winnett Orr 87
 Wires beaded use of 121
 finger 157
 Kirschner 131 150
 Wounds anaesthesia in 72
 chemotherapy in 83
 excision of 75
 facial 245
 infected 69
 primary closure 89
 in war 103

